


A comprehensive step-by-step guide

Programming in Scala

Third Edition



Updated for Scala 2.12

artima

Martin Odersky
Lex Spoon
Bill Venners

Praise for the earlier editions of *Programming in Scala*

Programming in Scala is probably one of the best programming books I've ever read. I like the writing style, the brevity, and the thorough explanations. The book seems to answer every question as it enters my mind—it's always one step ahead of me. The authors don't just give you some code and take things for granted. They give you the meat so you really understand what's going on. I really like that.

- Ken Egervari, Chief Software Architect

Programming in Scala is clearly written, thorough, and easy to follow. It has great examples and useful tips throughout. It has enabled our organization to ramp up on the Scala language quickly and efficiently. This book is great for any programmer who is trying to wrap their head around the flexibility and elegance of the Scala language.

- Larry Morroni, Owner, Morroni Technologies, Inc.

The *Programming in Scala* book serves as an excellent tutorial to the Scala language. Working through the book, it flows well with each chapter building on concepts and examples described in earlier ones. The book takes care to explain the language constructs in depth, often providing examples of how the language differs from Java. As well as the main language, there is also some coverage of libraries such as containers and actors.

I have found the book really easy to work through, and it is probably one of the better written technical books I have read recently. I really would recommend this book to any programmer wanting to find out more about the Scala language.

- Matthew Todd

I am amazed by the effort undertaken by the authors of *Programming in Scala*. This book is an invaluable guide to what I like to call Scala the Platform: a vehicle to better coding, a constant inspiration for scalable software design and implementation. If only I had Scala in its present mature state and this book on my desk back in 2003, when co-designing and implementing parts of the Athens 2004 Olympic Games Portal infrastructure!

To all readers: No matter what your programming background is, I feel you will find programming in Scala liberating and this book will be a loyal friend in the journey.

- Christos KK Loverdos, Software Consultant, Researcher

Programming in Scala is a superb in-depth introduction to Scala, and it's also an excellent reference. I'd say that it occupies a prominent place on my bookshelf, except that I'm still carrying it around with me nearly everywhere I go.

- Brian Clapper, President, ArdenTex, Inc.

Great book, well written with thoughtful examples. I would recommend it to both seasoned programmers and newbies.

- Howard Lovatt

The book *Programming in Scala* is not only about *how*, but more importantly, *why* to develop programs in this new programming language. The book's pragmatic approach in introducing the power of combining object-oriented and functional programming leaves the reader without any doubts as to what Scala really is.

- Dr. Ervin Varga, CEO/founder, EXPRO I.T. Consulting

This is a great introduction to functional programming for OO programmers. Learning about FP was my main goal, but I also got acquainted with some nice Scala surprises like case classes and pattern matching. Scala is an intriguing language and this book covers it well.

There's always a fine line to walk in a language introduction book between giving too much or not enough information. I find *Programming in Scala* to achieve a perfect balance.

- Jeff Heon, Programmer Analyst

I bought an early electronic version of the *Programming in Scala* book, by Odersky, Spoon, and Venners, and I was immediately a fan. In addition to the fact that it contains the most comprehensive information about the language, there are a few key features of the electronic format that impressed me. I have never seen links used as well in a PDF, not just for bookmarks, but also providing active links from the table of contents and index. I don't know why more authors don't use this feature, because it's really a joy for the reader. Another feature which I was impressed with was links to the forums ("Discuss") and a way to send comments ("Suggest") to the authors via email. The comments feature by itself isn't all that uncommon, but the simple inclusion of a page number in what is generated to send to the authors is valuable for both the authors and readers. I contributed more comments than I would have if the process would have been more arduous.

Read *Programming in Scala* for the content, but if you're reading the electronic version, definitely take advantage of the digital features that the authors took the care to build in!

- Dianne Marsh, Founder/Software Consultant, SRT Solutions

Lucidity and technical completeness are hallmarks of any well-written book, and I congratulate Martin Odersky, Lex Spoon, and Bill Venners on a job indeed very well done! The *Programming in Scala* book starts by setting a strong foundation with the basic concepts and ramps up the user to an intermediate level & beyond. This book is certainly a must buy for anyone aspiring to learn Scala.

- Jagan Nambi, Enterprise Architecture, GMAC Financial Services

Programming in Scala is a pleasure to read. This is one of those well-written technical books that provide deep and comprehensive coverage of the subject in an exceptionally concise and elegant manner.

The book is organized in a very natural and logical way. It is equally well suited for a curious technologist who just wants to stay on top of the current trends and a professional seeking deep understanding of the language core features and its design rationales. I highly recommend it to all interested in functional programming in general. For Scala developers, this book is unconditionally a must-read.

- Igor Khlystov, Software Architect/Lead Programmer, Greystone Inc.

The book *Programming in Scala* outright oozes the huge amount of hard work that has gone into it. I've never read a tutorial-style book before that accomplishes to be introductory yet comprehensive: in their (misguided) attempt to be approachable and not "confuse" the reader, most tutorials silently ignore aspects of a subject that are too advanced for the current discussion. This leaves a very bad taste, as one can never be sure as to the understanding one has achieved. There is always some residual "magic" that hasn't been explained and cannot be judged at all by the reader. This book never does that, it never takes anything for granted: every detail is either sufficiently explained or a reference to a later explanation is given. Indeed, the text is extensively cross-referenced and indexed, so that forming a complete picture of a complex topic is relatively easy.

- Gerald Loeffler, Enterprise Java Architect

Programming in Scala by Martin Odersky, Lex Spoon, and Bill Venners: in times where good programming books are rare, this excellent introduction for intermediate programmers really stands out. You'll find everything here you need to learn this promising language.

- Christian Neukirchen

Programming in Scala

Third Edition

Programming in Scala

Third Edition

Martin Odersky, Lex Spoon, Bill Venners

artima
ARTIMA PRESS
WALNUT CREEK, CALIFORNIA

Programming in Scala
Third Edition

Martin Odersky is the creator of the Scala language and a professor at EPFL in Lausanne, Switzerland. Lex Spoon worked on Scala for two years as a post-doc with Martin Odersky. Bill Venners is president of Artima, Inc.

Artima Press is an imprint of Artima, Inc.
P.O. Box 305, Walnut Creek, California 94597

Copyright © 2007-2016 Martin Odersky, Lex Spoon, and Bill Venners.
All rights reserved.

First edition published as PrePrint™ eBook 2007
First edition published 2008
Second edition published as PrePrint™ eBook 2010
Second edition published 2010
Third edition published as PrePrint™ eBook 2016
Third edition published 2016
Build date of this impression April 6, 2016
Produced in the United States of America

No part of this publication may be reproduced, modified, distributed, stored in a retrieval system, republished, displayed, or performed, for commercial or noncommercial purposes or for compensation of any kind without prior written permission from Artima, Inc.

All information and materials in this book are provided "as is" and without warranty of any kind.

The term "Artima" and the Artima logo are trademarks or registered trademarks of Artima, Inc. All other company and/or product names may be trademarks or registered trademarks of their owners.

to Nastaran - M.O.

to Fay - L.S.

to Siew - B.V.

Overview

Contents	xi
List of Figures	xxi
List of Tables	xxiii
List of Listings	xxv
Foreword	xxxii
Acknowledgments	xxxiv
Introduction	xxxvii
1. A Scalable Language	45
2. First Steps in Scala	64
3. Next Steps in Scala	77
4. Classes and Objects	99
5. Basic Types and Operations	112
6. Functional Objects	135
7. Built-in Control Structures	155
8. Functions and Closures	180
9. Control Abstraction	203
10. Composition and Inheritance	218
11. Scala's Hierarchy	246
12. Traits	257
13. Packages and Imports	276
14. Assertions and Tests	294
15. Case Classes and Pattern Matching	306
16. Working with Lists	340
17. Working with Other Collections	373
18. Mutable Objects	395
19. Type Parameterization	418
20. Abstract Members	443
21. Implicit Conversions and Parameters	474
22. Implementing Lists	499
23. For Expressions Revisited	512
24. Collections in Depth	528
25. The Architecture of Scala Collections	597
26. Extractors	621
27. Annotations	637
28. Working with XML	645
29. Modular Programming Using Objects	659
30. Object Equality	674
31. Combining Scala and Java	698
32. Futures and Concurrency	714
33. Combinator Parsing	736
34. GUI Programming	765
35. The SCells Spreadsheet	777
A. Scala Scripts on Unix and Windows	802
Glossary	803
Bibliography	819
About the Authors	822
Index	823

Contents

Contents	xi
List of Figures	xxi
List of Tables	xxiii
List of Listings	xxv
Foreword	xxxii
Acknowledgments	xxxiv
Introduction	xxxvii
1 A Scalable Language	45
1.1 A language that grows on you	46
1.2 What makes Scala scalable?	51
1.3 Why Scala?	54
1.4 Scala's roots	61
1.5 Conclusion	63
2 First Steps in Scala	64
Step 1. Learn to use the Scala interpreter	64
Step 2. Define some variables	66
Step 3. Define some functions	68
Step 4. Write some Scala scripts	70
Step 5. Loop with <code>while</code> ; decide with <code>if</code>	71
Step 6. Iterate with <code>foreach</code> and <code>for</code>	73
Conclusion	76

3	Next Steps in Scala	77
Step 7.	Parameterize arrays with types	77
Step 8.	Use lists	81
Step 9.	Use tuples	86
Step 10.	Use sets and maps	87
Step 11.	Learn to recognize the functional style	92
Step 12.	Read lines from a file	95
	Conclusion	98
4	Classes and Objects	99
4.1	Classes, fields, and methods	99
4.2	Semicolon inference	104
4.3	Singleton objects	105
4.4	A Scala application	108
4.5	The App trait	110
4.6	Conclusion	111
5	Basic Types and Operations	112
5.1	Some basic types	112
5.2	Literals	113
5.3	String interpolation	119
5.4	Operators are methods	121
5.5	Arithmetic operations	124
5.6	Relational and logical operations	125
5.7	Bitwise operations	127
5.8	Object equality	128
5.9	Operator precedence and associativity	130
5.10	Rich wrappers	133
5.11	Conclusion	133
6	Functional Objects	135
6.1	A specification for class Rational	135
6.2	Constructing a Rational	136
6.3	Reimplementing the <code>toString</code> method	138
6.4	Checking preconditions	139
6.5	Adding fields	139
6.6	Self references	141
6.7	Auxiliary constructors	142

6.8	Private fields and methods	144
6.9	Defining operators	145
6.10	Identifiers in Scala	147
6.11	Method overloading	150
6.12	Implicit conversions	152
6.13	A word of caution	153
6.14	Conclusion	153
7	Built-in Control Structures	155
7.1	If expressions	156
7.2	While loops	157
7.3	For expressions	160
7.4	Exception handling with <code>try</code> expressions	165
7.5	Match expressions	169
7.6	Living without <code>break</code> and <code>continue</code>	171
7.7	Variable scope	173
7.8	Refactoring imperative-style code	177
7.9	Conclusion	179
8	Functions and Closures	180
8.1	Methods	180
8.2	Local functions	182
8.3	First-class functions	184
8.4	Short forms of function literals	186
8.5	Placeholder syntax	187
8.6	Partially applied functions	188
8.7	Closures	191
8.8	Special function call forms	195
8.9	Tail recursion	198
8.10	Conclusion	202
9	Control Abstraction	203
9.1	Reducing code duplication	203
9.2	Simplifying client code	207
9.3	Currying	209
9.4	Writing new control structures	211
9.5	By-name parameters	214
9.6	Conclusion	217

10 Composition and Inheritance	218
10.1 A two-dimensional layout library	218
10.2 Abstract classes	219
10.3 Defining parameterless methods	220
10.4 Extending classes	223
10.5 Overriding methods and fields	225
10.6 Defining parametric fields	226
10.7 Invoking superclass constructors	228
10.8 Using override modifiers	229
10.9 Polymorphism and dynamic binding	231
10.10 Declaring final members	233
10.11 Using composition and inheritance	235
10.12 Implementing above, beside, and <code>toString</code>	236
10.13 Defining a factory object	238
10.14 Heighten and widen	240
10.15 Putting it all together	244
10.16 Conclusion	245
11 Scala's Hierarchy	246
11.1 Scala's class hierarchy	246
11.2 How primitives are implemented	250
11.3 Bottom types	252
11.4 Defining your own value classes	253
11.5 Conclusion	256
12 Traits	257
12.1 How traits work	257
12.2 Thin versus rich interfaces	260
12.3 Example: Rectangular objects	261
12.4 The <code>Ordered</code> trait	264
12.5 Traits as stackable modifications	266
12.6 Why not multiple inheritance?	270
12.7 To trait or not to trait?	274
12.8 Conclusion	275
13 Packages and Imports	276
13.1 Putting code in packages	276
13.2 Concise access to related code	277

13.3	Imports	281
13.4	Implicit imports	285
13.5	Access modifiers	286
13.6	Package objects	291
13.7	Conclusion	293
14	Assertions and Tests	294
14.1	Assertions	294
14.2	Testing in Scala	296
14.3	Informative failure reports	297
14.4	Tests as specifications	299
14.5	Property-based testing	302
14.6	Organizing and running tests	304
14.7	Conclusion	305
15	Case Classes and Pattern Matching	306
15.1	A simple example	306
15.2	Kinds of patterns	311
15.3	Pattern guards	320
15.4	Pattern overlaps	321
15.5	Sealed classes	323
15.6	The Option type	325
15.7	Patterns everywhere	327
15.8	A larger example	331
15.9	Conclusion	339
16	Working with Lists	340
16.1	List literals	340
16.2	The List type	341
16.3	Constructing lists	341
16.4	Basic operations on lists	342
16.5	List patterns	343
16.6	First-order methods on class List	345
16.7	Higher-order methods on class List	357
16.8	Methods of the List object	365
16.9	Processing multiple lists together	367
16.10	Understanding Scala's type inference algorithm	368
16.11	Conclusion	372

17 Working with Other Collections	373
17.1 Sequences	373
17.2 Sets and maps	377
17.3 Selecting mutable versus immutable collections	385
17.4 Initializing collections	388
17.5 Tuples	392
17.6 Conclusion	394
18 Mutable Objects	395
18.1 What makes an object mutable?	395
18.2 Reassignable variables and properties	398
18.3 Case study: Discrete event simulation	401
18.4 A language for digital circuits	402
18.5 The Simulation API	405
18.6 Circuit Simulation	409
18.7 Conclusion	417
19 Type Parameterization	418
19.1 Functional queues	418
19.2 Information hiding	422
19.3 Variance annotations	425
19.4 Checking variance annotations	429
19.5 Lower bounds	432
19.6 Contravariance	434
19.7 Object private data	437
19.8 Upper bounds	439
19.9 Conclusion	442
20 Abstract Members	443
20.1 A quick tour of abstract members	443
20.2 Type members	444
20.3 Abstract vals	445
20.4 Abstract vars	446
20.5 Initializing abstract vals	447
20.6 Abstract types	455
20.7 Path-dependent types	457
20.8 Refinement types	460
20.9 Enumerations	461

20.10 Case study: Currencies	463
20.11 Conclusion	473
21 Implicit Conversions and Parameters	474
21.1 Implicit conversions	474
21.2 Rules for implicits	477
21.3 Implicit conversion to an expected type	480
21.4 Converting the receiver	482
21.5 Implicit parameters	485
21.6 Context bounds	491
21.7 When multiple conversions apply	494
21.8 Debugging implicits	496
21.9 Conclusion	497
22 Implementing Lists	499
22.1 The List class in principle	499
22.2 The ListBuffer class	505
22.3 The List class in practice	507
22.4 Functional on the outside	509
22.5 Conclusion	510
23 For Expressions Revisited	512
23.1 For expressions	513
23.2 The n-queens problem	515
23.3 Querying with for expressions	518
23.4 Translation of for expressions	520
23.5 Going the other way	524
23.6 Generalizing for	525
23.7 Conclusion	527
24 Collections in Depth	528
24.1 Mutable and immutable collections	529
24.2 Collections consistency	531
24.3 Trait Traversable	533
24.4 Trait Iterable	538
24.5 The sequence traits Seq, IndexedSeq, and LinearSeq .	542
24.6 Sets	547
24.7 Maps	552

24.8	Concrete immutable collection classes	556
24.9	Concrete mutable collection classes	563
24.10	Arrays	570
24.11	Strings	575
24.12	Performance characteristics	575
24.13	Equality	578
24.14	Views	579
24.15	Iterators	584
24.16	Creating collections from scratch	592
24.17	Conversions between Java and Scala collections	594
24.18	Conclusion	596
25	The Architecture of Scala Collections	597
25.1	Builders	597
25.2	Factoring out common operations	599
25.3	Integrating new collections	604
25.4	Conclusion	620
26	Extractors	621
26.1	An example: extracting email addresses	621
26.2	Extractors	622
26.3	Patterns with zero or one variables	625
26.4	Variable argument extractors	627
26.5	Extractors and sequence patterns	630
26.6	Extractors versus case classes	631
26.7	Regular expressions	632
26.8	Conclusion	636
27	Annotations	637
27.1	Why have annotations?	637
27.2	Syntax of annotations	638
27.3	Standard annotations	640
27.4	Conclusion	644
28	Working with XML	645
28.1	Semi-structured data	645
28.2	XML overview	646
28.3	XML literals	647

28.4	Serialization	649
28.5	Taking XML apart	651
28.6	Deserialization	652
28.7	Loading and saving	653
28.8	Pattern matching on XML	655
28.9	Conclusion	658
29	Modular Programming Using Objects	659
29.1	The problem	660
29.2	A recipe application	661
29.3	Abstraction	664
29.4	Splitting modules into traits	667
29.5	Runtime linking	670
29.6	Tracking module instances	671
29.7	Conclusion	673
30	Object Equality	674
30.1	Equality in Scala	674
30.2	Writing an equality method	675
30.3	Defining equality for parameterized types	688
30.4	Recipes for equals and hashCode	692
30.5	Conclusion	697
31	Combining Scala and Java	698
31.1	Using Scala from Java	698
31.2	Annotations	701
31.3	Wildcard types	706
31.4	Compiling Scala and Java together	709
31.5	Java 8 integration in Scala 2.12	709
31.6	Conclusion	713
32	Futures and Concurrency	714
32.1	Trouble in paradise	714
32.2	Asynchronous execution and Trys	716
32.3	Working with Futures	718
32.4	Testing with Futures	733
32.5	Conclusion	735

33 Combinator Parsing	736
33.1 Example: Arithmetic expressions	737
33.2 Running your parser	739
33.3 Basic regular expression parsers	740
33.4 Another example: JSON	741
33.5 Parser output	743
33.6 Implementing combinator parsers	749
33.7 String literals and regular expressions	758
33.8 Lexing and parsing	759
33.9 Error reporting	759
33.10 Backtracking versus LL(1)	761
33.11 Conclusion	763
34 GUI Programming	765
34.1 A first Swing application	765
34.2 Panels and layouts	768
34.3 Handling events	770
34.4 Example: Celsius/Fahrenheit converter	773
34.5 Conclusion	775
35 The SCeLLs Spreadsheet	777
35.1 The visual framework	777
35.2 Disconnecting data entry and display	780
35.3 Formulas	783
35.4 Parsing formulas	785
35.5 Evaluation	790
35.6 Operation libraries	793
35.7 Change propagation	796
35.8 Conclusion	800
A Scala Scripts on Unix and Windows	802
Glossary	803
Bibliography	819
About the Authors	822
Index	823

List of Figures

2.1	The basic form of a function definition in Scala.	69
2.2	The syntax of a function literal in Scala.	75
3.1	All operations are method calls in Scala.	80
3.2	Class hierarchy for Scala sets.	88
3.3	Class hierarchy for Scala maps.	90
10.1	Class diagram for <code>ArrayElement</code>	224
10.2	Class diagram for <code>LineElement</code>	229
10.3	Class hierarchy of layout elements.	232
10.4	Class hierarchy with revised <code>LineElement</code>	236
11.1	Class hierarchy of Scala.	248
12.1	Inheritance hierarchy and linearization of class <code>Cat</code>	273
14.1	The output of <code>org.scalatest.run</code>	305
18.1	Basic gates.	402
18.2	A half-adder circuit.	404
18.3	A full-adder circuit.	405
19.1	Covariance and contravariance in function type parameters. .	437
22.1	Class hierarchy for Scala lists.	500
22.2	The structure of the Scala lists shown in Listing 22.2.	504
24.1	Collection hierarchy.	532
25.1	An example Patricia trie.	615

32.1 Class hierarchy for Try.	718
34.1 A simple Swing application: initial (left) and resized (right).	766
34.2 A reactive Swing application: initial (left) after clicks (right).	768
34.3 A converter between degrees Celsius and Fahrenheit.	773
35.1 A simple spreadsheet table.	778
35.2 Cells displaying themselves.	783
35.3 Cells displaying their formulas.	789
35.4 Cells that evaluate.	795

List of Tables

3.1	Some List methods and usages	84
5.1	Some basic types	113
5.2	Special character literal escape sequences	117
5.3	Operator precedence	131
5.4	Some rich operations	134
5.5	Rich wrapper classes	134
12.1	Linearization of types in Cat's hierarchy	274
13.1	Effects of private qualifiers on LegOfJourney.distance .	289
16.1	Basic list operations	343
17.1	Common operations for sets	380
17.2	Common operations for maps	382
17.3	Default immutable set implementations	384
17.4	Default immutable map implementations	384
24.1	Operations in trait Traversable	535
24.2	Operations in trait Iterable	540
24.3	Operations in trait Seq	544
24.4	Operations in trait Buffer	547
24.5	Operations in trait Set	548
24.6	Operations in trait mutable.Set	549
24.7	Operations in trait Map	553
24.8	Operations in trait mutable.Map	554
24.9	Operations in trait ConcurrentMap	569
24.10	Performance characteristics of sequence types	576

24.11 Performance characteristics of set and map types	576
24.12 Operations in trait <code>Iterator</code>	587
24.13 Factory methods for sequences	594
33.1 Summary of parser combinators	747

List of Listings

3.1	Parameterizing an array with a type.	78
3.2	Creating and initializing an array.	81
3.3	Creating and initializing a list.	82
3.4	Creating and using a tuple.	86
3.5	Creating, initializing, and using an immutable set.	87
3.6	Creating, initializing, and using a mutable set.	89
3.7	Creating, initializing, and using a mutable map.	90
3.8	Creating, initializing, and using an immutable map.	91
3.9	A function without side effects or vars.	93
3.10	Reading lines from a file.	95
3.11	Printing formatted character counts for the lines of a file.	98
4.1	Final version of class <code>ChecksumAccumulator</code>	103
4.2	Companion object for class <code>ChecksumAccumulator</code>	106
4.3	The <code>Summer</code> application.	108
4.4	Using the <code>App</code> trait.	110
6.1	<code>Rational</code> with fields.	141
6.2	<code>Rational</code> with an auxiliary constructor.	143
6.3	<code>Rational</code> with a private field and method.	144
6.4	<code>Rational</code> with operator methods.	146
6.5	<code>Rational</code> with overloaded methods.	151
7.1	Scala’s idiom for conditional initialization.	156
7.2	Calculating greatest common divisor with a <code>while</code> loop.	157
7.3	Reading from the standard input with <code>do-while</code>	158
7.4	Calculating greatest common divisor with recursion.	159
7.5	Listing files in a directory with a <code>for</code> expression.	160

7.6	Finding .scala files using a for with a filter.	162
7.7	Using multiple filters in a for expression.	162
7.8	Using multiple generators in a for expression.	163
7.9	Mid-stream assignment in a for expression.	164
7.10	Transforming an <code>Array[File]</code> to <code>Array[Int]</code> with a for.	165
7.11	A try-catch clause in Scala.	167
7.12	A try-finally clause in Scala.	168
7.13	A catch clause that yields a value.	169
7.14	A match expression with side effects.	170
7.15	A match expression that yields a value.	170
7.16	Looping without break or continue.	172
7.17	A recursive alternative to looping with vars.	172
7.18	Variable scoping when printing a multiplication table.	175
7.19	A functional way to create a multiplication table.	178
8.1	LongLines with a private <code>processLine</code> method.	181
8.2	LongLines with a local <code>processLine</code> function.	183
8.3	A parameter with a default value.	197
8.4	A function with two parameters that have defaults.	198
9.1	Using closures to reduce code duplication.	207
9.2	Defining and invoking a “plain old” function.	210
9.3	Defining and invoking a curried function.	210
9.4	Using the loan pattern to write to a file.	214
9.5	Using a by-name parameter.	215
10.1	Defining an abstract method and class.	220
10.2	Defining parameterless methods <code>width</code> and <code>height</code>	221
10.3	Defining <code>ArrayElement</code> as a subclass of <code>Element</code>	223
10.4	Overriding a parameterless method with a field.	225
10.5	Defining <code>contents</code> as a parametric field.	227
10.6	Invoking a superclass constructor.	228
10.7	Declaring a final method.	234
10.8	Declaring a final class.	234
10.9	Class <code>Element</code> with <code>above</code> , <code>beside</code> , and <code>toString</code>	239
10.10	A factory object with factory methods.	240
10.11	Class <code>Element</code> refactored to use factory methods.	241
10.12	Hiding implementation with private classes.	242

10.13	Element with widen and heighten methods.	243
10.14	The Spiral application.	244
12.1	The definition of trait Philosophical.	257
12.2	Mixing in a trait using extends.	258
12.3	Mixing in a trait using with.	259
12.4	Mixing in multiple traits.	259
12.5	Defining an enrichment trait.	263
12.6	Abstract class IntQueue.	267
12.7	A BasicIntQueue implemented with an ArrayBuffer. . .	267
12.8	The Doubling stackable modification trait.	268
12.9	Mixing in a trait when instantiating with new.	269
12.10	Stackable modification traits Incrementing and Filtering.	269
13.1	Placing the contents of an entire file into a package.	277
13.2	Long form of a simple package declaration.	277
13.3	Multiple packages in the same file.	278
13.4	Concise access to classes and packages.	278
13.5	Symbols in enclosing packages not automatically available.	279
13.6	Accessing hidden package names.	279
13.7	Bob's delightful fruits, ready for import.	282
13.8	Importing the members of a regular (not singleton) object. .	282
13.9	Importing a package name.	283
13.10	How private access differs in Scala and Java.	286
13.11	How protected access differs in Scala and Java.	287
13.12	Flexible scope of protection with access qualifiers.	288
13.13	Accessing private members of companion classes and objects.	291
13.14	A package object.	292
14.1	Using an assertion.	295
14.2	Using ensuring to assert a function's result.	295
14.3	Writing tests with FunSuite.	296
14.4	Specifying and testing behavior with a ScalaTest FlatSpec.	300
14.5	Specifying and testing behavior with the specs2 framework.	301
14.6	Using tests to facilitate communication among stakeholders.	302
14.7	Writing property-based tests with ScalaCheck.	303
15.1	Defining case classes.	307
15.2	The simplifyTop function, which does a pattern match. . .	309

15.3	A pattern match with an empty “default” case.	311
15.4	A pattern match with wildcard patterns.	312
15.5	A pattern match with constant patterns.	312
15.6	A pattern match with a variable pattern.	313
15.7	A pattern match with a constructor pattern.	315
15.8	A sequence pattern with a fixed length.	315
15.9	A sequence pattern with an arbitrary length.	316
15.10	A pattern match with a tuple pattern.	316
15.11	A pattern match with typed patterns.	317
15.12	Using <code>isInstanceOf</code> and <code>asInstanceOf</code> (poor style).	318
15.13	A pattern with a variable binding (via the @ sign).	320
15.14	A <code>match</code> expression with a pattern guard.	321
15.15	Match expression in which case order matters.	322
15.16	A sealed hierarchy of case classes.	324
15.17	Defining multiple variables with one assignment.	327
15.18	A <code>for</code> expression with a tuple pattern.	331
15.19	Picking elements of a list that match a pattern.	331
15.20	The top half of the expression formatter.	334
15.21	The bottom half of the expression formatter.	335
15.22	An application that prints formatted expressions.	338
16.1	A merge sort function for <code>Lists</code>	356
17.1	Default map and set definitions in <code>Predef</code>	378
18.1	A mutable bank account class.	396
18.2	A class with public vars.	398
18.3	How public vars are expanded into getter and setter methods.	399
18.4	Defining getter and setter methods directly.	399
18.5	Defining a getter and setter without an associated field.	400
18.6	The <code>halfAdder</code> method.	403
18.7	The <code>fullAdder</code> method.	404
18.8	The <code>Simulation</code> class.	406
18.9	The first half of the <code>BasicCircuitSimulation</code> class.	410
18.10	The second half of the <code>BasicCircuitSimulation</code> class.	411
18.11	The <code>CircuitSimulation</code> class.	415
19.1	A basic functional queue.	421
19.2	Hiding a primary constructor by making it private.	422

19.3	An apply factory method in a companion object.	423
19.4	Type abstraction for functional queues.	424
19.5	A nonvariant (rigid) Cell class.	427
19.6	A type parameter with a lower bound.	433
19.7	A contravariant output channel.	434
19.8	Covariance and contravariance of <code>Function1</code> s.	435
19.9	Demonstration of function type parameter variance.	436
19.10	An optimized functional queue.	438
19.11	A Person class that mixes in the <code>Ordered</code> trait.	440
19.12	A merge sort function with an upper bound.	440
20.1	Overriding abstract vals and parameterless methods.	446
20.2	Declaring abstract vars.	446
20.3	How abstract vars are expanded into getters and setters.	447
20.4	A trait that uses its abstract vals.	449
20.5	Pre-initialized fields in an anonymous class expression.	450
20.6	Pre-initialized fields in an object definition.	450
20.7	Pre-initialized fields in a class definition.	450
20.8	Initializing a trait with lazy vals.	453
20.9	Modeling suitable food with an abstract type.	456
20.10	Implementing an abstract type in a subclass.	457
20.11	The US currency zone.	469
20.12	Currency zones for Europe and Japan.	470
20.13	A converter object with an exchange rates map.	471
20.14	The full code of class <code>CurrencyZone</code>	472
21.1	An implicit parameter list with multiple parameters.	488
21.2	A function with an upper bound.	489
21.3	A function with an implicit parameter.	490
21.4	A function that uses an implicit parameter internally.	492
21.5	A function that uses <code>implicitly</code>	493
21.6	A function with a context bound.	494
21.7	Sample code that uses an implicit parameter.	498
21.8	Sample code after type checking and insertion of implicits.	498
22.1	The definition of the <code>Nil</code> singleton object.	501
22.2	Prepending a supertype element to a subtype list.	503
22.3	The definition of method <code>::</code> (cons) in class <code>List</code>	503

22.4	The definition of method <code>:::</code> in class <code>List</code>	505
22.5	The definition of method <code>map</code> in class <code>List</code>	507
22.6	The definition of the <code>::</code> subclass of <code>List</code>	508
25.1	An outline of the <code>Builder</code> class.	598
25.2	Implementation of <code>filter</code> in <code>TraversableLike</code>	600
25.3	Implementation of <code>map</code> in <code>TraversableLike</code>	602
25.4	The <code>CanBuildFrom</code> trait.	602
25.5	RNA Bases.	605
25.6	RNA strands class, first version.	606
25.7	RNA strands class, second version.	608
25.8	RNA strands class, final version.	612
25.9	RNA companion object—final version.	613
25.10	An implementation of prefix maps with Patricia tries.	616
25.11	The companion object for prefix maps.	619
26.1	The <code>EMail</code> string extractor object.	623
26.2	The <code>Twice</code> string extractor object.	626
26.3	The <code>UpperCase</code> string extractor object.	626
26.4	The <code>Domain</code> string extractor object.	628
26.5	The <code>ExpandedEMail</code> extractor object.	629
26.6	An extractor that defines an <code>unapplySeq</code> method.	630
26.7	How the <code>r</code> method is defined in <code>StringOps</code>	634
29.1	A simple <code>Food</code> entity class.	661
29.2	Simple <code>Recipe</code> entity class.	662
29.3	Food and Recipe examples for use in tests.	662
29.4	Mock database and browser modules.	663
29.5	Database and browser modules with categories added.	664
29.6	A <code>Browser</code> class with an abstract database <code>val</code>	665
29.7	A <code>Database</code> class with abstract methods.	666
29.8	The <code>SimpleDatabase</code> object as a <code>Database</code> subclass.	666
29.9	The <code>SimpleBrowser</code> object as a <code>Browser</code> subclass.	667
29.10	A student database and browser.	667
29.11	A trait for food categories.	668
29.12	A <code>Database</code> class that mixes in the <code>FoodCategories</code> trait.	668
29.13	A <code>SimpleDatabase</code> object composed solely of mixins.	668
29.14	A <code>SimpleFoods</code> trait.	668

29.15 A SimpleRecipes trait with a self type.	669
29.16 An app that dynamically selects a module implementation.	670
29.17 Using a singleton type.	672
30.1 A superclass equals method that calls canEqual.	686
30.2 A subclass equals method that calls canEqual.	687
30.3 Hierarchy for binary trees.	689
30.4 A parameterized type with equals and hashCode.	693
30.5 Class Rational with equals and hashCode.	696
31.1 A Scala method that declares a Java throws clause.	703
32.1 Returning a future assertion to ScalaTest.	735
33.1 An arithmetic expression parser.	738
33.2 A regular expression parser for Java identifiers.	740
33.3 Data in JSON format.	742
33.4 A simple JSON parser.	743
33.5 A full JSON parser that returns meaningful results.	747
33.6 The ~ combinator method.	755
34.1 A simple Swing application in Scala.	766
34.2 Component assembly on a panel.	768
34.3 Implementing a reactive Swing application.	772
34.4 An implementation of the temperature converter.	774
35.1 Code for spreadsheet in Figure 35.1.	779
35.2 The main program for the spreadsheet application.	780
35.3 A spreadsheet with a rendererComponent method.	781
35.4 First version of the Model class.	782
35.5 Classes representing formulas.	784
35.6 A spreadsheet that parses formulas.	788
35.7 The evaluate method of trait Evaluator.	791
35.8 A library for arithmetic operations.	793
35.9 The finished spreadsheet component.	799

Foreword

You've chosen a great time to pick up this book! Scala adoption keeps accelerating, our community is thriving, and job ads abound. Whether you're programming for fun or profit (or both), Scala's promise of joy and productivity is proving hard to resist. To me, the true joy of programming comes from tackling interesting challenges with simple, sophisticated solutions. Scala's mission is not just to make this possible, but enjoyable, and this book will show you how.

I first experimented with Scala 2.5, and was immediately drawn to its syntactic and conceptual regularity. When I ran into the irregularity that type parameters couldn't have type parameters themselves, I (timidly) walked up to Martin Odersky at a conference in 2006 and proposed an internship to remove that restriction. My contribution was accepted, bringing support for type constructor polymorphism to Scala 2.7 and up. Since then, I've worked on most other parts of the compiler. In 2012 I went from post-doc in Martin's lab to Scala team lead at Typesafe, as Scala, with version 2.10, graduated from its pragmatic academic roots to a robust language for the enterprise.

Scala 2.10 was a turning point from fast-paced, feature-rich releases based on academic research, towards a focus on simplification and increased adoption in the enterprise. We shifted our attention to issues that won't be written up in dissertations, such as binary compatibility between major releases. To balance stability with our desire to keep evolving and refining the Scala platform, we're working towards a smaller core library, which we aim to stabilize while evolving the platform as a whole. To enable this, my first project as Scala tech lead was to begin modularizing the Scala standard library in 2.11.

To reduce the rate of change, Typesafe also decided to alternate changing the library and the compiler. This edition of *Programming in Scala* covers Scala 2.12, which will be a compiler release sporting a new back-end and op-

timer to make the most of Java 8’s new features. For interoperability with Java and to enjoy the same benefits from JVM optimizations, Scala compiles functions to the same bytecode as the Java 8 compiler. Similarly, Scala traits now compile to Java interfaces with default methods. Both compilation schemes reduce the magic that older Scala compilers had to perform, aligning us more closely with the Java platform, while improving both compile-time and run-time performance, with a smoother binary compatibility story to boot!

These improvement to the Java 8 platform are very exciting for Scala, and it’s very rewarding to see Java align with the trend Scala has been setting for over a decade! There’s no doubt that Scala provides a much better functional programming experience, with immutability by default, a uniform treatment of expressions (there’s hardly a return statement in sight in this book), pattern matching, definition-site variance (Java’s use-site variance make function subtyping quite awkward), and so on! To be blunt, there’s more to functional programming than nice syntax for lambdas.

As stewards of the language, our goal is to develop the core language as much as to foster the ecosystem. Scala is successful because of the many excellent libraries, outstanding IDEs and tools, and the friendly and ever helpful members of our community. I’ve thoroughly enjoyed my first decade of Scala—as an implementer of the language, it’s such a thrill and inspiration to meet programmers having fun with Scala across so many domains.

I love programming in Scala, and I hope you will too. On behalf of the Scala community, welcome!

Adriaan Moors
San Francisco, CA
January 14, 2016

Acknowledgments

Many people have contributed to this book and to the material it covers. We are grateful to all of them.

Scala itself has been a collective effort of many people. The design and the implementation of version 1.0 was helped by Philippe Altherr, Vincent Crechet, Gilles Dubochet, Burak Emir, Stéphane Micheloud, Nikolay Mihaylov, Michel Schinz, Erik Stenman, and Matthias Zenger. Phil Bagwell, Antonio Cunei, Iulian Dragos, Gilles Dubochet, Miguel Garcia, Philipp Haller, Sean McDermid, Ingo Maier, Donna Malayeri, Adriaan Moors, Hubert Plociniczak, Paul Phillips, Aleksandar Prokopec, Tiark Rompf, Lukas Rytz, and Geoffrey Washburn joined in the effort to develop the second and current version of the language and tools.

Gilad Bracha, Nathan Bronson, Caoyuan, Aemon Cannon, Craig Chambers, Chris Conrad, Erik Ernst, Matthias Felleisen, Mark Harrah, Shriram Krishnamurti, Gary Leavens, David MacIver, Sebastian Maneth, Rickard Nilsson, Erik Meijer, Lalit Pant, David Pollak, Jon Pretty, Klaus Ostermann, Jorge Ortiz, Didier Rémy, Miles Sabin, Vijay Saraswat, Daniel Spiewak, James Strachan, Don Syme, Erik Torreborre, Mads Torgersen, Philip Wadler, Jamie Webb, John Williams, Kevin Wright, and Jason Zaugg have shaped the design of the language by graciously sharing their ideas with us in lively and inspiring discussions, by contributing important pieces of code to the open source effort, as well as through comments on previous versions of this document. The contributors to the Scala mailing list have also given very useful feedback that helped us improve the language and its tools.

George Berger has worked tremendously to make the build process and the web presence for the book work smoothly. As a result this project has been delightfully free of technical snafus.

Many people gave us valuable feedback on early versions of the text. Thanks goes to Eric Armstrong, George Berger, Alex Blewitt, Gilad Bracha,

William Cook, Bruce Eckel, Stéphane Micheloud, Todd Millstein, David Pollak, Frank Sommers, Philip Wadler, and Matthias Zenger. Thanks also to the Silicon Valley Patterns group for their very helpful review: Dave Astels, Tracy Bialik, John Brewer, Andrew Chase, Bradford Cross, Raoul Duke, John P. Eurich, Steven Ganz, Phil Goodwin, Ralph Jocham, Yan-Fa Li, Tao Ma, Jeffery Miller, Suresh Pai, Russ Rufer, Dave W. Smith, Scott Turnquest, Walter Vannini, Darlene Wallach, and Jonathan Andrew Wolter. And we'd like to thank Dewayne Johnson and Kim Leedy for their help with the cover art, and Frank Sommers for his work on the index.

We'd also like to extend a special thanks to all of our readers who contributed comments. Your comments were very helpful to us in shaping this into an even better book. We couldn't print the names of everyone who contributed comments, but here are the names of readers who submitted at least five comments during the eBook PrePrint™ stage by clicking on the Suggest link, sorted first by the highest total number of comments submitted, then alphabetically. Thanks goes to: David Biesack, Donn Stephan, Mats Henricson, Rob Dickens, Blair Zajac, Tony Sloane, Nigel Harrison, Javier Diaz Soto, William Heelan, Justin Forder, Gregor Purdy, Colin Perkins, Bjarte S. Karlsen, Ervin Varga, Eric Willigers, Mark Hayes, Martin Elwin, Calum MacLean, Jonathan Wolter, Les Pruszynski, Seth Tisue, Andrei Formiga, Dmitry Grigoriev, George Berger, Howard Lovatt, John P. Eurich, Marius Scurtescu, Jeff Ervin, Jamie Webb, Kurt Zoglmann, Dean Wampler, Nikolaj Lindberg, Peter McLain, Arkadiusz Stryjski, Shanky Surana, Craig Bordegon, Alexandre Patry, Filip Moens, Fred Janon, Jeff Heon, Boris Lorbeer, Jim Menard, Tim Azzopardi, Thomas Jung, Walter Chang, Jeroen Dijkmeijer, Casey Bowman, Martin Smith, Richard Dallaway, Antony Stubbs, Lars Westergren, Maarten Hazewinkel, Matt Russell, Remigiusz Michalowski, Andrew Tolopko, Curtis Stanford, Joshua Cough, Zemian Deng, Christopher Rodrigues Macias, Juan Miguel Garcia Lopez, Michel Schinz, Peter Moore, Randolph Kahle, Vladimir Kelman, Daniel Gronau, Dirk Detering, Hiroaki Nakamura, Ole Hougard, Bhaskar Maddala, David Bernard, Derek Mahar, George Kollias, Kristian Nordal, Normen Mueller, Rafael Ferreira, Binil Thomas, John Nilsson, Jorge Ortiz, Marcus Schulte, Vadim Gerassimov, Cameron Taggart, Jon-Anders Teigen, Silvestre Zabala, Will McQueen, and Sam Owen.

We would also like to thank those who submitted comments and errata after the first two editions were published, including Felix Siegrist, Lothar Meyer-Lerbs, Diethard Michaelis, Roshan Dawrani, Donn Stephan,

William Uther, Francisco Reverbel, Jim Balter, and Freek de Brujin, Ambrose Laing, Sekhar Prabhala, Levon Saldamli, Andrew Bursavich, Hjalmar Peters, Thomas Fehr, Alain O'Dea, Rob Dickens, Tim Taylor, Christian Sternagel, Michel Parisien, Joel Neely, Brian McKeon, Thomas Fehr, Joseph Elliott, Gabriel da Silva Ribeiro, Thomas Fehr, Pablo Ripolles, Douglas Gaylor, Kevin Squire, Harry-Anton Talvik, Christopher Simpkins, Martin Witmann-Funk, Jim Balter, Peter Foster, Craig Bordelon, Heinz-Peter Gumm, Peter Chapin, Kevin Wright, Ananthan Srinivasan, Omar Kilani, Donn Stephan, Guenther Waffler.

Lex would like to thank Aaron Abrams, Jason Adams, Henry and Emily Crutcher, Joey Gibson, Gunnar Hillert, Matthew Link, Toby Reyelts, Jason Snape, John and Melinda Weathers, and all of the Atlanta Scala Enthusiasts for many helpful discussions about the language design, its mathematical underpinnings, and how to present Scala to working engineers.

A special thanks to Dave Briccetti and Adriaan Moors for reviewing the third edition, and to Marconi Lanna for not only reviewing, but providing motivation for the third edition by giving a talk entitled “What’s new since *Programming in Scala*.”

Bill would like to thank Gary Cornell, Greg Doench, Andy Hunt, Mike Leonard, Tyler Ortman, Bill Pollock, Dave Thomas, and Adam Wright for providing insight and advice on book publishing. Bill would also like to thank Dick Wall for collaborating on Escalate’s *Stairway to Scala* course, which is in great part based on this book. Our many years of experience teaching *Stairway to Scala* has helped make this book better. Lastly, Bill would like to thank Darlene Gruendl and Samantha Woolf for their help in getting the third edition completed.

Introduction

This book is a tutorial for the Scala programming language, written by people directly involved in the development of Scala. Our goal is that by reading this book, you can learn everything you need to be a productive Scala programmer. All examples in this book compile with Scala version 2.11.7, except for those marked 2.12, which compile with 2.12.0-M3.

Who should read this book

The main target audience for this book is programmers who want to learn to program in Scala. If you want to do your next software project in Scala, then this is the book for you. In addition, the book should be interesting to programmers wishing to expand their horizons by learning new concepts. If you're a Java programmer, for example, reading this book will expose you to many concepts from functional programming as well as advanced object-oriented ideas. We believe learning about Scala, and the ideas behind it, can help you become a better programmer in general.

General programming knowledge is assumed. While Scala is a fine first programming language, this is not the book to use to learn programming.

On the other hand, no specific knowledge of programming languages is required. Even though most people use Scala on the Java platform, this book does not presume you know anything about Java. However, we expect many readers to be familiar with Java, and so we sometimes compare Scala to Java to help such readers understand the differences.

How to use this book

Because the main purpose of this book is to serve as a tutorial, the recommended way to read this book is in chapter order, from front to back. We

have tried hard to introduce one topic at a time, and explain new topics only in terms of topics we've already introduced. Thus, if you skip to the back to get an early peek at something, you may find it explained in terms of concepts you don't quite understand. To the extent you read the chapters in order, we think you'll find it quite straightforward to gain competency in Scala, one step at a time.

If you see a term you do not know, be sure to check the glossary and the index. Many readers will skim parts of the book, and that is just fine. The glossary and index can help you backtrack whenever you skim over something too quickly.

After you have read the book once, it should also serve as a language reference. There is a formal specification of the Scala language, but the language specification tries for precision at the expense of readability. Although this book doesn't cover every detail of Scala, it is quite comprehensive and should serve as an approachable language reference as you become more adept at programming in Scala.

How to learn Scala

You will learn a lot about Scala simply by reading this book from cover to cover. You can learn Scala faster and more thoroughly, though, if you do a few extra things.

First of all, you can take advantage of the many program examples included in the book. Typing them in yourself is a way to force your mind through each line of code. Trying variations is a way to make them more fun and to make sure you really understand how they work.

Second, keep in touch with the numerous online forums. That way, you and other Scala enthusiasts can help each other. There are numerous mailing lists, discussion forums, a chat room, a wiki, and multiple Scala-specific article feeds. Take some time to find ones that fit your information needs. You will spend a lot less time stuck on little problems, so you can spend your time on deeper, more important questions.

Finally, once you have read enough, take on a programming project of your own. Work on a small program from scratch or develop an add-in to a larger program. You can only go so far by reading.

EBook features

This book is available in both paper and PDF eBook form. The eBook is not simply an electronic copy of the paper version of the book. While the content is the same as in the paper version, the eBook has been carefully designed and optimized for reading on a computer screen.

The first thing to notice is that most references within the eBook are hyperlinked. If you select a reference to a chapter, figure, or glossary entry, your PDF viewer should take you immediately to the selected item so that you do not have to flip around to find it.

Additionally, at the bottom of each page in the eBook are a number of navigation links. The Cover, Overview, and Contents links take you to the front matter of the book. The Glossary and Index links take you to reference parts of the book. Finally, the Discuss link takes you to an online forum where you discuss questions with other readers, the authors, and the larger Scala community. If you find a typo, or something you think could be explained better, please click on the Suggest link, which will take you to an online web application where you can give the authors feedback.

Although the same pages appear in the eBook as in the printed book, blank pages are removed and the remaining pages renumbered. The pages are numbered differently so that it is easier for you to determine PDF page numbers when printing only a portion of the eBook. The pages in the eBook are, therefore, numbered exactly as your PDF viewer will number them.

Typographic conventions

The first time a *term* is used, it is italicized. Small code examples, such as `x + 1`, are written inline with a mono-spaced font. Larger code examples are put into mono-spaced quotation blocks like this:

```
def hello() = {
    println("Hello, world!")
}
```

When interactive shells are shown, responses from the shell are shown in a lighter font:

```
scala> 3 + 4
res0: Int = 7
```

Content overview

- [Chapter 1](#), “A Scalable Language,” gives an overview of Scala’s design as well as the reasoning, and history, behind it.
- [Chapter 2](#), “First Steps in Scala,” shows you how to do a number of basic programming tasks in Scala, without going into great detail about how they work. The goal of this chapter is to get your fingers started typing and running Scala code.
- [Chapter 3](#), “Next Steps in Scala,” shows you several more basic programming tasks that will help you get up to speed quickly in Scala. After completing this chapter, you should be able to start using Scala for simple scripting tasks.
- [Chapter 4](#), “Classes and Objects,” starts the in-depth coverage of Scala with a description of its basic object-oriented building blocks and instructions on how to compile and run a Scala application.
- [Chapter 5](#), “Basic Types and Operations,” covers Scala’s basic types, their literals, the operations you can perform on them, how precedence and associativity works, and what rich wrappers are.
- [Chapter 6](#), “Functional Objects,” dives more deeply into the object-oriented features of Scala, using functional (*i.e.*, immutable) rational numbers as an example.
- [Chapter 7](#), “Built-in Control Structures,” shows you how to use Scala’s built-in control structures: `if`, `while`, `for`, `try`, and `match`.
- [Chapter 8](#), “Functions and Closures,” provides in-depth coverage of functions, the basic building block of functional languages.
- [Chapter 9](#), “Control Abstraction,” shows how to augment Scala’s basic control structures by defining your own control abstractions.
- [Chapter 10](#), “Composition and Inheritance,” discusses more of Scala’s support for object-oriented programming. The topics are not as fundamental as those in Chapter 4, but they frequently arise in practice.
- [Chapter 11](#), “Scala’s Hierarchy,” explains Scala’s inheritance hierarchy and discusses its universal methods and bottom types.

- [Chapter 12](#), “Traits,” covers Scala’s mechanism for mixin composition. The chapter shows how traits work, describes common uses, and explains how traits improve on traditional multiple inheritance.
- [Chapter 13](#), “Packages and Imports,” discusses issues with programming in the large, including top-level packages, import statements, and access control modifiers like `protected` and `private`.
- [Chapter 14](#), “Assertions and Tests,” shows Scala’s assertion mechanism and gives a tour of several tools available for writing tests in Scala, focusing on `ScalaTest` in particular.
- [Chapter 15](#), “Case Classes and Pattern Matching,” introduces twin constructs that support you when writing regular, non-encapsulated data structures. Case classes and pattern matching are particularly helpful for tree-like recursive data.
- [Chapter 16](#), “Working with Lists,” explains in detail lists, which are probably the most commonly used data structure in Scala programs.
- [Chapter 17](#), “Working with Other Collections,” shows you how to use the basic Scala collections, such as lists, arrays, tuples, sets, and maps.
- [Chapter 18](#), “Mutable Objects,” explains mutable objects and the syntax Scala provides to express them. The chapter concludes with a case study on discrete event simulation, which shows some mutable objects in action.
- [Chapter 19](#), “Type Parameterization,” explains some of the techniques for information hiding introduced in Chapter 13 by means of a concrete example: the design of a class for purely functional queues. The chapter builds up to a description of variance of type parameters and how it interacts with information hiding.
- [Chapter 20](#), “Abstract Members,” describes all kinds of abstract members that Scala supports; not only methods, but also fields and types, can be declared abstract.
- [Chapter 21](#), “Implicit Conversions and Parameters,” covers two constructs that can help you omit tedious details from source code, letting the compiler supply them instead.

- [Chapter 22](#), “Implementing Lists,” describes the implementation of class `List`. It is important to understand how lists work in Scala, and furthermore the implementation demonstrates the use of several of Scala’s features.
- [Chapter 23](#), “For Expressions Revisited,” shows how for expressions are translated to invocations of `map`, `flatMap`, `filter`, and `foreach`.
- [Chapter 24](#), “Collections in Depth,” gives a detailed tour of the collections library.
- [Chapter 25](#), “The Architecture of Scala Collections,” shows how the collection library is built and how you can implement your own collections.
- [Chapter 26](#), “Extractors,” shows how to pattern match against arbitrary classes, not just case classes.
- [Chapter 27](#), “Annotations,” shows how to work with language extension via annotation. The chapter describes several standard annotations and shows you how to make your own.
- [Chapter 28](#), “Working with XML,” explains how to process XML in Scala. The chapter shows you idioms for generating XML, parsing it, and processing it once it is parsed.
- [Chapter 29](#), “Modular Programming Using Objects,” shows how you can use Scala’s objects as a modules system.
- [Chapter 30](#), “Object Equality,” points out several issues to consider when writing an `equals` method. There are several pitfalls to avoid.
- [Chapter 31](#), “Combining Scala and Java,” discusses issues that arise when combining Scala and Java together in the same project, and suggests ways to deal with them.
- [Chapter 32](#), “Futures and Concurrency,” shows you how to use Scala’s `Future`. Although you can use the Java platform’s concurrency primitives and libraries for Scala programs, futures can help you avoid the deadlocks and race conditions that plague the traditional “threads and locks” approach to concurrency.

- Chapter 33, “Combinator Parsing,” shows how to build parsers using Scala’s library of parser combinators.
- Chapter 34, “GUI Programming,” gives a quick tour of a Scala library that simplifies GUI programming with Swing.
- Chapter 35, “The SCells Spreadsheet,” ties everything together by showing a complete spreadsheet application written in Scala.

Resources

At <http://www.scala-lang.org>, the main website for Scala, you’ll find the latest Scala release and links to documentation and community resources. For a more condensed page of links to Scala resources, visit this book’s website: http://booksites.artima.com/programming_in_scala_3ed. To interact with other readers of this book, check out the Programming in Scala Forum, at: <http://www.artima.com/forums/forum.jsp?forum=282>.

Source code

You can download a ZIP file containing the source code of this book, which is released under the Apache 2.0 open source license, from the book’s website: http://booksites.artima.com/programming_in_scala_3ed.

Errata

Although this book has been heavily reviewed and checked, errors will inevitably slip through. For a (hopefully short) list of errata for this book, visit http://booksites.artima.com/programming_in_scala_3ed/errata. If you find an error, please report it at the above URL, so that we can fix it in a future printing or edition of this book.

Programming in Scala

Third Edition

```
println("Hello, reader!")
```

Chapter 1

A Scalable Language

The name Scala stands for “scalable language.” The language is so named because it was designed to grow with the demands of its users. You can apply Scala to a wide range of programming tasks, from writing small scripts to building large systems.¹

Scala is easy to get into. It runs on the standard Java platform and interoperates seamlessly with all Java libraries. It’s quite a good language for writing scripts that pull together Java components. But it can apply its strengths even more when used for building large systems and frameworks of reusable components.

Technically, Scala is a blend of object-oriented and functional programming concepts in a statically typed language. The fusion of object-oriented and functional programming shows up in many different aspects of Scala; it is probably more pervasive than in any other widely used language. The two programming styles have complementary strengths when it comes to scalability. Scala’s functional programming constructs make it easy to build interesting things quickly from simple parts. Its object-oriented constructs make it easy to structure larger systems and adapt them to new demands. The combination of both styles in Scala makes it possible to express new kinds of programming patterns and component abstractions. It also leads to a legible and concise programming style. And because it is so malleable, programming in Scala can be a lot of fun.

This initial chapter answers the question, “Why Scala?” It gives a high-level view of Scala’s design and the reasoning behind it. After reading the chapter you should have a basic feel for what Scala is and what kinds of

¹Scala is pronounced *skah-lah*.

tasks it might help you accomplish. Although this book is a Scala tutorial, this chapter isn't really part of the tutorial. If you're eager to start writing some Scala code, you should jump ahead to [Chapter 2](#).

1.1 A language that grows on you

Programs of different sizes tend to require different programming constructs. Consider, for example, the following small Scala program:

```
var capital = Map("US" -> "Washington", "France" -> "Paris")
capital += ("Japan" -> "Tokyo")
println(capital("France"))
```

This program sets up a map from countries to their capitals, modifies the map by adding a new binding ("Japan" -> "Tokyo"), and prints the capital associated with the country France.² The notation in this example is high level, to the point, and not cluttered with extraneous semicolons or type annotations. Indeed, the feel is that of a modern “scripting” language like Perl, Python, or Ruby. One common characteristic of these languages, which is relevant for the example above, is that they each support an “associative map” construct in the syntax of the language.

Associative maps are very useful because they help keep programs legible and concise, but sometimes you might not agree with their “one size fits all” philosophy because you need to control the properties of the maps you use in your program in a more fine-grained way. Scala gives you this fine-grained control if you need it, because maps in Scala are not language syntax. They are library abstractions that you can extend and adapt.

In the above program, you'll get a default Map implementation, but you can easily change that. You could for example specify a particular implementation, such as a HashMap or a TreeMap, or invoke the par method to obtain a ParMap that executes operations in parallel. You could specify a default value for the map, or you could override any other method of the map you create. In each case, you can use the same easy access syntax for maps as in the example above.

²Please bear with us if you don't understand all the details of this program. They will be explained in the next two chapters.

This example shows that Scala can give you both convenience and flexibility. Scala has a set of convenient constructs that help you get started quickly and let you program in a pleasantly concise style. At the same time, you have the assurance that you will not outgrow the language. You can always tailor the program to your requirements, because everything is based on library modules that you can select and adapt as needed.

Growing new types

Eric Raymond introduced the cathedral and bazaar as two metaphors of software development.³ The cathedral is a near-perfect building that takes a long time to build. Once built, it stays unchanged for a long time. The bazaar, by contrast, is adapted and extended each day by the people working in it. In Raymond's work the bazaar is a metaphor for open-source software development. Guy Steele noted in a talk on “growing a language” that the same distinction can be applied to language design.⁴ Scala is much more like a bazaar than a cathedral, in the sense that it is designed to be extended and adapted by the people programming in it. Instead of providing all constructs you might ever need in one “perfectly complete” language, Scala puts the tools for building such constructs into your hands.

Here's an example. Many applications need a type of integer that can become arbitrarily large without overflow or “wrap-around” of arithmetic operations. Scala defines such a type in library class `scala.BigInt`. Here is the definition of a method using that type, which calculates the factorial of a passed integer value:⁵

```
def factorial(x: BigInt): BigInt =  
  if (x == 0) 1 else x * factorial(x - 1)
```

Now, if you call `factorial(30)` you would get:

265252859812191058636308480000000

`BigInt` looks like a built-in type because you can use integer literals and operators such as `*` and `-` with values of that type. Yet it is just a class that

³Raymond, *The Cathedral and the Bazaar*. [Ray99]

⁴Steele, “Growing a language.” [Ste99]

⁵`factorial(x)`, or $x!$ in mathematical notation, is the result of computing $1 * 2 * \dots * x$, with $0!$ defined to be 1.

happens to be defined in Scala’s standard library.⁶ If the class were missing, it would be straightforward for any Scala programmer to write an implementation, for instance, by wrapping Java’s class `java.math.BigInteger` (in fact that’s how Scala’s `BigInt` class is implemented).

Of course, you could also use Java’s class directly. But the result is not nearly as pleasant, because although Java allows you to create new types, those types don’t feel much like native language support:

```
import java.math.BigInteger

def factorial(x: BigInteger): BigInteger =
  if (x == BigInteger.ZERO)
    BigInteger.ONE
  else
    x.multiply(factorial(x.subtract(BigInteger.ONE)))
```

`BigInt` is representative of many other number-like types—big decimals, complex numbers, rational numbers, confidence intervals, polynomials—the list goes on. Some programming languages implement some of these types natively. For instance, Lisp, Haskell, and Python implement big integers; Fortran and Python implement complex numbers. But any language that attempted to implement all of these abstractions at the same time would simply become too big to be manageable. What’s more, even if such a language were to exist, some applications would surely benefit from other number-like types that were not supplied. So the approach of attempting to provide everything in one language doesn’t scale very well. Instead, Scala allows users to grow and adapt the language in the directions they need by defining easy-to-use libraries that *feel* like native language support.

Growing new control constructs

The previous example demonstrates that Scala lets you add new types that can be used as conveniently as built-in types. The same extension principle also applies to control structures. This kind of extensibility is illustrated by Akka, a Scala API for “actor-based” concurrent programming.

⁶Scala comes with a standard library, some of which will be covered in this book. For more information, you can also consult the library’s Scaladoc documentation, which is available in the distribution and online at <http://www.scala-lang.org>.

As multicore processors continue to proliferate in the coming years, achieving acceptable performance may increasingly require that you exploit more parallelism in your applications. Often, this will mean rewriting your code so that computations are distributed over several concurrent threads. Unfortunately, creating dependable multi-threaded applications has proven challenging in practice. Java’s threading model is built around shared memory and locking, a model that is often difficult to reason about, especially as systems scale up in size and complexity. It is hard to be sure you don’t have a race condition or deadlock lurking—something that didn’t show up during testing, but might just show up in production. An arguably safer alternative is a message passing architecture, such as the “actors” approach used by the Erlang programming language.

Java comes with a rich, thread-based concurrency library. Scala programs can use it like any other Java API. However, Akka is an additional Scala library that implements an actor model similar to Erlang’s.

Actors are concurrency abstractions that can be implemented on top of threads. They communicate by sending messages to each other. An actor can perform two basic operations, message send and receive. The send operation, denoted by an exclamation point (!), sends a message to an actor. Here’s an example in which the actor is named `recipient`:

```
recipient ! msg
```

A send is asynchronous; that is, the sending actor can proceed immediately, without waiting for the message to be received and processed. Every actor has a *mailbox* in which incoming messages are queued. An actor handles messages that have arrived in its mailbox via a `receive` block:

```
def receive = {
    case Msg1 => ... // handle Msg1
    case Msg2 => ... // handle Msg2
    ...
}
```

A `receive` block consists of a number of cases that each query the mailbox with a message pattern. The first message in the mailbox that matches any of the cases is selected, and the corresponding action is performed on it. Once the mailbox does not contain any messages, the actor suspends and waits for further incoming messages.

As an example, here is a simple Akka actor implementing a checksum calculator service:

```
class ChecksumActor extends Actor {  
    var sum = 0  
    def receive = {  
        case Data(byte) => sum += byte  
        case GetChecksum(requester) =>  
            val checksum = ~(sum & 0xFF) + 1  
            requester ! checksum  
    }  
}
```

This actor first defines a local variable named `sum` with initial value zero. It defines a `receive` block that will handle messages. If it receives a `Data` message, it adds the contained `byte` to the `sum` variable. If it receives a `GetChecksum` message, it calculates a checksum from the current value of `sum` and sends the result back to the `requester` using the message send `requester ! sum`. The `requester` field is embedded in the `GetChecksum` message; it usually refers to the actor that made the request.

We don't expect you to fully understand the actor example at this point. Rather, what's significant about this example for the topic of scalability is that neither the `receive` block nor message send (!) are built-in operations in Scala. Even though the `receive` block may look and act very much like a built-in control construct, it is in fact a method defined in Akka's actors library. Likewise, even though '!' looks like a built-in operator, it too is just a method defined in the Akka actors library. Both of these constructs are completely independent of the Scala programming language.

The `receive` block and send (!) syntax look in Scala much like they look in Erlang, but in Erlang, these constructs are built into the language. Akka also implements most of Erlang's other concurrent programming constructs, such as monitoring failed actors and time-outs. All in all, the actor model has turned out to be a very pleasant means for expressing concurrent and distributed computations. Even though they must be defined in a library, actors can feel like an integral part of the Scala language.

This example illustrates that you can "grow" the Scala language in new directions even as specialized as concurrent programming. To be sure, you need good architects and programmers to do this. But the crucial thing is

that it is feasible—you can design and implement abstractions in Scala that address radically new application domains, yet still feel like native language support when used.

1.2 What makes Scala scalable?

Scalability is influenced by many factors, ranging from syntax details to component abstraction constructs. If we were forced to name just one aspect of Scala that helps scalability, though, we'd pick its combination of object-oriented and functional programming (well, we cheated, that's really two aspects, but they are intertwined).

Scala goes further than all other well-known languages in fusing object-oriented and functional programming into a uniform language design. For instance, where other languages might have objects and functions as two different concepts, in Scala a function value *is* an object. Function types are classes that can be inherited by subclasses. This might seem nothing more than an academic nicety, but it has deep consequences for scalability. In fact the actor concept shown previously could not have been implemented without this unification of functions and objects. This section gives an overview of Scala's way of blending object-oriented and functional concepts.

Scala is object-oriented

Object-oriented programming has been immensely successful. Starting from Simula in the mid-60s and Smalltalk in the 70s, it is now available in more languages than not. In some domains, objects have taken over completely. While there is not a precise definition of what object-oriented means, there is clearly something about objects that appeals to programmers.

In principle, the motivation for object-oriented programming is very simple: all but the most trivial programs need some sort of structure. The most straightforward way to do this is to put data and operations into some form of containers. The great idea of object-oriented programming is to make these containers fully general, so that they can contain operations as well as data, and that they are themselves values that can be stored in other containers, or passed as parameters to operations. Such containers are called objects. Alan Kay, the inventor of Smalltalk, remarked that in this way the simplest object has the same construction principle as a full computer: it combines data with

operations under a formalized interface.⁷ So objects have a lot to do with language scalability: the same techniques apply to the construction of small as well as large programs.

Even though object-oriented programming has been mainstream for a long time, there are relatively few languages that have followed Smalltalk in pushing this construction principle to its logical conclusion. For instance, many languages admit values that are not objects, such as the primitive values in Java. Or they allow static fields and methods that are not members of any object. These deviations from the pure idea of object-oriented programming look quite harmless at first, but they have an annoying tendency to complicate things and limit scalability.

By contrast, Scala is an object-oriented language in pure form: every value is an object and every operation is a method call. For example, when you say `1 + 2` in Scala, you are actually invoking a method named `+` defined in class `Int`. You can define methods with operator-like names that clients of your API can then use in operator notation. This is how the designer of Akka’s actors API enabled you to use expressions such as `requester ! sum` shown in the previous example: ‘`!`’ is a method of the `Actor` class.

Scala is more advanced than most other languages when it comes to composing objects. An example is Scala’s *traits*. Traits are like interfaces in Java, but they can also have method implementations and even fields.⁸ Objects are constructed by *mixin composition*, which takes the members of a class and adds the members of a number of traits to them. In this way, different aspects of classes can be encapsulated in different traits. This looks a bit like multiple inheritance, but differs when it comes to the details. Unlike a class, a trait can add some new functionality to an unspecified superclass. This makes traits more “pluggable” than classes. In particular, it avoids the classical “diamond inheritance” problems of multiple inheritance, which arise when the same class is inherited via several different paths.

Scala is functional

In addition to being a pure object-oriented language, Scala is also a full-blown functional language. The ideas of functional programming are older than (electronic) computers. Their foundation was laid in Alonzo Church’s

⁷Kay, “The Early History of Smalltalk.” [Kay96]

⁸Starting with Java 8, interfaces can have default method implementations, but these do not offer all the features of Scala’s traits.

lambda calculus, which he developed in the 1930s. The first functional programming language was Lisp, which dates from the late 50s. Other popular functional languages are Scheme, SML, Erlang, Haskell, OCaml, and F#. For a long time, functional programming has been a bit on the sidelines—popular in academia, but not that widely used in industry. However, in recent years, there has been an increased interest in functional programming languages and techniques.

Functional programming is guided by two main ideas. The first idea is that functions are first-class values. In a functional language, a function is a value of the same status as, say, an integer or a string. You can pass functions as arguments to other functions, return them as results from functions, or store them in variables. You can also define a function inside another function, just as you can define an integer value inside a function. And you can define functions without giving them a name, sprinkling your code with function literals as easily as you might write integer literals like 42.

Functions that are first-class values provide a convenient means for abstracting over operations and creating new control structures. This generalization of functions provides great expressiveness, which often leads to very legible and concise programs. It also plays an important role for scalability. As an example, the ScalaTest testing library offers an `eventually` construct that takes a function as an argument. It is used like this:

```
val xs = 1 to 3
val it = xs.iterator
eventually { it.next() shouldBe 3 }
```

The code inside `eventually`—the assertion, `it.next() shouldBe 3`—is wrapped in a function that is passed unexecuted to the `eventually` method. For a configured amount of time, `eventually` will repeatedly execute the function until the assertion succeeds.

In most traditional languages, by contrast, functions are not values. Languages that do have function values often relegate them to second-class status. For example, the function pointers of C and C++ do not have the same status as non-functional values in those languages: Function pointers can only refer to global functions, they do not allow you to define first-class nested functions that refer to some values in their environment. Nor do they allow you to define unnamed function literals.

The second main idea of functional programming is that the operations of a program should map input values to output values rather than change

data in place. To see the difference, consider the implementation of strings in Ruby and Java. In Ruby, a string is an array of characters. Characters in a string can be changed individually. For instance you can change a semicolon character in a string to a period inside the same string object. In Java and Scala, on the other hand, a string is a sequence of characters in the mathematical sense. Replacing a character in a string using an expression like `s.replace(';', '.')` yields a new string object, which is different from `s`. Another way of expressing this is that strings are immutable in Java whereas they are mutable in Ruby. So looking at just strings, Java is a functional language, whereas Ruby is not. Immutable data structures are one of the cornerstones of functional programming. The Scala libraries define many more immutable data types on top of those found in the Java APIs. For instance, Scala has immutable lists, tuples, maps, and sets.

Another way of stating this second idea of functional programming is that methods should not have any *side effects*. They should communicate with their environment only by taking arguments and returning results. For instance, the `replace` method in Java's `String` class fits this description. It takes a string and two characters and yields a new string where all occurrences of one character are replaced by the other. There is no other effect of calling `replace`. Methods like `replace` are called *referentially transparent*, which means that for any given input the method call could be replaced by its result without affecting the program's semantics.

Functional languages encourage immutable data structures and referentially transparent methods. Some functional languages even require them. Scala gives you a choice. When you want to, you can write in an *imperative* style, which is what programming with mutable data and side effects is called. But Scala generally makes it easy to avoid imperative constructs when you want because good functional alternatives exist.

1.3 Why Scala?

Is Scala for you? You will have to see and decide for yourself. We have found that there are actually many reasons besides scalability to like programming in Scala. Four of the most important aspects will be discussed in this section: compatibility, brevity, high-level abstractions, and advanced static typing.

Scala is compatible

Scala doesn't require you to leap backwards off the Java platform to step forward from the Java language. It allows you to add value to existing code—to build on what you already have—because it was designed for seamless interoperability with Java.⁹ Scala programs compile to JVM bytecodes. Their run-time performance is usually on par with Java programs. Scala code can call Java methods, access Java fields, inherit from Java classes, and implement Java interfaces. None of this requires special syntax, explicit interface descriptions, or glue code. In fact, almost all Scala code makes heavy use of Java libraries, often without programmers being aware of this fact.

Another aspect of full interoperability is that Scala heavily re-uses Java types. Scala's Ints are represented as Java primitive integers of type `int`, Floats are represented as `floats`, Booleans as `booleans`, and so on. Scala arrays are mapped to Java arrays. Scala also re-uses many of the standard Java library types. For instance, the type of a string literal "abc" in Scala is `java.lang.String`, and a thrown exception must be a subclass of `java.lang.Throwable`.

Scala not only re-uses Java's types, but also “dresses them up” to make them nicer. For instance, Scala's strings support methods like `toInt` or `toFloat`, which convert the string to an integer or floating-point number. So you can write `str.toInt` instead of `Integer.parseInt(str)`. How can this be achieved without breaking interoperability? Java's `String` class certainly has no `toInt` method! In fact, Scala has a very general solution to solve this tension between advanced library design and interoperability. Scala lets you define *implicit conversions*, which are always applied when types would not normally match up, or when non-existing members are selected. In the case above, when looking for a `toInt` method on a string, the Scala compiler will find no such member of class `String`, but it will find an implicit conversion that converts a Java `String` to an instance of the Scala class `StringOps`, which does define such a member. The conversion will then be applied implicitly before performing the `toInt` operation.

Scala code can also be invoked from Java code. This is sometimes a bit more subtle, because Scala is a richer language than Java, so some of Scala's

⁹Originally, there was an implementation of Scala that ran on the .NET platform, but it is no longer active. More recently, an implementation of Scala that runs on JavaScript, `Scala.js`, has become increasingly popular.

more advanced features need to be encoded before they can be mapped to Java. [Chapter 31](#) explains the details.

Scala is concise

Scala programs tend to be short. Scala programmers have reported reductions in number of lines of up to a factor of ten compared to Java. These might be extreme cases. A more conservative estimate would be that a typical Scala program should have about half the number of lines of the same program written in Java. Fewer lines of code mean not only less typing, but also less effort at reading and understanding programs and fewer possibilities of defects. There are several factors that contribute to this reduction in lines of code.

First, Scala's syntax avoids some of the boilerplate that burdens Java programs. For instance, semicolons are optional in Scala and are usually left out. There are also several other areas where Scala's syntax is less noisy. As an example, compare how you write classes and constructors in Java and Scala. In Java, a class with a constructor often looks like this:

```
// this is Java
class MyClass {
    private int index;
    private String name;
    public MyClass(int index, String name) {
        this.index = index;
        this.name = name;
    }
}
```

In Scala, you would likely write this instead:

```
class MyClass(index: Int, name: String)
```

Given this code, the Scala compiler will produce a class that has two private instance variables, an `Int` named `index` and a `String` named `name`, and a constructor that takes initial values for those variables as parameters. The code of this constructor will initialize the two instance variables with the

values passed as parameters. In short, you get essentially the same functionality as the more verbose Java version.¹⁰ The Scala class is quicker to write, easier to read, and most importantly, less error prone than the Java class.

Scala's type inference is another factor that contributes to its conciseness. Repetitive type information can be left out, so programs become less cluttered and more readable.

But probably the most important key to compact code is code you don't have to write because it is done in a library for you. Scala gives you many tools to define powerful libraries that let you capture and factor out common behavior. For instance, different aspects of library classes can be separated out into traits, which can then be mixed together in flexible ways. Or, library methods can be parameterized with operations, which lets you define constructs that are, in effect, your own control structures. Together, these constructs allow the definition of libraries that are both high-level and flexible to use.

Scala is high-level

Programmers are constantly grappling with complexity. To program productively, you must understand the code on which you are working. Overly complex code has been the downfall of many a software project. Unfortunately, important software usually has complex requirements. Such complexity can't be avoided; it must instead be managed.

Scala helps you manage complexity by letting you raise the level of abstraction in the interfaces you design and use. As an example, imagine you have a `String` variable `name`, and you want to find out whether or not that `String` contains an upper case character. Prior to Java 8, you might have written a loop, like this:

```
boolean nameHasUpperCase = false; // this is Java
for (int i = 0; i < name.length(); ++i) {
    if (Character.isUpperCase(name.charAt(i))) {
        nameHasUpperCase = true;
        break;
    }
}
```

¹⁰The only real difference is that the instance variables produced in the Scala case will be final. You'll learn how to make them non-final in [Section 10.6](#).

Whereas in Scala, you could write this:

```
val nameHasUpperCase = name.exists(_.isUpper)
```

The Java code treats strings as low-level entities that are stepped through character by character in a loop. The Scala code treats the same strings as higher-level sequences of characters that can be queried with *predicates*. Clearly the Scala code is much shorter and—for trained eyes—easier to understand than the Java code. So the Scala code weighs less heavily on the total complexity budget. It also gives you less opportunity to make mistakes.

The predicate `_.isUpper` is an example of a function literal in Scala.¹¹ It describes a function that takes a character argument (represented by the underscore character) and tests whether it is an upper case letter.¹²

Java 8 introduced support for *lambdas* and *streams*, which enable you to perform a similar operation in Java. Here’s what it might look like:

```
boolean nameHasUpperCase =    // This is Java 8
    name.chars().anyMatch(
        (int ch) -> Character.isUpperCase((char) ch)
    );
```

Although a great improvement over earlier versions of Java, the Java 8 code is still more verbose than the equivalent Scala code. This extra “heaviness” of Java code, as well as Java’s long tradition of loops, may encourage many Java programmers in need of new methods like `exists` to just write out loops and live with the increased complexity in their code.

On the other hand, function literals in Scala are really lightweight, so they are used frequently. As you get to know Scala better you’ll find more and more opportunities to define and use your own control abstractions. You’ll find that this helps avoid code duplication and thus keeps your programs shorter and clearer.

Scala is statically typed

A static type system classifies variables and expressions according to the kinds of values they hold and compute. Scala stands out as a language with a very advanced static type system. Starting from a system of nested class

¹¹A function literal can be called a *predicate* if its result type is Boolean.

¹²This use of the underscore as a placeholder for arguments is described in [Section 8.5](#).

types much like Java’s, it allows you to parameterize types with *generics*, to combine types using *intersections*, and to hide details of types using *abstract types*.¹³ These give a strong foundation for building and composing your own types, so that you can design interfaces that are at the same time safe and flexible to use.

If you like dynamic languages, such as Perl, Python, Ruby, or Groovy, you might find it a bit strange that Scala’s static type system is listed as one of its strong points. After all, the absence of a static type system has been cited by some as a major advantage of dynamic languages. The most common arguments against static types are that they make programs too verbose, prevent programmers from expressing themselves as they wish, and make impossible certain patterns of dynamic modifications of software systems. However, often these arguments do not go against the idea of static types in general, but against specific type systems, which are perceived to be too verbose or too inflexible. For instance, Alan Kay, the inventor of the Smalltalk language, once remarked: “I’m not against types, but I don’t know of any type systems that aren’t a complete pain, so I still like dynamic typing.”¹⁴

We hope to convince you in this book that Scala’s type system is far from being a “complete pain.” In fact, it addresses nicely two of the usual concerns about static typing: Verbosity is avoided through type inference, and flexibility is gained through pattern matching and several new ways to write and compose types. With these impediments out of the way, the classical benefits of static type systems can be better appreciated. Among the most important of these benefits are verifiable properties of program abstractions, safe refactorings, and better documentation.

Verifiable properties. Static type systems can prove the absence of certain run-time errors. For instance, they can prove properties like: Booleans are never added to integers; private variables are not accessed from outside their class; functions are applied to the right number of arguments; only strings are ever added to a set of strings.

Other kinds of errors are not detected by today’s static type systems. For instance, they will usually not detect non-terminating functions, array bounds violations, or divisions by zero. They will also not detect that your

¹³Generics are discussed in Chapter 19; intersections (e.g., A with B with C) in Chapter 12; and abstract types in Chapter 20.

¹⁴Kay, in an email on the meaning of object-oriented programming. [Kay03]

program does not conform to its specification (assuming there is a spec, that is!). Static type systems have therefore been dismissed by some as not being very useful. The argument goes that since such type systems can only detect simple errors, whereas unit tests provide more extensive coverage, why bother with static types at all? We believe that these arguments miss the point. Although a static type system certainly cannot *replace* unit testing, it can reduce the number of unit tests needed by taking care of some properties that would otherwise need to be tested. Likewise, unit testing cannot replace static typing. After all, as Edsger Dijkstra said, testing can only prove the presence of errors, never their absence.¹⁵ So the guarantees that static typing gives may be simple, but they are real guarantees of a form no amount of testing can deliver.

Safe refactorings. A static type system provides a safety net that lets you make changes to a codebase with a high degree of confidence. Consider for instance a refactoring that adds an additional parameter to a method. In a statically typed language you can do the change, re-compile your system, and simply fix all lines that cause a type error. Once you have finished with this, you are sure to have found all places that need to be changed. The same holds for many other simple refactorings, like changing a method name or moving methods from one class to another. In all cases a static type check will provide enough assurance that the new system works just like the old.

Documentation. Static types are program documentation that is checked by the compiler for correctness. Unlike a normal comment, a type annotation can never be out of date (at least not if the source file that contains it has recently passed a compiler). Furthermore, compilers and integrated development environments (IDEs) can make use of type annotations to provide better context help. For instance, an IDE can display all the members available for a selection by determining the static type of the expression on which the selection is made and looking up all members of that type.

Even though static types are generally useful for program documentation, they can sometimes be annoying when they clutter the program. Typically, useful documentation is what readers of a program cannot easily derive by themselves. In a method definition like:

¹⁵Dijkstra, “Notes on Structured Programming.” [Dij70]

```
def f(x: String) = ...
```

it's useful to know that `f`'s argument should be a `String`. On the other hand, at least one of the two annotations in the following example is annoying:

```
val x: HashMap[Int, String] = new HashMap[Int, String]()
```

Clearly, it should be enough to say just once that `x` is a `HashMap` with `Ints` as keys and `Strings` as values; there's no need to repeat the same phrase twice.

Scala has a very sophisticated type inference system that lets you omit almost all type information that's usually considered annoying. In the previous example, the following two less annoying alternatives would work just as well:

```
val x = new HashMap[Int, String]()
val x: Map[Int, String] = new HashMap()
```

Type inference in Scala can go quite far. In fact, it's not uncommon for user code to have no explicit types at all. Therefore, Scala programs often look a bit like programs written in a dynamically typed scripting language. This holds particularly for client application code, which glues together pre-written library components. It's less true for the library components themselves, because these often employ fairly sophisticated types to allow flexible usage patterns. This is only natural. After all, the type signatures of the members that make up the interface of a reusable component should be explicitly given, because they constitute an essential part of the contract between the component and its clients.

1.4 Scala's roots

Scala's design has been influenced by many programming languages and ideas in programming language research. In fact, only a few features of Scala are genuinely new; most have been already applied in some form in other languages. Scala's innovations come primarily from how its constructs are put together. In this section, we list the main influences on Scala's design. The list cannot be exhaustive—there are simply too many smart ideas around in programming language design to enumerate them all here.

At the surface level, Scala adopts a large part of the syntax of Java and C#, which in turn borrowed most of their syntactic conventions from C and

C++. Expressions, statements, and blocks are mostly as in Java, as is the syntax of classes, packages and imports.¹⁶ Besides syntax, Scala adopts other elements of Java, such as its basic types, its class libraries, and its execution model.

Scala also owes much to other languages. Its uniform object model was pioneered by Smalltalk and taken up subsequently by Ruby. Its idea of universal nesting (almost every construct in Scala can be nested inside any other construct) is also present in Algol, Simula, and, more recently, in Beta and gbeta. Its uniform access principle for method invocation and field selection comes from Eiffel. Its approach to functional programming is quite similar in spirit to the ML family of languages, which has SML, OCaml, and F# as prominent members. Many higher-order functions in Scala's standard library are also present in ML or Haskell. Scala's implicit parameters were motivated by Haskell's type classes; they achieve analogous results in a more classical object-oriented setting. Scala's main actor-based concurrency library, Akka, was heavily inspired by Erlang.

Scala is not the first language to emphasize scalability and extensibility. The historic root of extensible languages that can span different application areas is Peter Landin's 1966 paper, "The Next 700 Programming Languages."¹⁷ (The language described in this paper, Iswim, stands beside Lisp as one of the pioneering functional languages.) The specific idea of treating an infix operator as a function can be traced back to Iswim and Smalltalk. Another important idea is to permit a function literal (or block) as a parameter, which enables libraries to define control structures. Again, this goes back to Iswim and Smalltalk. Smalltalk and Lisp both have a flexible syntax that has been applied extensively for building internal domain-specific languages. C++ is another scalable language that can be adapted and extended through operator overloading and its template system; compared to Scala it is built on a lower-level, more systems-oriented core.

¹⁶ The major deviation from Java concerns the syntax for type annotations: it's "variable: Type" instead of "Type variable" in Java. Scala's postfix type syntax resembles Pascal, Modula-2, or Eiffel. The main reason for this deviation has to do with type inference, which often lets you omit the type of a variable or the return type of a method. Using the "variable: Type" syntax is easy—just leave out the colon and the type. But in C-style "Type variable" syntax you cannot simply leave off the type; there would be no marker to start the definition anymore. You'd need some alternative keyword to be a placeholder for a missing type (C# 3.0, which does some type inference, uses var for this purpose). Such an alternative keyword feels more ad-hoc and less regular than Scala's approach.

¹⁷Landin, "The Next 700 Programming Languages." [Lan66]

Scala is also not the first language to integrate functional and object-oriented programming, although it probably goes furthest in this direction. Other languages that have integrated some elements of functional programming into object-oriented programming (OOP) include Ruby, Smalltalk, and Python. On the Java platform, Pizza, Nice, Multi-Java—and Java 8 itself—have all extended a Java-like core with functional ideas. There are also primarily functional languages that have acquired an object system; examples are OCaml, F#, and PLT-Scheme.

Scala has also contributed some innovations to the field of programming languages. For instance, its abstract types provide a more object-oriented alternative to generic types, its traits allow for flexible component assembly, and its extractors provide a representation-independent way to do pattern matching. These innovations have been presented in papers at programming language conferences in recent years.¹⁸

1.5 Conclusion

In this chapter, we gave you a glimpse of what Scala is and how it might help you in your programming. To be sure, Scala is not a silver bullet that will magically make you more productive. To advance, you will need to apply Scala artfully, and that will require some learning and practice. If you’re coming to Scala from Java, the most challenging aspects of learning Scala may involve Scala’s type system (which is richer than Java’s) and its support for functional programming. The goal of this book is to guide you gently up Scala’s learning curve, one step at a time. We think you’ll find it a rewarding intellectual experience that will expand your horizons and make you think differently about program design. Hopefully, you will also gain pleasure and inspiration from programming in Scala.

In the next chapter, we’ll get you started writing some Scala code.

¹⁸For more information, see [[Ode03](#)], [[Ode05](#)], and [[Emi07](#)] in the bibliography.

Chapter 2

First Steps in Scala

It's time to write some Scala code. Before we start on the in-depth Scala tutorial, we put in two chapters that will give you the big picture of Scala, and most importantly, get you writing code. We encourage you to actually try out all the code examples presented in this chapter and the next as you go. The best way to start learning Scala is to program in it.

To run the examples in this chapter, you should have a standard Scala installation. To get one, go to <http://www.scala-lang.org/downloads> and follow the directions for your platform. You can also use a Scala plug-in for Eclipse, IntelliJ, or NetBeans. For the steps in this chapter, we'll assume you're using the Scala distribution from scala-lang.org.¹

If you are a veteran programmer new to Scala, the next two chapters should give you enough understanding to enable you to start writing useful programs in Scala. If you are less experienced, some of the material may seem a bit mysterious to you. But don't worry. To get you up to speed quickly, we had to leave out some details. Everything will be explained in a less "fire hose" fashion in later chapters. In addition, we inserted quite a few footnotes in these next two chapters to point you to later sections of the book where you'll find more detailed explanations.

Step 1. Learn to use the Scala interpreter

The easiest way to get started with Scala is by using the Scala interpreter, an interactive "shell" for writing Scala expressions and programs. The inter-

¹We tested the examples in this book with Scala version 2.11.7.

preter, which is called `scala`, will evaluate expressions you type and print the resulting value. You use it by typing `scala` at a command prompt:²

```
$ scala  
Welcome to Scala version 2.11.7  
Type in expressions to have them evaluated.  
Type :help for more information.  
scala>
```

After you type an expression, such as `1 + 2`, and hit enter:

```
scala> 1 + 2
```

The interpreter will print:

```
res0: Int = 3
```

This line includes:

- an automatically generated or user-defined name to refer to the computed value (`res0`, which means result 0),
- a colon (:), followed by the type of the expression (`Int`),
- an equals sign (=),
- the value resulting from evaluating the expression (3).

The type `Int` names the class `Int` in the package `scala`. Packages in Scala are similar to packages in Java: They partition the global namespace and provide a mechanism for information hiding.³ Values of class `Int` correspond to Java's `int` values. More generally, all of Java's primitive types have corresponding classes in the `scala` package. For example, `scala.Boolean` corresponds to Java's `boolean`. `scala.Float` corresponds to Java's `float`. And when you compile your Scala code to Java bytecodes, the Scala compiler will use Java's primitive types where possible to give you the performance benefits of the primitive types.

²If you're using Windows, you'll need to type the `scala` command into the "Command Prompt" DOS box.

³If you're not familiar with Java packages, you can think of them as providing a full name for classes. Because `Int` is a member of package `scala`, "Int" is the class's simple name, and "`scala.Int`" is its full name. The details of packages are explained in [Chapter 13](#).

The `resX` identifier may be used in later lines. For instance, since `res0` was set to 3 previously, `res0 * 3` will be 9:

```
scala> res0 * 3
res1: Int = 9
```

To print the necessary, but not sufficient, `Hello, world!` greeting, type:

```
scala> println("Hello, world!")
Hello, world!
```

The `println` function prints the passed string to the standard output, similar to `System.out.println` in Java.

Step 2. Define some variables

Scala has two kinds of variables, `vals` and `vars`. A `val` is similar to a final variable in Java. Once initialized, a `val` can never be reassigned. A `var`, by contrast, is similar to a non-final variable in Java. A `var` can be reassigned throughout its lifetime. Here's a `val` definition:

```
scala> val msg = "Hello, world!"
msg: String = Hello, world!
```

This statement introduces `msg` as a name for the string `"Hello, world!"`. The type of `msg` is `java.lang.String`, because Scala strings are implemented by Java's `String` class.

If you're used to declaring variables in Java, you'll notice one striking difference here: neither `java.lang.String` nor `String` appear anywhere in the `val` definition. This example illustrates *type inference*, Scala's ability to figure out types you leave off. In this case, because you initialized `msg` with a string literal, Scala inferred the type of `msg` to be `String`. When the Scala interpreter (or compiler) can infer types, it is often best to let it do so rather than fill the code with unnecessary, explicit type annotations. You can, however, specify a type explicitly if you wish, and sometimes you probably should. An explicit type annotation can both ensure the Scala compiler infers the type you intend, as well as serve as useful documentation for future readers of the code. In contrast to Java, where you specify a variable's type before its name, in Scala you specify a variable's type after its name, separated by a colon. For example:

```
scala> val msg2: java.lang.String = "Hello again, world!"  
msg2: String = Hello again, world!
```

Or, since `java.lang` types are visible with their simple names⁴ in Scala programs, simply:

```
scala> val msg3: String = "Hello yet again, world!"  
msg3: String = Hello yet again, world!
```

Going back to the original `msg`, now that it is defined, you can use it as you'd expect, for example:

```
scala> println(msg)  
Hello, world!
```

What you can't do with `msg`, given that it is a `val`, not a `var`, is reassign it.⁵ For example, see how the interpreter complains when you attempt the following:

```
scala> msg = "Goodbye cruel world!"  
<console>:8: error: reassignment to val  
      msg = "Goodbye cruel world!"  
           ^
```

If reassignment is what you want, you'll need to use a `var`, as in:

```
scala> var greeting = "Hello, world!"  
greeting: String = Hello, world!
```

Since `greeting` is a `var` not a `val`, you can reassign it later. If you are feeling grouchy later, for example, you could change your greeting to:

```
scala> greeting = "Leave me alone, world!"  
greeting: String = Leave me alone, world!
```

To enter something into the interpreter that spans multiple lines, just keep typing after the first line. If the code you typed so far is not complete, the interpreter will respond with a vertical bar on the next line.

⁴The simple name of `java.lang.String` is `String`.

⁵In the interpreter, however, you can *define* a new `val` with a name that was already used before. This mechanism is explained in [Section 7.7](#).

```
scala> val multiLine =  
|   "This is the next line."  
multiLine: String = This is the next line.
```

If you realize you have typed something wrong, but the interpreter is still waiting for more input, you can escape by pressing enter twice:

```
scala> val oops =  
|  
|  
You typed two blank lines. Starting a new command.  
scala>
```

In the rest of the book, we'll leave out the vertical bars to make the code easier to read (and easier to copy and paste from the PDF eBook into the interpreter).

Step 3. Define some functions

Now that you've worked with Scala variables, you'll probably want to write some functions. Here's how you do that in Scala:

```
scala> def max(x: Int, y: Int): Int = {  
|   if (x > y) x  
|   else y  
}  
max: (x: Int, y: Int)Int
```

Function definitions start with `def`. The function's name, in this case `max`, is followed by a comma-separated list of parameters in parentheses. A type annotation must follow every function parameter, preceded by a colon, because the Scala compiler (and interpreter, but from now on we'll just say compiler) does not infer function parameter types. In this example, the function named `max` takes two parameters, `x` and `y`, both of type `Int`. After the close parenthesis of `max`'s parameter list you'll find another "`: Int`" type annotation. This one defines the *result type* of the `max` function itself.⁶ Following the

⁶In Java, the type of the value returned from a method is its return type. In Scala, that same concept is called *result type*.




Figure 2.1 · The basic form of a function definition in Scala.

function’s result type is an equals sign and pair of curly braces that contain the body of the function. In this case, the body contains a single `if` expression, which selects either `x` or `y`, whichever is greater, as the result of the `max` function. As demonstrated here, Scala’s `if` expression can result in a value, similar to Java’s ternary operator. For example, the Scala expression “`if (x > y) x else y`” behaves similarly to “`(x > y) ? x : y`” in Java. The equals sign that precedes the body of a function hints that in the functional world view, a function defines an expression that results in a value. The basic structure of a function is illustrated in Figure 2.1.

Sometimes the Scala compiler will require you to specify the result type of a function. If the function is *recursive*,⁷ for example, you must explicitly specify the function’s result type. In the case of `max`, however, you may leave the result type off and the compiler will infer it.⁸ Also, if a function consists of just one statement, you can optionally leave off the curly braces. Thus, you could alternatively write the `max` function like this:

```
scala> def max(x: Int, y: Int) = if (x > y) x else y
max: (x: Int, y: Int)Int
```

⁷A function is recursive if it calls itself.

⁸Nevertheless, it is often a good idea to indicate function result types explicitly, even when the compiler doesn’t require it. Such type annotations can make the code easier to read, because the reader need not study the function body to figure out the inferred result type.

Once you have defined a function, you can call it by name, as in:

```
scala> max(3, 5)
res4: Int = 5
```

Here's the definition of a function that takes no parameters and returns no interesting result:

```
scala> def greet() = println("Hello, world!")
greet: ()Unit
```

When you define the `greet()` function, the interpreter will respond with `greet: ()Unit`. “`greet`” is, of course, the name of the function. The empty parentheses indicate the function takes no parameters. And `Unit` is `greet`'s result type. A result type of `Unit` indicates the function returns no interesting value. Scala's `Unit` type is similar to Java's `void` type; in fact, every `void`-returning method in Java is mapped to a `Unit`-returning method in Scala. Methods with the result type of `Unit`, therefore, are only executed for their side effects. In the case of `greet()`, the side effect is a friendly greeting printed to the standard output.

In the next step, you'll place Scala code in a file and run it as a script. If you wish to exit the interpreter, you can do so by entering `:quit` or `:q`.

```
scala> :quit
$
```

Step 4. Write some Scala scripts

Although Scala is designed to help programmers build very large-scale systems, it also scales down nicely to scripting. A script is just a sequence of statements in a file that will be executed sequentially. Put this into a file named `hello.scala`:

```
println("Hello, world, from a script!")
```

then run:⁹

⁹You can run scripts without typing “`scala`” on Unix and Windows using a “pound-bang” syntax, which is shown in [Appendix A](#).

```
$ scala hello.scala
```

And you should get yet another greeting:

```
Hello, world, from a script!
```

Command line arguments to a Scala script are available via a Scala array named `args`. In Scala, arrays are zero based, and you access an element by specifying an index in parentheses. So the first element in a Scala array named `steps` is `steps(0)`, not `steps[0]`, as in Java. To try this out, type the following into a new file named `helloarg.scala`:

```
// Say hello to the first argument
println("Hello, " + args(0) + "!")
```

then run:

```
$ scala helloarg.scala planet
```

In this command, "planet" is passed as a command line argument, which is accessed in the script as `args(0)`. Thus, you should see:

```
Hello, planet!
```

Note that this script included a comment. The Scala compiler will ignore characters between `//` and the next end of line and any characters between `/*` and `*/`. This example also shows Strings being concatenated with the `+` operator. This works as you'd expect. The expression `"Hello, " + "world!"` will result in the string `"Hello, world!"`.

Step 5. Loop with `while`; decide with `if`

To try out a `while`, type the following into a file named `printargs.scala`:

```
var i = 0
while (i < args.length) {
    println(args(i))
    i += 1
}
```

Note

Although the examples in this section help explain `while` loops, they do not demonstrate the best Scala style. In the next section, you'll see better approaches that avoid iterating through arrays with indexes.

This script starts with a variable definition, `var i = 0`. Type inference gives `i` the type `scala.Int`, because that is the type of its initial value, 0. The `while` construct on the next line causes the *block* (the code between the curly braces) to be repeatedly executed until the boolean expression `i < args.length` is false. `args.length` gives the length of the `args` array. The block contains two statements, each indented two spaces, the recommended indentation style for Scala. The first statement, `println(args(i))`, prints out the `i`th command line argument. The second statement, `i += 1`, increments `i` by one. Note that Java's `++i` and `i++` don't work in Scala. To increment in Scala, you need to say either `i = i + 1` or `i += 1`. Run this script with the following command:

```
$ scala printargs.scala Scala is fun
```

And you should see:

```
Scala  
is  
fun
```

For even more fun, type the following code into a new file with the name `echoargs.scala`:

```
var i = 0  
while (i < args.length) {  
    if (i != 0)  
        print(" ")  
    print(args(i))  
    i += 1  
}  
println()
```

In this version, you've replaced the `println` call with a `print` call, so that all the arguments will be printed out on the same line. To make this readable, you've inserted a single space before each argument except the first via the

`if (i != 0)` construct. Since `i != 0` will be `false` the first time through the `while` loop, no space will get printed before the initial argument. Lastly, you've added one more `println` to the end, to get a line return after printing out all the arguments. Your output will be very pretty indeed. If you run this script with the following command:

```
$ scala echoargs.scala Scala is even more fun
```

You'll get:

```
Scala is even more fun
```

Note that in Scala, as in Java, you must put the boolean expression for a `while` or an `if` in parentheses. (In other words, you can't say in Scala things like `if i < 10` as you can in a language such as Ruby. You must say `if (i < 10)` in Scala.) Another similarity to Java is that if a block has only one statement, you can optionally leave off the curly braces, as demonstrated by the `if` statement in `echoargs.scala`. And although you haven't seen any of them, Scala does use semicolons to separate statements as in Java, except that in Scala the semicolons are very often optional, giving some welcome relief to your right little finger. If you had been in a more verbose mood, therefore, you could have written the `echoargs.scala` script as follows:

```
var i = 0;
while (i < args.length) {
    if (i != 0) {
        print(" ");
    }
    print(args(i));
    i += 1;
}
println();
```

Step 6. Iterate with `foreach` and `for`

Although you may not have realized it, when you wrote the `while` loops in the previous step, you were programming in an *imperative* style. In the imperative style, which is the style you normally use with languages like Java,

C++, and C, you give one imperative command at a time, iterate with loops, and often mutate state shared between different functions. Scala enables you to program imperatively, but as you get to know Scala better, you'll likely often find yourself programming in a more *functional* style. In fact, one of the main aims of this book is to help you become as comfortable with the functional style as you are with imperative style.

One of the main characteristics of a functional language is that functions are first class constructs, and that's very true in Scala. For example, another (far more concise) way to print each command line argument is:

```
args.foreach(arg => println(arg))
```

In this code, you call the `foreach` method on `args` and pass in a function. In this case, you're passing in a *function literal* that takes one parameter named `arg`. The body of the function is `println(arg)`. If you type the above code into a new file named `pa.scala` and execute with the command:

```
$ scala pa.scala Concise is nice
```

You should see:

```
Concise  
is  
nice
```

In the previous example, the Scala interpreter infers the type of `arg` to be `String`, since `String` is the element type of the array on which you're calling `foreach`. If you'd prefer to be more explicit, you can mention the type name. But when you do, you'll need to wrap the argument portion in parentheses (which is the normal form of the syntax anyway):

```
args.foreach((arg: String) => println(arg))
```

Running this script has the same behavior as the previous one.

If you're in the mood for more conciseness instead of more explicitness, you can take advantage of a special shorthand in Scala. If a function literal consists of one statement that takes a single argument, you need not explicitly name and specify the argument.¹⁰ Thus, the following code also works:

¹⁰This shorthand, called a *partially applied function*, is described in [Section 8.6](#).




Figure 2.2 · The syntax of a function literal in Scala.

```
args.foreach(println)
```

To summarize, the syntax for a function literal is a list of named parameters, in parentheses, a right arrow, and then the body of the function. This syntax is illustrated in [Figure 2.2](#).

Now, by this point you may be wondering what happened to those trusty `for` loops you have been accustomed to using in imperative languages, such as Java or C. In an effort to guide you in a functional direction, only a functional relative of the imperative `for` (called a *for expression*) is available in Scala. While you won't see their full power and expressiveness until you reach (or peek ahead to) [Section 7.3](#), we'll give you a glimpse here. In a new file named `forargs.scala`, type the following:

```
for (arg <- args)
    println(arg)
```

The parentheses after the “`for`” contain `arg <- args`.¹¹ To the right of the `<-` symbol is the familiar `args` array. To the left of `<-` is “`arg`”, the name of a `val`, not a `var`. (Because it is always a `val`, you just write “`arg`” by itself, not “`val arg`”.) Although `arg` may seem to be a `var`, because it will get a new value on each iteration, it really is a `val`: `arg` can't be reassigned inside the body of the `for` expression. Instead, for each element of the `args` array, a *new* `arg` `val` will be created and initialized to the element value, and the body of the `for` will be executed.

If you run the `forargs.scala` script with the command:

¹¹You can say “in” for the `<-` symbol. You'd read `for (arg <- args)`, therefore, as “`for arg in args`.”

```
$ scala forargs.scala for arg in args
```

You'll see:

```
for  
arg  
in  
args
```

Scala's for expression can do much more than this, but this example is enough to get you started. We'll show you more about for in [Section 7.3](#) and [Chapter 23](#).

Conclusion

In this chapter, you learned some Scala basics and, hopefully, took advantage of the opportunity to write a bit of Scala code. In the next chapter, we'll continue this introductory overview and get into more advanced topics.

Chapter 3

Next Steps in Scala

This chapter continues the previous chapter’s introduction to Scala. In this chapter, we’ll introduce some more advanced features. When you complete this chapter, you should have enough knowledge to enable you to start writing useful scripts in Scala. As with the previous chapter, we recommend you try out these examples as you go. The best way to get a feel for Scala is to start writing Scala code.

Step 7. Parameterize arrays with types

In Scala, you can instantiate objects, or class instances, using `new`. When you instantiate an object in Scala, you can *parameterize* it with values and types. Parameterization means “configuring” an instance when you create it. You parameterize an instance with values by passing objects to a constructor in parentheses. For example, the following Scala code instantiates a new `java.math.BigInteger` and parameterizes it with the value "12345":

```
val big = new java.math.BigInteger("12345")
```

You parameterize an instance with types by specifying one or more types in square brackets. An example is shown in [Listing 3.1](#). In this example, `greetStrings` is a value of type `Array[String]` (an “array of string”) that is initialized to length 3 by parameterizing it with the value 3 in the first line of code. If you run the code in [Listing 3.1](#) as a script, you’ll see yet another `Hello, world!` greeting. Note that when you parameterize an instance with both a type and a value, the type comes first in its square brackets, followed by the value in parentheses.

```
val greetStrings = new Array[String](3)
greetStrings(0) = "Hello"
greetStrings(1) = ", "
greetStrings(2) = "world!\n"
for (i <- 0 to 2)
  print(greetStrings(i))
```

Listing 3.1 · Parameterizing an array with a type.

Note

Although the code in Listing 3.1 demonstrates important concepts, it does not show the recommended way to create and initialize an array in Scala. You'll see a better way in Listing 3.2 on page 81.

Had you been in a more explicit mood, you could have specified the type of `greetStrings` explicitly like this:

```
val greetStrings: Array[String] = new Array[String](3)
```

Given Scala's type inference, this line of code is semantically equivalent to the actual first line of Listing 3.1. But this form demonstrates that while the type parameterization portion (the type names in square brackets) forms part of the type of the instance, the value parameterization part (the values in parentheses) does not. The type of `greetStrings` is `Array[String]`, not `Array[String](3)`.

The next three lines of code in Listing 3.1 initialize each element of the `greetStrings` array:

```
greetStrings(0) = "Hello"
greetStrings(1) = ", "
greetStrings(2) = "world!\n"
```

As mentioned previously, arrays in Scala are accessed by placing the index inside parentheses, not square brackets as in Java. Thus the zeroth element of the array is `greetStrings(0)`, not `greetStrings[0]`.

These three lines of code illustrate an important concept to understand about Scala concerning the meaning of `val`. When you define a variable with `val`, the variable can't be reassigned, but the object to which it refers could potentially still be changed. So in this case, you couldn't reassign

`greetStrings` to a different array; `greetStrings` will always point to the same `Array[String]` instance with which it was initialized. But you *can* change the elements of that `Array[String]` over time, so the array itself is mutable.

The final two lines in [Listing 3.1](#) contain a `for` expression that prints out each `greetStrings` array element in turn:

```
for (i <- 0 to 2)
    print(greetStrings(i))
```

The first line of code in this `for` expression illustrates another general rule of Scala: if a method takes only one parameter, you can call it without a dot or parentheses. The `to` in this example is actually a method that takes one `Int` argument. The code `0 to 2` is transformed into the method call `(0).to(2)`.¹ Note that this syntax only works if you explicitly specify the receiver of the method call. You cannot write “`println 10`”, but you can write “`Console println 10`”.

Scala doesn’t technically have operator overloading, because it doesn’t actually have operators in the traditional sense. Instead, characters such as `+`, `-`, `*`, and `/` can be used in method names. Thus, when you typed `1 + 2` into the Scala interpreter in Step 1, you were actually invoking a method named `+` on the `Int` object `1`, passing in `2` as a parameter. As illustrated in [Figure 3.1](#), you could alternatively have written `1 + 2` using traditional method invocation syntax, `(1).+(2)`.

Another important idea illustrated by this example will give you insight into why arrays are accessed with parentheses in Scala. Scala has fewer special cases than Java. Arrays are simply instances of classes like any other class in Scala. When you apply parentheses surrounding one or more values to a variable, Scala will transform the code into an invocation of a method named `apply` on that variable. So `greetStrings(i)` gets transformed into `greetStrings.apply(i)`. Thus accessing an element of an array in Scala is simply a method call like any other. This principle is not restricted to arrays: any application of an object to some arguments in parentheses will be transformed to an `apply` method call. Of course this will compile only

¹This `to` method actually returns not an array but a different kind of sequence, containing the values `0`, `1`, and `2`, which the `for` expression iterates over. Sequences and other collections will be described in [Chapter 17](#).




Figure 3.1 · All operations are method calls in Scala.

if that type of object actually defines an `apply` method. So it's not a special case; it's a general rule.

Similarly, when an assignment is made to a variable to which parentheses and one or more arguments have been applied, the compiler will transform that into an invocation of an `update` method that takes the arguments in parentheses as well as the object to the right of the equals sign. For example:

```
greetStrings(0) = "Hello"
```

will be transformed into:

```
greetStrings.update(0, "Hello")
```

Thus, the following is semantically equivalent to the code in Listing 3.1:

```
val greetStrings = new Array[String](3)
greetStrings.update(0, "Hello")
greetStrings.update(1, "", "")
greetStrings.update(2, "world!\n")
for (i <- 0.to(2))
  print(greetStrings.apply(i))
```

Scala achieves a conceptual simplicity by treating everything, from arrays to expressions, as objects with methods. You don't have to remember special cases, such as the differences in Java between primitive and their corresponding wrapper types, or between arrays and regular objects. Moreover,

this uniformity does not incur a significant performance cost. The Scala compiler uses Java arrays, primitive types, and native arithmetic where possible in the compiled code.

Although the examples you've seen so far in this step compile and run just fine, Scala provides a more concise way to create and initialize arrays that you would normally use (see [Listing 3.2](#)). This code creates a new array of length three, initialized to the passed strings, "zero", "one", and "two". The compiler infers the type of the array to be `Array[String]`, because you passed strings to it.

```
val numNames = Array("zero", "one", "two")
```

[Listing 3.2](#) · Creating and initializing an array.

What you're actually doing in [Listing 3.2](#) is calling a factory method, named `apply`, which creates and returns the new array. This `apply` method takes a variable number of arguments² and is defined on the *Array companion object*. You'll learn more about companion objects in [Section 4.3](#). If you're a Java programmer, you can think of this as calling a static method named `apply` on class `Array`. A more verbose way to call the same `apply` method is:

```
val numNames2 = Array.apply("zero", "one", "two")
```

Step 8. Use lists

One of the big ideas of the functional style of programming is that methods should not have side effects. A method's only act should be to compute and return a value. Some benefits gained when you take this approach are that methods become less entangled, and therefore more reliable and reusable. Another benefit (in a statically typed language) is that everything that goes into and out of a method is checked by a type checker, so logic errors are more likely to manifest themselves as type errors. Applying this functional philosophy to the world of objects means making objects immutable.

As you've seen, a Scala array is a mutable sequence of objects that all share the same type. An `Array[String]` contains only strings, for example.

²Variable-length argument lists, or *repeated parameters*, are described in [Section 8.8](#).

Although you can't change the length of an array after it is instantiated, you can change its element values. Thus, arrays are mutable objects.

For an immutable sequence of objects that share the same type you can use Scala's `List` class. As with arrays, a `List[String]` contains only strings. Scala's `List`, `scala.List`, differs from Java's `java.util.List` type in that Scala Lists are always immutable (whereas Java Lists can be mutable). More generally, Scala's `List` is designed to enable a functional style of programming. Creating a list is easy, and [Listing 3.3](#) shows how:

```
val oneTwoThree = List(1, 2, 3)
```

Listing 3.3 · Creating and initializing a list.

The code in [Listing 3.3](#) establishes a new `val` named `oneTwoThree`, initialized with a new `List[Int]` with the integer elements 1, 2, and 3.³ Because Lists are immutable, they behave a bit like Java strings: when you call a method on a list that might seem by its name to imply the list will mutate, it instead creates and returns a new list with the new value. For example, `List` has a method named '`:::`' for list concatenation. Here's how you use it:

```
val oneTwo = List(1, 2)
val threeFour = List(3, 4)
val oneTwoThreeFour = oneTwo :: threeFour
println(oneTwo + " and " + threeFour + " were not mutated.")
println("Thus, " + oneTwoThreeFour + " is a new list.")
```

If you run this script, you'll see:

```
List(1, 2) and List(3, 4) were not mutated.
Thus, List(1, 2, 3, 4) is a new list.
```

Perhaps the most common operator you'll use with lists is '`::`', which is pronounced "cons." Cons prepends a new element to the beginning of an existing list and returns the resulting list. For example, if you run this script:

```
val twoThree = List(2, 3)
val oneTwoThree = 1 :: twoThree
println(oneTwoThree)
```

³You don't need to say `new List` because "`List.apply()`" is defined as a factory method on the `scala.List` companion object. You'll read more on companion objects in [Section 4.3](#).

You'll see:

`List(1, 2, 3)`

Note

In the expression “`1 :: twoThree`”, `::` is a method of its *right* operand, the list, `twoThree`. You might suspect there's something amiss with the associativity of the `::` method, but it is actually a simple rule to remember: If a method is used in operator notation, such as `a * b`, the method is invoked on the left operand, as in `a.*(b)`—unless the method name ends in a colon. If the method name ends in a colon, the method is invoked on the *right* operand. Therefore, in `1 :: twoThree`, the `::` method is invoked on `twoThree`, passing in `1`, like this: `twoThree.::(1)`. Operator associativity will be described in more detail in [Section 5.9](#).

Given that a shorthand way to specify an empty list is `Nil`, one way to initialize new lists is to string together elements with the `cons` operator, with `Nil` as the last element.⁴ For example, the following script will produce the same output as the previous one, “`List(1, 2, 3)`”:

```
val oneTwoThree = 1 :: 2 :: 3 :: Nil  
println(oneTwoThree)
```

Scala's `List` is packed with useful methods, many of which are shown in [Table 3.1](#). The full power of lists will be revealed in [Chapter 16](#).

Why not append to lists?

Class `List` does offer an “append” operation—it's written `:+` and is explained in [Chapter 24](#)—but this operation is rarely used, because the time it takes to append to a list grows linearly with the size of the list, whereas prepending with `::` takes constant time. If you want to build a list efficiently by appending elements, you can prepend them and when you're done call `reverse`. Or you can use a `ListBuffer`, a mutable list that does offer an append operation, and when you're done call `toList`. `ListBuffer` will be described in [Section 22.2](#).

⁴The reason you need `Nil` at the end is that `::` is defined on class `List`. If you try to just say `1 :: 2 :: 3`, it won't compile because `3` is an `Int`, which doesn't have a `::` method.

Table 3.1 · Some List methods and usages

What it is	What it does
List() or Nil	The empty List
List("Cool", "tools", "rule")	Creates a new List[String] with the three values "Cool", "tools", and "rule"
val thrill = "Will" :: "fill" :: "until" :: Nil	Creates a new List[String] with the three values "Will", "fill", and "until"
List("a", "b") :: List("c", "d")	Concatenates two lists (returns a new List[String] with values "a", "b", "c", and "d")
thrill(2)	Returns the element at index 2 (zero based) of the thrill list (returns "until")
thrill.count(s => s.length == 4)	Counts the number of string elements in thrill that have length 4 (returns 2)
thrill.drop(2)	Returns the thrill list without its first 2 elements (returns List("until"))
thrill.dropRight(2)	Returns the thrill list without its rightmost 2 elements (returns List("Will"))
thrill.exists(s => s == "until")	Determines whether a string element exists in thrill that has the value "until" (returns true)
thrill.filter(s => s.length == 4)	Returns a list of all elements, in order, of the thrill list that have length 4 (returns List("Will", "fill"))
thrill.forall(s => s.endsWith("l"))	Indicates whether all elements in the thrill list end with the letter "l" (returns true)
thrill.foreach(s => print(s))	Executes the print statement on each of the strings in the thrill list (prints "Willfilluntil")

Table 3.1 · continued

<code>thrill.foreach(print)</code>	Same as the previous, but more concise (also prints "Willfilluntil")
<code>thrill.head</code>	Returns the first element in the <code>thrill</code> list (returns "Will")
<code>thrill.init</code>	Returns a list of all but the last element in the <code>thrill</code> list (returns <code>List("Will", "fill")</code>)
<code>thrill.isEmpty</code>	Indicates whether the <code>thrill</code> list is empty (returns <code>false</code>)
<code>thrill.last</code>	Returns the last element in the <code>thrill</code> list (returns "until")
<code>thrill.length</code>	Returns the number of elements in the <code>thrill</code> list (returns 3)
<code>thrill.map(s => s + "y")</code>	Returns a list resulting from adding a "y" to each string element in the <code>thrill</code> list (returns <code>List("Willy", "filly", "untily")</code>)
<code>thrill.mkString(", ")</code>	Makes a string with the elements of the list (returns "Will, fill, until")
<code>thrill.filterNot(s => s.length == 4)</code>	Returns a list of all elements, in order, of the <code>thrill</code> list <i>except those</i> that have length 4 (returns <code>List("until")</code>)
<code>thrill.reverse</code>	Returns a list containing all elements of the <code>thrill</code> list in reverse order (returns <code>List("until", "fill", "Will")</code>)
<code>thrill.sort((s, t) => s.charAt(0).toLowerCase < t.charAt(0).toLowerCase)</code>	Returns a list containing all elements of the <code>thrill</code> list in alphabetical order of the first character lowercased (returns <code>List("fill", "until", "Will")</code>)
<code>thrill.tail</code>	Returns the <code>thrill</code> list minus its first element (returns <code>List("fill", "until")</code>)

Step 9. Use tuples

Another useful container object is the *tuple*. Like lists, tuples are immutable, but unlike lists, tuples can contain different types of elements. Whereas a list might be a `List[Int]` or a `List[String]`, a tuple could contain both an integer and a string at the same time. Tuples are very useful, for example, if you need to return multiple objects from a method. Whereas in Java you would often create a JavaBean-like class to hold the multiple return values, in Scala you can simply return a tuple. And it is simple: To instantiate a new tuple that holds some objects, just place the objects in parentheses, separated by commas. Once you have a tuple instantiated, you can access its elements individually with a dot, underscore, and the one-based index of the element. An example is shown in [Listing 3.4](#):

```
val pair = (99, "Luftballons")
println(pair._1)
println(pair._2)
```

[Listing 3.4](#) · Creating and using a tuple.

In the first line of [Listing 3.4](#), you create a new tuple that contains the integer 99, as its first element, and the string, "Luftballons", as its second element. Scala infers the type of the tuple to be `Tuple2[Int, String]`, and gives that type to the variable `pair` as well. In the second line, you access the `_1` field, which will produce the first element, 99. The `."` in the second line is the same dot you'd use to access a field or invoke a method. In this case you are accessing a field named `_1`. If you run this script, you'll see:

```
99
Luftballons
```

The actual type of a tuple depends on the number of elements it contains and the types of those elements. Thus, the type of `(99, "Luftballons")` is `Tuple2[Int, String]`. The type of `('u', 'r', "the", 1, 4, "me")` is `Tuple6[Char, Char, String, Int, Int, String]`.⁵

⁵Although conceptually you could create tuples of any length, currently the Scala library only defines them up to `Tuple22`.

Accessing the elements of a tuple

You may be wondering why you can't access the elements of a tuple like the elements of a list, for example, with "pair(0)". The reason is that a list's `apply` method always returns the same type, but each element of a tuple may be a different type: `_1` can have one result type, `_2` another, and so on. These `_N` numbers are one-based, instead of zero-based, because starting with 1 is a tradition set by other languages with statically typed tuples, such as Haskell and ML.

Step 10. Use sets and maps

Because Scala aims to help you take advantage of both functional and imperative styles, its collections libraries make a point to differentiate between mutable and immutable collections. For example, arrays are always mutable; lists are always immutable. Scala also provides mutable and immutable alternatives for sets and maps, but uses the same simple names for both versions. For sets and maps, Scala models mutability in the class hierarchy.

For example, the Scala API contains a base *trait* for sets, where a trait is similar to a Java interface. (You'll find out more about traits in [Chapter 12](#).) Scala then provides two subtraits, one for mutable sets and another for immutable sets.

As you can see in [Figure 3.2](#), these three traits all share the same simple name, `Set`. Their fully qualified names differ, however, because each resides in a different package. Concrete set classes in the Scala API, such as the `HashSet` classes shown in [Figure 3.2](#), extend either the mutable or immutable `Set` trait. (Although in Java you "implement" interfaces, in Scala you "extend" or "mix in" traits.) Thus, if you want to use a `HashSet`, you can choose between mutable and immutable varieties depending upon your needs. The default way to create a set is shown in [Listing 3.5](#):

```
var jetSet = Set("Boeing", "Airbus")
jetSet += "Lear"
println(jetSet.contains("Cessna"))
```

[Listing 3.5](#) · Creating, initializing, and using an immutable set.




Figure 3.2 · Class hierarchy for Scala sets.

In the first line of code in [Listing 3.5](#), you define a new var named `jetSet` and initialize it with an immutable set containing the two strings, "Boeing" and "Airbus". As this example shows, you can create sets in Scala similarly to how you create lists and arrays: by invoking a factory method named `apply` on a `Set` companion object. In [Listing 3.5](#), you invoke `apply` on the companion object for `scala.collection.immutable.Set`, which returns an instance of a default, immutable `Set`. The Scala compiler infers `jetSet`'s type to be the `immutable Set[String]`.

To add a new element to a set, you call `+` on the set, passing in the new element. On both mutable and immutable sets, the `+` method will create and return a new set with the element added. In [Listing 3.5](#), you're working with an immutable set. Although mutable sets offer an actual `+=` method, immutable sets do not.

In this case, the second line of code, "`jetSet += "Lear"`", is essentially a shorthand for:

```
jetSet = jetSet + "Lear"
```

Thus, in the second line of [Listing 3.5](#), you reassign the `jetSet` var with a new set containing "Boeing", "Airbus", and "Lear". Finally, the last line

of Listing 3.5 prints out whether or not the set contains the string "Cessna".
(As you'd expect, it prints false.)

If you want a mutable set, you'll need to use an *import*, as shown in Listing 3.6:

```
import scala.collection.mutable  
  
val movieSet = mutable.Set("Hitch", "Poltergeist")  
movieSet += "Shrek"  
println(movieSet)
```

Listing 3.6 · Creating, initializing, and using a mutable set.

In the first line of Listing 3.6 you import the mutable Set. As with Java, an import statement allows you to use a simple name, such as Set, instead of the longer, fully qualified name. As a result, when you say Set on the third line, the compiler knows you mean scala.collection.mutable.Set. On that line, you initialize movieSet with a new mutable set that contains the strings "Hitch" and "Poltergeist". The subsequent line adds "Shrek" to the mutable set by calling the += method on the set, passing in the string "Shrek". As mentioned previously, += is an actual method defined on mutable sets. Had you wanted to, instead of writing movieSet += "Shrek", you could have written movieSet.+=("Shrek").⁶

Although the default set implementations produced by the mutable and immutable Set factory methods shown thus far will likely be sufficient for most situations, occasionally you may want an explicit set class. Fortunately, the syntax is similar. Simply import that class you need, and use the factory method on its companion object. For example, if you need an immutable HashSet, you could do this:

```
import scala.collection.immutable.HashSet  
  
val hashSet = HashSet("Tomatoes", "Chilies")  
println(hashSet + "Coriander")
```

Another useful collection class in Scala is Map. As with sets, Scala provides mutable and immutable versions of Map, using a class hierarchy. As

⁶Because the set in Listing 3.6 is mutable, there is no need to reassign movieSet, which is why it can be a val. By contrast, using += with the immutable set in Listing 3.5 required reassigning jetSet, which is why it must be a var.




Figure 3.3 · Class hierarchy for Scala maps.

you can see in [Figure 3.3](#), the class hierarchy for maps looks a lot like the one for sets. There's a base `Map` trait in package `scala.collection`, and two subtrait `Maps`: a mutable `Map` in `scala.collection.mutable` and an immutable one in `scala.collection.immutable`.

Implementations of `Map`, such as the `HashMaps` shown in the class hierarchy in [Figure 3.3](#), extend either the mutable or immutable trait. You can create and initialize maps using factory methods similar to those used for arrays, lists, and sets.

```
import scala.collection.mutable  
  
val treasureMap = mutable.Map[Int, String]()  
treasureMap += (1 -> "Go to island.")  
treasureMap += (2 -> "Find big X on ground.")  
treasureMap += (3 -> "Dig.")  
println(treasureMap(2))
```

[Listing 3.7](#) · Creating, initializing, and using a mutable map.

For example, [Listing 3.7](#) shows a mutable map in action. On the first

line of Listing 3.7, you import the mutable Map. You then define a val named treasureMap, and initialize it with an empty mutable Map that has integer keys and string values. The map is empty because you pass nothing to the factory method (the parentheses in “Map[Int, String]()” are empty).⁷ On the next three lines you add key/value pairs to the map using the `->` and `+=` methods. As illustrated previously, the Scala compiler transforms a binary operation expression like `1 -> "Go to island."` into `(1) .->("Go to island.")`. Thus, when you say `1 -> "Go to island."`, you are actually calling a method named `->` on an integer with the value 1, passing in a string with the value "Go to island." This `->` method, which you can invoke on any object in a Scala program, returns a two-element tuple containing the key and value.⁸ You then pass this tuple to the `+=` method of the map object to which `treasureMap` refers. Finally, the last line prints the value that corresponds to the key 2 in the `treasureMap`.

If you run this code, it will print:

Find big X on ground.

If you prefer an immutable map, no import is necessary, as immutable is the default map. An example is shown in Listing 3.8:

```
val romanNumeral = Map(  
    1 -> "I", 2 -> "II", 3 -> "III", 4 -> "IV", 5 -> "V"  
)  
println(romanNumeral(4))
```

Listing 3.8 · Creating, initializing, and using an immutable map.

Given there are no imports, when you say `Map` in the first line of Listing 3.8, you'll get the default: a `scala.collection.immutable.Map`. You pass five key/value tuples to the map's factory method, which returns an immutable Map containing the passed key/value pairs. If you run the code in Listing 3.8 it will print “IV”.

⁷The explicit type parameterization, “[Int, String]”, is required in Listing 3.7 because without any values passed to the factory method, the compiler is unable to infer the map's type parameters. By contrast, the compiler can infer the type parameters from the values passed to the map factory shown in Listing 3.8, thus no explicit type parameters are needed.

⁸The Scala mechanism that allows you to invoke `->` on any object, *implicit conversion*, will be covered in Chapter 21.

Step 11. Learn to recognize the functional style

As mentioned in [Chapter 1](#), Scala allows you to program in an imperative style, but encourages you to adopt a more functional style. If you are coming to Scala from an imperative background—for example, if you are a Java programmer—one of the main challenges you may face when learning Scala is figuring out how to program in the functional style. We realize this style might be unfamiliar at first, and in this book we try hard to guide you through the transition. It will require some work on your part, and we encourage you to make the effort. If you come from an imperative background, we believe that learning to program in a functional style will not only make you a better Scala programmer, it will expand your horizons and make you a better programmer in general.

The first step is to recognize the difference between the two styles in code. One telltale sign is that if code contains any `vars`, it is probably in an imperative style. If the code contains no `vars` at all—*i.e.*, it contains *only* `vals`—it is probably in a functional style. One way to move towards a functional style, therefore, is to try to program without `vars`.

If you’re coming from an imperative background, such as Java, C++, or C#, you may think of `var` as a regular variable and `val` as a special kind of variable. On the other hand, if you’re coming from a functional background, such as Haskell, OCaml, or Erlang, you might think of `val` as a regular variable and `var` as akin to blasphemy. The Scala perspective, however, is that `val` and `var` are just two different tools in your toolbox, both useful, neither inherently evil. Scala encourages you to lean towards `vals`, but ultimately reach for the best tool given the job at hand. Even if you agree with this balanced philosophy, however, you may still find it challenging at first to figure out how to get rid of `vars` in your code.

Consider the following `while` loop example, adapted from [Chapter 2](#), which uses a `var` and is therefore in the imperative style:

```
def printArgs(args: Array[String]): Unit = {  
    var i = 0  
    while (i < args.length) {  
        println(args(i))  
        i += 1  
    }  
}
```

You can transform this bit of code into a more functional style by getting rid of the var, for example, like this:

```
def printArgs(args: Array[String]): Unit = {  
    for (arg <- args)  
        println(arg)  
}
```

or this:

```
def printArgs(args: Array[String]): Unit = {  
    args.foreach(println)  
}
```

This example illustrates one benefit of programming with fewer vars. The refactored (more functional) code is clearer, more concise, and less error-prone than the original (more imperative) code. The reason Scala encourages a functional style is that it can help you write more understandable, less error-prone code.

But you can go even further. The refactored `printArgs` method is not *purely* functional because it has side effects—in this case, its side effect is printing to the standard output stream. The telltale sign of a function with side effects is that its result type is `Unit`. If a function isn't returning any interesting value, which is what a result type of `Unit` means, the only way that function can make a difference in the world is through some kind of side effect. A more functional approach would be to define a method that formats the passed args for printing, but just returns the formatted string, as shown in Listing 3.9:

```
def formatArgs(args: Array[String]) = args.mkString("\n")
```

Listing 3.9 · A function without side effects or vars.

Now you're really functional: no side effects or vars in sight. The `mkString` method, which you can call on any iterable collection (including arrays, lists, sets, and maps), returns a string consisting of the result of calling `toString` on each element, separated by the passed string. Thus if `args` contains three elements "zero", "one", and "two", `formatArgs` will return "zero\none\ntwo". Of course, this function doesn't actually print

anything out like the `printArgs` methods did, but you can easily pass its result to `println` to accomplish that:

```
println(formatArgs(args))
```

Every useful program is likely to have side effects of some form; otherwise, it wouldn't be able to provide value to the outside world. Preferring methods without side effects encourages you to design programs where side-effecting code is minimized. One benefit of this approach is that it can help make your programs easier to test.

For example, to test any of the three `printArgs` methods shown earlier in this section, you'd need to redefine `println`, capture the output passed to it, and make sure it is what you expect. By contrast, you could test the `formatArgs` function simply by checking its result:

```
val res = formatArgs(Array("zero", "one", "two"))
assert(res == "zero\none\nthree")
```

Scala's `assert` method checks the passed Boolean and if it is false, throws `AssertionError`. If the passed Boolean is true, `assert` just returns quietly. You'll learn more about assertions and tests in [Chapter 14](#).

That said, bear in mind that neither vars nor side effects are inherently evil. Scala is not a pure functional language that forces you to program everything in the functional style. Scala is a hybrid imperative/functional language. You may find that in some situations an imperative style is a better fit for the problem at hand, and in such cases you should not hesitate to use it. To help you learn how to program without vars, however, we'll show you many specific examples of code with vars and how to transform those vars to vals in [Chapter 7](#).

A balanced attitude for Scala programmers

Prefer vals, immutable objects, and methods without side effects.

Reach for them first. Use vars, mutable objects, and methods with side effects when you have a specific need and justification for them.

Step 12. Read lines from a file

Scripts that perform small, everyday tasks often need to process lines in files. In this section, you'll build a script that reads lines from a file and prints them out prepended with the number of characters in each line. The first version is shown in [Listing 3.10](#):

```
import scala.io.Source
if (args.length > 0) {
    for (line <- Source.fromFile(args(0)).getLines())
        println(line.length + " " + line)
}
else
    Console.err.println("Please enter filename")
```

Listing 3.10 · Reading lines from a file.

This script starts with an import of a class named `Source` from package `scala.io`. It then checks to see if at least one argument was specified on the command line. If so, the first argument is interpreted as a filename to open and process. The expression `Source.fromFile(args(0))` attempts to open the specified file and returns a `Source` object, on which you call `getLines`. The `getLines` method returns an `Iterator[String]`, which provides one line on each iteration, excluding the end-of-line character. The `for` expression iterates through these lines and prints for each the length of the line, a space, and the line itself. If there were no arguments supplied on the command line, the final `else` clause will print a message to the standard error stream. If you place this code in a file named `countchars1.scala`, and run it on itself with:

```
$ scala countchars1.scala countchars1.scala
```

You should see:

```
22 import scala.io.Source
0
22 if (args.length > 0) {
0
51   for (line <- Source.fromFile(args(0)).getLines())
```

```
37     println(line.length + " " + line)
1 }
4 else
46   Console.err.println("Please enter filename")
```

Although the script in its current form prints out the needed information, you may wish to line up the numbers, right adjusted, and add a pipe character, so that the output looks instead like:

```
22 | import scala.io.Source
0 |
22 | if (args.length > 0) {
0 |
51 |   for (line <- Source.fromFile(args(0)).getLines())
37 |     println(line.length + " " + line)
1 |
4 | else
46 |   Console.err.println("Please enter filename")
```

To accomplish this, you can iterate through the lines twice. The first time through you'll determine the maximum width required by any line's character count. The second time through you'll print the output, using the maximum width calculated previously. Because you'll be iterating through the lines twice, you may as well assign them to a variable:

```
val lines = Source.fromFile(args(0)).getLines().toList
```

The final `toList` is required because the `getLines` method returns an iterator. Once you've iterated through an iterator, it is spent. By transforming it into a list via the `toList` call, you gain the ability to iterate as many times as you wish, at the cost of storing all lines from the file in memory at once. The `lines` variable, therefore, references a list of strings that contains the contents of the file specified on the command line. Next, because you'll be calculating the width of each line's character count twice, once per iteration, you might factor that expression out into a small function, which calculates the character width of the passed string's length:

```
def widthOfLength(s: String) = s.length.toString.length
```

With this function, you could calculate the maximum width like this:

```
var maxWidth = 0
for (line <- lines)
  maxWidth = maxWidth.max(widthOfLength(line))
```

Here you iterate through each line with a `for` expression, calculate the character width of that line's length, and, if it is larger than the current maximum, assign it to `maxWidth`, a `var` that was initialized to 0. (The `max` method, which you can invoke on any `Int`, returns the greater of the value on which it was invoked and the value passed to it.) Alternatively, if you prefer to find the maximum without `vars`, you could first find the longest line like this:

```
val longestLine = lines.reduceLeft(
  (a, b) => if (a.length > b.length) a else b
)
```

The `reduceLeft` method applies the passed function to the first two elements in `lines`, then applies it to the result of the first application and the next element in `lines`, and so on, all the way through the list. On each such application, the result will be the longest line encountered so far because the passed function, `(a, b) => if (a.length > b.length) a else b`, returns the longest of the two passed strings. “`reduceLeft`” will return the result of the last application of the function, which in this case will be the longest string element contained in `lines`.

Given this result, you can calculate the maximum width by passing the longest line to `widthOfLength`:

```
val maxWidth = widthOfLength(longestLine)
```

All that remains is to print out the lines with proper formatting. You can do that like this:

```
for (line <- lines) {
  val numSpaces = maxWidth - widthOfLength(line)
  val padding = " " * numSpaces
  println(padding + line.length + " | " + line)
}
```

In this `for` expression, you once again iterate through the lines. For each line, you first calculate the number of spaces required before the line length and assign it to `numSpaces`. Then you create a string containing `numSpaces`

spaces with the expression " " * numSpaces. Finally, you print out the information with the desired formatting. The entire script looks as shown in Listing 3.11:

```
import scala.io.Source
def widthOfLength(s: String) = s.length.toString.length
if (args.length > 0) {
    val lines = Source.fromFile(args(0)).getLines().toList
    val longestLine = lines.reduceLeft(
        (a, b) => if (a.length > b.length) a else b
    )
    val maxWidth = widthOfLength(longestLine)
    for (line <- lines) {
        val numSpaces = maxWidth - widthOfLength(line)
        val padding = " " * numSpaces
        println(padding + line.length + " | " + line)
    }
} else
    Console.err.println("Please enter filename")
```

Listing 3.11 · Printing formatted character counts for the lines of a file.

Conclusion

With the knowledge you've gained in this chapter, you should be able to start using Scala for small tasks, especially scripts. In later chapters, we will dive further into these topics and introduce other topics that weren't even hinted at here.

Chapter 4

Classes and Objects

You've now seen the basics of classes and objects in Scala from the previous two chapters. In this chapter, we'll take you a bit deeper. You'll learn more about classes, fields, and methods, and get an overview of semicolon inference. We'll discuss singleton objects, including how to use them to write and run a Scala application. If you are familiar with Java, you'll find that the concepts in Scala are similar, but not exactly the same. So even if you're a Java guru, it will pay to read on.

4.1 Classes, fields, and methods

A class is a blueprint for objects. Once you define a class, you can create objects from the class blueprint with the keyword new. For example, given the class definition:

```
class ChecksumAccumulator {  
    // class definition goes here  
}
```

You can create `ChecksumAccumulator` objects with:

```
new ChecksumAccumulator
```

Inside a class definition, you place fields and methods, which are collectively called *members*. Fields, which you define with either `val` or `var`, are variables that refer to objects. Methods, which you define with `def`, contain executable code. The fields hold the state, or data, of an object, whereas the methods use that data to do the computational work of the object. When you


instantiate a class, the runtime sets aside some memory to hold the image of that object's state (*i.e.*, the content of its variables). For example, if you defined a `ChecksumAccumulator` class and gave it a `var` field named `sum`:

```
class ChecksumAccumulator {  
    var sum = 0  
}
```

and you instantiated it twice with:

```
val acc = new ChecksumAccumulator  
val csa = new ChecksumAccumulator
```


The image of the objects in memory might look like this:



Since `sum`, a field declared inside class `ChecksumAccumulator`, is a `var`, not a `val`, you can later reassign to `sum` a different `Int` value, like this:

```
acc.sum = 3
```

Now the picture would look like this:



One thing to notice about this picture is that there are two `sum` variables, one in the object referenced by `acc` and the other in the object referenced

by `cса`. Fields are also known as *instance variables*, because every instance gets its own set of the variables. Collectively, an object's instance variables make up the memory image of the object. You see this illustrated here not only in that you see two `sum` variables, but also that when you changed one, the other was unaffected.

Another thing to note in this example is that you were able to mutate the object `acc` referred to, even though `acc` is a `val`. What you can't do with `acc` (or `cса`), given that they are `vals`, not `vars`, is reassign a different object to them. For example, the following attempt would fail:

```
// Won't compile, because acc is a val
acc = new ChecksumAccumulator
```

What you can count on, therefore, is that `acc` will always refer to the same `ChecksumAccumulator` object with which you initialize it, but the fields contained inside that object might change over time.

One important way to pursue robustness of an object is to ensure that the object's state—the values of its instance variables—remains valid during its entire lifetime. The first step is to prevent outsiders from accessing the fields directly by making the fields *private*. Because private fields can only be accessed by methods defined in the same class, all the code that can update the state will be localized to the class. To declare a field private, you place a `private` access modifier in front of the field, like this:

```
class ChecksumAccumulator {
    private var sum = 0
}
```

Given this definition of `ChecksumAccumulator`, any attempt to access `sum` from the outside of the class would fail:

```
val acc = new ChecksumAccumulator
acc.sum = 5 // Won't compile, because sum is private
```

Note

The way you make members public in Scala is by not explicitly specifying any access modifier. Put another way, where you'd say “public” in Java, you simply say nothing in Scala. Public is Scala's default access level.

Now that `sum` is private, the only code that can access `sum` is code defined inside the body of the class itself. Thus, `ChecksumAccumulator` won't be of much use to anyone unless we define some methods in it:

```
class ChecksumAccumulator {  
    private var sum = 0  
  
    def add(b: Byte): Unit = {  
        sum += b  
    }  
  
    def checksum(): Int = {  
        return ~(sum & 0xFF) + 1  
    }  
}
```

The `ChecksumAccumulator` now has two methods, `add` and `checksum`, both of which exhibit the basic form of a function definition, shown in [Figure 2.1](#) on [page 69](#).

Any parameters to a method can be used inside the method. One important characteristic of method parameters in Scala is that they are `vals`, not `vars`.¹ If you attempt to reassign a parameter inside a method in Scala, therefore, it won't compile:

```
def add(b: Byte): Unit = {  
    b = 1      // This won't compile, because b is a val  
    sum += b  
}
```

Although `add` and `checksum` in this version of `ChecksumAccumulator` correctly implement the desired functionality, you can express them using a more concise style. First, the `return` at the end of the `checksum` method is superfluous and can be dropped. In the absence of any explicit `return` statement, a Scala method returns the last value computed by the method.

The recommended style for methods is in fact to avoid having explicit, and especially multiple, `return` statements. Instead, think of each method as an expression that yields one value, which is returned. This philosophy will encourage you to make methods quite small, to factor larger methods

¹The reason parameters are `vals` is that `vals` are easier to reason about. You needn't look further to determine if a `val` is reassigned, as you must do with a `var`.

into multiple smaller ones. On the other hand, design choices depend on the design context, and Scala makes it easy to write methods that have multiple, explicit returns if that's what you desire.

Because all `checksum` does is calculate a value, it does not need an explicit return. Another shorthand for methods is that you can leave off the curly braces if a method computes only a single result expression. If the result expression is short, it can even be placed on the same line as the `def` itself. For the utmost in conciseness, you can leave off the result type and Scala will infer it. With these changes, class `ChecksumAccumulator` looks like this:

```
class ChecksumAccumulator {  
    private var sum = 0  
    def add(b: Byte) = sum += b  
    def checksum() = ~(sum & 0xFF) + 1  
}
```

Although the Scala compiler will correctly infer the result types of the `add` and `checksum` methods shown in the previous example, readers of the code will also need to *mentally infer* the result types by studying the bodies of the methods. As a result it is often better to explicitly provide the result types of public methods declared in a class even when the compiler would infer it for you. [Listing 4.1](#) shows this style.

```
// In file ChecksumAccumulator.scala  
class ChecksumAccumulator {  
    private var sum = 0  
    def add(b: Byte): Unit = { sum += b }  
    def checksum(): Int = ~(sum & 0xFF) + 1  
}
```

[Listing 4.1](#) · Final version of class `ChecksumAccumulator`.

Methods with a result type of `Unit`, such as `ChecksumAccumulator`'s `add` method, are executed for their side effects. A side effect is generally defined as mutating state somewhere external to the method or performing an I/O action. In `add`'s case, the side effect is that `sum` is reassigned. A method that is executed only for its side effects is known as a *procedure*.

4.2 Semicolon inference

In a Scala program, a semicolon at the end of a statement is usually optional. You can type one if you want but you don't have to if the statement appears by itself on a single line. On the other hand, a semicolon is required if you write multiple statements on a single line:

```
val s = "hello"; println(s)
```

If you want to enter a statement that spans multiple lines, most of the time you can simply enter it and Scala will separate the statements in the correct place. For example, the following is treated as one four-line statement:

```
if (x < 2)
  println("too small")
else
  println("ok")
```

Occasionally, however, Scala will split a statement into two parts against your wishes:

```
x
+ y
```

This parses as two statements `x` and `+y`. If you intend it to parse as one statement `x + y`, you can always wrap it in parentheses:

```
(x
+ y)
```

Alternatively, you can put the `+` at the end of a line. For just this reason, whenever you are chaining an infix operation such as `+`, it is a common Scala style to put the operators at the end of the line instead of the beginning:

```
x +
y +
z
```

The rules of semicolon inference

The precise rules for statement separation are surprisingly simple for how well they work. In short, a line ending is treated as a semicolon unless one of the following conditions is true:

1. The line in question ends in a word that would not be legal as the end of a statement, such as a period or an infix operator.
2. The next line begins with a word that cannot start a statement.
3. The line ends while inside parentheses (...) or brackets [...], because these cannot contain multiple statements anyway.

4.3 Singleton objects

As mentioned in [Chapter 1](#), one way in which Scala is more object-oriented than Java is that classes in Scala cannot have static members. Instead, Scala has *singleton objects*. A singleton object definition looks like a class definition, except instead of the keyword `class` you use the keyword `object`. [Listing 4.2](#) shows an example.

The singleton object in this figure is named `ChecksumAccumulator`, the same name as the class in the previous example. When a singleton object shares the same name with a class, it is called that class's *companion object*. You must define both the class and its companion object in the same source file. The class is called the *companion class* of the singleton object. A class and its companion object can access each other's private members.

The `ChecksumAccumulator` singleton object has one method, named `calculate`, which takes a `String` and calculates a checksum for the characters in the `String`. It also has one private field, `cache`, a mutable map in which previously calculated checksums are cached.² The first line of the method, “`if (cache.contains(s))`”, checks the cache to see if the passed string is already contained as a key in the map. If so, it just returns the mapped value, `cache(s)`. Otherwise, it executes the `else` clause, which cal-

²We used a cache here to show a singleton object with a field. A cache such as this is a performance optimization that trades off memory for computation time. In general, you would likely use such a cache only if you encountered a performance problem that the cache solves, and might use a weak map, such as `WeakHashMap` in `scala.collection.jcl`, so that entries in the cache could be garbage collected if memory becomes scarce.

```
// In file ChecksumAccumulator.scala
import scala.collection.mutable

object ChecksumAccumulator {
    private val cache = mutable.Map.empty[String, Int]

    def calculate(s: String): Int =
        if (cache.contains(s))
            cache(s)
        else {
            val acc = new ChecksumAccumulator
            for (c <- s)
                acc.add(c.toByte)
            val cs = acc.checksum()
            cache += (s -> cs)
            cs
        }
}
```

Listing 4.2 · Companion object for class ChecksumAccumulator.

culates the checksum. The first line of the else clause defines a `val` named `acc` and initializes it with a new `ChecksumAccumulator` instance.³ The next line is a `for` expression, which cycles through each character in the passed string, converts the character to a `Byte` by invoking `toByte` on it, and passes that to the `add` method of the `ChecksumAccumulator` instances to which `acc` refers. After the `for` expression completes, the next line of the method invokes `checksum` on `acc`, which gets the checksum for the passed `String`, and stores it into a `val` named `cs`. In the next line, `cache += (s -> cs)`, the passed string key is mapped to the integer checksum value, and this key-value pair is added to the cache map. The last expression of the method, `cs`, ensures the checksum is the result of the method.


If you are a Java programmer, one way to think of singleton objects is as the home for any static methods you might have written in Java. You can invoke methods on singleton objects using a similar syntax: the name of the singleton object, a dot, and the name of the method. For example, you can

³Because the keyword `new` is only used to instantiate classes, the new object created here is an instance of the `ChecksumAccumulator` class, not the singleton object of the same name.

invoke the `calculate` method of singleton object `ChecksumAccumulator` like this:

```
ChecksumAccumulator.calculate("Every value is an object.")
```

A singleton object is more than a holder of static methods, however. It is a first-class object. You can think of a singleton object's name, therefore, as a “name tag” attached to the object:



Defining a singleton object doesn't define a type (at the Scala level of abstraction). Given just a definition of object `ChecksumAccumulator`, you can't make a variable of type `ChecksumAccumulator`. Rather, the type named `ChecksumAccumulator` is defined by the singleton object's companion class. However, singleton objects extend a superclass and can mix in traits. Given each singleton object is an instance of its superclasses and mixed-in traits, you can invoke its methods via these types, refer to it from variables of these types, and pass it to methods expecting these types. We'll show some examples of singleton objects inheriting from classes and traits in [Chapter 13](#).

One difference between classes and singleton objects is that singleton objects cannot take parameters, whereas classes can. Because you can't instantiate a singleton object with the `new` keyword, you have no way to pass parameters to it. Each singleton object is implemented as an instance of a *synthetic class* referenced from a static variable, so they have the same initialization semantics as Java statics.⁴ In particular, a singleton object is initialized the first time some code accesses it.

A singleton object that does not share the same name with a companion class is called a *standalone object*. You can use standalone objects for many purposes, including collecting related utility methods together or defining an entry point to a Scala application. This use case is shown in the next section.

⁴The name of the synthetic class is the object name plus a dollar sign. Thus the synthetic class for the singleton object named `ChecksumAccumulator` is `ChecksumAccumulator$`.

4.4 A Scala application

To run a Scala program, you must supply the name of a standalone singleton object with a `main` method that takes one parameter, an `Array[String]`, and has a result type of `Unit`. Any standalone object with a `main` method of the proper signature can be used as the entry point into an application. An example is shown in [Listing 4.3](#):

```
// In file Summer.scala
import ChecksumAccumulator.calculate

object Summer {
    def main(args: Array[String]) = {
        for (arg <- args)
            println(arg + ":" + calculate(arg))
    }
}
```

[Listing 4.3](#) · The `Summer` application.

The name of the singleton object in [Listing 4.3](#) is `Summer`. Its `main` method has the proper signature, so you can use it as an application. The first statement in the file is an import of the `calculate` method defined in the `ChecksumAccumulator` object in the previous example. This import statement allows you to use the method's simple name in the rest of the file.⁵ The body of the `main` method simply prints out each argument and the checksum for the argument, separated by a colon.

Note

Scala implicitly imports members of packages `java.lang` and `scala`, as well as the members of a singleton object named `Predef`, into every Scala source file. `Predef`, which resides in package `scala`, contains many useful methods. For example, when you say `println` in a Scala source file, you're actually invoking `println` on `Predef`. (`Predef.println` turns around and invokes `Console.println`, which does the real work.) When you say `assert`, you're invoking `Predef.assert`.

⁵If you're a Java programmer, you can think of this import as similar to the static import feature introduced in Java 5. One difference in Scala, however, is that you can import members from any object, not just singleton objects.

To run the `Summer` application, place the code from Listing 4.3 into a file named `Summer.scala`. Because `Summer` uses `ChecksumAccumulator`, place the code for `ChecksumAccumulator`, both the class shown in Listing 4.1 and its companion object shown in Listing 4.2, into a file named `ChecksumAccumulator.scala`.

One difference between Scala and Java is that whereas Java requires you to put a public class in a file named after the class—for example, you’d put class `SpeedRacer` in file `SpeedRacer.java`—in Scala, you can name `.scala` files anything you want, no matter what Scala classes or code you put in them. In general in the case of non-scripts, however, it is recommended style to name files after the classes they contain as is done in Java, so that programmers can more easily locate classes by looking at file names. This is the approach we’ve taken with the two files in this example, `Summer.scala` and `ChecksumAccumulator.scala`.

Neither `ChecksumAccumulator.scala` nor `Summer.scala` are scripts, because they end in a definition. A script, by contrast, must end in a result expression. Thus if you try to run `Summer.scala` as a script, the Scala interpreter will complain that `Summer.scala` does not end in a result expression (assuming of course you didn’t add any expression of your own after the `Summer` object definition). Instead, you’ll need to actually compile these files with the Scala compiler, then run the resulting class files. One way to do this is to use `scalac`, which is the basic Scala compiler, like this:

```
$ scalac ChecksumAccumulator.scala Summer.scala
```

This compiles your source files, but there may be a perceptible delay before the compilation finishes. The reason is that every time the compiler starts up, it spends time scanning the contents of jar files and doing other initial work before it even looks at the fresh source files you submit to it. For this reason, the Scala distribution also includes a Scala compiler *daemon* called `fsc` (for fast Scala compiler). You use it like this:

```
$ fsc ChecksumAccumulator.scala Summer.scala
```

The first time you run `fsc`, it will create a local server daemon attached to a port on your computer. It will then send the list of files to compile to the daemon via the port, and the daemon will compile the files. The next time you run `fsc`, the daemon will already be running, so `fsc` will simply send the file list to the daemon, which will immediately compile the files. Using

fsc, you only need to wait for the Java runtime to startup the first time. If you ever want to stop the fsc daemon, you can do so with fsc -shutdown.

Running either of these scalac or fsc commands will produce Java class files that you can then run via the scala command, the same command you used to invoke the interpreter in previous examples. However, instead of giving it a filename with a .scala extension containing Scala code to interpret as you did in every previous example,⁶ in this case you'll give it the name of a standalone object containing a main method of the proper signature. You can run the Summer application, therefore, by typing:

```
$ scala Summer of love
```

You will see checksums printed for the two command line arguments:

```
of: -213  
love: -182
```

4.5 The App trait

Scala provides a trait, `scala.App`, that can save you some finger typing. Although we haven't yet covered everything you'll need to understand exactly how this trait works, we figured you'd want to know about it now anyway. Listing 4.4 shows an example:

```
import ChecksumAccumulator.calculate  
object FallWinterSpringSummer extends App {  
    for (season <- List("fall", "winter", "spring"))  
        println(season + ": " + calculate(season))  
}
```

Listing 4.4 · Using the App trait.

To use the trait, you first write “extends App” after the name of your singleton object. Then instead of writing a main method, you place the code

⁶The actual mechanism that the scala program uses to “interpret” a Scala source file is that it compiles the Scala source code to Java bytecodes, loads them immediately via a class loader, and executes them.

you would have put in the `main` method directly between the curly braces of the singleton object. You can access command-line arguments via an array of strings named `args`. That's it. You can compile and run this application just like any other.

4.6 Conclusion

This chapter has given you the basics of classes and objects in Scala, and shown you how to compile and run applications. In the next chapter, you'll learn about Scala's basic types and how to use them.

Chapter 5

Basic Types and Operations

Now that you've seen classes and objects in action, it's a good time to look at Scala's basic types and operations in more depth. If you're familiar with Java, you'll be glad to find that Java's basic types and operators have the same meaning in Scala. However, there are some interesting differences that will make this chapter worth reading even if you're an experienced Java developer. Because some aspects of Scala covered in this chapter are essentially the same as in Java, we've inserted notes indicating what sections Java developers can safely skip.

In this chapter, you'll get an overview of Scala's basic types, including `Strings` and the value types `Int`, `Long`, `Short`, `Byte`, `Float`, `Double`, `Char`, and `Boolean`. You'll learn the operations you can perform on these types, including how operator precedence works in Scala expressions. You'll also learn how implicit conversions can "enrich" variants of these basic types, giving you additional operations beyond those supported by Java.

5.1 Some basic types

Several fundamental types of Scala, along with the ranges of values instances of these types may have, are shown in [Table 5.1](#). Collectively, types `Byte`, `Short`, `Int`, `Long`, and `Char` are called *integral types*. The integral types plus `Float` and `Double` are called *numeric types*.

Other than `String`, which resides in package `java.lang`, all of the types shown in [Table 5.1](#) are members of package `scala`.¹ For example, the full

¹Packages, which were briefly described in [Step 1](#) in [Chapter 2](#), will be covered in depth in [Chapter 13](#).

Table 5.1 · Some basic types

Basic type	Range
Byte	8-bit signed two's complement integer (-2 ⁷ to 2 ⁷ - 1, inclusive)
Short	16-bit signed two's complement integer (-2 ¹⁵ to 2 ¹⁵ - 1, inclusive)
Int	32-bit signed two's complement integer (-2 ³¹ to 2 ³¹ - 1, inclusive)
Long	64-bit signed two's complement integer (-2 ⁶³ to 2 ⁶³ - 1, inclusive)
Char	16-bit unsigned Unicode character (0 to 2 ¹⁶ - 1, inclusive)
String	a sequence of Chars
Float	32-bit IEEE 754 single-precision float
Double	64-bit IEEE 754 double-precision float
Boolean	true or false

name of Int is `scala.Int`. However, given that all the members of package `scala` and `java.lang` are automatically imported into every Scala source file, you can just use the simple names (*i.e.*, names like Boolean, Char, or String) everywhere.

Savvy Java developers will note that Scala's basic types have the exact same ranges as the corresponding types in Java. This enables the Scala compiler to transform instances of Scala *value types*, such as Int or Double, down to Java primitive types in the bytecodes it produces.

5.2 Literals

All of the basic types listed in Table 5.1 can be written with *literals*. A literal is a way to write a constant value directly in code.

Fast track for Java programmers

The syntax of most literals shown in this section are exactly the same as in Java, so if you're a Java master, you can safely skip much of this section.

Some differences you should read about are Scala's literals for raw strings and symbols, described starting on page 117, and string interpolation, described starting on page 119. Also, Scala does not support octal literals; integer literals that start with a 0, such as 031, do not compile.

Integer literals

Integer literals for the types Int, Long, Short, and Byte come in two forms: decimal and hexadecimal. The way an integer literal begins indicates the base of the number. If the number begins with a 0x or 0X, it is hexadecimal (base 16), and may contain 0 through 9 as well as upper or lowercase digits A through F. Some examples are:

```
scala> val hex = 0x5
hex: Int = 5

scala> val hex2 = 0x00FF
hex2: Int = 255

scala> val magic = 0xcafebabe
magic: Int = -889275714
```

Note that the Scala shell always prints integer values in base 10, no matter what literal form you may have used to initialize it. Thus the interpreter displays the value of the hex2 variable you initialized with literal 0x00FF as decimal 255. (Of course, you don't need to take our word for it. A good way to start getting a feel for the language is to try these statements out in the interpreter as you read this chapter.) If the number begins with a non-zero digit, and is otherwise undecorated, it is decimal (base 10). For example:

```
scala> val dec1 = 31
dec1: Int = 31

scala> val dec2 = 255
dec2: Int = 255

scala> val dec3 = 20
dec3: Int = 20
```

If an integer literal ends in an L or l, it is a Long; otherwise it is an Int. Some examples of Long integer literals are:

```
scala> val prog = 0XCAFEBABEL
prog: Long = 3405691582

scala> val tower = 35L
tower: Long = 35
```

```
scala> val of = 311
of: Long = 31
```

If an Int literal is assigned to a variable of type Short or Byte, the literal is treated as if it were a Short or Byte type so long as the literal value is within the valid range for that type. For example:

```
scala> val little: Short = 367
little: Short = 367

scala> val littler: Byte = 38
littler: Byte = 38
```

Floating point literals

Floating point literals are made up of decimal digits, optionally containing a decimal point, and optionally followed by an E or e and an exponent. Some examples of floating-point literals are:

```
scala> val big = 1.2345
big: Double = 1.2345

scala> val bigger = 1.2345e1
bigger: Double = 12.345

scala> val biggerStill = 123E45
biggerStill: Double = 1.23E47
```

Note that the exponent portion means the power of 10 by which the other portion is multiplied. Thus, 1.2345e1 is 1.2345 *times* 10^1 , which is 12.345. If a floating-point literal ends in an F or f, it is a Float; otherwise it is a Double. Optionally, a Double floating-point literal can end in D or d. Some examples of Float literals are:

```
scala> val little = 1.2345F
little: Float = 1.2345

scala> val littleBigger = 3e5f
littleBigger: Float = 300000.0
```

That last value expressed as a Double could take these (and other) forms:

```
scala> val anotherDouble = 3e5
anotherDouble: Double = 300000.0

scala> val yetAnother = 3e5D
yetAnother: Double = 300000.0
```

Character literals

Character literals are composed of any Unicode character between single quotes, such as:

```
scala> val a = 'A'
a: Char = A
```

In addition to providing an explicit character between the single quotes, you can identify a character using its Unicode code point. To do so, write \u followed by four hex digits with the code point, like this:

```
scala> val d = '\u0041'
d: Char = A

scala> val f = '\u0044'
f: Char = D
```

In fact, such Unicode characters can appear anywhere in a Scala program. For instance you could also write an identifier like this:

```
scala> val B\u0041\u0044 = 1
BAD: Int = 1
```

This identifier is treated as identical to BAD, the result of expanding the two Unicode characters in the code above. In general, it is a bad idea to name identifiers like this because it is hard to read. Rather, this syntax is intended to allow Scala source files that include non-ASCII Unicode characters to be represented in ASCII.

Finally, there are also a few character literals represented by special escape sequences, shown in [Table 5.2](#). For example:

```
scala> val backslash = '\\'
backslash: Char = \
```

Table 5.2 · Special character literal escape sequences

Literal	Meaning
\n	line feed (\u000A)
\b	backspace (\u0008)
\t	tab (\u0009)
\f	form feed (\u000C)
\r	carriage return (\u000D)
\"	double quote (\u0022)
\'	single quote (\u0027)
\\	backslash (\u005C)

String literals

A string literal is composed of characters surrounded by double quotes:

```
scala> val hello = "hello"
hello: String = hello
```

The syntax of the characters within the quotes is the same as with character literals. For example:

```
scala> val escapes = "\\\\"\'"
escapes: String = \"'"
```

Because this syntax is awkward for strings that contain a lot of escape sequences or strings that span multiple lines, Scala includes a special syntax for *raw strings*. You start and end a raw string with three double quotation marks in a row ("""""). The interior of a raw string may contain any characters whatsoever, including newlines, quotation marks, and special characters, except of course three quotes in a row. For example, the following program prints out a message using a raw string:

```
println("""Welcome to Ultamix 3000.
Type "HELP" for help.""")
```

However, running this code does not produce quite what is desired:

```
Welcome to Ultamix 3000.
Type "HELP" for help.
```

The issue is that the leading spaces before the second line are included in the string! To help with this common situation, you can call `stripMargin` on strings. To use this method, put a pipe character (|) at the front of each line, and then call `stripMargin` on the whole string:

```
println("""|Welcome to Ultamix 3000.  
|Type "HELP" for help.""".stripMargin)
```

Now the code behaves as desired:

```
Welcome to Ultamix 3000.  
Type "HELP" for help.
```

Symbol literals

A symbol literal is written '*ident*', where *ident* can be any alphanumeric identifier. Such literals are mapped to instances of the predefined class `scala.Symbol`. Specifically, the literal 'cymbal' will be expanded by the compiler to a factory method invocation: `Symbol("cymbal")`. Symbol literals are typically used in situations where you would use just an identifier in a dynamically typed language. For instance, you might want to define a method that updates a record in a database:

```
scala> def updateRecordByName(r: Symbol, value: Any) = {  
    // code goes here  
}  
updateRecordByName: (Symbol,Any)Unit
```

The method takes as parameters a symbol indicating the name of a record field and a value with which the field should be updated in the record. In a dynamically typed language, you could invoke this operation passing an undeclared field identifier to the method, but in Scala this would not compile:

```
scala> updateRecordByName(favoriteAlbum, "OK Computer")  
<console>:6: error: not found: value favoriteAlbum  
        updateRecordByName(favoriteAlbum, "OK Computer")  
               ^
```

Instead, and almost as concisely, you can pass a symbol literal:

```
scala> updateRecordByName('favoriteAlbum, "OK Computer")
```

There is not much you can do with a symbol, except find out its name:

```
scala> val s = 'aSymbol
s: Symbol = 'aSymbol

scala> val nm = s.name
nm: String = aSymbol
```

Another thing that's noteworthy is that symbols are *interned*. If you write the same symbol literal twice, both expressions will refer to the exact same `Symbol` object.

Boolean literals

The Boolean type has two literals, `true` and `false`:

```
scala> val bool = true
bool: Boolean = true

scala> val fool = false
fool: Boolean = false
```

That's all there is to it. You are now literally² an expert in Scala.

5.3 String interpolation

Scala includes a flexible mechanism for string interpolation, which allows you to embed expressions within string literals. Its most common use case is to provide a concise and readable alternative to string concatenation. Here's an example:

```
val name = "reader"
println(s"Hello, $name!")
```

The expression, `s"Hello, $name!"` is a *processed* string literal. Because the letter `s` immediately precedes the open quote, Scala will use the *s string interpolator* to process the literal. The `s` interpolator will evaluate each embedded expression, invoke `toString` on each result, and replace the embedded expressions in the literal with those results. Thus `s"Hello, $name!"` yields `"Hello, reader!"`, the same result as `"Hello, " + name + "!"`.

²figuratively speaking

You can place any expression after a dollar sign (\$) in a processed string literal. For single-variable expressions, you can often just place the variable name after the dollar sign. Scala will interpret all characters up to the first non-identifier character as the expression. If the expression includes non-identifier characters, you must place it in curly braces, with the open curly brace immediately following the dollar sign. Here's an example:

```
scala> s"The answer is ${6 * 7}."  
res0: String = The answer is 42.
```

Scala provides two other string interpolators by default: `raw` and `f`. The `raw` string interpolator behaves like `s`, except it does not recognize character literal escape sequences (such as those shown in [Table 5.2](#)). For example, the following statement prints four backslashes, not two:

```
println(raw"No\\\\\\escape!") // prints: No\\\\\\escape!
```

The `f` string interpolator allows you to attach `printf`-style formatting instructions to embedded expressions. You place the instructions after the expression, starting with a percent sign (%), using the syntax specified by `java.util.Formatter`. For example, here's how you might format pi:

```
scala> f"${math.Pi}.5f"  
res1: String = 3.14159
```

If you provide no formatting instructions for an embedded expression, the `f` string interpolator will default to `%s`, which means the `toString` value will be substituted, just like the `s` string interpolator. For example:

```
scala> val pi = "Pi"  
pi: String = Pi  
  
scala> f"$pi is approximately ${math.Pi}.8f."  
res2: String = Pi is approximately 3.14159265.
```

In Scala, string interpolation is implemented by rewriting code at compile time. The compiler will treat any expression consisting of an identifier followed immediately by the open double quote of a string literal as a string interpolator expression. The `s`, `f`, and `raw` string interpolators are implemented via this general mechanism. Libraries and users can define other string interpolators for other purposes.

5.4 Operators are methods

Scala provides a rich set of operators for its basic types. As mentioned in previous chapters, these operators are actually just a nice syntax for ordinary method calls. For example, `1 + 2` really means the same thing as `1.+(2)`. In other words, class `Int` contains a method named `+` that takes an `Int` and returns an `Int` result. This `+` method is invoked when you add two `Int`s:

```
scala> val sum = 1 + 2      // Scala invokes 1.+(2)
sum: Int = 3
```

To prove this to yourself, you can write the expression explicitly as a method invocation:

```
scala> val sumMore = 1.+ (2)
sumMore: Int = 3
```

In fact, `Int` contains several *overloaded* `+` methods that take different parameter types.³ For example, `Int` has another method, also named `+`, that takes and returns a `Long`. If you add a `Long` to an `Int`, this alternate `+` method will be invoked, as in:

```
scala> val longSum = 1 + 2L      // Scala invokes 1.+(2L)
longSum: Long = 3
```

The `+` symbol is an operator—an infix operator to be specific. Operator notation is not limited to methods like `+` that look like operators in other languages. You can use *any* method in operator notation. For example, class `String` has a method, `index0f`, that takes one `Char` parameter. The `index0f` method searches the string for the first occurrence of the specified character and returns its index or `-1` if it doesn't find the character. You can use `index0f` as an operator, like this:

```
scala> val s = "Hello, world!"
s: String = Hello, world!
scala> s index0f 'o'      // Scala invokes s.index0f('o')
res0: Int = 4
```

³*Overloaded* methods have the same name but different argument types. More on method overloading in [Section 6.11](#).

In addition, `String` offers an overloaded `index0f` method that takes two parameters, the character for which to search and an index at which to start. (The other `index0f` method, shown previously, starts at index zero, the beginning of the `String`.) Even though this `index0f` method takes two arguments, you can use it in operator notation. But whenever you call a method that takes multiple arguments using operator notation, you have to place those arguments in parentheses. For example, here's how you use this other `index0f` form as an operator (continuing from the previous example):

```
scala> s index0f ('o', 5) // Scala invokes s.index0f('o', 5)
res1: Int = 8
```

Any method can be an operator

In Scala operators are not special language syntax; any method can be an operator. What makes a method an operator is how you *use* it. When you write “`s.index0f('o')`”, `index0f` is not an operator. But when you write “`s index0f 'o'`”, `index0f` *is* an operator, because you're using it in operator notation.

So far, you've seen examples of *infix* operator notation, which means the method to invoke sits between the object and the parameter (or parameters) you wish to pass to the method, as in “`7 + 2`”. Scala also has two other operator notations: *prefix* and *postfix*. In *prefix* notation, you put the method name before the object on which you are invoking the method (for example, the ‘`-`’ in `-7`). In *postfix* notation, you put the method after the object (for example, the “`toLong`” in “`7 toLong`”).

In contrast to the *infix* operator notation—in which operators take two operands, one to the left and the other to the right—*prefix* and *postfix* operators are *unary*: they take just one operand. In *prefix* notation, the operand is to the right of the operator. Some examples of *prefix* operators are `-2.0`, `!found`, and `~0xFF`. As with the *infix* operators, these *prefix* operators are a shorthand way of invoking methods. In this case, however, the name of the method has “`unary_-`” prepended to the operator character. For instance, Scala will transform the expression `-2.0` into the method invocation “`(2.0).unary_-`”. You can demonstrate this to yourself by typing the method call both via operator notation and explicitly:

```
scala> -2.0                                // Scala invokes (2.0).unary_-  
res2: Double = -2.0  
  
scala> (2.0).unary_-  
res3: Double = -2.0
```

The only identifiers that can be used as prefix operators are `+`, `-`, `!`, and `~`. Thus, if you define a method named `unary_!`, you could invoke that method on a value or variable of the appropriate type using prefix operator notation, such as `!p`. But if you define a method named `unary_*`, you wouldn't be able to use prefix operator notation because `*` isn't one of the four identifiers that can be used as prefix operators. You could invoke the method normally, as in `p.unary_*`, but if you attempted to invoke it via `*p`, Scala will parse it as if you'd written `*.p`, which is probably not what you had in mind!⁴

Postfix operators are methods that take no arguments, when they are invoked without a dot or parentheses. In Scala, you can leave off empty parentheses on method calls. The convention is that you include parentheses if the method has side effects, such as `println()`, but you can leave them off if the method has no side effects, such as `toLowerCase` invoked on a `String`:

```
scala> val s = "Hello, world!"  
s: String = Hello, world!  
  
scala> s.toLowerCase  
res4: String = hello, world!
```

In this latter case of a method that requires no arguments, you can alternatively leave off the dot and use postfix operator notation:

```
scala> s.toLowerCase  
res5: String = hello, world!
```

In this case, `toLowerCase` is used as a postfix operator on the operand `s`.

Therefore, to see what operators you can use with Scala's basic types, all you really need to do is look at the methods declared in the type's classes in the Scala API documentation. Given that this is a Scala tutorial, however, we'll give you a quick tour of most of these methods in the next few sections.

⁴All is not necessarily lost, however. There is an extremely slight chance your program with the `*p` might compile as C++.

Fast track for Java programmers

Many aspects of Scala described in the remainder of this chapter are the same as in Java. If you're a Java guru in a rush, you can safely skip to [Section 5.8 on page 128](#), which describes how Scala differs from Java in the area of object equality.

5.5 Arithmetic operations

You can invoke arithmetic methods via infix operator notation for addition (+), subtraction (-), multiplication (*), division (/), and remainder (%) on any numeric type. Here are some examples:

```
scala> 1.2 + 2.3
res6: Double = 3.5

scala> 3 - 1
res7: Int = 2

scala> 'b' - 'a'
res8: Int = 1

scala> 2L * 3L
res9: Long = 6

scala> 11 / 4
res10: Int = 2

scala> 11 % 4
res11: Int = 3

scala> 11.0f / 4.0f
res12: Float = 2.75

scala> 11.0 % 4.0
res13: Double = 3.0
```

When both the left and right operands are integral types (Int, Long, Byte, Short, or Char), the / operator will tell you the whole number portion of the quotient, excluding any remainder. The % operator indicates the remainder of an implied integer division.

The floating-point remainder you get with % is not the one defined by the IEEE 754 standard. The IEEE 754 remainder uses rounding division, not truncating division, in calculating the remainder, so it is quite different from

the integer remainder operation. If you really want an IEEE 754 remainder, you can call `IEEEremainder` on `scala.math`, as in:

```
scala> math.IEEEremainder(11.0, 4.0)
res14: Double = -1.0
```

The numeric types also offer unary prefix operators `+` (method `unary_+`) and `-` (method `unary_-`), which allow you to indicate whether a literal number is positive or negative, as in `-3` or `+4.0`. If you don't specify a unary `+` or `-`, a literal number is interpreted as positive. Unary `+` exists solely for symmetry with unary `-`, but has no effect. The unary `-` can also be used to negate a variable. Here are some examples:

```
scala> val neg = 1 + -3
neg: Int = -2

scala> val y = +3
y: Int = 3

scala> -neg
res15: Int = 2
```

5.6 Relational and logical operations

You can compare numeric types with relational methods greater than (`>`), less than (`<`), greater than or equal to (`>=`), and less than or equal to (`<=`), which yield a Boolean result. In addition, you can use the unary ‘`!`’ operator (the `unary_!` method) to invert a Boolean value. Here are a few examples:

```
scala> 1 > 2
res16: Boolean = false

scala> 1 < 2
res17: Boolean = true

scala> 1.0 <= 1.0
res18: Boolean = true

scala> 3.5f >= 3.6f
res19: Boolean = false
```

```
scala> 'a' >= 'A'  
res20: Boolean = true  
  
scala> val untrue = !true  
untrue: Boolean = false
```

Logical methods, logical-and (`&&` and `&`) and logical-or (`||` and `|`), take Boolean operands in infix notation and yield a Boolean result. For example:

```
scala> val toBe = true  
toBe: Boolean = true  
  
scala> val question = toBe || !toBe  
question: Boolean = true  
  
scala> val paradox = toBe && !toBe  
paradox: Boolean = false
```

The `&&` and `||` operations *short-circuit* as in Java: expressions built from these operators are only evaluated as far as needed to determine the result. In other words, the right-hand side of `&&` and `||` expressions won't be evaluated if the left-hand side determines the result. For example, if the left-hand side of a `&&` expression evaluates to `false`, the result of the expression will definitely be `false`, so the right-hand side is not evaluated. Likewise, if the left-hand side of a `||` expression evaluates to `true`, the result of the expression will definitely be `true`, so the right-hand side is not evaluated.

```
scala> def salt() = { println("salt"); false }  
salt: ()Boolean  
  
scala> def pepper() = { println("pepper"); true }  
pepper: ()Boolean  
  
scala> pepper() && salt()  
pepper  
salt  
res21: Boolean = false  
  
scala> salt() && pepper()  
salt  
res22: Boolean = false
```

In the first expression, `pepper` and `salt` are invoked, but in the second, only `salt` is invoked. Given `salt` returns `false`, there's no need to call `pepper`.

If you want to evaluate the right hand side no matter what, use `&` and `|` instead. The `&` method performs a logical-and operation, and `|` a logical-or, but don't short-circuit like `&&` and `||`. Here's an example:

```
scala> salt() & pepper()
salt
pepper
res23: Boolean = false
```

Note

You may be wondering how short-circuiting can work given operators are just methods. Normally, all arguments are evaluated before entering a method, so how can a method avoid evaluating its second argument? The answer is that all Scala methods have a facility for delaying the evaluation of their arguments, or even declining to evaluate them at all. The facility is called *by-name parameters* and is discussed in [Section 9.5](#).

5.7 Bitwise operations

Scala enables you to perform operations on individual bits of integer types with several bitwise methods. The bitwise methods are: bitwise-and (`&`), bitwise-or (`|`), and bitwise-xor (`^`).⁵ The unary bitwise complement operator (`~`), the method `unary_~`) inverts each bit in its operand. For example:

```
scala> 1 & 2
res24: Int = 0

scala> 1 | 2
res25: Int = 3

scala> 1 ^ 3
res26: Int = 2

scala> ~1
res27: Int = -2
```

The first expression, `1 & 2`, bitwise-ands each bit in 1 (0001) and 2 (0010), which yields 0 (0000). The second expression, `1 | 2`, bitwise-ors each bit in

⁵The bitwise-xor method performs an *exclusive or* on its operands. Identical bits yield a 0. Different bits yield a 1. Thus $0011 \wedge 0101$ yields 0110.

the same operands, yielding 3 (0011). The third expression, $1 \wedge 3$, bitwise-xors each bit in 1 (0001) and 3 (0011), yielding 2 (0010). The final expression, ~ 1 , inverts each bit in 1 (0001), yielding -2, which in binary looks like 11111111111111111111111111111111.

Scala integer types also offer three shift methods: shift left ($<<$), shift right ($>>$), and unsigned shift right ($>>>$). The shift methods, when used in infix operator notation, shift the integer value on the left of the operator by the amount specified by the integer value on the right. Shift left and unsigned shift right fill with zeroes as they shift. Shift right fills with the highest bit (the sign bit) of the left-hand value as it shifts. Here are some examples:

```
scala> -1 >> 31
res28: Int = -1
scala> -1 >>> 31
res29: Int = 1
scala> 1 << 2
res30: Int = 4
```

-1 in binary is 11111111111111111111111111111111. In the first example, $-1 >> 31$, -1 is shifted to the right 31 bit positions. Since an Int consists of 32 bits, this operation effectively moves the leftmost bit over until it becomes the rightmost bit.⁶ Since the $>>$ method fills with ones as it shifts right, because the leftmost bit of -1 is 1, the result is identical to the original left operand, 32 one bits, or -1. In the second example, $-1 >>> 31$, the leftmost bit is again shifted right until it is in the rightmost position, but this time filling with zeroes along the way. Thus the result this time is binary 00000000000000000000000000000001, or 1. In the final example, $1 << 2$, the left operand, 1, is shifted left two positions (filling in with zeroes), resulting in binary 0000000000000000000000000000000100, or 4.

5.8 Object equality

If you want to compare two objects for equality, you can use either `==` or its inverse `!=`. Here are a few simple examples:

⁶The leftmost bit in an integer type is the sign bit. If the leftmost bit is 1, the number is negative. If 0, the number is positive.

```
scala> 1 == 2
res31: Boolean = false

scala> 1 != 2
res32: Boolean = true

scala> 2 == 2
res33: Boolean = true
```

These operations actually apply to all objects, not just basic types. For example, you can use `==` to compare lists:

```
scala> List(1, 2, 3) == List(1, 2, 3)
res34: Boolean = true

scala> List(1, 2, 3) == List(4, 5, 6)
res35: Boolean = false
```

Going further, you can compare two objects that have different types:

```
scala> 1 == 1.0
res36: Boolean = true

scala> List(1, 2, 3) == "hello"
res37: Boolean = false
```

You can even compare against `null`, or against things that might be `null`. No exception will be thrown:

```
scala> List(1, 2, 3) == null
res38: Boolean = false

scala> null == List(1, 2, 3)
res39: Boolean = false
```

As you see, `==` has been carefully crafted so that you get just the equality comparison you want in most cases. This is accomplished with a very simple rule: First check the left side for `null`. If it is not `null`, call the `equals` method. Since `equals` is a method, the precise comparison you get depends on the type of the left-hand argument. Since there is an automatic `null` check, you do not have to do the check yourself.⁷

⁷The automatic check does not look at the right-hand side, but any reasonable `equals` method should return `false` if its argument is `null`.

This kind of comparison will yield `true` on different objects, so long as their contents are the same and their `equals` method is written to be based on contents. For example, here is a comparison between two strings that happen to have the same five letters in them:

```
scala> ("he" + "llo") == "hello"  
res40: Boolean = true
```

How Scala's `==` differs from Java's

In Java, you can use `==` to compare both primitive and reference types. On primitive types, Java's `==` compares value equality, as in Scala. On reference types, however, Java's `==` compares *reference equality*, which means the two variables point to the same object on the JVM's heap. Scala provides a facility for comparing reference equality, as well, under the name `eq`. However, `eq` and its opposite, `ne`, only apply to objects that directly map to Java objects. The full details about `eq` and `ne` are given in [Sections 11.1](#) and [11.2](#). Also, see [Chapter 30](#) on how to write a good `equals` method.

5.9 Operator precedence and associativity

Operator precedence determines which parts of an expression are evaluated before the other parts. For example, the expression $2 + 2 * 7$ evaluates to 16, not 28, because the `*` operator has a higher precedence than the `+` operator. Thus the multiplication part of the expression is evaluated before the addition part. You can of course use parentheses in expressions to clarify evaluation order or to override precedence. For example, if you really wanted the result of the expression above to be 28, you could write the expression like this:

```
(2 + 2) * 7
```

Given that Scala doesn't have operators, per se, just a way to use methods in operator notation, you may be wondering how operator precedence works. Scala decides precedence based on the first character of the methods used in operator notation (there's one exception to this rule, which will be discussed in the following pages). If the method name starts with a `*`, for example,

it will have a higher precedence than a method that starts with a `+`. Thus `2 + 2 * 7` will be evaluated as `2 + (2 * 7)`. Similarly, `a +++ b *** c` (in which `a`, `b`, and `c` are variables, and `+++` and `***` are methods) will be evaluated as `a +++ (b *** c)`, because the `***` method has a higher precedence than the `+++` method.

Table 5.3 · Operator precedence

(all other special characters)
<code>*</code> / <code>%</code>
<code>+</code> <code>-</code>
<code>:</code>
<code>=</code> <code>!</code>
<code><</code> <code>></code>
<code>&</code>
<code>^</code>
<code> </code>
(all letters)
(all assignment operators)

Table 5.3 shows the precedence given to the first character of a method in decreasing order of precedence, with characters on the same line having the same precedence. The higher a character is in this table, the higher the precedence of methods that start with that character. Here's an example that illustrates the influence of precedence:

```
scala> 2 << 2 + 2
res41: Int = 32
```

The `<<` method starts with the character `<`, which appears lower in Table 5.3 than the character `+`, which is the first and only character of the `+` method. Thus `<<` will have lower precedence than `+`, and the expression will be evaluated by first invoking the `+` method, then the `<<` method, as in `2 << (2 + 2)`. $2 + 2$ is 4, by our math, and $2 << 4$ yields 32. If you swap the operators, you'll get a different result:

```
scala> 2 + 2 << 2
res42: Int = 16
```

Since the first characters are the same as in the previous example, the methods will be invoked in the same order. First the `+` method will be invoked, then the `<<` method. So `2 + 2` will again yield `4`, and `4 << 2` is `16`.

The one exception to the precedence rule, alluded to earlier, concerns *assignment operators*, which end in an equals character. If an operator ends in an equals character (`=`), and the operator is not one of the comparison operators `<=`, `>=`, `==`, or `!=`, then the precedence of the operator is the same as that of simple assignment (`=`). That is, it is lower than the precedence of any other operator. For instance:

```
x *= y + 1
```

means the same as:

```
x *= (y + 1)
```

because `**=` is classified as an assignment operator whose precedence is lower than `+`, even though the operator's first character is `*`, which would suggest a precedence higher than `+`.

When multiple operators of the same precedence appear side by side in an expression, the *associativity* of the operators determines the way operators are grouped. The associativity of an operator in Scala is determined by its *last* character. As mentioned on [page 83](#) of [Chapter 3](#), any method that ends in a `:` character is invoked on its right operand, passing in the left operand. Methods that end in any other character are the other way around: They are invoked on their left operand, passing in the right operand. So `a * b` yields `a.*(b)`, but `a :: b` yields `b.:::(a)`.

No matter what associativity an operator has, however, its operands are always evaluated left to right. So if `a` is an expression that is not just a simple reference to an immutable value, then `a :: b` is more precisely treated as the following block:

```
{ val x = a; b.:::(x) }
```

In this block `a` is still evaluated before `b`, and then the result of this evaluation is passed as an operand to `b`'s `:::` method.

This associativity rule also plays a role when multiple operators of the same precedence appear side by side. If the methods end in `:`, they are grouped right to left; otherwise, they are grouped left to right. For example,

`a :::: b :::: c` is treated as `a :::: (b :::: c)`. But `a * b * c`, by contrast, is treated as `(a * b) * c`.

Operator precedence is part of the Scala language. You needn't be afraid to use it. Nevertheless, it is good style to use parentheses to clarify what operators are operating upon what expressions. Perhaps the only precedence you can truly count on other programmers knowing without looking up is that multiplicative operators, `*`, `/`, and `%`, have a higher precedence than the additive ones `+` and `-`. Thus even if `a + b << c` yields the result you want without parentheses, the extra clarity you get by writing `(a + b) << c` may reduce the frequency with which your peers utter your name in operator notation, for example, by shouting in disgust, “`bills !*&^%~ code!`”.⁸

5.10 Rich wrappers

You can invoke many more methods on Scala's basic types than were described in the previous sections. A few examples are shown in [Table 5.4](#). These methods are available via *implicit conversions*, a technique that will be described in detail in [Chapter 21](#). All you need to know for now is that for each basic type described in this chapter, there is also a “rich wrapper” that provides several additional methods. To see all the available methods on the basic types, therefore, you should look at the API documentation on the rich wrapper for each basic type. Those classes are listed in [Table 5.5](#).

5.11 Conclusion

The main take-aways from this chapter are that operators in Scala are method calls, and that implicit conversions to rich variants exist for Scala's basic types that add even more useful methods. In the next chapter, we'll show you what it means to design objects in a functional style that gives new implementations of some of the operators that you have seen in this chapter.

⁸By now you should be able to figure out that given this code, the Scala compiler would invoke `(bills.!*&^%~(code)).!()`.

Table 5.4 · Some rich operations

Code	Result
<code>0 max 5</code>	5
<code>0 min 5</code>	0
<code>-2.7 abs</code>	2.7
<code>-2.7 round</code>	-3L
<code>1.5 isInfinity</code>	false
<code>(1.0 / 0) isInfinity</code>	true
<code>4 to 6</code>	Range(4, 5, 6)
<code>"bob" capitalize</code>	"Bob"
<code>"robert" drop 2</code>	"bert"

Table 5.5 · Rich wrapper classes

Basic type	Rich wrapper
<code>Byte</code>	<code>scala.runtime.RichByte</code>
<code>Short</code>	<code>scala.runtime.RichShort</code>
<code>Int</code>	<code>scala.runtime.RichInt</code>
<code>Long</code>	<code>scala.runtime.RichLong</code>
<code>Char</code>	<code>scala.runtime.RichChar</code>
<code>Float</code>	<code>scala.runtime.RichFloat</code>
<code>Double</code>	<code>scala.runtime.RichDouble</code>
<code>Boolean</code>	<code>scala.runtime.RichBoolean</code>
<code>String</code>	<code>scala.collection.immutable.StringOps</code>

Chapter 6

Functional Objects

With the understanding of Scala basics you've gained from previous chapters, you're ready to design more full-featured classes in Scala. In this chapter, the emphasis is on classes that define functional objects, or objects that do not have any mutable state. As a running example, we'll create several variants of a class that models rational numbers as immutable objects. Along the way, we'll show you more aspects of object-oriented programming in Scala: class parameters and constructors, methods and operators, private members, overriding, checking preconditions, overloading, and self references.

6.1 A specification for class Rational

A *rational number* is a number that can be expressed as a ratio $\frac{n}{d}$, where n and d are integers, except that d cannot be zero. n is called the *numerator* and d the *denominator*. Examples of rational numbers are $\frac{1}{2}$, $\frac{2}{3}$, $\frac{112}{239}$, and $\frac{2}{1}$. Compared to floating-point numbers, rational numbers have the advantage that fractions are represented exactly, without rounding or approximation.

The class we'll design in this chapter must model the behavior of rational numbers, including allowing them to be added, subtracted, multiplied, and divided. To add two rationals, you must first obtain a common denominator, then add the two numerators. For example, to add $\frac{1}{2} + \frac{2}{3}$, you multiply both parts of the left operand by 3 and both parts of the right operand by 2, which gives you $\frac{3}{6} + \frac{4}{6}$. Adding the two numerators yields the result, $\frac{7}{6}$. To multiply two rational numbers, you can simply multiply their numerators and multiply their denominators. Thus, $\frac{1}{2} * \frac{2}{5}$ gives $\frac{2}{10}$, which can be represented more compactly in its “normalized” form as $\frac{1}{5}$. You divide by swapping the

numerator and denominator of the right operand and then multiplying. For instance $\frac{1}{2}/\frac{3}{5}$ is the same as $\frac{1}{2} * \frac{5}{3}$, or $\frac{5}{6}$.

One, maybe rather trivial, observation is that in mathematics, rational numbers do not have mutable state. You can add one rational number to another, but the result will be a new rational number. The original numbers will not have “changed.” The immutable Rational class we’ll design in this chapter will have the same property. Each rational number will be represented by one Rational object. When you add two Rational objects, you’ll create a new Rational object to hold the sum.

This chapter will give you a glimpse of some of the ways Scala enables you to write libraries that feel like native language support. For example, at the end of this chapter you’ll be able to do this with class Rational:

```
scala> val oneHalf = new Rational(1, 2)
oneHalf: Rational = 1/2

scala> val twoThirds = new Rational(2, 3)
twoThirds: Rational = 2/3

scala> (oneHalf / 7) + (1 - twoThirds)
res0: Rational = 17/42
```

6.2 Constructing a Rational

A good place to start designing class Rational is to consider how client programmers will create a new Rational object. Given we’ve decided to make Rational objects immutable, we’ll require that clients provide all data needed by an instance (in this case, a numerator and a denominator) when they construct the instance. Thus, we will start the design with this:

```
class Rational(n: Int, d: Int)
```

One of the first things to note about this line of code is that if a class doesn’t have a body, you don’t need to specify empty curly braces (though you could, of course, if you wanted to). The identifiers n and d in the parentheses after the class name, Rational, are called *class parameters*. The Scala compiler will gather up these two class parameters and create a *primary constructor* that takes the same two parameters.

Immutable object trade-offs

Immutable objects offer several advantages over mutable objects, and one potential disadvantage. First, immutable objects are often easier to reason about than mutable ones, because they do not have complex state spaces that change over time. Second, you can pass immutable objects around quite freely, whereas you may need to make defensive copies of mutable objects before passing them to other code. Third, there is no way for two threads concurrently accessing an immutable to corrupt its state once it has been properly constructed, because no thread can change the state of an immutable. Fourth, immutable objects make safe hash table keys. If a mutable object is mutated after it is placed into a `HashSet`, for example, that object may not be found the next time you look into the `HashSet`.

The main disadvantage of immutable objects is that they sometimes require that a large object graph be copied, whereas an update could be done in its place. In some cases this can be awkward to express and might also cause a performance bottleneck. As a result, it is not uncommon for libraries to provide mutable alternatives to immutable classes. For example, class `StringBuilder` is a mutable alternative to the immutable `String`. We'll give you more information on designing mutable objects in Scala in [Chapter 18](#).

Note

This initial `Rational` example highlights a difference between Java and Scala. In Java, classes have constructors, which can take parameters; whereas in Scala, classes can take parameters directly. The Scala notation is more concise—class parameters can be used directly in the body of the class; there's no need to define fields and write assignments that copy constructor parameters into fields. This can yield substantial savings in boilerplate code, especially for small classes.

The Scala compiler will compile any code you place in the class body, which isn't part of a field or a method definition, into the primary constructor. For example, you could print a debug message like this:

```
class Rational(n: Int, d: Int) {  
    println("Created " + n + "/" + d)  
}
```

Given this code, the Scala compiler would place the call to `println` into `Rational`'s primary constructor. The `println` call will, therefore, print its debug message whenever you create a new `Rational` instance:

```
scala> new Rational(1, 2)
Created 1/2
res0: Rational = Rational@2591e0c9
```

6.3 Reimplementing the `toString` method

When we created an instance of `Rational` in the previous example, the interpreter printed “`Rational@90110a`”. The interpreter obtained this somewhat funny looking string by calling `toString` on the `Rational` object. By default, class `Rational` inherits the implementation of `toString` defined in class `java.lang.Object`, which just prints the class name, an @ sign, and a hexadecimal number. The result of `toString` is primarily intended to help programmers by providing information that can be used in debug print statements, log messages, test failure reports, and interpreter and debugger output. The result currently provided by `toString` is not especially helpful because it doesn't give any clue about the rational number's value. A more useful implementation of `toString` would print out the values of the `Rational`'s numerator and denominator. You can *override* the default implementation by adding a method `toString` to class `Rational`, like this:

```
class Rational(n: Int, d: Int) {
    override def toString = n + "/" + d
}
```

The `override` modifier in front of a method definition signals that a previous method definition is overridden (more on this in [Chapter 10](#)). Since `Rational` numbers will display nicely now, we removed the debug `println` statement we put into the body of previous version of class `Rational`. You can test the new behavior of `Rational` in the interpreter:

```
scala> val x = new Rational(1, 3)
x: Rational = 1/3

scala> val y = new Rational(5, 7)
y: Rational = 5/7
```

6.4 Checking preconditions

As a next step, we will turn our attention to a problem with the current behavior of the primary constructor. As mentioned at the beginning of this chapter, rational numbers may not have a zero in the denominator. Currently, however, the primary constructor accepts a zero passed as d:

```
scala> new Rational(5, 0)
res1: Rational = 5/0
```

One of the benefits of object-oriented programming is that it allows you to encapsulate data inside objects so that you can ensure the data is valid throughout its lifetime. In the case of an immutable object such as Rational, this means that you should ensure the data is valid when the object is constructed. Given that a zero denominator is an invalid state for a Rational number, you should not let a Rational be constructed if a zero is passed in the d parameter.

The best way to approach this problem is to define as a *precondition* of the primary constructor that d must be non-zero. A precondition is a constraint on values passed into a method or constructor, a requirement which callers must fulfill. One way to do that is to use require,¹ like this:

```
class Rational(n: Int, d: Int) {
    require(d != 0)
    override def toString = n + "/" + d
}
```

The require method takes one boolean parameter. If the passed value is true, require will return normally. Otherwise, require will prevent the object from being constructed by throwing an IllegalArgumentException.

6.5 Adding fields

Now that the primary constructor is properly enforcing its precondition, we will turn our attention to supporting addition. To do so, we'll define a public add method on class Rational that takes another Rational as a parameter. To keep Rational immutable, the add method must not add the passed

¹The require method is defined in standalone object, Predef. As mentioned in Section 4.4, Predef's members are imported automatically into every Scala source file.

rational number to itself. Rather, it must create and return a new Rational that holds the sum. You might think you could write add this way:

```
class Rational(n: Int, d: Int) { // This won't compile
    require(d != 0)
    override def toString = n + "/" + d
    def add(that: Rational): Rational =
        new Rational(n * that.d + that.n * d, d * that.d)
}
```

However, given this code the compiler will complain:

```
<console>:11: error: value d is not a member of Rational
    new Rational(n * that.d + that.n * d, d * that.d)
                           ^
<console>:11: error: value d is not a member of Rational
    new Rational(n * that.d + that.n * d, d * that.d)
                           ^
```

Although class parameters n and d are in scope in the code of your add method, you can only access their value on the object on which add was invoked. Thus, when you say n or d in add's implementation, the compiler is happy to provide you with the values for these class parameters. But it won't let you say that.n or that.d because that does not refer to the Rational object on which add was invoked.² To access the numerator and denominator on that, you'll need to make them into fields. Listing 6.1 shows how you could add these fields to class Rational.³

In the version of Rational shown in Listing 6.1, we added two fields named numer and denom, and initialized them with the values of class parameters n and d.⁴ We also changed the implementation of `toString` and `add` so that they use the fields, not the class parameters. This version of class Rational compiles. You can test it by adding some rational numbers:

²Actually, you could add a Rational to itself, in which case that would refer to the object on which add was invoked. But because you can pass any Rational object to add, the compiler still won't let you say that.n.

³In Section 10.6 you'll find out about *parametric fields*, which provide a shorthand for writing the same code.

⁴Even though n and d are used in the body of the class, given they are only used inside constructors, the Scala compiler will not emit fields for them. Thus, given this code the Scala compiler will generate a class with two Int fields, one for numer and one for denom.

```
class Rational(n: Int, d: Int) {  
    require(d != 0)  
    val numer: Int = n  
    val denom: Int = d  
    override def toString = numer + "/" + denom  
    def add(that: Rational): Rational =  
        new Rational(  
            numer * that.denom + that.numer * denom,  
            denom * that.denom  
        )  
}
```

Listing 6.1 · Rational with fields.

```
scala> val oneHalf = new Rational(1, 2)  
oneHalf: Rational = 1/2  
  
scala> val twoThirds = new Rational(2, 3)  
twoThirds: Rational = 2/3  
  
scala> oneHalf add twoThirds  
res2: Rational = 7/6
```

One other thing you can do now that you couldn't do before is access the numerator and denominator values from outside the object. Simply access the public `numer` and `denom` fields, like this:

```
scala> val r = new Rational(1, 2)  
r: Rational = 1/2  
  
scala> r.numer  
res3: Int = 1  
  
scala> r.denom  
res4: Int = 2
```

6.6 Self references

The keyword `this` refers to the object instance on which the currently executing method was invoked, or if used in a constructor, the object instance

being constructed. As an example, consider adding a method, `lessThan`, which tests whether the given `Rational` is smaller than a parameter:

```
def lessThan(that: Rational) =  
    this.numer * that.denom < that.numer * this.denom
```

Here, `this.numer` refers to the numerator of the object on which `lessThan` was invoked. You can also leave off the `this` prefix and write just `numer`; the two notations are equivalent.

As an example of where you can't do without `this`, consider adding a `max` method to class `Rational` that returns the greater of the given rational number and an argument:

```
def max(that: Rational) =  
    if (this.lessThan(that)) that else this
```

Here, the first `this` is redundant. You could have left it off and written: `lessThan(that)`. But the second `this` represents the result of the method in the case where the test returns false; were you to omit it, there would be nothing left to return!

6.7 Auxiliary constructors

Sometimes you need multiple constructors in a class. In Scala, constructors other than the primary constructor are called *auxiliary constructors*. For example, a rational number with a denominator of 1 can be written more succinctly as simply the numerator. Instead of $\frac{5}{1}$, for example, you can just write 5. It might be nice, therefore, if instead of writing `new Rational(5, 1)`, client programmers could simply write `new Rational(5)`. This would require adding an auxiliary constructor to `Rational` that takes only one argument, the numerator, with the denominator predefined to be 1. Listing 6.2 shows what that would look like.

Auxiliary constructors in Scala start with `def this(...)`. The body of `Rational`'s auxiliary constructor merely invokes the primary constructor, passing along its lone argument, `n`, as the numerator and 1 as the denominator. You can see the auxiliary constructor in action by typing the following into the interpreter:

```
scala> val y = new Rational(3)  
y: Rational = 3/1
```

```
class Rational(n: Int, d: Int) {  
    require(d != 0)  
    val numer: Int = n  
    val denom: Int = d  
    def this(n: Int) = this(n, 1) // auxiliary constructor  
    override def toString = numer + "/" + denom  
    def add(that: Rational): Rational =  
        new Rational(  
            numer * that.denom + that.numer * denom,  
            denom * that.denom  
        )  
}
```

Listing 6.2 · Rational with an auxiliary constructor.

In Scala, every auxiliary constructor must invoke another constructor of the same class as its first action. In other words, the first statement in every auxiliary constructor in every Scala class will have the form “this(...)”. The invoked constructor is either the primary constructor (as in the Rational example), or another auxiliary constructor that comes textually before the calling constructor. The net effect of this rule is that every constructor invocation in Scala will end up eventually calling the primary constructor of the class. The primary constructor is thus the single point of entry of a class.

Note

If you’re familiar with Java, you may wonder why Scala’s rules for constructors are a bit more restrictive than Java’s. In Java, a constructor must either invoke another constructor of the same class, or directly invoke a constructor of the superclass, as its first action. In a Scala class, only the primary constructor can invoke a superclass constructor. The increased restriction in Scala is really a design trade-off that needed to be paid in exchange for the greater conciseness and simplicity of Scala’s constructors compared to Java’s. Superclasses and the details of how constructor invocation and inheritance interact will be explained in [Chapter 10](#).

6.8 Private fields and methods

In the previous version of Rational, we simply initialized numer with n and denom with d. As a result, the numerator and denominator of a Rational can be larger than needed. For example, the fraction $\frac{66}{42}$ could be normalized to an equivalent reduced form, $\frac{11}{7}$, but Rational's primary constructor doesn't currently do this:

```
scala> new Rational(66, 42)
res5: Rational = 66/42
```

To normalize in this way, you need to divide the numerator and denominator by their *greatest common divisor*. For example, the greatest common divisor of 66 and 42 is 6. (In other words, 6 is the largest integer that divides evenly into both 66 and 42.) Dividing both the numerator and denominator of $\frac{66}{42}$ by 6 yields its reduced form, $\frac{11}{7}$. Listing 6.3 shows one way to do this:

```
class Rational(n: Int, d: Int) {
    require(d != 0)
    private val g = gcd(n.abs, d.abs)
    val numer = n / g
    val denom = d / g
    def this(n: Int) = this(n, 1)
    def add(that: Rational): Rational =
        new Rational(
            numer * that.denom + that.numer * denom,
            denom * that.denom
        )
    override def toString = numer + "/" + denom
    private def gcd(a: Int, b: Int): Int =
        if (b == 0) a else gcd(b, a % b)
}
```

Listing 6.3 · Rational with a private field and method.

In this version of Rational, we added a private field, g, and modified the initializers for numer and denom. (An *initializer* is the code that initializes

a variable; for example, the “`n / g`” that initializes `numer`.) Because `g` is private, it can be accessed inside the body of the class, but not outside. We also added a private method, `gcd`, which calculates the greatest common divisor of two passed `Ints`. For example, `gcd(12, 8)` is 4. As you saw in [Section 4.1](#), to make a field or method private you simply place the `private` keyword in front of its definition. The purpose of the private “helper method” `gcd` is to factor out code needed by some other part of the class, in this case, the primary constructor. To ensure `g` is always positive, we pass the absolute value of `n` and `d`, which we obtain by invoking `abs` on them, a method you can invoke on any `Int` to get its absolute value.

The Scala compiler will place the code for the initializers of `Rational`’s three fields into the primary constructor in the order in which they appear in the source code. Thus, `g`’s initializer, `gcd(n.abs, d.abs)`, will execute before the other two, because it appears first in the source. Field `g` will be initialized with the result, the greatest common divisor of the absolute value of the class parameters, `n` and `d`. Field `g` is then used in the initializers of `numer` and `denom`. By dividing `n` and `d` by their greatest common divisor, `g`, every `Rational` will be constructed in its normalized form:

```
scala> new Rational(66, 42)
res6: Rational = 11/7
```

6.9 Defining operators

The current implementation of `Rational` addition is OK, but could be made more convenient to use. You might ask yourself why you can write:

`x + y`

if `x` and `y` are integers or floating-point numbers, but you have to write:

`x.add(y)`

or at least:

`x add y`

if they are rational numbers. There’s no convincing reason why this should be so. Rational numbers are numbers just like other numbers. In a mathematical sense they are even more natural than, say, floating-point numbers.

Why should you not use the natural arithmetic operators on them? In Scala you can do this. In the rest of this chapter, we'll show you how.

The first step is to replace `add` by the usual mathematical symbol. This is straightforward, as `+` is a legal identifier in Scala. We can simply define a method with `+` as its name. While we're at it, we may as well implement a method named `*` that performs multiplication. The result is shown in Listing 6.4:

```
class Rational(n: Int, d: Int) {  
    require(d != 0)  
    private val g = gcd(n.abs, d.abs)  
    val numer = n / g  
    val denom = d / g  
    def this(n: Int) = this(n, 1)  
    def + (that: Rational): Rational =  
        new Rational(  
            numer * that.denom + that.numer * denom,  
            denom * that.denom  
        )  
    def * (that: Rational): Rational =  
        new Rational(numer * that.numer, denom * that.denom)  
    override def toString = numer + "/" + denom  
    private def gcd(a: Int, b: Int): Int =  
        if (b == 0) a else gcd(b, a % b)  
}
```

Listing 6.4 · Rational with operator methods.

With class `Rational` defined in this manner, you can now write:

```
scala> val x = new Rational(1, 2)  
x: Rational = 1/2  
scala> val y = new Rational(2, 3)  
y: Rational = 2/3  
scala> x + y  
res7: Rational = 7/6
```

As always, the operator syntax on the last input line is equivalent to a method call. You could also write:

```
scala> x.+(y)
res8: Rational = 7/6
```

but this is not as readable.

Another thing to note is that given Scala's rules for operator precedence, which were described in [Section 5.9](#), the `*` method will bind more tightly than the `+` method for `Rationals`. In other words, expressions involving `+` and `*` operations on `Rationals` will behave as expected. For example, `x + x * y` will execute as `x + (x * y)`, not `(x + x) * y`:

```
scala> x + x * y
res9: Rational = 5/6

scala> (x + x) * y
res10: Rational = 2/3

scala> x + (x * y)
res11: Rational = 5/6
```

6.10 Identifiers in Scala

You have now seen the two most important ways to form an identifier in Scala: alphanumeric and operator. Scala has very flexible rules for forming identifiers. Besides the two forms you have seen there are also two others. All four forms of identifier formation are described in this section.

An *alphanumeric identifier* starts with a letter or underscore, which can be followed by further letters, digits, or underscores. The ‘\$’ character also counts as a letter; however, it is reserved for identifiers generated by the Scala compiler. Identifiers in user programs should not contain ‘\$’ characters, even though it will compile; if they do, this might lead to name clashes with identifiers generated by the Scala compiler.

Scala follows Java’s convention of using camel-case⁵ identifiers, such as `toString` and `HashSet`. Although underscores are legal in identifiers, they are not used that often in Scala programs, in part to be consistent with Java,

⁵This style of naming identifiers is called *camel case* because the identifiers have humps consisting of the embedded capital letters.

but also because underscores have many other non-identifier uses in Scala code. As a result, it is best to avoid identifiers like `to_string`, `__init__`, or `name_`. Camel-case names of fields, method parameters, local variables, and functions should start with a lower case letter, for example: `length`, `flatMap`, and `s`. Camel-case names of classes and traits should start with an upper case letter, for example: `BigInt`, `List`, and `UnbalancedTreeMap`.⁶

Note

One consequence of using a trailing underscore in an identifier is that if you attempt, for example, to write a declaration like this, “`val name_ : Int = 1`”, you’ll get a compiler error. The compiler will think you are trying to declare a `val` named “`name_`”. To get this to compile, you would need to insert an extra space before the colon, as in: “`val name_ : Int = 1`”.

One way in which Scala’s conventions depart from Java’s involves constant names. In Scala, the word *constant* does not just mean `val`. Even though a `val` does remain constant after it is initialized, it is still a variable. For example, method parameters are `vals`, but each time the method is called those `vals` can hold different values. A constant is more permanent. For example, `scala.math.Pi` is defined to be the double value closest to the real value of π , the ratio of a circle’s circumference to its diameter. This value is unlikely to change ever; thus, `Pi` is clearly a constant. You can also use constants to give names to values that would otherwise be *magic numbers* in your code: literal values with no explanation, which in the worst case appear in multiple places. You may also want to define constants for use in pattern matching, a use case that will be described in [Section 15.2](#). In Java, the convention is to give constants names that are all upper case, with underscores separating the words, such as `MAX_VALUE` or `PI`. In Scala, the convention is merely that the first character should be upper case. Thus, constants named in the Java style, such as `X_OFFSET`, will work as Scala constants, but the Scala convention is to use camel case for constants, such as `XOffset`.

An *operator identifier* consists of one or more operator characters. Operator characters are printable ASCII characters such as `+`, `:`, `?`, `~` or `#`.⁷ Here

⁶In [Section 16.5](#), you’ll see that sometimes you may want to give a special kind of class known as a *case class* a name consisting solely of operator characters. For example, the Scala API contains a class named `::`, which facilitates pattern matching on `Lists`.

⁷More precisely, an operator character belongs to the Unicode set of mathematical symbols(Sm) or other symbols(So), or to the 7-bit ASCII characters that are not letters, digits,

are some examples of operator identifiers:

```
+  ++  :::  <?>  :->
```

The Scala compiler will internally “mangle” operator identifiers to turn them into legal Java identifiers with embedded \$ characters. For instance, the identifier `:>` would be represented internally as `$colon$minus$greater`. If you ever wanted to access this identifier from Java code, you’d need to use this internal representation.

Because operator identifiers in Scala can become arbitrarily long, there is a small difference between Java and Scala. In Java, the input `x<-y` would be parsed as four lexical symbols, so it would be equivalent to `x < - y`. In Scala, `<-` would be parsed as a single identifier, giving `x <- y`. If you want the first interpretation, you need to separate the `<` and the `-` characters by a space. This is unlikely to be a problem in practice, as very few people would write `x<-y` in Java without inserting spaces or parentheses between the operators.

A *mixed identifier* consists of an alphanumeric identifier, which is followed by an underscore and an operator identifier. For example, `unary_+` used as a method name defines a unary `+` operator. Or, `myvar_=` used as method name defines an assignment operator. In addition, the mixed identifier form `myvar_=` is generated by the Scala compiler to support *properties* (more on that in [Chapter 18](#)).

A *literal identifier* is an arbitrary string enclosed in back ticks (`` ... ``). Some examples of literal identifiers are:

```
`x`  `<clinit>`  `yield`
```

The idea is that you can put any string that’s accepted by the runtime as an identifier between back ticks. The result is always a Scala identifier. This works even if the name contained in the back ticks would be a Scala reserved word. A typical use case is accessing the static `yield` method in Java’s `Thread` class. You cannot write `Thread.yield()` because `yield` is a reserved word in Scala. However, you can still name the method in back ticks, e.g., `Thread.`yield`()`.

parentheses, square brackets, curly braces, single or double quote, or an underscore, period, semi-colon, comma, or back tick character.

6.11 Method overloading

Back to class Rational. With the latest changes, you can now do addition and multiplication operations in a natural style on rational numbers. But one thing still missing is mixed arithmetic. For instance, you cannot multiply a rational number by an integer because the operands of `*` always have to be `Rationals`. So for a rational number `r` you can't write `r * 2`. You must write `r * new Rational(2)`, which is not as nice.

To make Rational even more convenient, we'll add new methods to the class that perform mixed addition and multiplication on rational numbers and integers. While we're at it, we'll add methods for subtraction and division too. The result is shown in [Listing 6.5](#).

There are now two versions each of the arithmetic methods: one that takes a rational as its argument and another that takes an integer. In other words, each of these method names is *overloaded* because each name is now being used by multiple methods. For example, the name `+` is used by one method that takes a `Rational` and another that takes an `Int`. In a method call, the compiler picks the version of an overloaded method that correctly matches the types of the arguments. For instance, if the argument `y` in `x.+(y)` is a `Rational`, the compiler will pick the method `+` that takes a `Rational` parameter. But if the argument is an integer, the compiler will pick the method `+` that takes an `Int` parameter instead. If you try this:

```
scala> val x = new Rational(2, 3)
x: Rational = 2/3

scala> x * x
res12: Rational = 4/9

scala> x * 2
res13: Rational = 4/3
```

You'll see that the `*` method invoked is determined in each case by the type of the right operand.

Note

Scala's process of overloaded method resolution is very similar to Java's. In every case, the chosen overloaded version is the one that best matches the static types of the arguments. Sometimes there is no unique best matching version; in that case the compiler will give you an "ambiguous reference" error.

```
class Rational(n: Int, d: Int) {  
    require(d != 0)  
    private val g = gcd(n.abs, d.abs)  
    val numer = n / g  
    val denom = d / g  
    def this(n: Int) = this(n, 1)  
    def + (that: Rational): Rational =  
        new Rational(  
            numer * that.denom + that.numer * denom,  
            denom * that.denom  
        )  
    def + (i: Int): Rational =  
        new Rational(numer + i * denom, denom)  
    def - (that: Rational): Rational =  
        new Rational(  
            numer * that.denom - that.numer * denom,  
            denom * that.denom  
        )  
    def - (i: Int): Rational =  
        new Rational(numer - i * denom, denom)  
    def * (that: Rational): Rational =  
        new Rational(numer * that.numer, denom * that.denom)  
    def * (i: Int): Rational =  
        new Rational(numer * i, denom)  
    def / (that: Rational): Rational =  
        new Rational(numer * that.denom, denom * that.numer)  
    def / (i: Int): Rational =  
        new Rational(numer, denom * i)  
    override def toString = numer + "/" + denom  
    private def gcd(a: Int, b: Int): Int =  
        if (b == 0) a else gcd(b, a % b)  
}
```

Listing 6.5 · Rational with overloaded methods.

6.12 Implicit conversions

Now that you can write `r * 2`, you might also want to swap the operands, as in `2 * r`. Unfortunately this does not work yet:

```
scala> 2 * r
<console>:10: error: overloaded method value * with
alternatives:
  (x: Double)Double <and>
  (x: Float)Float <and>
  (x: Long)Long <and>
  (x: Int)Int <and>
  (x: Char)Int <and>
  (x: Short)Int <and>
  (x: Byte)Int
cannot be applied to (Rational)
      2 * r
          ^
```

The problem here is that `2 * r` is equivalent to `2.*(r)`, so it is a method call on the number 2, which is an integer. But the `Int` class contains no multiplication method that takes a `Rational` argument—it couldn't because class `Rational` is not a standard class in the Scala library.

However, there is another way to solve this problem in Scala: You can create an implicit conversion that automatically converts integers to rational numbers when needed. Try adding this line in the interpreter:

```
scala> implicit def intToRational(x: Int) = new Rational(x)
```

This defines a conversion method from `Int` to `Rational`. The `implicit` modifier in front of the method tells the compiler to apply it automatically in a number of situations. With the conversion defined, you can now retry the example that failed before:

```
scala> val r = new Rational(2,3)
r: Rational = 2/3

scala> 2 * r
res15: Rational = 4/3
```

For an implicit conversion to work, it needs to be in scope. If you place the implicit method definition inside class `Rational`, it won't be in scope in the interpreter. For now, you'll need to define it directly in the interpreter.

As you can glimpse from this example, implicit conversions are a very powerful technique for making libraries more flexible and more convenient to use. Because they are so powerful, they can also be easily misused. You'll find out more on implicit conversions, including ways to bring them into scope where they are needed, in [Chapter 21](#).

6.13 A word of caution

As this chapter has demonstrated, creating methods with operator names and defining implicit conversions can help you design libraries for which client code is concise and easy to understand. Scala gives you a great deal of power to design such easy-to-use libraries. But please bear in mind that with power comes responsibility.

If used unartfully, both operator methods and implicit conversions can give rise to client code that is hard to read and understand. Because implicit conversions are applied implicitly by the compiler, not explicitly written down in the source code, it can be non-obvious to client programmers what implicit conversions are being applied. And although operator methods will usually make client code more concise, they will only make it more readable to the extent client programmers will be able to recognize and remember the meaning of each operator.

The goal you should keep in mind as you design libraries is not merely enabling concise client code, but readable, understandable client code. Conciseness will often be a big part of that readability, but you can take conciseness too far. By designing libraries that enable tastefully concise and at the same time understandable client code, you can help those client programmers work productively.

6.14 Conclusion

In this chapter, you saw more aspects of classes in Scala. You saw how to add parameters to a class, define several constructors, define operators as methods, and customize classes so that they are natural to use. Maybe most

importantly, you saw that defining and using immutable objects is a quite natural way to code in Scala.

Although the final version of `Rational` shown in this chapter fulfills the requirements set forth at the beginning of the chapter, it could still be improved. We will in fact return to this example later in the book. For example, in [Chapter 30](#), you'll learn how to override `equals` and `hashCode` to allow `Rationals` to behave better when compared with `==` or placed into hash tables. In [Chapter 21](#), you'll learn how to place implicit method definitions in a companion object for `Rational`, so they can be more easily placed into scope when client programmers are working with `Rationals`.

Chapter 7

Built-in Control Structures

Scala has only a handful of built-in control structures. The only control structures are `if`, `while`, `for`, `try`, `match`, and function calls. The reason Scala has so few is that it has included function literals since its inception. Instead of accumulating one higher-level control structure after another in the base syntax, Scala accumulates them in libraries. ([Chapter 9](#) will show precisely how that is done.) This chapter will show those few control structures that are built in.

One thing you will notice is that almost all of Scala's control structures result in some value. This is the approach taken by functional languages, where programs are viewed as computing a value, thus the components of a program should also compute values. You can also view this approach as the logical conclusion of a trend already present in imperative languages. In imperative languages, function calls can return a value, even though having the called function update an output variable passed as an argument would work just as well. In addition, imperative languages often have a ternary operator (such as the `?:` operator of C, C++, and Java), which behaves exactly like `if`, but results in a value. Scala adopts this ternary operator model, but calls it `if`. In other words, Scala's `if` can result in a value. Scala then continues this trend by having `for`, `try`, and `match` also result in values.

Programmers can use these result values to simplify their code, just as they use return values of functions. Without this facility, the programmer must create temporary variables just to hold results that are calculated inside a control structure. Removing these temporary variables makes the code a little simpler, and it also prevents many bugs where you set the variable in one branch but forget to set it in another.

Overall, Scala's basic control structures, minimal as they are, provide all of the essentials from imperative languages. Further, they allow you to shorten your code by consistently having result values. To show you how this works, we'll take a closer look at each of Scala's basic control structures.

7.1 If expressions

Scala's `if` works just like in many other languages. It tests a condition and then executes one of two code branches depending on whether the condition holds true. Here is a common example, written in an imperative style:

```
var filename = "default.txt"
if (!args.isEmpty)
    filename = args(0)
```

This code declares a variable, `filename`, and initializes it to a default value. It then uses an `if` expression to check whether any arguments were supplied to the program. If so, it changes the variable to hold the value specified in the argument list. If no arguments were supplied, it leaves the variable set to the default value.

This code can be written more nicely because, as mentioned in [Step 3](#) in [Chapter 2](#), Scala's `if` is an expression that results in a value. [Listing 7.1](#) shows how you can accomplish the same effect as the previous example, without using any `vars`:

```
val filename =
  if (!args.isEmpty) args(0)
  else "default.txt"
```

[Listing 7.1](#) · Scala's idiom for conditional initialization.

This time, the `if` has two branches. If `args` is not empty, the initial element, `args(0)`, is chosen; otherwise, the default value is chosen. The `if` expression results in the chosen value, and the `filename` variable is initialized with that value. This code is slightly shorter, but its real advantage is that it uses a `val` instead of a `var`. Using a `val` is the functional style, and it helps you in much the same way as a `final` variable in Java. It tells readers of the code that the variable will never change, saving them from scanning all code in the variable's scope to see if it ever changes.

A second advantage to using a `val` instead of a `var` is that it better supports *equational reasoning*. The introduced variable is *equal* to the expression that computes it, assuming that expression has no side effects. Thus, any time you are about to write the variable name, you could instead write the expression. Instead of `println(filename)`, for example, you could just write this:

```
println(if (!args.isEmpty) args(0) else "default.txt")
```

The choice is yours. You can write it either way. Using `vals` helps you safely make this kind of refactoring as your code evolves over time.

Look for opportunities to use `vals`. They can make your code both easier to read and easier to refactor.

7.2 While loops

Scala's while loop behaves as in other languages. It has a condition and a body, and the body is executed over and over as long as the condition holds true. [Listing 7.2](#) shows an example:

```
def gcdLoop(x: Long, y: Long): Long = {
    var a = x
    var b = y
    while (a != 0) {
        val temp = a
        a = b % a
        b = temp
    }
    b
}
```

[Listing 7.2](#) · Calculating greatest common divisor with a while loop.

Scala also has a do-while loop. This works like the while loop except that it tests the condition after the loop body instead of before. [Listing 7.3](#)

shows a Scala script that uses a do-while to echo lines read from the standard input, until an empty line is entered:

```
var line = ""
do {
    line = readLine()
    println("Read: " + line)
} while (line != "")
```

Listing 7.3 · Reading from the standard input with do-while.

The while and do-while constructs are called “loops,” not expressions, because they don’t result in an interesting value. The type of the result is Unit. It turns out that a value (and in fact, only one value) exists whose type is Unit. It is called the *unit value* and is written (). The existence of () is how Scala’s Unit differs from Java’s void. Try this in the interpreter:

```
scala> def greet() = { println("hi") }
greet: ()Unit
scala> () == greet()
hi
res0: Boolean = true
```

Because no equals sign precedes its body, greet is defined to be a procedure with a result type of Unit. Therefore, greet returns the unit value, (). This is confirmed in the next line: comparing the greet’s result for equality with the unit value, (), yields true.

One other construct that results in the unit value, which is relevant here, is reassignment to vars. For example, were you to attempt to read lines in Scala using the following while loop idiom from Java (and C and C++), you’ll run into trouble:

```
var line = ""
while ((line = readLine()) != "") // This doesn't work!
    println("Read: " + line)
```

When you compile this code, Scala will give you a warning that comparing values of type Unit and String using != will always yield true. Whereas in Java, assignment results in the value assigned (in this case a line from

the standard input), in Scala assignment always results in the unit value, `()`. Thus, the value of the assignment “`line = readLine()`” will always be `()` and never be `""`. As a result, this while loop’s condition will never be false, and the loop will, therefore, never terminate.

Because the while loop results in no value, it is often left out of pure functional languages. Such languages have expressions, not loops. Scala includes the while loop nonetheless because sometimes an imperative solution can be more readable, especially to programmers with a predominantly imperative background. For example, if you want to code an algorithm that repeats a process until some condition changes, a while loop can express it directly while the functional alternative, which likely uses recursion, may be less obvious to some readers of the code.

For example, Listing 7.4 shows an alternate way to determine a greatest common divisor of two numbers.¹ Given the same two values for `x` and `y`, the `gcd` function shown in Listing 7.4 will return the same result as the `gcdLoop` function, shown in Listing 7.2. The difference between these two approaches is that `gcdLoop` is written in an imperative style, using vars and a while loop, whereas `gcd` is written in a more functional style that involves recursion (`gcd` calls itself) and requires no vars.

```
def gcd(x: Long, y: Long): Long =
  if (y == 0) x else gcd(y, x % y)
```

Listing 7.4 · Calculating greatest common divisor with recursion.

In general, we recommend you challenge while loops in your code in the same way you challenge vars. In fact, while loops and vars often go hand in hand. Because while loops don’t result in a value, to make any kind of difference to your program, a while loop will usually either need to update vars or perform I/O. You can see this in action in the `gcdLoop` example shown previously. As that while loop does its business, it updates vars `a` and `b`. Thus, we suggest you be a bit suspicious of while loops in your code. If there isn’t a good justification for a particular while or do-while loop, try to find a way to do the same thing without it.

¹The `gcd` function shown in Listing 7.4 uses the same approach used by the like-named function, first shown in Listing 6.3, to calculate greatest common divisors for class `Rational`. The main difference is that instead of `Ints` the `gcd` of Listing 7.4 works with `Longs`.

7.3 For expressions

Scala’s for expression is a Swiss army knife of iteration. It lets you combine a few simple ingredients in different ways to express a wide variety of iterations. Simple uses enable common tasks such as iterating through a sequence of integers. More advanced expressions can iterate over multiple collections of different kinds, filter out elements based on arbitrary conditions, and produce new collections.

Iteration through collections

The simplest thing you can do with for is to iterate through all the elements of a collection. For example, Listing 7.5 shows some code that prints out all files in the current directory. The I/O is performed using the Java API. First, we create a `java.io.File` on the current directory, `".."`, and call its `listFiles` method. This method returns an array of `File` objects, one per directory and file contained in the current directory. We store the resulting array in the `filesHere` variable.

```
val filesHere = (new java.io.File(".")).listFiles
for (file <- filesHere)
  println(file)
```

Listing 7.5 · Listing files in a directory with a for expression.

With the “`file <- filesHere`” syntax, which is called a *generator*, we iterate through the elements of `filesHere`. In each iteration, a new `val` named `file` is initialized with an element value. The compiler infers the type of `file` to be `File`, because `filesHere` is an `Array[File]`. For each iteration, the body of the for expression, `println(file)`, will be executed. Because `File`’s `toString` method yields the name of the file or directory, the names of all the files and directories in the current directory will be printed.

The for expression syntax works for any kind of collection, not just arrays.² One convenient special case is the Range type, which you briefly

²To be precise, the expression to the right of the `<-` symbol in a for expression can be any type that has certain methods (in this case `foreach`) with appropriate signatures. Details on how the Scala compiler processes for expressions are described in Chapter 23.

saw in [Table 5.4](#) on [page 134](#). You can create Ranges using syntax like “1 to 5” and can iterate through them with a `for`. Here is a simple example:

```
scala> for (i <- 1 to 4)
           println("Iteration " + i)
Iteration 1
Iteration 2
Iteration 3
Iteration 4
```

If you don’t want to include the upper bound of the range in the values that are iterated over, use `until` instead of `to`:

```
scala> for (i <- 1 until 4)
           println("Iteration " + i)
Iteration 1
Iteration 2
Iteration 3
```

Iterating through integers like this is common in Scala, but not nearly as much as in other languages. In other languages, you might use this facility to iterate through an array, like this:

```
// Not common in Scala...
for (i <- 0 to filesHere.length - 1)
    println(filesHere(i))
```

This `for` expression introduces a variable `i`, sets it in turn to each integer between 0 and `filesHere.length - 1`, and executes the body of the `for` expression for each setting of `i`. For each setting of `i`, the `i`’th element of `filesHere` is extracted and processed.

The reason this kind of iteration is less common in Scala is that you can just iterate over the collection directly. When you do, your code becomes shorter and you sidestep many of the off-by-one errors that can arise when iterating through arrays. Should you start at 0 or 1? Should you add -1, +1, or nothing to the final index? Such questions are easily answered, but also easily answered wrong. It is safer to avoid such questions entirely.

Filtering

Sometimes you don't want to iterate through a collection in its entirety; you want to filter it down to some subset. You can do this with a `for` expression by adding a *filter*, an `if` clause inside the `for`'s parentheses. For example, the code shown in Listing 7.6 lists only those files in the current directory whose names end with “`.scala`”:

```
val filesHere = (new java.io.File(".")).listFiles
for (file <- filesHere if file.getName.endsWith(".scala"))
  println(file)
```

Listing 7.6 · Finding `.scala` files using a `for` with a filter.

You could alternatively accomplish the same goal with this code:

```
for (file <- filesHere)
  if (file.getName.endsWith(".scala"))
    println(file)
```

This code yields the same output as the previous code, and likely looks more familiar to programmers with an imperative background. The imperative form, however, is only an option because this particular `for` expression is executed for its printing side-effects and results in the unit value `()`. As demonstrated later in this section, the `for` expression is called an “expression” because it can result in an interesting value, a collection whose type is determined by the `for` expression’s `<-` clauses.

You can include more filters if you want. Just keep adding `if` clauses. For example, to be extra defensive, the code in Listing 7.7 prints only files and not directories. It does so by adding a filter that checks the `file`'s `isFile` method.

```
for (
  file <- filesHere
  if file.isFile
  if file.getName.endsWith(".scala"))
  ) println(file)
```

Listing 7.7 · Using multiple filters in a `for` expression.

Nested iteration

If you add multiple `<-` clauses, you will get nested “loops.” For example, the `for` expression shown in Listing 7.8 has two nested loops. The outer loop iterates through `filesHere`, and the inner loop iterates through `fileLines(file)` for any file that ends with `.scala`.

```
def fileLines(file: java.io.File) =  
    scala.io.Source.fromFile(file).getLines().toList  
  
def grep(pattern: String) =  
    for (  
        file <- filesHere  
        if file.getName.endsWith(".scala");  
        line <- fileLines(file)  
        if line.trim.matches(pattern)  
    ) println(file + ": " + line.trim)  
  
grep(".*gcd.*")
```

Listing 7.8 · Using multiple generators in a `for` expression.

If you prefer, you can use curly braces instead of parentheses to surround the generators and filters. One advantage to using curly braces is that you can leave off some of the semicolons that are needed when you use parentheses because, as explained in Section 4.2, the Scala compiler will not infer semicolons while inside parentheses.

Mid-stream variable bindings

Note that the previous code repeats the expression `line.trim`. This is a non-trivial computation, so you might want to only compute it once. You can do this by binding the result to a new variable using an equals sign (`=`). The bound variable is introduced and used just like a `val`, only with the `val` keyword left out. Listing 7.9 shows an example.

In Listing 7.9, a variable named `trimmed` is introduced halfway through the `for` expression. That variable is initialized to the result of `line.trim`. The rest of the `for` expression then uses the new variable in two places, once in an `if` and once in `println`.

```
def grep(pattern: String) =  
  for {  
    file <- filesHere  
    if file.getName.endsWith(".scala")  
    line <- fileLines(file)  
    trimmed = line.trim  
    if trimmed.matches(pattern)  
  } println(file + ": " + trimmed)  
  
grep(".*gcd.*")
```

Listing 7.9 · Mid-stream assignment in a for expression.

Producing a new collection

While all of the examples so far have operated on the iterated values and then forgotten them, you can also generate a value to remember for each iteration. To do so, you prefix the body of the for expression by the keyword `yield`. For example, here is a function that identifies the `.scala` files and stores them in an array:

```
def scalaFiles =  
  for {  
    file <- filesHere  
    if file.getName.endsWith(".scala")  
  } yield file
```

Each time the body of the for expression executes, it produces one value, in this case simply `file`. When the for expression completes, the result will include all of the yielded values contained in a single collection. The type of the resulting collection is based on the kind of collections processed in the iteration clauses. In this case the result is an `Array[File]`, because `filesHere` is an array and the type of the yielded expression is `File`.

Be careful, by the way, where you place the `yield` keyword. The syntax of a for-yield expression is like this:

```
for clauses yield body
```

The `yield` goes before the entire body. Even if the body is a block surrounded by curly braces, put the `yield` before the first curly brace, not be-

fore the last expression of the block. Avoid the temptation to write things like this:

```
for (file <- filesHere if file.getName.endsWith(".scala")) {  
    yield file // Syntax error!  
}
```

For example, the for expression shown in Listing 7.10 first transforms the `Array[File]` named `filesHere`, which contains all files in the current directory, to one that contains only `.scala` files. For each of these it generates an `Iterator[String]`, the result of the `fileLines` method, whose definition is shown in Listing 7.8. An `Iterator` offers methods `next` and `hasNext` that allow you to iterate over a collection of elements. This initial iterator is transformed into another `Iterator[String]` containing only trimmed lines that include the substring "for". Finally, for each of these, an integer length is yielded. The result of this for expression is an `Array[Int]` containing those lengths.

```
val forLineLengths =  
    for {  
        file <- filesHere  
        if file.getName.endsWith(".scala")  
        line <- fileLines(file)  
        trimmed = line.trim  
        if trimmed.matches(".*for.*")  
    } yield trimmed.length
```

Listing 7.10 · Transforming an `Array[File]` to `Array[Int]` with a for.

At this point, you have seen all the major features of Scala's for expression, but we went through them rather quickly. A more thorough coverage of for expressions is given in Chapter 23.

7.4 Exception handling with try expressions

Scala's exceptions behave just like in many other languages. Instead of returning a value in the normal way, a method can terminate by throwing an exception. The method's caller can either catch and handle that exception,

or it can itself simply terminate, in which case the exception propagates to the caller's caller. The exception propagates in this way, unwinding the call stack, until a method handles it or there are no more methods left.

Throwing exceptions

Throwing an exception in Scala looks the same as in Java. You create an exception object and then throw it with the `throw` keyword:

```
throw new IllegalArgumentException
```

Although it may seem somewhat paradoxical, in Scala, `throw` is an expression that has a result type. Here's an example where result type matters:

```
val half =  
  if (n % 2 == 0)  
    n / 2  
  else  
    throw new RuntimeException("n must be even")
```

What happens here is that if `n` is even, `half` will be initialized to half of `n`. If `n` is not even, an exception will be thrown before `half` can be initialized to anything at all. Because of this, it is safe to treat a thrown exception as any kind of value whatsoever. Any context that tries to use the return from a `throw` will never get to do so, and thus no harm will come.

Technically, an exception throw has type `Nothing`. You can use a `throw` as an expression even though it will never actually evaluate to anything. This little bit of technical gymnastics might sound weird, but is frequently useful in cases like the previous example. One branch of an `if` computes a value, while the other throws an exception and computes `Nothing`. The type of the whole `if` expression is then the type of that branch which does compute something. Type `Nothing` is discussed further in [Section 11.3](#).

Catching exceptions

You catch exceptions using the syntax shown in [Listing 7.11](#). The syntax for `catch` clauses was chosen for its consistency with an important part of Scala: *pattern matching*. Pattern matching, a powerful feature, is described briefly in this chapter and in more detail in [Chapter 15](#).

```
import java.io.FileReader
import java.io.FileNotFoundException
import java.io.IOException

try {
    val f = new FileReader("input.txt")
    // Use and close file
} catch {
    case ex: FileNotFoundException => // Handle missing file
    case ex: IOException => // Handle other I/O error
}
```

Listing 7.11 · A try-catch clause in Scala.

The behavior of this try-catch expression is the same as in other languages with exceptions. The body is executed, and if it throws an exception, each catch clause is tried in turn. In this example, if the exception is of type `FileNotFoundException`, the first clause will execute. If it is of type `IOException`, the second clause will execute. If the exception is of neither type, the try-catch will terminate and the exception will propagate further.

Note

One difference you'll quickly notice in Scala is that, unlike Java, Scala does not require you to catch checked exceptions or declare them in a throws clause. You can declare a throws clause if you wish with the `@throws` annotation, but it is not required. See [Section 31.2](#) for more information on `@throws`.

The `finally` clause

You can wrap an expression with a `finally` clause if you want to cause some code to execute no matter how the expression terminates. For example, you might want to be sure an open file gets closed even if a method exits by throwing an exception. [Listing 7.12](#) shows an example.³

³Although you must always surround the `case` statements of a `catch` clause in parentheses, `try` and `finally` do not require parentheses if they contain only one expression. For example, you could write: `try t() catch { case e: Exception => ... } finally f()`.

```
import java.io.FileReader
val file = new FileReader("input.txt")
try {
    // Use the file
} finally {
    file.close() // Be sure to close the file
}
```

Listing 7.12 · A try-finally clause in Scala.

Note

[Listing 7.12](#) shows the idiomatic way to ensure a non-memory resource, such as a file, socket, or database connection, is closed. First you acquire the resource. Then you start a `try` block in which you use the resource. Lastly, you close the resource in a `finally` block. This idiom is the same in Scala as in Java; alternatively, in Scala you can employ a technique called the *loan pattern* to achieve the same goal more concisely. The loan pattern will be described in [Section 9.4](#).

Yielding a value

As with most other Scala control structures, `try-catch-finally` results in a value. For example, [Listing 7.13](#) shows how you can try to parse a URL but use a default value if the URL is badly formed. The result is that of the `try` clause if no exception is thrown, or the relevant `catch` clause if an exception is thrown and caught. If an exception is thrown but not caught, the expression has no result at all. The value computed in the `finally` clause, if there is one, is dropped. Usually `finally` clauses do some kind of clean up, such as closing a file. Normally, they should not change the value computed in the main body or a `catch` clause of the `try`.

If you’re familiar with Java, it’s worth noting that Scala’s behavior differs from Java only because Java’s `try-finally` does not result in a value. As in Java, if a `finally` clause includes an explicit return statement, or throws an exception, that return value or exception will “overrule” any previous one that originated in the `try` block or one of its `catch` clauses. For example, given this, rather contrived, function definition:

```
def f(): Int = try return 1 finally return 2
```

```
import java.net.URL
import java.net.MalformedURLException

def urlFor(path: String) =
  try {
    new URL(path)
  } catch {
    case e: MalformedURLException =>
      new URL("http://www.scala-lang.org")
  }
```

Listing 7.13 · A catch clause that yields a value.

calling `f()` results in 2. By contrast, given:

```
def g(): Int = try 1 finally 2
```

calling `g()` results in 1. Both of these functions exhibit behavior that could surprise most programmers, so it's usually best to avoid returning values from `finally` clauses. The best way to think of `finally` clauses is as a way to ensure some side effect happens, such as closing an open file.

7.5 Match expressions

Scala's match expression lets you select from a number of *alternatives*, just like switch statements in other languages. In general a match expression lets you select using arbitrary *patterns*, which will be described in Chapter 15. The general form can wait. For now, just consider using match to select among a number of alternatives.

As an example, the script in Listing 7.14 reads a food name from the argument list and prints a companion to that food. This match expression examines `firstArg`, which has been set to the first argument out of the argument list. If it is the string "salt", it prints "pepper", while if it is the string "chips", it prints "salsa", and so on. The default case is specified with an underscore (`_`), a wildcard symbol frequently used in Scala as a placeholder for a completely unknown value.

There are a few important differences from Java's switch statement. One is that any kind of constant, as well as other things, can be used in cases

```
val firstArg = if (args.length > 0) args(0) else ""
firstArg match {
    case "salt" => println("pepper")
    case "chips" => println("salsa")
    case "eggs" => println("bacon")
    case _ => println("huh?")
}
```

Listing 7.14 · A `match` expression with side effects.

in Scala, not just the integer-type, enum, and string constants Java's case statements. In Listing 7.14, the alternatives are strings. Another difference is that there are no `breaks` at the end of each alternative. Instead the break is implicit, and there is no fall through from one alternative to the next. The common case—not falling through—becomes shorter, and a source of errors is avoided because programmers can no longer fall through by accident.

The most significant difference from Java's `switch`, however, may be that `match` expressions result in a value. In the previous example, each alternative in the `match` expression prints out a value. It would work just as well to yield the value rather than print it, as shown in Listing 7.15. The value that results from this `match` expression is stored in the `friend` variable. Aside from the code getting shorter (in number of tokens anyway), the code now disentangles two separate concerns: first it chooses a food and then prints it.

```
val firstArg = if (!args.isEmpty) args(0) else ""
val friend =
  firstArg match {
    case "salt" => "pepper"
    case "chips" => "salsa"
    case "eggs" => "bacon"
    case _ => "huh?"
  }
  println(friend)
```

Listing 7.15 · A `match` expression that yields a value.

7.6 Living without break and continue

You may have noticed that there has been no mention of `break` or `continue`. Scala leaves out these commands because they do not mesh well with function literals, a feature described in the next chapter. It is clear what `continue` means inside a `while` loop, but what would it mean inside a function literal? While Scala supports both imperative and functional styles of programming, in this case it leans slightly towards functional programming in exchange for simplifying the language. Do not worry, though. There are many ways to program without `break` and `continue`, and if you take advantage of function literals, those alternatives can often be shorter than the original code.

The simplest approach is to replace every `continue` by an `if` and every `break` by a boolean variable. The boolean variable indicates whether the enclosing `while` loop should continue. For example, suppose you are searching through an argument list for a string that ends with `".scala"` but does not start with a hyphen. In Java you could—if you were quite fond of `while` loops, `break`, and `continue`—write the following:

```
int i = 0;                      // This is Java
boolean foundIt = false;
while (i < args.length) {
    if (args[i].startsWith("-")) {
        i = i + 1;
        continue;
    }
    if (args[i].endsWith(".scala")) {
        foundIt = true;
        break;
    }
    i = i + 1;
}
```

To transliterate this Java code directly to Scala, instead of doing an `if` and then a `continue`, you could write an `if` that surrounds the entire remainder of the `while` loop. To get rid of the `break`, you would normally add a boolean variable indicating whether to keep going, but in this case you can reuse `foundIt`. Using both of these tricks, the code ends up looking as shown in Listing 7.16.

```
var i = 0
var foundIt = false

while (i < args.length && !foundIt) {
    if (!args(i).startsWith("-")) {
        if (args(i).endsWith(".scala"))
            foundIt = true
    }
    i = i + 1
}
```

Listing 7.16 · Looping without break or continue.

This Scala code in [Listing 7.16](#) is quite similar to the original Java code. All the basic pieces are still there and in the same order. There are two reassignable variables and a while loop. Inside the loop, there is a test that `i` is less than `args.length`, a check for `"-"`, and a check for `".scala"`.

If you wanted to get rid of the vars in [Listing 7.16](#), one approach you could try is to rewrite the loop as a recursive function. You could, for example, define a `searchFrom` function that takes an integer as an input, searches forward from there, and then returns the index of the desired argument. Using this technique the code would look as shown in [Listing 7.17](#):

```
def searchFrom(i: Int): Int =
    if (i >= args.length) -1
    else if (args(i).startsWith("-")) searchFrom(i + 1)
    else if (args(i).endsWith(".scala")) i
    else searchFrom(i + 1)

val i = searchFrom(0)
```

Listing 7.17 · A recursive alternative to looping with vars.

The version in [Listing 7.17](#) gives a human-meaningful name to what the function does, and it uses recursion to substitute for looping. Each `continue` is replaced by a recursive call with `i + 1` as the argument, effectively skipping to the next integer. Many people find this style of programming easier to understand, once they get used to the recursion.

Note

The Scala compiler will not actually emit a recursive function for the code shown in Listing 7.17. Because all of the recursive calls are in *tail-call* position, the compiler will generate code similar to a while loop. Each recursive call will be implemented as a jump back to the beginning of the function. Tail-call optimization is discussed in Section 8.9.

If after all this discussion you still feel the need to use break, there's help in Scala's standard library. Class Breaks in package `scala.util.control` offers a `break` method, which can be used to exit an enclosing block that's marked with `breakable`. Here is an example how this library-supplied `break` method could be applied:

```
import scala.util.control.Breaks._  
import java.io._  
  
val in = new BufferedReader(new InputStreamReader(System.in))  
  
breakable {  
    while (true) {  
        println(">? ")  
        if (in.readLine() == "") break  
    }  
}
```

This will repeatedly read non-empty lines from the standard input. Once the user enters an empty line, control flow exits from the enclosing `breakable`, and with it the while loop.

The `Breaks` class implements `break` by throwing an exception that is caught by an enclosing application of the `breakable` method. Therefore, the call to `break` does not need to be in the same method as the call to `breakable`.

7.7 Variable scope

Now that you've seen Scala's built-in control structures, we'll use them in this section to explain how scoping works in Scala.

Fast track for Java programmers

If you’re a Java programmer, you’ll find that Scala’s scoping rules are almost identical to Java’s. One difference between Java and Scala is that Scala allows you to define variables of the same name in nested scopes. So if you’re a Java programmer, you may wish to at least skim this section.

Variable declarations in Scala programs have a *scope* that defines where you can use the name. The most common example of scoping is that curly braces generally introduce a new scope, so anything defined inside curly braces leaves scope after the final closing brace.⁴ As an illustration, consider the function shown in Listing 7.18.

The `printMultiTable` function shown in Listing 7.18 prints out a multiplication table.⁵ The first statement of this function introduces a variable named `i` and initializes it to the integer 1. You can then use the name `i` for the remainder of the function.

The next statement in `printMultiTable` is a while loop:

```
while (i <= 10) {  
    var j = 1  
    ...  
}
```

You can use `i` here because it is still in scope. In the first statement inside that while loop, you introduce another variable, this time named `j`, and again initialize it to 1. Because the variable `j` was defined inside the open curly brace of the while loop, it can be used only within that while loop. If you were to attempt to do something with `j` after the closing curly brace of this while loop, after the comment that says `j`, `prod`, and `k` are out of scope, your program would not compile.

All variables defined in this example—`i`, `j`, `prod`, and `k`—are *local variables*. Such variables are “local” to the function in which they are defined. Each time a function is invoked, a new set of its local variables is used.

Once a variable is defined, you can’t define a new variable with the same name in the same scope. For example, the following script with two variables named `a` in the same scope would not compile:

⁴There are a few exceptions to this rule because in Scala you can sometimes use curly braces in place of parentheses. One example of this kind of curly-brace use is the alternative for expression syntax described in Section 7.3.

⁵The `printMultiTable` function shown in Listing 7.18 is written in an imperative style. We’ll refactor it into a functional style in the next section.

```
def printMultiTable() = {
    var i = 1
    // only i in scope here
    while (i <= 10) {
        var j = 1
        // both i and j in scope here
        while (j <= 10) {
            val prod = (i * j).toString
            // i, j, and prod in scope here
            var k = prod.length
            // i, j, prod, and k in scope here
            while (k < 4) {
                print(" ")
                k += 1
            }
            print(prod)
            j += 1
        }
        // i and j still in scope; prod and k out of scope
        println()
        i += 1
    }
    // i still in scope; j, prod, and k out of scope
}
```

Listing 7.18 · Variable scoping when printing a multiplication table.

```
val a = 1
val a = 2 // Does not compile
println(a)
```

You can, on the other hand, define a variable in an inner scope that has the same name as a variable in an outer scope. The following script would compile and run:

```
val a = 1;
{
    val a = 2 // Compiles just fine
    println(a)
}
println(a)
```

When executed, the script shown previously would print 2 then 1, because the a defined inside the curly braces is a different variable, which is in scope only until the closing curly brace.⁶ One difference to note between Scala and Java is that Java will not let you create a variable in an inner scope that has the same name as a variable in an outer scope. In a Scala program, an inner variable is said to *shadow* a like-named outer variable, because the outer variable becomes invisible in the inner scope.

You might have already noticed something that looks like shadowing in the interpreter:

```
scala> val a = 1
a: Int = 1
scala> val a = 2
a: Int = 2
scala> println(a)
2
```

In the interpreter, you can reuse variable names to your heart's content. Among other things, this allows you to change your mind if you made a mistake when you defined a variable the first time in the interpreter. You can do this because conceptually the interpreter creates a new nested scope

⁶By the way, the semicolon is required in this case after the first definition of a because Scala's semicolon inference mechanism will not place one there.

for each new statement you type in. Thus, you could visualize the previous interpreted code like this:

```
val a = 1;
{
  val a = 2;
  {
    println(a)
  }
}
```

This code will compile and run as a Scala script, and like the code typed into the interpreter, will print 2. Keep in mind that such code can be very confusing to readers, because variable names adopt new meanings in nested scopes. It is usually better to choose a new, meaningful variable name rather than to shadow an outer variable.

7.8 Refactoring imperative-style code

To help you gain insight into the functional style, in this section we'll refactor the imperative approach to printing a multiplication table shown in [Listing 7.18](#). Our functional alternative is shown in [Listing 7.19](#).

The imperative style reveals itself in [Listing 7.18](#) in two ways. First, invoking `printMultiTable` has a side effect: printing a multiplication table to the standard output. In [Listing 7.19](#), we refactored the function so that it returns the multiplication table as a string. Since the function no longer prints, we renamed it `multiTable`. As mentioned previously, one advantage of side-effect-free functions is they are easier to unit test. To test `printMultiTable`, you would need to somehow redefine `print` and `println` so you could check the output for correctness. You could test `multiTable` more easily by checking its string result.

The other telltale sign of the imperative style in `printMultiTable` is its `while` loop and `vars`. By contrast, the `multiTable` function uses `vals`, for expressions, *helper functions*, and calls to `mkString`.

We factored out the two helper functions, `makeRow` and `makeRowSeq`, to make the code easier to read. Function `makeRowSeq` uses a `for` expression whose generator iterates through column numbers 1 through 10. The body of this `for` calculates the product of row and column, determines the padding

```
// Returns a row as a sequence
def makeRowSeq(row: Int) =
  for (col <- 1 to 10) yield {
    val prod = (row * col).toString
    val padding = " " * (4 - prod.length)
    padding + prod
  }

// Returns a row as a string
def makeRow(row: Int) = makeRowSeq(row).mkString

// Returns table as a string with one row per line
def multiTable() = {
  val tableSeq = // a sequence of row strings
    for (row <- 1 to 10)
      yield makeRow(row)

  tableSeq.mkString("\n")
}
```

Listing 7.19 · A functional way to create a multiplication table.

needed for the product, and yields the result of concatenating the padding and product strings. The result of the `for` expression will be a sequence (some subclass of `scala.Seq`) containing these yielded strings as elements. The other helper function, `makeRow`, simply invokes `mkString` on the result returned by `makeRowSeq`. `mkString` will concatenate the strings in the sequence and return them as one string.

The `multiTable` method first initializes `tableSeq` with the result of a `for` expression whose generator iterates through row numbers 1 to 10, and for each calls `makeRow` to get the string for that row. This string is yielded; thus the result of this `for` expression will be a sequence of row strings. The only remaining task is to convert the sequence of strings into a single string. The call to `mkString` accomplishes this, and because we pass "`\n`", we get an end of line character inserted between each string. If you pass the string returned by `multiTable` to `println`, you'll see the same output that's produced by calling `printMultiTable`.

1	2	3	4	5	6	7	8	9	10
2	4	6	8	10	12	14	16	18	20
3	6	9	12	15	18	21	24	27	30
4	8	12	16	20	24	28	32	36	40
5	10	15	20	25	30	35	40	45	50
6	12	18	24	30	36	42	48	54	60
7	14	21	28	35	42	49	56	63	70
8	16	24	32	40	48	56	64	72	80
9	18	27	36	45	54	63	72	81	90
10	20	30	40	50	60	70	80	90	100

7.9 Conclusion

Scala’s built-in control structures are minimal, but they do the job. They act much like their imperative equivalents, but because they tend to result in a value, they support a functional style, too. Just as important, they are careful in what they omit, thus leaving room for one of Scala’s most powerful features, the function literal, which will be described in the next chapter.

Chapter 8

Functions and Closures

When programs get larger, you need some way to divide them into smaller, more manageable pieces. For dividing up control flow, Scala offers an approach familiar to all experienced programmers: divide the code into functions. In fact, Scala offers several ways to define functions that are not present in Java. Besides methods, which are functions that are members of some object, there are also functions nested within functions, function literals, and function values. This chapter takes you on a tour through all of these flavors of functions in Scala.

8.1 Methods

The most common way to define a function is as a member of some object; such a function is called a *method*. As an example, Listing 8.1 shows two methods that together read a file with a given name and print out all lines whose length exceeds a given width. Every printed line is prefixed with the name of the file it appears in.

The `processFile` method takes a `filename` and `width` as parameters. It creates a `Source` object from the file name and, in the generator of the `for` expression, calls `getLines` on the source. As mentioned in Step 12 of Chapter 3, `getLines` returns an iterator that provides one line from the file on each iteration, excluding the end-of-line character. The `for` expression processes each of these lines by calling the helper method, `processLine`. The `processLine` method takes three parameters: a `filename`, a `width`, and a `line`. It tests whether the length of the line is greater than the given width, and, if so, it prints the `filename`, a colon, and the `line`.

```
import scala.io.Source

object LongLines {

    def processFile(filename: String, width: Int) = {
        val source = Source.fromFile(filename)
        for (line <- source.getLines())
            processLine(filename, width, line)
    }

    private def processLine(filename: String,
                           width: Int, line: String) = {
        if (line.length > width)
            println(filename + ": " + line.trim)
    }
}
```

Listing 8.1 · LongLines with a private processLine method.

To use LongLines from the command line, we'll create an application that expects the line width as the first command-line argument, and interprets subsequent arguments as filenames:¹

```
object FindLongLines {
    def main(args: Array[String]) = {
        val width = args(0).toInt
        for (arg <- args.drop(1))
            LongLines.processFile(arg, width)
    }
}
```

Here's how you'd use this application to find the lines in `LongLines.scala` that are over 45 characters in length (there's just one):

```
$ scala FindLongLines 45 LongLines.scala
LongLines.scala: def processFile(filename: String, width: Int) = {
```

¹In this book, we usually won't check command-line arguments for validity in example applications, both to save trees and reduce boilerplate code that can obscure the example's important code. The trade-off is that instead of producing a helpful error message when given bad input, our example applications will throw an exception.

So far, this is very similar to what you would do in any object-oriented language. However, the concept of a function in Scala is more general than a method. Scala's other ways to express functions will be explained in the following sections.

8.2 Local functions

The construction of the `processFile` method in the previous section demonstrated an important design principle of the functional programming style: programs should be decomposed into many small functions that each do a well-defined task. Individual functions are often quite small. The advantage of this style is that it gives a programmer many building blocks that can be flexibly composed to do more difficult things. Each building block should be simple enough to be understood individually.

One problem with this approach is that all the helper function names can pollute the program namespace. In the interpreter this is not so much of a problem, but once functions are packaged in reusable classes and objects, it's desirable to hide the helper functions from clients of a class. They often do not make sense individually, and you often want to keep enough flexibility to delete the helper functions if you later rewrite the class a different way.

In Java, your main tool for this purpose is the `private` method. This `private`-method approach works in Scala as well, as demonstrated in [Listing 8.1](#), but Scala offers an additional approach: you can define functions inside other functions. Just like local variables, such `local functions` are visible only in their enclosing block. Here's an example:

```
def processFile(filename: String, width: Int) = {  
    def processLine(filename: String,  
                   width: Int, line: String) = {  
        if (line.length > width)  
            println(filename + ":" + line.trim)  
    }  
    val source = Source.fromFile(filename)  
    for (line <- source.getLines()) {  
        processLine(filename, width, line)  
    }  
}
```

In this example, we refactored the original `LongLines` version, shown in [Listing 8.1](#), by transforming private method, `processLine`, into a local function of `processFile`. To do so we removed the `private` modifier, which can only be applied (and is only needed) for members, and placed the definition of `processLine` inside the definition of `processFile`. As a local function, `processLine` is in scope inside `processFile`, but inaccessible outside.

Now that `processLine` is defined inside `processFile`, however, another improvement becomes possible. Notice how `filename` and `width` are passed unchanged into the helper function? This is not necessary because local functions can access the parameters of their enclosing function. You can just use the parameters of the outer `processLine` function, as shown in [Listing 8.2](#).

```
import scala.io.Source
object LongLines {
    def processFile(filename: String, width: Int) = {
        def processLine(line: String) = {
            if (line.length > width)
                println(filename + ":" + line.trim)
        }
        val source = Source.fromFile(filename)
        for (line <- source.getLines())
            processLine(line)
    }
}
```

[Listing 8.2 · LongLines with a local `processLine` function.](#)

Simpler, isn't it? This use of an enclosing function's parameters is a common and useful example of the general nesting Scala provides. The nesting and scoping described in [Section 7.7](#) applies to all Scala constructs, including functions. It's a simple principle, but very powerful, especially in a language with first-class functions.

8.3 First-class functions

Scala has *first-class functions*. Not only can you define functions and call them, but you can write down functions as unnamed *literals* and then pass them around as *values*. We introduced function literals in [Chapter 2](#) and showed the basic syntax in [Figure 2.2 on page 75](#).

A function literal is compiled into a class that when instantiated at runtime is a *function value*.² Thus the distinction between function literals and values is that function literals exist in the source code, whereas function values exist as objects at runtime. The distinction is much like that between classes (source code) and objects (runtime).

Here is a simple example of a function literal that adds one to a number:

```
(x: Int) => x + 1
```

The `=>` designates that this function converts the thing on the left (any integer `x`) to the thing on the right (`x + 1`). So, this is a function mapping any integer `x` to `x + 1`.

Function values are objects, so you can store them in variables if you like. They are functions, too, so you can invoke them using the usual parentheses function-call notation. Here is an example of both activities:

```
scala> var increase = (x: Int) => x + 1
increase: Int => Int = <function1>
scala> increase(10)
res0: Int = 11
```

Because `increase`, in this example, is a `var`, you can assign a different function value to it later on.

```
scala> increase = (x: Int) => x + 9999
increase: Int => Int = <function1>
scala> increase(10)
res1: Int = 10009
```

²Every function value is an instance of some class that extends one of several `FunctionN` traits in package `scala`, such as `Function0` for functions with no parameters, `Function1` for functions with one parameter, and so on. Each `FunctionN` trait has an `apply` method used to invoke the function.

If you want to have more than one statement in the function literal, surround its body by curly braces and put one statement per line, thus forming a **block**. Just like a method, when the function value is invoked, all of the statements will be executed, and the value returned from the function is whatever results from evaluating the last expression.

```
scala> increase = (x: Int) => {  
    println("We")  
    println("are")  
    println("here!")  
    x + 1  
}  
increase: Int => Int = <function1>  
  
scala> increase(10)  
We  
are  
here!  
res2: Int = 11
```

So now you have seen the nuts and bolts of function literals and function values. Many Scala libraries give you opportunities to use them. For example, a `foreach` method is available for all collections.³ It takes a function as an argument and invokes that function on each of its elements. Here is how it can be used to print out all of the elements of a list:

```
scala> val someNumbers = List(-11, -10, -5, 0, 5, 10)  
someNumbers: List[Int] = List(-11, -10, -5, 0, 5, 10)  
  
scala> someNumbers.foreach((x: Int) => println(x))  
-11  
-10  
-5  
0  
5  
10
```

³A `foreach` method is defined in trait `Traversable`, a common supertype of `List`, `Set`, `Array`, and `Map`. See [Chapter 17](#) for the details.

As another example, collection types also have a `filter` method. This method selects those elements of a collection that pass a test the user supplies. That test is supplied using a function. For example, the function `(x: Int) => x > 0` could be used for filtering. This function maps positive integers to true and all others to false. Here is how to use it with `filter`:

```
scala> someNumbers.filter((x: Int) => x > 0)
res4: List[Int] = List(5, 10)
```

Methods like `foreach` and `filter` are described further later in the book. [Chapter 16](#) talks about their use in class `List`. [Chapter 17](#) discusses their use with other collection types.

8.4 Short forms of function literals

Scala provides a number of ways to leave out redundant information and write function literals more briefly. Keep your eyes open for these opportunities, because they allow you to remove clutter from your code.

One way to make a function literal more brief is to leave off the parameter types. Thus, the previous example with `filter` could be written like this:

```
scala> someNumbers.filter((x) => x > 0)
res5: List[Int] = List(5, 10)
```

The Scala compiler knows that `x` must be an integer, because it sees that you are immediately using the function to filter a list of integers (referred to by `someNumbers`). This is called *target typing* because the targeted usage of an expression (in this case, an argument to `someNumbers.filter()`) is allowed to influence the typing of that expression (in this case to determine the type of the `x` parameter). The precise details of target typing are not important. You can simply start by writing a function literal without the argument type, and if the compiler gets confused, add in the type. Over time you'll get a feel for which situations the compiler can and cannot puzzle out.

A second way to remove useless characters is to leave out parentheses around a parameter whose type is inferred. In the previous example, the parentheses around `x` are unnecessary:

```
scala> someNumbers.filter(x => x > 0)
res6: List[Int] = List(5, 10)
```

8.5 Placeholder syntax

To make a function literal even more concise, you can use underscores as placeholders for one or more parameters, so long as each parameter appears only one time within the function literal. For example, `_ > 0` is very short notation for a function that checks whether a value is greater than zero:

```
scala> someNumbers.filter(_ > 0)
res7: List[Int] = List(5, 10)
```

You can think of the underscore as a “blank” in the expression that needs to be “filled in.” This blank will be filled in with an argument to the function each time the function is invoked. For example, given that `someNumbers` was initialized on [page 185](#) to the value `List(-11, -10, -5, 0, 5, 10)`, the `filter` method will replace the blank in `_ > 0` first with `-11`, as in `-11 > 0`, then with `-10`, as in `-10 > 0`, then with `-5`, as in `-5 > 0`, and so on to the end of the `List`. The function literal `_ > 0`, therefore, is equivalent to the slightly more verbose `x => x > 0`, as demonstrated here:

```
scala> someNumbers.filter(x => x > 0)
res8: List[Int] = List(5, 10)
```

Sometimes when you use underscores as placeholders for parameters, the compiler might not have enough information to infer missing parameter types. For example, suppose you write `_ + _` by itself:

```
scala> val f = _ + _
<console>:7: error: missing parameter type for expanded
      function ((x$1, x$2) => x$1.$plus(x$2))
           val f = _ + _
                           ^
```

In such cases, you can specify the types using a colon, like this:

```
scala> val f = (_: Int) + (_: Int)
f: (Int, Int) => Int = <function2>
scala> f(5, 10)
res9: Int = 15
```

Note that `_ + _` expands into a literal for a function that takes two parameters. This is why you can use this short form only if each parameter appears

in the function literal exactly once. Multiple underscores mean multiple parameters, not reuse of a single parameter repeatedly. The first underscore represents the first parameter, the second underscore the second parameter, the third underscore the third parameter, and so on.

8.6 Partially applied functions

Although the previous examples substitute underscores in place of individual parameters, you can also replace an entire parameter list with an underscore. For example, rather than writing `println(_)`, you could write `println _`. Here's an example:

```
someNumbers.foreach(println _)
```

Scala treats this short form exactly as if you had written the following:

```
someNumbers.foreach(x => println(x))
```

Thus, the underscore in this case is not a placeholder for a single parameter. It is a placeholder for an entire parameter list. Remember that you need to leave a space between the function name and the underscore; otherwise, the compiler will think you are referring to a different symbol, such as, for example, a method named `println_`, which likely does not exist.

When you use an underscore in this way, you are writing a *partially applied function*. In Scala, when you invoke a function, passing in any needed arguments, you *apply* that function *to* the arguments. For example, given the following function:

```
scala> def sum(a: Int, b: Int, c: Int) = a + b + c
sum: (a: Int, b: Int, c: Int)Int
```

You could apply the function `sum` to the arguments 1, 2, and 3 like this:

```
scala> sum(1, 2, 3)
res10: Int = 6
```

A partially applied function is an expression in which you don't supply all of the arguments needed by the function. Instead, you supply some, or none, of the needed arguments. For example, to create a partially applied function expression involving `sum`, in which you supply none of the three required

arguments, you just place an underscore after “sum”. The resulting function can then be stored in a variable. Here’s an example:

```
scala> val a = sum _
a: (Int, Int, Int) => Int = <function3>
```

Given this code, the Scala compiler instantiates a function value that takes the three integer parameters missing from the partially applied function expression, `sum _`, and assigns a reference to that new function value to the variable `a`. When you apply three arguments to this new function value, it will turn around and invoke `sum`, passing in those same three arguments:

```
scala> a(1, 2, 3)
res11: Int = 6
```

Here’s what just happened: The variable named `a` refers to a function value object. This function value is an instance of a class generated automatically by the Scala compiler from `sum _`, the partially applied function expression. The class generated by the compiler has an `apply` method that takes three arguments.⁴ The generated class’s `apply` method takes three arguments because three is the number of arguments missing in the `sum _` expression. The Scala compiler translates the expression `a(1, 2, 3)` into an invocation of the function value’s `apply` method, passing in the three arguments 1, 2, and 3. Thus, `a(1, 2, 3)` is a short form for:

```
scala> a.apply(1, 2, 3)
res12: Int = 6
```

This `apply` method, defined in the class generated automatically by the Scala compiler from the expression `sum _`, simply forwards those three missing parameters to `sum`, and returns the result. In this case `apply` invokes `sum(1, 2, 3)`, and returns what `sum` returns, which is 6.

Another way to think about this kind of expression, in which an underscore is used to represent an entire parameter list, is as a way to transform a `def` into a function value. For example, if you have a local function, such as `sum(a: Int, b: Int, c: Int): Int`, you can “wrap” it in a function value whose `apply` method has the same parameter list and result types. When you apply this function value to some arguments, it in turn applies `sum` to

⁴The generated class extends trait `Function3`, which declares a three-arg `apply` method.

those same arguments and returns the result. Although you can't assign a method or nested function to a variable, or pass it as an argument to another function, you can do these things if you wrap the method or nested function in a function value by placing an underscore after its name.

Now, although `sum _` is indeed a partially applied function, it may not be obvious to you why it is called this. It has this name because you are not applying that function to all of its arguments. In the case of `sum _`, you are applying it to *none* of its arguments. But you can also express a partially applied function by supplying only *some* of the required arguments. Here's an example:

```
scala> val b = sum(1, _: Int, 3)
b: Int => Int = <function1>
```

In this case, you've supplied the first and last argument to `sum`, but not the middle argument. Since only one argument is missing, the Scala compiler generates a new function class whose `apply` method takes one argument. When invoked with that one argument, this generated function's `apply` method invokes `sum`, passing in 1, the argument passed to the function, and 3. Here are some examples:

```
scala> b(2)
res13: Int = 6
```

In this case, `b.apply` invoked `sum(1, 2, 3)`.

```
scala> b(5)
res14: Int = 9
```

And in this case, `b.apply` invoked `sum(1, 5, 3)`.

If you are writing a partially applied function expression in which you leave off all parameters, such as `println _` or `sum _`, you can express it more concisely by leaving off the underscore if a function is required at that point in the code. For example, instead of printing out each of the numbers in `someNumbers` (defined on page 185) like this:

```
someNumbers.foreach(println _)
```

You could just write:

```
someNumbers.foreach(println)
```

This last form is allowed only in places where a function is required, such as the invocation of `foreach` in this example. The compiler knows a function is required in this case, because `foreach` requires that a function be passed as an argument. In situations where a function is not required, attempting to use this form will cause a compilation error. Here's an example:

```
scala> val c = sum
<console>:8: error: missing arguments for method sum;
follow this method with '_' if you want to treat it as a
partially applied function
    val c = sum
                           ^
scala> val d = sum _
d: (Int, Int, Int) => Int = <function3>
scala> d(10, 20, 30)
res14: Int = 60
```

8.7 Closures

So far in this chapter, all the examples of function literals have referred only to passed parameters. For example, in `(x: Int) => x > 0`, the only variable used in the function body, `x > 0`, is `x`, which is defined as a parameter to the function. You can, however, refer to variables defined elsewhere:

```
(x: Int) => x + more // how much more?
```

This function adds “more” to its argument, but what is more? From the point of view of this function, `more` is a *free variable* because the function literal does not itself give a meaning to it. The `x` variable, by contrast, is a *bound variable* because it does have a meaning in the context of the function: it is defined as the function’s lone parameter, an `Int`. If you try using this function literal by itself, without any `more` defined in its scope, the compiler will complain:

```
scala> (x: Int) => x + more
<console>:8: error: not found: value more
    (x: Int) => x + more
                           ^
```

Why the trailing underscore?

Scala's syntax for partially applied functions highlights a difference in the design trade-offs of Scala and classical functional languages, such as Haskell or ML. In these languages, partially applied functions are considered the normal case. Furthermore, these languages have a fairly strict static type system that will usually highlight every error with partial applications that you can make. Scala bears a much closer relation to imperative languages, such as Java, where a method that's not applied to all its arguments is considered an error. Furthermore, the object-oriented tradition of subtyping and a universal root type accepts some programs that would be considered erroneous in classical functional languages.

For instance, say you mistook the `drop(n: Int)` method of `List` for `tail()`, and therefore forgot you need to pass a number to `drop`. You might write, “`println(drop)`”. Had Scala adopted the classical functional tradition that partially applied functions are OK everywhere, this code would type check. However, you might be surprised to find out that the output printed by this `println` statement would always be `<function>!` What would have happened is that the expression `drop` would have been treated as a function object. Because `println` takes objects of any type, this would have compiled OK, but it would have given an unexpected result.

To avoid situations like this, Scala normally requires you to specify function arguments that are left out explicitly, even if the indication is as simple as a ‘`_`’. Scala allows you to leave off even the `_` only when a function type is expected.

On the other hand, the same function literal will work fine so long as there is something available named `more`:

```
scala> var more = 1
more: Int = 1

scala> val addMore = (x: Int) => x + more
addMore: Int => Int = <function1>

scala> addMore(10)
res16: Int = 11
```

The function value (the object) that's created at runtime from this function literal is called a *closure*. The name arises from the act of “closing” the function literal by “capturing” the bindings of its free variables. A function literal with no free variables, such as `(x: Int) => x + 1`, is called a *closed term*, where a *term* is a bit of source code. Thus a function value created at runtime from this function literal is not a closure in the strictest sense, because `(x: Int) => x + 1` is already closed as written. But any function literal with free variables, such as `(x: Int) => x + more`, is an *open term*. Therefore, any function value created at runtime from `(x: Int) => x + more` will, by definition, require that a binding for its free variable, `more`, be captured. The resulting function value, which will contain a reference to the captured `more` variable, is called a closure because the function value is the end product of the act of closing the open term, `(x: Int) => x + more`.

This example brings up a question: What happens if `more` changes after the closure is created? In Scala, the answer is that the closure sees the change. For example:

```
scala> more = 9999
more: Int = 9999

scala> addMore(10)
res17: Int = 10009
```

Intuitively, Scala's closures capture variables themselves, not the value to which variables refer.⁵ As the previous example shows, the closure created for `(x: Int) => x + more` sees the change to `more` made outside the closure. The same is true in the opposite direction. Changes made by a closure to a captured variable are visible outside the closure. Here's an example:

```
scala> val someNumbers = List(-11, -10, -5, 0, 5, 10)
someNumbers: List[Int] = List(-11, -10, -5, 0, 5, 10)

scala> var sum = 0
sum: Int = 0

scala> someNumbers.foreach(sum += _)
```

⁵By contrast, Java's inner classes do not allow you to access modifiable variables in surrounding scopes at all, so there is no difference between capturing a variable and capturing its currently held value.

```
scala> sum
res19: Int = -11
```

This example uses a roundabout way to sum the numbers in a List. Variable `sum` is in a surrounding scope from the function literal `sum += _`, which adds numbers to `sum`. Even though it is the closure modifying `sum` at runtime, the resulting total, `-11`, is still visible outside the closure.

What if a closure accesses some variable that has several different copies as the program runs? For example, what if a closure uses a local variable of some function, and the function is invoked many times? Which instance of that variable gets used at each access?

Only one answer is consistent with the rest of the language: the instance used is the one that was active at the time the closure was created. For example, here is a function that creates and returns “increase” closures:

```
def makeIncreaser(more: Int) = (x: Int) => x + more
```

Each time this function is called it will create a new closure. Each closure will access the `more` variable that was active when the closure was created.

```
scala> val inc1 = makeIncreaser(1)
inc1: Int => Int = <function1>
scala> val inc9999 = makeIncreaser(9999)
inc9999: Int => Int = <function1>
```

When you call `makeIncreaser(1)`, a closure is created and returned that captures the value `1` as the binding for `more`. Similarly, when you call `makeIncreaser(9999)`, a closure that captures the value `9999` for `more` is returned. When you apply these closures to arguments (in this case, there’s just one argument, `x`, which must be passed in), the result that comes back depends on how `more` was defined when the closure was created:

```
scala> inc1(10)
res20: Int = 11
scala> inc9999(10)
res21: Int = 10009
```

It makes no difference that the `more` in this case is a parameter to a method call that has already returned. The Scala compiler rearranges things in cases

like these so that the captured parameter lives out on the heap, instead of the stack, and thus can outlive the method call that created it. This rearrangement is all taken care of automatically, so you don't have to worry about it. Capture any variable you like: val, var, or parameter.

8.8 Special function call forms

Most functions and function calls you encounter will be as you have seen so far in this chapter. The function will have a fixed number of parameters, the call will have an equal number of arguments, and the arguments will be specified in the same order and number as the parameters.

Since function calls are so central to programming in Scala, however, a few special forms of function definitions and function calls have been added to the language to address some special needs. Scala supports repeated parameters, named arguments, and default arguments.

Repeated parameters

Scala allows you to indicate that the last parameter to a function may be repeated. This allows clients to pass variable length argument lists to the function. To denote a repeated parameter, place an asterisk after the type of the parameter. For example:

```
scala> def echo(args: String*) =  
        for (arg <- args) println(arg)  
echo: (args: String*)Unit
```

Defined this way, echo can be called with zero to many String arguments:

```
scala> echo()  
scala> echo("one")  
one  
scala> echo("hello", "world!")  
hello  
world!
```

Inside the function, the type of the repeated parameter is an Array of the declared type of the parameter. Thus, the type of args inside the echo

function, which is declared as type “String*” is actually `Array[String]`. Nevertheless, if you have an array of the appropriate type, and you attempt to pass it as a repeated parameter, you’ll get a compiler error:

```
scala> val arr = Array("What's", "up", "doc?")
arr: Array[String] = Array(What's, up, doc?)

scala> echo(arr)
<console>:10: error: type mismatch;
         found   : Array[String]
         required: String
                  echo(arr)
                           ^
```

To accomplish this, you’ll need to append the array argument with a colon and an `_*` symbol, like this:

```
scala> echo(arr: _*)
What's
up
doc?
```

This notation tells the compiler to pass each element of `arr` as its own argument to `echo`, rather than all of it as a single argument.

Named arguments

In a normal function call, the arguments in the call are matched one by one in the order of the parameters of the called function:

```
scala> def speed(distance: Float, time: Float): Float =
           distance / time
speed: (distance: Float, time: Float)Float

scala> speed(100, 10)
res27: Float = 10.0
```

In this call, the 100 is matched to `distance` and the 10 to `time`. The 100 and 10 are matched in the same order as the formal parameters are listed.

Named arguments allow you to pass arguments to a function in a different order. The syntax is simply that each argument is preceded by a parameter name and an equals sign. For example, the following call to `speed` is equivalent to `speed(100,10)`:

```
scala> speed(distance = 100, time = 10)
res28: Float = 10.0
```

Called with named arguments, the arguments can be reversed without changing the meaning:

```
scala> speed(time = 10, distance = 100)
res29: Float = 10.0
```

It is also possible to mix positional and named arguments. In that case, the positional arguments come first. Named arguments are most frequently used in combination with default parameter values.

Default parameter values

Scala lets you specify default values for function parameters. The argument for such a parameter can optionally be omitted from a function call, in which case the corresponding argument will be filled in with the default.

An example is shown in Listing 8.3. Function `printTime` has one parameter, `out`, and it has a default value of `Console.out`.

```
def printTime(out: java.io.PrintStream = Console.out) =
  out.println("time = " + System.currentTimeMillis())
```

Listing 8.3 · A parameter with a default value.

If you call the function as `printTime()`, thus specifying no argument to be used for `out`, then `out` will be set to its default value of `Console.out`. You could also call the function with an explicit output stream. For example, you could send logging to the standard error output by calling the function as `printTime(Console.err)`.

Default parameters are especially helpful when used in combination with named parameters. In Listing 8.4, function `printTime2` has two optional parameters. The `out` parameter has a default of `Console.out`, and the `divisor` parameter has a default value of 1.

Function `printTime2` can be called as `printTime2()` to have both parameters filled in with their default values. Using named arguments, however, either one of the parameters can be specified while leaving the other as the default. To specify the output stream, call it like this:

```
def printTime2(out: java.io.PrintStream = Console.out,
              divisor: Int = 1) =
  out.println("time = " + System.currentTimeMillis() / divisor)
```

Listing 8.4 · A function with two parameters that have defaults.

```
printTime2(out = Console.err)
```

To specify the time divisor, call it like this:

```
printTime2(divisor = 1000)
```

8.9 Tail recursion

In [Section 7.2](#), we mentioned that to transform a while loop that updates vars into a more functional style that uses only vals, you may sometimes need to use recursion. Here's an example of a recursive function that approximates a value by repeatedly improving a guess until it is good enough:

```
def approximate(guess: Double): Double =
  if (isGoodEnough(guess)) guess
  else approximate(improve(guess))
```

A function like this is often used in search problems, with appropriate implementations for `isGoodEnough` and `improve`. If you want the `approximate` function to run faster, you might be tempted to write it with a while loop to try and speed it up, like this:

```
def approximateLoop(initialGuess: Double): Double = {
  var guess = initialGuess
  while (!isGoodEnough(guess))
    guess = improve(guess)
  guess
}
```

Which of the two versions of `approximate` is preferable? In terms of brevity and var avoidance, the first, functional one wins. But is the imperative approach perhaps more efficient? In fact, if we measure execution times, it turns out that they are almost exactly the same!

This might seem surprising because a recursive call looks much more “expansive” than a simple jump from the end of a loop to its beginning. However, in the case of `approximate` above, the Scala compiler is able to apply an important optimization. Note that the recursive call is the last thing that happens in the evaluation of function `approximate`’s body. Functions like `approximate`, which call themselves as their last action, are called *tail recursive*. The Scala compiler detects tail recursion and replaces it with a jump back to the beginning of the function, after updating the function parameters with the new values.

The moral is that you should not shy away from using recursive algorithms to solve your problem. Often, a recursive solution is more elegant and concise than a loop-based one. If the solution is tail recursive, there won’t be any runtime overhead to be paid.

Tracing tail-recursive functions

A tail-recursive function will not build a new stack frame for each call; all calls will execute in a single frame. This may surprise a programmer inspecting a stack trace of a program that failed. For example, this function calls itself some number of times then throws an exception:

```
def boom(x: Int): Int =  
  if (x == 0) throw new Exception("boom!")  
  else boom(x - 1) + 1
```

This function is *not* tail recursive, because it performs an increment operation after the recursive call. You’ll get what you expect when you run it:

```
scala> boom(3)  
java.lang.Exception: boom!  
  at .boom(<console>:5)  
  at .boom(<console>:6)  
  at .boom(<console>:6)  
  at .boom(<console>:6)  
  at .<init>(<console>:6)  
...  
...
```

If you now modify `boom` so that it does become tail recursive:

Tail call optimization

The compiled code for `approximate` is essentially the same as the compiled code for `approximateLoop`. Both functions compile down to the same thirteen instructions of Java bytecodes. If you look through the bytecodes generated by the Scala compiler for the tail recursive method, `approximate`, you'll see that although both `isGoodEnough` and `improve` are invoked in the body of the method, `approximate` is not. The Scala compiler optimized away the recursive call:

```
public double approximate(double);  
Code:  
 0:  aload_0  
 1:  astore_3  
 2:  aload_0  
 3:  dload_1  
 4:  invokevirtual #24; //Method isGoodEnough:(D)Z  
 7:  ifeq    12  
10:  dload_1  
11:  dreturn  
12:  aload_0  
13:  dload_1  
14:  invokevirtual #27; //Method improve:(D)D  
17:  dstore_1  
18:  goto    2
```

```
def bang(x: Int): Int =  
  if (x == 0) throw new Exception("bang!")  
  else bang(x - 1)
```

You'll get:

```
scala> bang(5)  
java.lang.Exception: bang!  
  at .bang(<console>:5)  
  at .<init>(<console>:6) ...
```

This time, you see only a single stack frame for bang. You might think that bang crashed before it called itself, but this is not the case. If you think you might be confused by tail-call optimizations when looking at a stack trace, you can turn them off by giving the following argument to the scala shell or to the scalac compiler:

```
-g:nottailcalls
```

With that option specified, you will get a longer stack trace:

```
scala> bang(5)
java.lang.Exception: bang!
    at .bang(<console>:5)
    at .<init>(<console>:6) ...
```

Limits of tail recursion

The use of tail recursion in Scala is fairly limited because the JVM instruction set makes implementing more advanced forms of tail recursion very difficult. Scala only optimizes directly recursive calls back to the same function making the call. If the recursion is indirect, as in the following example of two mutually recursive functions, no optimization is possible:

```
def isEven(x: Int): Boolean =
  if (x == 0) true else isOdd(x - 1)
def isOdd(x: Int): Boolean =
  if (x == 0) false else isEven(x - 1)
```

You also won't get a tail-call optimization if the final call goes to a function value. Consider for instance the following recursive code:

```
val funValue = nestedFun _
def nestedFun(x: Int) : Unit = {
  if (x != 0) { println(x); funValue(x - 1) }
}
```

The `funValue` variable refers to a function value that essentially wraps a call to `nestedFun`. When you apply the function value to an argument, it turns around and applies `nestedFun` to that same argument, and returns the result. Therefore, you might hope the Scala compiler would perform a tail-call optimization, but in this case it would not. Tail-call optimization is limited to situations where a method or nested function calls itself directly as its last operation, without going through a function value or some other intermediary. (If you don't fully understand tail recursion yet, see [Section 8.9](#)).

8.10 Conclusion

This chapter has given you a grand tour of functions in Scala. In addition to methods, Scala provides local functions, function literals, and function values. In addition to normal function calls, Scala provides partially applied functions and functions with repeated parameters. When possible, function calls are implemented as optimized tail calls, and thus many nice-looking recursive functions run just as quickly as hand-optimized versions that use `while` loops. The next chapter will build on these foundations and show how Scala's rich support for functions helps you abstract over control.

Chapter 9

Control Abstraction

In [Chapter 7](#), we pointed out that Scala doesn't have many built-in control abstractions because it gives you the ability to create your own. In the previous chapter, you learned about function values. In this chapter, we'll show you how to apply function values to create new control abstractions. Along the way, you'll also learn about currying and by-name parameters.

9.1 Reducing code duplication

All functions are separated into common parts, which are the same in every invocation of the function, and non-common parts, which may vary from one function invocation to the next. The common parts are in the body of the function, while the non-common parts must be supplied via arguments. When you use a function value as an argument, the non-common part of the algorithm is itself some other algorithm! At each invocation of such a function, you can pass in a different function value as an argument, and the invoked function will, at times of its choosing, invoke the passed function value. These *higher-order functions*—functions that take functions as parameters—give you extra opportunities to condense and simplify code.

One benefit of higher-order functions is they enable you to create control abstractions that allow you to reduce code duplication. For example, suppose you are writing a file browser, and you want to provide an API that allows users to search for files matching some criterion. First, you add a facility to search for files whose names end in a particular string. This would enable your users to find, for example, all files with a “.scala” extension. You could provide such an API by defining a public `filesEnding` method inside

a singleton object like this:

```
object FileMatcher {  
    private def filesHere = (new java.io.File(".")).listFiles  
  
    def filesEnding(query: String) =  
        for (file <- filesHere; if file.getName.endsWith(query))  
            yield file  
}
```

The `filesEnding` method obtains the list of all files in the current directory using the private helper method `filesHere`, then filters them based on whether each file name ends with the user-specified query. Given `filesHere` is private, the `filesEnding` method is the only accessible method defined in `FileMatcher`, the API you provide to your users.

So far so good, and there is no repeated code yet. Later on, though, you decide to let people search based on any part of the file name. This is good for when your users cannot remember if they named a file `phb-important.doc`, `stupid-phb-report.doc`, `may2003salesdoc.phb`, or something entirely different; they just know that “phb” appears in the name somewhere. You go back to work and add this function to your `FileMatcher` API:

```
def filesContaining(query: String) =  
    for (file <- filesHere; if file.getName.contains(query))  
        yield file
```

This function works just like `filesEnding`. It searches `filesHere`, checks the name, and returns the file if the name matches. The only difference is that this function uses `contains` instead of `endsWith`.

The months go by, and the program becomes more successful. Eventually, you give in to the requests of a few power users who want to search based on regular expressions. These sloppy guys have immense directories with thousands of files, and they would like to do things like find all “pdf” files that have “oopsla” in the title somewhere. To support them, you write this function:

```
def filesRegex(query: String) =  
    for (file <- filesHere; if file.getName.matches(query))  
        yield file
```

Experienced programmers will notice all of this repetition and wonder if it can be factored into a common helper function. Doing it the obvious way does not work, however. You would like to be able to do the following:

```
def filesMatching(query: String, method) =  
    for (file <- filesHere; if file.getName.method(query))  
        yield file
```

This approach would work in some dynamic languages, but Scala does not allow pasting together code at runtime like this. So what do you do?

Function values provide an answer. While you cannot pass around a method name as a value, you can get the same effect by passing around a function value that calls the method for you. In this case, you could add a matcher parameter to the method whose sole purpose is to check a file name against a query:

```
def filesMatching(query: String,  
    matcher: (String, String) => Boolean) = {  
    for (file <- filesHere; if matcher(file.getName, query))  
        yield file  
}
```

In this version of the method, the `if` clause now uses `matcher` to check the file name against the query. Precisely what this check does depends on what is specified as the matcher. Take a look, now, at the type of `matcher` itself. It is a function, and thus has a `=>` in the type. This function takes two string arguments—the file name and the query—and returns a boolean, so the type of this function is `(String, String) => Boolean`.

Given this new `filesMatching` helper method, you can simplify the three searching methods by having them call the helper method, passing in an appropriate function:

```
def filesEnding(query: String) =  
    filesMatching(query, _.endsWith(_))  
  
def filesContaining(query: String) =  
    filesMatching(query, _.contains(_))  
  
def filesRegex(query: String) =  
    filesMatching(query, _.matches(_))
```

The function literals shown in this example use the placeholder syntax, introduced in the previous chapter, which may not as yet feel very natural to you. So here's a clarification of how placeholders are used: The function literal `_.endsWith(_)`, used in the `filesEnding` method, means the same thing as:

```
(fileName: String, query: String) => fileName.endsWith(query)
```

Because `filesMatching` takes a function that requires two `String` arguments, you need not specify the types of the arguments; you could just write `(fileName, query) => fileName.endsWith(query)`. Since the parameters are each used only once in the body of the function (*i.e.*, the first parameter, `fileName`, is used first in the body, and the second parameter, `query`, is used second), you can use the placeholder syntax: `_.endsWith(_)`. The first underscore is a placeholder for the first parameter, the file name, and the second underscore a placeholder for the second parameter, the query string.

This code is already simplified, but it can actually be even shorter. Notice that the `query` gets passed to `filesMatching`, but `filesMatching` does nothing with the `query` except to pass it back to the passed `matcher` function. This passing back and forth is unnecessary because the caller already knew the `query` to begin with! You might as well remove the `query` parameter from `filesMatching` and `matcher`, thus simplifying the code as shown in [Listing 9.1](#).

This example demonstrates the way in which first-class functions can help you eliminate code duplication where it would be very difficult to do so without them. In Java, for example, you could create an interface containing a method that takes one `String` and returns a `Boolean`, then create and pass anonymous inner class instances that implement this interface to `filesMatching`. Although this approach would remove the code duplication you are trying to eliminate, it would, at the same time, add as much or more new code. Thus the benefit is not worth the cost, and you may as well live with the duplication.

Moreover, this example demonstrates how closures can help you reduce code duplication. The function literals used in the previous example, such as `_.endsWith(_)` and `_.contains(_)`, are instantiated at runtime into function values that are *not* closures because they don't capture any free variables. Both variables used in the expression, `_.endsWith(_)`, for example, are represented by underscores, which means they are taken from arguments

```
object FileMatcher {
    private def filesHere = (new java.io.File(".")).listFiles
    private def filesMatching(matcher: String => Boolean) =
        for (file <- filesHere; if matcher(file.getName))
            yield file
    def filesEnding(query: String) =
        filesMatching(_.endsWith(query))
    def filesContaining(query: String) =
        filesMatching(_.contains(query))
    def filesRegex(query: String) =
        filesMatching(_.matches(query))
}
```

Listing 9.1 · Using closures to reduce code duplication.

to the function. Thus, `_.endsWith(_)` uses two bound variables, and no free variables. By contrast, the function literal `_.endsWith(query)`, used in the most recent example, contains one bound variable, the argument represented by the underscore, and one free variable named `query`. It is only because Scala supports closures that you were able to remove the `query` parameter from `filesMatching` in the most recent example, thereby simplifying the code even further.

9.2 Simplifying client code

The previous example demonstrated that higher-order functions can help reduce code duplication as you implement an API. Another important use of higher-order functions is to put them in an API itself to make client code more concise. A good example is provided by the special-purpose looping methods of Scala’s collection types.¹ Many of these are listed in Table 3.1 in Chapter 3, but take a look at just one example for now to see why these methods are so useful.

¹These special-purpose looping methods are defined in trait Traversable, which is extended by List, Set, and Map. See Chapter 17 for a discussion.

Consider `exists`, a method that determines whether a passed value is contained in a collection. You could, of course, search for an element by having a var initialized to false, looping through the collection checking each item, and setting the var to true if you find what you are looking for. Here's a method that uses this approach to determine whether a passed List contains a negative number:

```
def containsNeg(nums: List[Int]): Boolean = {  
    var exists = false  
    for (num <- nums)  
        if (num < 0)  
            exists = true  
    exists  
}
```

If you define this method in the interpreter, you can call it like this:

```
scala> containsNeg(List(1, 2, 3, 4))  
res0: Boolean = false  
  
scala> containsNeg(List(1, 2, -3, 4))  
res1: Boolean = true
```

A more concise way to define the method, though, is by calling the higher-order function `exists` on the passed List, like this:

```
def containsNeg(nums: List[Int]) = nums.exists(_ < 0)
```

This version of `containsNeg` yields the same results as the previous:

```
scala> containsNeg(Nil)  
res2: Boolean = false  
  
scala> containsNeg(List(0, -1, -2))  
res3: Boolean = true
```

The `exists` method represents a control abstraction. It is a special-purpose looping construct provided by the Scala library, rather than built into the Scala language like `while` or `for`. In the previous section, the higher-order function, `filesMatching`, reduces code duplication in the implementation of the object `FileMatcher`. The `exists` method provides a similar benefit, but because `exists` is public in Scala's collections API, the code duplication

it reduces is client code of that API. If `exists` didn't exist, and you wanted to write a `containsOdd` method to test whether a list contains odd numbers, you might write it like this:

```
def containsOdd(nums: List[Int]): Boolean = {
    var exists = false
    for (num <- nums)
        if (num % 2 == 1)
            exists = true
    exists
}
```

If you compare the body of `containsNeg` with that of `containsOdd`, you'll find that everything is repeated except the test condition of an `if` expression. Using `exists`, you could write this instead:

```
def containsOdd(nums: List[Int]) = nums.exists(_ % 2 == 1)
```

The body of the code in this version is again identical to the body of the corresponding `containsNeg` method (the version that uses `exists`), except the condition for which to search is different. Yet the amount of code duplication is much smaller because all of the looping infrastructure is factored out into the `exists` method itself.

There are many other looping methods in Scala's standard library. As with `exists`, they can often shorten your code if you recognize opportunities to use them.

9.3 Currying

In Chapter 1, we said that Scala allows you to create new control abstractions that “feel like native language support.” Although the examples you've seen so far are indeed control abstractions, it is unlikely anyone would mistake them for native language support. To understand how to make control abstractions that feel more like language extensions, you first need to understand the functional programming technique called *currying*.

A curried function is applied to multiple argument lists, instead of just one. Listing 9.2 shows a regular, non-curried function, which adds two `Int` parameters, `x` and `y`.

```
scala> def plainOldSum(x: Int, y: Int) = x + y
plainOldSum: (x: Int, y: Int)Int
scala> plainOldSum(1, 2)
res4: Int = 3
```

Listing 9.2 · Defining and invoking a “plain old” function.

By contrast, Listing 9.3 shows a similar function that’s curried. Instead of one list of two Int parameters, you apply this function to two lists of one Int parameter each.

```
scala> def curriedSum(x: Int)(y: Int) = x + y
curriedSum: (x: Int)(y: Int)Int
scala> curriedSum(1)(2)
res5: Int = 3
```

Listing 9.3 · Defining and invoking a curried function.

What’s happening here is that when you invoke `curriedSum`, you actually get two traditional function invocations back to back. The first function invocation takes a single Int parameter named `x`, and returns a function value for the second function. This second function takes the Int parameter `y`. Here’s a function named `first` that does in spirit what the first traditional function invocation of `curriedSum` would do:

```
scala> def first(x: Int) = (y: Int) => x + y
first: (x: Int)Int => Int
```

Applying the `first` function to 1—in other words, invoking the `first` function and passing in 1—yields the second function:

```
scala> val second = first(1)
second: Int => Int = <function1>
```

Applying the `second` function to 2 yields the result:

```
scala> second(2)
res6: Int = 3
```

These first and second functions are just an illustration of the currying process. They are not directly connected to the `curriedSum` function. Nevertheless, there is a way to get an actual reference to `curriedSum`'s “second” function. You can use the placeholder notation to use `curriedSum` in a partially applied function expression, like this:

```
scala> val onePlus = curriedSum(1)_  
onePlus: Int => Int = <function1>
```

The underscore in `curriedSum(1)_` is a placeholder for the second parameter list.² The result is a reference to a function that, when invoked, adds one to its sole `Int` argument and returns the result:

```
scala> onePlus(2)  
res7: Int = 3
```

And here's how you'd get a function that adds two to its sole `Int` argument:

```
scala> val twoPlus = curriedSum(2)_  
twoPlus: Int => Int = <function1>  
  
scala> twoPlus(2)  
res8: Int = 4
```

9.4 Writing new control structures

In languages with first-class functions, you can effectively make new control structures even though the syntax of the language is fixed. All you need to do is create methods that take functions as arguments.

For example, here is the “twice” control structure, which repeats an operation two times and returns the result:

```
scala> def twice(op: Double => Double, x: Double) = op(op(x))  
twice: (op: Double => Double, x: Double)Double  
  
scala> twice(_ + 1, 5)  
res9: Double = 7.0
```

²In the previous chapter, when the placeholder notation was used on traditional methods, like `println_`, you had to leave a space between the name and the underscore. In this case you don't, because whereas `println_` is a legal identifier in Scala, `curriedSum(1)_` is not.

The type of `op` in this example is `Double => Double`, which means it is a function that takes one `Double` as an argument and returns another `Double`.

Any time you find a control pattern repeated in multiple parts of your code, you should think about implementing it as a new control structure. Earlier in the chapter you saw `filesMatching`, a very specialized control pattern. Consider now a more widely used coding pattern: open a resource, operate on it, and then close the resource. You can capture this in a control abstraction using a method like the following:

```
def withPrintWriter(file: File, op: PrintWriter => Unit) = {  
    val writer = new PrintWriter(file)  
    try {  
        op(writer)  
    } finally {  
        writer.close()  
    }  
}
```

Given such a method, you can use it like this:

```
withPrintWriter(  
    new File("date.txt"),  
    writer => writer.println(new java.util.Date)  
)
```

The advantage of using this method is that it's `withPrintWriter`, not user code, that assures the file is closed at the end. So it's impossible to forget to close the file. This technique is called the *loan pattern*, because a control-abstraction function, such as `withPrintWriter`, opens a resource and "loans" it to a function. For instance, `withPrintWriter` in the previous example loans a `PrintWriter` to the function, `op`. When the function completes, it signals that it no longer needs the "borrowed" resource. The resource is then closed in a `finally` block, to ensure it is indeed closed, regardless of whether the function completes by returning normally or throwing an exception.

One way in which you can make the client code look a bit more like a built-in control structure is to use curly braces instead of parentheses to surround the argument list. In any method invocation in Scala in which you're

passing in exactly one argument, you can opt to use curly braces to surround the argument instead of parentheses.

For example, instead of:

```
scala> println("Hello, world!")
Hello, world!
```

You could write:

```
scala> println { "Hello, world!" }
Hello, world!
```

In the second example, you used curly braces instead of parentheses to surround the arguments to `println`. This curly braces technique will work, however, only if you're passing in one argument. Here's an attempt at violating that rule:

```
scala> val g = "Hello, world!"
g: String = Hello, world!
scala> g.substring { 7, 9 }
<console>:1: error: ';' expected but ',' found.
          g.substring { 7, 9 }
                           ^
```

Because you are attempting to pass in two arguments to `substring`, you get an error when you try to surround those arguments with curly braces. Instead, you'll need to use parentheses:

```
scala> g.substring(7, 9)
res12: String = wo
```

The purpose of this ability to substitute curly braces for parentheses for passing in one argument is to enable client programmers to write function literals between curly braces. This can make a method call feel more like a control abstraction. Take the `withPrintWriter` method defined previously as an example. In its most recent form, `withPrintWriter` takes two arguments, so you can't use curly braces. Nevertheless, because the function passed to `withPrintWriter` is the last argument in the list, you can use currying to pull the first argument, the `File`, into a separate argument list. This will leave the function as the lone parameter of the second argument list. Listing 9.4 shows how you'd need to redefine `withPrintWriter`.

```
def withPrintWriter(file: File)(op: PrintWriter => Unit) = {
    val writer = new PrintWriter(file)
    try {
        op(writer)
    } finally {
        writer.close()
    }
}
```

Listing 9.4 · Using the loan pattern to write to a file.

The new version differs from the old one only in that there are now two parameter lists with one parameter each instead of one parameter list with two parameters. Look between the two parameters. In the previous version of `withPrintWriter`, shown on [page 212](#), you see `...File, op....`. But in this version, you see `...File)(op....`. Given the above definition, you can call the method with a more pleasing syntax:

```
val file = new File("date.txt")
withPrintWriter(file) { writer =>
    writer.println(new java.util.Date)
}
```

In this example, the first argument list, which contains one `File` argument, is written surrounded by parentheses. The second argument list, which contains one function argument, is surrounded by curly braces.

9.5 By-name parameters

The `withPrintWriter` method shown in the previous section differs from built-in control structures of the language, such as `if` and `while`, in that the code between the curly braces takes an argument. The function passed to `withPrintWriter` requires one argument of type `PrintWriter`. This argument shows up as the “`writer =>`” in:

```
withPrintWriter(file) { writer =>
    writer.println(new java.util.Date)
}
```

But what if you want to implement something more like `if` or `while`, where there is no value to pass into the code between the curly braces? To help with such situations, Scala provides by-name parameters.

As a concrete example, suppose you want to implement an assertion construct called `myAssert`.³ The `myAssert` function will take a function value as input and consult a flag to decide what to do. If the flag is set, `myAssert` will invoke the passed function and verify that it returns `true`. If the flag is turned off, `myAssert` will quietly do nothing at all.

Without using by-name parameters, you could write `myAssert` like this:

```
var assertionsEnabled = true

def myAssert(predicate: () => Boolean) =
  if (assertionsEnabled && !predicate())
    throw new AssertionError
```

The definition is fine, but using it is a little bit awkward:

```
myAssert(() => 5 > 3)
```

You would really prefer to leave out the empty parameter list and `=>` symbol in the function literal and write the code like this:

```
myAssert(5 > 3) // Won't work, because missing () =>
```

By-name parameters exist precisely so that you can do this. To make a by-name parameter, you give the parameter a type starting with `=>` instead of `() =>`. For example, you could change `myAssert`'s predicate parameter into a by-name parameter by changing its type, “`(() => Boolean)`”, into “`=> Boolean`”. Listing 9.5 shows how that would look:

```
def byNameAssert(predicate: => Boolean) =
  if (assertionsEnabled && !predicate)
    throw new AssertionError
```

Listing 9.5 · Using a by-name parameter.

Now you can leave out the empty parameter in the property you want to assert. The result is that using `byNameAssert` looks exactly like using a built-in control structure:

³You'll call this `myAssert`, not `assert`, because Scala provides an `assert` of its own, which will be described in Section 14.1.

```
byNameAssert(5 > 3)
```

A by-name type, in which the empty parameter list, (), is left out, is only allowed for parameters. There is no such thing as a by-name variable or a by-name field.

Now, you may be wondering why you couldn't simply write `myAssert` using a plain old Boolean for the type of its parameter, like this:

```
def boolAssert(predicate: Boolean) =  
  if (assertionsEnabled && !predicate)  
    throw new AssertionException
```

This formulation is also legal, of course, and the code using this version of `boolAssert` would still look exactly as before:

```
boolAssert(5 > 3)
```

Nevertheless, one difference exists between these two approaches that is important to note. Because the type of `boolAssert`'s parameter is `Boolean`, the expression inside the parentheses in `boolAssert(5 > 3)` is evaluated *before* the call to `boolAssert`. The expression `5 > 3` yields `true`, which is passed to `boolAssert`. By contrast, because the type of `byNameAssert`'s `predicate` parameter is `=> Boolean`, the expression inside the parentheses in `byNameAssert(5 > 3)` is *not* evaluated before the call to `byNameAssert`. Instead a function value will be created whose `apply` method will evaluate `5 > 3`, and this function value will be passed to `byNameAssert`.

The difference between the two approaches, therefore, is that if assertions are disabled, you'll see any side effects that the expression inside the parentheses may have in `boolAssert`, but not in `byNameAssert`. For example, if assertions are disabled, attempting to assert on "`x / 0 == 0`" will yield an exception in `boolAssert`'s case:

```
scala> val x = 5  
x: Int = 5  
  
scala> var assertionsEnabled = false  
assertionsEnabled: Boolean = false  
  
scala> boolAssert(x / 0 == 0)  
java.lang.ArithmetricException: / by zero  
... 33 elided
```

But attempting to assert on the same code in `byNameAssert`'s case will *not* yield an exception:

```
scala> byNameAssert(x / 0 == 0)
```

9.6 Conclusion

This chapter has shown you how to build on Scala's rich function support to build control abstractions. You can use functions within your code to factor out common control patterns, and you can take advantage of higher-order functions in the Scala library to reuse control patterns that are common across all programmers' code. We also discussed how to use currying and by-name parameters so that your own higher-order functions can be used with a concise syntax.

In the previous chapter and this one, you have seen quite a lot of information about functions. The next few chapters will go back to discussing more object-oriented features of the language.

Chapter 10

Composition and Inheritance

[Chapter 6](#) introduced some basic object-oriented aspects of Scala. This chapter picks up where [Chapter 6](#) left off and dives into Scala’s support for object-oriented programming in much greater detail.

We’ll compare two fundamental relationships between classes: composition and inheritance. Composition means one class holds a reference to another, using the referenced class to help it fulfill its mission. Inheritance is the superclass/subclass relationship.

In addition to these topics, we’ll discuss abstract classes, parameterless methods, extending classes, overriding methods and fields, parametric fields, invoking superclass constructors, polymorphism and dynamic binding, final members and classes, and factory objects and methods.

10.1 A two-dimensional layout library

As a running example in this chapter, we’ll create a library for building and rendering two-dimensional layout elements. Each element will represent a rectangle filled with text. For convenience, the library will provide factory methods named “elem” that construct new elements from passed data. For example, you’ll be able to create a layout element containing a string using a factory method with the following signature:

```
elem(s: String): Element
```

As you can see, elements will be modeled with a type named `Element`. You’ll be able to call `above` or `beside` on an element, passing in a second element, to get a new element that combines the two. For example,

the following expression would construct a larger element consisting of two columns, each with a height of two:

```
val column1 = elem("hello") above elem("***")
val column2 = elem("***") above elem("world")
column1 beside column2
```

Printing the result of this expression would give you:

```
hello ***
*** world
```

Layout elements are a good example of a system in which objects can be constructed from simple parts with the aid of composing operators. In this chapter, we'll define classes that enable element objects to be constructed from arrays, lines, and rectangles. These basic element objects will be the simple parts. We'll also define composing operators `above` and `beside`. Such composing operators are also often called *combinators* because they combine elements of some domain into new elements.

Thinking in terms of combinators is generally a good way to approach library design: it pays to think about the fundamental ways to construct objects in an application domain. What are the simple objects? In what ways can more interesting objects be constructed out of simpler ones? How do combinators hang together? What are the most general combinations? Do they satisfy any interesting laws? If you have good answers to these questions, your library design is on track.

10.2 Abstract classes

Our first task is to define type `Element`, which represents layout elements. Since elements are two dimensional rectangles of characters, it makes sense to include a member, `contents`, that refers to the contents of a layout element. The contents can be represented as an array of strings, where each string represents a line. Hence, the type of the result returned by `contents` will be `Array[String]`. Listing 10.1 shows what it will look like.

In this class, `contents` is declared as a method that has no implementation. In other words, the method is an *abstract* member of class `Element`. A class with abstract members must itself be declared abstract, which is done by writing an `abstract` modifier in front of the `class` keyword:

```
abstract class Element {  
    def contents: Array[String]  
}
```

Listing 10.1 · Defining an abstract method and class.

```
abstract class Element ...
```

The `abstract` modifier signifies that the class may have abstract members that do not have an implementation. As a result, you cannot instantiate an abstract class. If you try to do so, you'll get a compiler error:

```
scala> new Element  
<console>:5: error: class Element is abstract;  
      cannot be instantiated  
      new Element  
           ^
```

Later in this chapter, you'll see how to create subclasses of class `Element`, which you'll be able to instantiate because they fill in the missing definition for `contents`.

Note that the `contents` method in class `Element` does not carry an `abstract` modifier. A method is abstract if it does not have an implementation (*i.e.*, no `equals` sign or body). Unlike Java, no `abstract` modifier is necessary (or allowed) on method declarations. Methods that have an implementation are called *concrete*.

Another bit of terminology distinguishes between *declarations* and *definitions*. Class `Element` *declares* the abstract method `contents`, but currently *defines* no concrete methods. In the next section, however, we'll enhance `Element` by defining some concrete methods.

10.3 Defining parameterless methods

As a next step, we'll add methods to `Element` that reveal its width and height, as shown in Listing 10.2. The `height` method returns the number of lines in `contents`. The `width` method returns the length of the first line, or if there are no lines in the element, returns zero. (This means you cannot define an element with a height of zero and a non-zero width.)

```
abstract class Element {  
    def contents: Array[String]  
    def height: Int = contents.length  
    def width: Int = if (height == 0) 0 else contents(0).length  
}
```

Listing 10.2 · Defining parameterless methods `width` and `height`.

Note that none of `Element`'s three methods has a parameter list, not even an empty one. For example, instead of:

```
def width(): Int
```

the method is defined without parentheses:

```
def width: Int
```

Such *parameterless methods* are quite common in Scala. By contrast, methods defined with empty parentheses, such as `def height(): Int`, are called *empty-paren methods*. The recommended convention is to use a parameterless method whenever there are no parameters *and* the method accesses mutable state only by reading fields of the containing object (in particular, it does not change mutable state). This convention supports the *uniform access principle*,¹ which says that client code should not be affected by a decision to implement an attribute as a field or method.

For instance, we could implement `width` and `height` as fields, instead of methods, simply by changing the `def` in each definition to a `val`:

```
abstract class Element {  
    def contents: Array[String]  
    val height = contents.length  
    val width =  
        if (height == 0) 0 else contents(0).length  
}
```

The two pairs of definitions are completely equivalent from a client's point of view. The only difference is that field accesses might be slightly faster than method invocations because the field values are pre-computed when the

¹Meyer, *Object-Oriented Software Construction* [Mey00]

class is initialized, instead of being computed on each method call. On the other hand, the fields require extra memory space in each `Element` object. So it depends on the usage profile of a class whether an attribute is better represented as a field or method, and that usage profile might change over time. The point is that clients of the `Element` class should not be affected when its internal implementation changes.

In particular, a client of class `Element` should not need to be rewritten if a field of that class gets changed into an access function, so long as the access function is *pure* (*i.e.*, it does not have any side effects and does not depend on mutable state). The client should not need to care either way.

So far so good. But there's still a slight complication that has to do with the way Java handles things. The problem is that Java does not implement the uniform access principle. So it's `string.length()` in Java, not `string.length`, even though it's `array.length`, not `array.length()`. Needless to say, this is very confusing.

To bridge that gap, Scala is very liberal when it comes to mixing parameterless and empty-paren methods. In particular, you can override a parameterless method with an empty-paren method, and *vice versa*. You can also leave off the empty parentheses on an invocation of any function that takes no arguments. For instance, the following two lines are both legal in Scala:

```
Array(1, 2, 3).toString  
"abc".length
```

In principle it's possible to leave out all empty parentheses in Scala function calls. However, it's still recommended to write the empty parentheses when the invoked method represents more than a property of its receiver object. For instance, empty parentheses are appropriate if the method performs I/O, writes reassignable variables (`vars`), or reads `vars` other than the receiver's fields, either directly or indirectly by using mutable objects. That way, the parameter list acts as a visual clue that some interesting computation is triggered by the call. For instance:

```
"hello".length // no () because no side-effect  
println()      // better to not drop the ()
```

To summarize, it is encouraged in Scala to define methods that take no parameters and have no side effects as parameterless methods (*i.e.*, leaving off the empty parentheses). On the other hand, you should never define a method

that has side-effects without parentheses, because invocations of that method would then look like a field selection. So your clients might be surprised to see the side effects.

Similarly, whenever you invoke a function that has side effects, be sure to include the empty parentheses when you write the invocation. Another way to think about this is if the function you’re calling performs an operation, use the parentheses. But if it merely provides access to a property, leave the parentheses off.

10.4 Extending classes

We still need to be able to create new element objects. You have already seen that “new Element” cannot be used for this because class Element is abstract. To instantiate an element, therefore, we will need to create a subclass that extends Element and implements the abstract contents method. Listing 10.3 shows one possible way to do that:

```
class ArrayElement(contents: Array[String]) extends Element {  
    def contents: Array[String] = contents  
}
```

Listing 10.3 · Defining ArrayElement as a subclass of Element.

Class ArrayElement is defined to *extend* class Element. Just like in Java, you use an extends clause after the class name to express this:

... extends Element ...

Such an extends clause has two effects: It makes class ArrayElement *inherit* all non-private members from class Element, and it makes the type ArrayElement a *subtype* of the type Element. Given ArrayElement extends Element, class ArrayElement is called a *subclass* of class Element. Conversely, Element is a *superclass* of ArrayElement. If you leave out an extends clause, the Scala compiler implicitly assumes your class extends from scala.AnyRef, which on the Java platform is the same as class java.lang.Object. Thus, class Element implicitly extends class AnyRef. You can see these inheritance relationships in Figure 10.1.




Figure 10.1 · Class diagram for `ArrayElement`.

Inheritance means that all members of the superclass are also members of the subclass, with two exceptions. First, private members of the superclass are not inherited in a subclass. Second, a member of a superclass is not inherited if a member with the same name and parameters is already implemented in the subclass. In that case we say the member of the subclass *overrides* the member of the superclass. If the member in the subclass is concrete and the member of the superclass is abstract, we also say that the concrete member *implements* the abstract one.

For example, the `contents` method in `ArrayElement` overrides (or alternatively: implements) abstract method `contents` in class `Element`.² By contrast, class `ArrayElement` inherits the `width` and `height` methods from class `Element`. For example, given an `ArrayElement` `ae`, you can query its `width` using `ae.width`, as if `width` were defined in class `ArrayElement`:

```
scala> val ae = new ArrayElement(Array("hello", "world"))
ae: ArrayElement = ArrayElement@39274bf7
scala> ae.width
```

²One flaw with this design is that because the returned array is mutable, clients could change it. For the book we'll keep things simple, but were `ArrayElement` part of a real project, you might consider returning a *defensive copy* of the array instead. Another problem is we aren't currently ensuring that every `String` element of the `contents` array has the same length. This could be solved by checking the precondition in the primary constructor and throwing an exception if it is violated.

```
res0: Int = 5
```

Subtyping means that a value of the subclass can be used wherever a value of the superclass is required. For example:

```
val e: Element = new ArrayElement(Array("hello"))
```

Variable `e` is defined to be of type `Element`, so its initializing value should also be an `Element`. In fact, the initializing value's type is `ArrayElement`. This is OK, because class `ArrayElement` extends class `Element`, and as a result, the type `ArrayElement` is compatible with the type `Element`.³

Figure 10.1 also shows the *composition* relationship that exists between `ArrayElement` and `Array[String]`. This relationship is called composition because class `ArrayElement` is “composed” out of class `Array[String]`, in that the Scala compiler will place into the binary class it generates for `ArrayElement` a field that holds a reference to the passed `conts` array. We'll discuss some design considerations concerning composition and inheritance later in this chapter, in Section 10.11.

10.5 Overriding methods and fields

The uniform access principle is just one aspect where Scala treats fields and methods more uniformly than Java. Another difference is that in Scala, fields and methods belong to the same namespace. This makes it possible for a field to override a parameterless method. For instance, you could change the implementation of `contents` in class `ArrayElement` from a method to a field without having to modify the abstract method definition of `contents` in class `Element`, as shown in Listing 10.4:

```
class ArrayElement(conts: Array[String]) extends Element {  
    val contents: Array[String] = conts  
}
```

Listing 10.4 · Overriding a parameterless method with a field.

Field `contents` (defined with a `val`) in this version of `ArrayElement` is a perfectly good implementation of the parameterless method `contents`

³For more perspective on the difference between subclass and subtype, see the glossary entry for *subtype*.

(declared with a `def`) in class `Element`. On the other hand, in Scala it is forbidden to define a field and method with the same name in the same class, whereas this is allowed in Java.

For example, this Java class would compile just fine:

```
// This is Java
class CompilesFine {
    private int f = 0;
    public int f() {
        return 1;
    }
}
```

But the corresponding Scala class would not compile:

```
class WontCompile {
    private var f = 0 // Won't compile, because a field
    def f = 1         // and method have the same name
}
```

Generally, Scala has just two namespaces for definitions in place of Java's four. Java's four namespaces are fields, methods, types, and packages. By contrast, Scala's two namespaces are:

- values (fields, methods, packages, and singleton objects)
- types (class and trait names)

The reason Scala places fields and methods into the same namespace is precisely so you can override a parameterless method with a `val`, something you can't do with Java.⁴

10.6 Defining parametric fields

Consider again the definition of class `ArrayElement` shown in the previous section. It has a parameter `conts` whose sole purpose is to be copied into the

⁴The reason that packages share the same namespace as fields and methods in Scala is to enable you to import packages (in addition to just the names of types) and the fields and methods of singleton objects. This is also something you can't do in Java. It will be described in [Section 13.3](#).

contents field. The name `conts` of the parameter was chosen just so that it would look similar to the field name `contents` without actually clashing with it. This is a “code smell,” a sign that there may be some unnecessary redundancy and repetition in your code.

You can avoid the code smell by combining the parameter and the field in a single *parametric field* definition, as shown in Listing 10.5:

```
class ArrayElement(  
    val contents: Array[String]  
) extends Element
```

Listing 10.5 · Defining `contents` as a parametric field.

Note that now the `contents` parameter is prefixed by `val`. This is a shorthand that defines at the same time a parameter and field with the same name. Specifically, class `ArrayElement` now has an (unre assignable) field `contents`, which can be accessed from outside the class. The field is initialized with the value of the parameter. It’s as if the class had been written as follows, where `x123` is an arbitrary fresh name for the parameter:

```
class ArrayElement(x123: Array[String]) extends Element {  
    val contents: Array[String] = x123  
}
```

You can also prefix a class parameter with `var`, in which case the corresponding field would be re assignable. Finally, it is possible to add modifiers, such as `private`, `protected`,⁵ or `override` to these parametric fields, just as you can for any other class member. Consider, for instance, the following class definitions:

```
class Cat {  
    val dangerous = false  
}  
class Tiger(  
    override val dangerous: Boolean,  
    private var age: Int  
) extends Cat
```

⁵The `protected` modifier, which grants access to subclasses, will be covered in detail in Chapter 13.

Tiger's definition is a shorthand for the following alternate class definition with an overriding member `dangerous` and a private member `age`:

```
class Tiger(param1: Boolean, param2: Int) extends Cat {  
    override val dangerous = param1  
    private var age = param2  
}
```

Both members are initialized from the corresponding parameters. We chose the names of those parameters, `param1` and `param2`, arbitrarily. The important thing was that they not clash with any other name in scope.

10.7 Invoking superclass constructors

You now have a complete system consisting of two classes: an abstract class `Element`, which is extended by a concrete class `ArrayElement`. You might also envision other ways to express an element. For example, clients might want to create a layout element consisting of a single line given by a string. Object-oriented programming makes it easy to extend a system with new data-variations. You can simply add subclasses. For example, Listing 10.6 shows a `LineElement` class that extends `ArrayElement`:

```
class LineElement(s: String) extends ArrayElement(Array(s)) {  
    override def width = s.length  
    override def height = 1  
}
```

Listing 10.6 · Invoking a superclass constructor.

Since `LineElement` extends `ArrayElement`, and `ArrayElement`'s constructor takes a parameter (an `Array[String]`), `LineElement` needs to pass an argument to the primary constructor of its superclass. To invoke a superclass constructor, you simply place the argument or arguments you want to pass in parentheses following the name of the superclass. For example, class `LineElement` passes `Array(s)` to `ArrayElement`'s primary constructor by placing it in parentheses after the superclass `ArrayElement`'s name:

```
... extends ArrayElement(Array(s)) ...
```




Figure 10.2 · Class diagram for LineElement.

With the new subclass, the inheritance hierarchy for layout elements now looks as shown in [Figure 10.2](#).

10.8 Using override modifiers

Note that the definitions of `width` and `height` in `LineElement` carry an `override` modifier. In [Section 6.3](#), you saw this modifier in the definition of a `toString` method. Scala requires such a modifier for all members that override a concrete member in a parent class. The modifier is optional if a member implements an abstract member with the same name. The modifier is forbidden if a member does not override or implement some other member in a base class. Since `height` and `width` in class `LineElement` override concrete definitions in class `Element`, `override` is required.

This rule provides useful information for the compiler that helps avoid some hard-to-catch errors and makes system evolution safer. For instance, if you happen to misspell the method or accidentally give it a different parameter list, the compiler will respond with an error message:

```
$ scalac LineElement.scala
.../LineElement.scala:50:
error: method hight overrides nothing
  override def hight = 1
^
```

The `override` convention is even more important when it comes to system evolution. Say you defined a library of 2D drawing methods. You made it publicly available, and it is widely used. In the next version of the library you want to add to your base class `Shape` a new method with this signature:

```
def hidden(): Boolean
```

Your new method will be used by various drawing methods to determine whether a shape needs to be drawn. This could lead to a significant speedup, but you cannot do this without the risk of breaking client code. After all, a client could have defined a subclass of `Shape` with a different implementation of `hidden`. Perhaps the client's method actually makes the receiver object disappear instead of testing whether the object is hidden. Because the two versions of `hidden` override each other, your drawing methods would end up making objects disappear, which is certainly not what you want!

These “accidental overrides” are the most common manifestation of what is called the “fragile base class” problem. The problem is that if you add new members to base classes (which we usually call superclasses) in a class hierarchy, you risk breaking client code. Scala cannot completely solve the fragile base class problem, but it improves on the situation compared to Java.⁶ If the drawing library and its clients were written in Scala, then the client's original implementation of `hidden` could not have had an `override` modifier, because at the time there was no other method with that name.

Once you add the `hidden` method to the second version of your shape class, a recompile of the client would give an error like the following:

```
.../Shapes.scala:6: error: error overriding method
      hidden in class Shape of type ()Boolean;
method hidden needs `override' modifier
def hidden(): Boolean =
^
```

That is, instead of wrong behavior your client would get a compile-time error, which is usually much preferable.

⁶In Java 1.5, an `@Override` annotation was introduced that works similarly to Scala's `override` modifier, but unlike Scala's `override`, is not required.

10.9 Polymorphism and dynamic binding

You saw in [Section 10.4](#) that a variable of type `Element` could refer to an object of type `ArrayElement`. The name for this phenomenon is *polymorphism*, which means “many shapes” or “many forms.” In this case, `Element` objects can have many forms.⁷

So far, you’ve seen two such forms: `ArrayElement` and `LineElement`. You can create more forms of `Element` by defining new `Element` subclasses. For example, you could define a new form of `Element` that has a given width and height, and is filled everywhere with a given character:

```
class UniformElement(  
    ch: Char,  
    override val width: Int,  
    override val height: Int  
) extends Element {  
    private val line = ch.toString * width  
    def contents = Array.fill(height)(line)  
}
```

The inheritance hierarchy for class `Element` now looks as shown in [Figure 10.3](#). As a result, Scala will accept all of the following assignments, because the type of the assigning expression conforms to the type of the defined variable:

```
val e1: Element = new ArrayElement(Array("hello", "world"))  
val ae: ArrayElement = new LineElement("hello")  
val e2: Element = ae  
val e3: Element = new UniformElement('x', 2, 3)
```

If you check the inheritance hierarchy, you’ll find that in each of these four `val` definitions, the type of the expression to the right of the equals sign is below the type of the `val` being initialized to the left of the equals sign.

The other half of the story, however, is that method invocations on variables and expressions are *dynamically bound*. This means that the actual method implementation invoked is determined at run time based on the class of the object, not the type of the variable or expression. To demonstrate this

⁷This kind of polymorphism is called *subtyping polymorphism*. Another kind of polymorphism in Scala called *universal polymorphism* is discussed in [Chapter 19](#).




Figure 10.3 · Class hierarchy of layout elements.

behavior, we'll temporarily remove all existing members from our `Element` classes and add a method named `demo` to `Element`. We'll override `demo` in `ArrayElement` and `LineElement`, but not in `UniformElement`:

```
abstract class Element {  
    def demo() = {  
        println("Element's implementation invoked")  
    }  
}  
  
class ArrayElement extends Element {  
    override def demo() = {  
        println("ArrayElement's implementation invoked")  
    }  
}  
  
class LineElement extends ArrayElement {  
    override def demo() = {  
        println("LineElement's implementation invoked")  
    }  
}  
  
// UniformElement inherits Element's demo  
class UniformElement extends Element
```

If you enter this code into the interpreter, you can then define this method

that takes an `Element` and invokes `demo` on it:

```
def invokeDemo(e: Element) = {
    e.demo()
}
```

If you pass an `ArrayElement` to `invokeDemo`, you'll see a message indicating `ArrayElement`'s implementation of `demo` was invoked, even though the type of the variable, `e`, on which `demo` was invoked is `Element`:

```
scala> invokeDemo(new ArrayElement)
ArrayElement's implementation invoked
```

Similarly, if you pass a `LineElement` to `invokeDemo`, you'll see a message that indicates `LineElement`'s `demo` implementation was invoked:

```
scala> invokeDemo(new LineElement)
LineElement's implementation invoked
```

The behavior when passing a `UniformElement` may at first glance look suspicious, but it is correct:

```
scala> invokeDemo(new UniformElement)
Element's implementation invoked
```

Because `UniformElement` does not override `demo`, it inherits the implementation of `demo` from its superclass, `Element`. Thus, `Element`'s implementation is the correct implementation of `demo` to invoke when the class of the object is `UniformElement`.

10.10 Declaring final members

Sometimes when designing an inheritance hierarchy, you want to ensure that a member cannot be overridden by subclasses. In Scala, as in Java, you do this by adding a `final` modifier to the member. As shown in Listing 10.7, you could place a `final` modifier on `ArrayElement`'s `demo` method.

Given this version of `ArrayElement`, an attempt to override `demo` in its subclass, `LineElement`, would not compile:

```
class ArrayElement extends Element {
    final override def demo() = {
        println("ArrayElement's implementation invoked")
    }
}
```

Listing 10.7 · Declaring a final method.

```
elem.scala:18: error: error overriding method demo
  in class ArrayElement of type ()Unit;
method demo cannot override final member
    override def demo() = {
        ^

```

You may also at times want to ensure that an entire class not be subclassed. To do this you simply declare the entire class final by adding a final modifier to the class declaration. For example, Listing 10.8 shows how you would declare ArrayElement final:

```
final class ArrayElement extends Element {
    override def demo() = {
        println("ArrayElement's implementation invoked")
    }
}
```

Listing 10.8 · Declaring a final class.

With this version of ArrayElement, any attempt at defining a subclass would fail to compile:

```
elem.scala: 18: error: illegal inheritance from final class
  ArrayElement
  class LineElement extends ArrayElement {
      ^

```

We'll now remove the final modifiers and demo methods, and go back to the earlier implementation of the Element family. We'll focus our attention in the remainder of this chapter to completing a working version of the layout library.

10.11 Using composition and inheritance

Composition and inheritance are two ways to define a new class in terms of another existing class. If what you’re after is primarily code reuse, you should in general prefer composition to inheritance. Only inheritance suffers from the fragile base class problem, in which you can inadvertently break subclasses by changing a superclass.

One question you can ask yourself about an inheritance relationship is whether it models an *is-a* relationship.⁸ For example, it would be reasonable to say that `ArrayElement` *is-an* `Element`. Another question you can ask is whether clients will want to use the subclass type as a superclass type.⁹ In the case of `ArrayElement`, we do indeed expect clients will want to use an `ArrayElement` as an `Element`.

If you ask these questions about the inheritance relationships shown in [Figure 10.3](#), do any of the relationships seem suspicious? In particular, does it seem obvious to you that a `LineElement` *is-an* `ArrayElement`? Do you think clients would ever need to use a `LineElement` as an `ArrayElement`?

In fact, we defined `LineElement` as a subclass of `ArrayElement` primarily to reuse `ArrayElement`’s definition of `contents`. Perhaps it would be better, therefore, to define `LineElement` as a direct subclass of `Element`, like this:

```
class LineElement(s: String) extends Element {  
    val contents = Array(s)  
    override def width = s.length  
    override def height = 1  
}
```

In the previous version, `LineElement` had an inheritance relationship with `ArrayElement`, from which it inherited `contents`. It now has a composition relationship with `Array`: it holds a reference to an array of strings from its own `contents` field.¹⁰ Given this implementation of `LineElement`, the inheritance hierarchy for `Element` now looks as shown in [Figure 10.4](#).

⁸Meyers, *Effective C++* [[Mey91](#)]

⁹Eckel, *Thinking in Java* [[Eck98](#)]

¹⁰Class `ArrayElement` also has a composition relationship with `Array`, because its parametric `contents` field holds a reference to an array of strings. The code for `ArrayElement` is shown in [Listing 10.5](#) on [page 227](#). Its composition relationship is represented in class diagrams by a diamond, as shown, for example, in [Figure 10.1](#) on [page 224](#).




Figure 10.4 · Class hierarchy with revised LineElement.

10.12 Implementing above, beside, and `toString`

As a next step, we'll implement method `above` in class `Element`. Putting one element above another means concatenating the two contents values of the elements. So a first draft of method `above` could look like this:

```
def above(that: Element): Element =  
    new ArrayElement(this.contents ++ that.contents)
```

The `++` operation concatenates two arrays. Arrays in Scala are represented as Java arrays, but support many more methods. Specifically, arrays in Scala can be converted to instances of a class `scala.Seq`, which represents sequence-like structures and contains a number of methods for accessing and transforming sequences. Some other array methods will be explained in this chapter and a more comprehensive discussion will be given in [Chapter 17](#).

In fact, the code shown previously is not quite sufficient because it does not let you put elements of different widths on top of each other. To keep things simple in this section, however, we'll leave this as is and only pass elements of the same length to `above`. In [Section 10.14](#), we'll make an enhancement to `above` so that clients can use it to combine elements of different widths.

The next method to implement is `beside`. To put two elements beside each other, we'll create a new element in which every line results from concatenating corresponding lines of the two elements. As before, to keep things simple, we'll start by assuming the two elements have the same height. This leads to the following design of method `beside`:

```
def beside(that: Element): Element = {
    val contents = new Array[String](this.contents.length)
    for (i <- 0 until this.contents.length)
        contents(i) = this.contents(i) + that.contents(i)
    new ArrayElement(contents)
}
```

The `beside` method first allocates a new array, `contents`, and fills it with the concatenation of the corresponding array elements in `this.contents` and `that.contents`. It finally produces a new `ArrayElement` containing the new `contents`.

Although this implementation of `beside` works, it is in an imperative style, the telltale sign of which is the loop in which we index through arrays. Alternatively, the method could be abbreviated to one expression:

```
new ArrayElement(
    for (
        (line1, line2) <- this.contents zip that.contents
    ) yield line1 + line2
)
```

Here, the two arrays, `this.contents` and `that.contents`, are transformed into an array of pairs (as `Tuple2`s are called) using the `zip` operator. The `zip` operator picks corresponding elements in its two operands and forms an array of pairs. For instance, this expression:

```
Array(1, 2, 3) zip Array("a", "b")
```

will evaluate to:

```
Array((1, "a"), (2, "b"))
```

If one of the two operand arrays is longer than the other, `zip` will drop the remaining elements. In the expression above, the third element of the left operand, 3, does not form part of the result, because it does not have a corresponding element in the right operand.

The zipped array is then iterated over by a `for` expression. Here, the syntax “`for ((line1, line2) <- ...)`” allows you to name both elements of a pair in one *pattern* (*i.e.*, `line1` stands now for the first element of the pair, and `line2` stands for the second). Scala’s pattern-matching system will

be described in detail in [Chapter 15](#). For now, you can just think of this as a way to define two vals, `line1` and `line2`, for each step of the iteration.

The `for` expression has a `yield` part and therefore yields a result. The result is of the same kind as the expression iterated over (*i.e.*, it is an array). Each element of the array is the result of concatenating the corresponding lines, `line1` and `line2`. So the end result of this code is the same as in the first version of `beside`, but because it avoids explicit array indexing, the result is obtained in a less error-prone way.

You still need a way to display elements. As usual, this is done by defining a `toString` method that returns an element formatted as a string. Here is its definition:

```
override def toString = contents mkString "\n"
```

The implementation of `toString` makes use of `mkString`, which is defined for all sequences, including arrays. As you saw in [Section 7.8](#), an expression like “`arr mkString sep`” returns a string consisting of all elements of the array `arr`. Each element is mapped to a string by calling its `toString` method. A separator string `sep` is inserted between consecutive element strings. So the expression, “`contents mkString "\n"`” formats the `contents` array as a string, where each array element appears on a line by itself.

Note that `toString` does not carry an empty parameter list. This follows the recommendations for the uniform access principle, because `toString` is a pure method that does not take any parameters. With the addition of these three methods, class `Element` now looks as shown in [Listing 10.9](#).

10.13 Defining a factory object

You now have a hierarchy of classes for layout elements. This hierarchy could be presented to your clients “as is,” but you might also choose to hide the hierarchy behind a factory object.

A factory object contains methods that construct other objects. Clients would then use these factory methods to construct objects, rather than constructing the objects directly with `new`. An advantage of this approach is that object creation can be centralized and the details of how objects are represented with classes can be hidden. This hiding will both make your library simpler for clients to understand, because less detail is exposed, and provide

```
abstract class Element {  
    def contents: Array[String]  
    def width: Int =  
        if (height == 0) 0 else contents(0).length  
    def height: Int = contents.length  
    def above(that: Element): Element =  
        new ArrayElement(this.contents ++ that.contents)  
    def beside(that: Element): Element =  
        new ArrayElement(  
            for (  
                (line1, line2) <- this.contents zip that.contents  
            ) yield line1 + line2  
        )  
    override def toString = contents mkString "\n"  
}
```

Listing 10.9 · Class `Element` with `above`, `beside`, and `toString`.

you with more opportunities to change your library’s implementation later without breaking client code.

The first task in constructing a factory for layout elements is to choose where the factory methods should be located. Should they be members of a singleton object or of a class? What should the containing object or class be called? There are many possibilities. A straightforward solution is to create a companion object of class `Element` and make this the factory object for layout elements. That way, you need to expose only the class/object combo of `Element` to your clients, and you can hide the three implementation classes `ArrayElement`, `LineElement`, and `UniformElement`.

[Listing 10.10](#) is a design of the `Element` object that follows this scheme. The `Element` object contains three overloaded variants of an `elem` method and each constructs a different kind of layout object.

With the advent of these factory methods, it makes sense to change the implementation of class `Element` so that it goes through the `elem` factory methods rather than creating new `ArrayElement` instances explicitly. To call the factory methods without qualifying them with `Element`, the name of the

```
object Element {  
    def elem(contents: Array[String]): Element =  
        new ArrayElement(contents)  
    def elem(chr: Char, width: Int, height: Int): Element =  
        new UniformElement(chr, width, height)  
    def elem(line: String): Element =  
        new LineElement(line)  
}
```

Listing 10.10 · A factory object with factory methods.

singleton object, we will import `Element.elem` at the top of the source file. In other words, instead of invoking the factory methods with `Element.elem` inside class `Element`, we'll import `Element.elem` so we can just call the factory methods by their simple name, `elem`. [Listing 10.11](#) shows what class `Element` will look like after these changes.

In addition, given the factory methods, the subclasses, `ArrayElement`, `LineElement`, and `UniformElement`, could now be private because they no longer need to be accessed directly by clients. In Scala, you can define classes and singleton objects inside other classes and singleton objects. One way to make the `Element` subclasses private is to place them inside the `Element` singleton object and declare them private there. The classes will still be accessible to the three `elem` factory methods, where they are needed. [Listing 10.12](#) shows how that will look.

10.14 Heighten and widen

We need one last enhancement. The version of `Element` shown in [Listing 10.11](#) is not quite sufficient because it does not allow clients to place elements of different widths on top of each other, or place elements of different heights beside each other.

For example, evaluating the following expression won't work correctly, because the second line in the combined element is longer than the first:

```
new ArrayElement(Array("hello")) above  
new ArrayElement(Array("world!"))
```

```
import Element.elem

abstract class Element {

    def contents: Array[String]

    def width: Int =
        if (height == 0) 0 else contents(0).length

    def height: Int = contents.length

    def above(that: Element): Element =
        elem(this.contents ++ that.contents)

    def beside(that: Element): Element =
        elem(
            for (
                (line1, line2) <- this.contents zip that.contents
            ) yield line1 + line2
        )

    override def toString = contents mkString "\n"
}
```

Listing 10.11 · Class `Element` refactored to use factory methods.

Similarly, evaluating the following expression would not work properly, because the first `ArrayElement` has a height of two and the second a height of only one:

```
new ArrayElement(Array("one", "two")) beside
new ArrayElement(Array("one"))
```

Listing 10.13 shows a private helper method, `widen`, which takes a width and returns an `Element` of that width. The result contains the contents of this `Element`, centered, padded to the left and right by any spaces needed to achieve the required width. Listing 10.13 also shows a similar method, `heighten`, which performs the same function in the vertical direction. The `widen` method is invoked by `above` to ensure that `Elements` placed above each other have the same width. Similarly, the `heighten` method is invoked by `beside` to ensure that elements placed beside each other have the same height. With these changes, the layout library is ready for use.

```
object Element {  
    private class ArrayElement(  
        val contents: Array[String]  
    ) extends Element  
  
    private class LineElement(s: String) extends Element {  
        val contents = Array(s)  
        override def width = s.length  
        override def height = 1  
    }  
  
    private class UniformElement(  
        ch: Char,  
        override val width: Int,  
        override val height: Int  
    ) extends Element {  
        private val line = ch.toString * width  
        def contents = Array.fill(height)(line)  
    }  
  
    def elem(contents: Array[String]): Element =  
        new ArrayElement(contents)  
  
    def elem(chr: Char, width: Int, height: Int): Element =  
        new UniformElement(chr, width, height)  
  
    def elem(line: String): Element =  
        new LineElement(line)  
}
```

Listing 10.12 · Hiding implementation with private classes.

```
import Element.elem

abstract class Element {
    def contents: Array[String]

    def width: Int = contents(0).length
    def height: Int = contents.length

    def above(that: Element): Element = {
        val this1 = this widen that.width
        val that1 = that widen this.width
        elem(this1.contents ++ that1.contents)
    }

    def beside(that: Element): Element = {
        val this1 = this heighten that.height
        val that1 = that heighten this.height
        elem(
            for ((line1, line2) <- this1.contents zip that1.contents)
            yield line1 + line2)
    }

    def widen(w: Int): Element =
        if (w <= width) this
        else {
            val left = elem(' ', (w - width) / 2, height)
            val right = elem(' ', w - width - left.width, height)
            left beside this beside right
        }

    def heighten(h: Int): Element =
        if (h <= height) this
        else {
            val top = elem(' ', width, (h - height) / 2)
            val bot = elem(' ', width, h - height - top.height)
            top above this above bot
        }

    override def toString = contents mkString "\n"
}
```

Listing 10.13 · Element with widen and heighten methods.

10.15 Putting it all together

A fun way to exercise almost all elements of the layout library is to write a program that draws a spiral with a given number of edges. This `Spiral` program, shown in Listing 10.14, will do just that.

```
import Element.elem

object Spiral {
    val space = elem(" ")
    val corner = elem("+")

    def spiral(nEdges: Int, direction: Int): Element = {
        if (nEdges == 1)
            elem("+")
        else {
            val sp = spiral(nEdges - 1, (direction + 3) % 4)
            def verticalBar = elem('|', 1, sp.height)
            def horizontalBar = elem('-', sp.width, 1)
            if (direction == 0)
                (corner beside horizontalBar) above (sp beside space)
            else if (direction == 1)
                (sp above space) beside (corner above verticalBar)
            else if (direction == 2)
                (space beside sp) above (horizontalBar beside corner)
            else
                (verticalBar above corner) beside (space above sp)
        }
    }

    def main(args: Array[String]) = {
        val nSides = args(0).toInt
        println(spiral(nSides, 0))
    }
}
```

Listing 10.14 · The `Spiral` application.

Because `Spiral` is a standalone object with a `main` method with the proper signature, it is a Scala application. `Spiral` takes one command-line

argument, an integer, and draws a spiral with the specified number of edges. For example, you could draw a six-edge spiral, as shown on the left, and larger spirals, as shown on the right.

```
$ scala Spiral 6      $ scala Spiral 11     $ scala Spiral 17
+----+
| |
| +-+
| + |
| |
+---+
          +-----+
| |
| | +---+
| | |
| | |
| |
+-----+
| | |
| | |
| | |
| |
+-----+
| | |
| | |
| | |
| |
+-----+
| | |
| | |
| | |
| |
+-----+
| | |
| | |
| | |
| |
+-----+
| | |
| | |
| | |
| |
+-----+
| | |
| | |
| | |
| |
+-----+
| | |
| | |
| | |
| |
+-----+
```

10.16 Conclusion

In this section, you saw more concepts related to object-oriented programming in Scala. Among others, you encountered abstract classes, inheritance and subtyping, class hierarchies, parametric fields, and method overriding. You should have developed a feel for constructing a non-trivial class hierarchy in Scala. We'll work with the layout library again in [Chapter 14](#).

Chapter 11

Scala’s Hierarchy

Now that you’ve seen the details of class inheritance in the previous chapter, it is a good time to take a step back and look at Scala’s class hierarchy as a whole. In Scala, every class inherits from a common superclass named `Any`. Because every class is a subclass of `Any`, the methods defined in `Any` are “universal” methods: they may be invoked on any object. Scala also defines some interesting classes at the bottom of the hierarchy, `Null` and `Nothing`, which essentially act as common *subclasses*. For example, just as `Any` is a superclass of every other class, `Nothing` is a subclass of every other class. In this chapter, we’ll give you a tour of Scala’s class hierarchy.

11.1 Scala’s class hierarchy

Figure 11.1 shows an outline of Scala’s class hierarchy. At the top of the hierarchy is class `Any`, which defines methods that include the following:

```
final def ==(that: Any): Boolean
final def !=(that: Any): Boolean
def equals(that: Any): Boolean
def ##: Int
def hashCode: Int
def toString: String
```

Because every class inherits from `Any`, every object in a Scala program can be compared using `==`, `!=`, or `equals`; hashed using `##` or `hashCode`; and formatted using `toString`. The equality and inequality methods, `==` and `!=`, are declared `final` in class `Any`, so they cannot be overridden in subclasses.

The `==` method is essentially the same as `equals` and `!=` is always the negation of `equals`.¹ So individual classes can tailor what `==` or `!=` means by overriding the `equals` method. We'll show an example later in this chapter.

The root class `Any` has two subclasses: `AnyVal` and `AnyRef`. `AnyVal` is the parent class of *value classes* in Scala. While you can define your own value classes (see [Section 11.4](#)), there are nine value classes built into Scala: `Byte`, `Short`, `Char`, `Int`, `Long`, `Float`, `Double`, `Boolean`, and `Unit`. The first eight of these correspond to Java's primitive types, and their values are represented at run time as Java's primitive values. The instances of these classes are all written as literals in Scala. For example, `42` is an instance of `Int`, `'x'` is an instance of `Char`, and `false` an instance of `Boolean`. You cannot create instances of these classes using `new`. This is enforced by the "trick" that value classes are all defined to be both abstract and final.

So if you were to write:

```
scala> new Int
```

you would get:

```
<console>:5: error: class Int is abstract; cannot be
instantiated
      new Int
      ^
```

The other value class, `Unit`, corresponds roughly to Java's `void` type; it is used as the result type of a method that does not otherwise return an interesting result. `Unit` has a single instance value, which is written `()`, as discussed in [Section 7.2](#).

As explained in [Chapter 5](#), the value classes support the usual arithmetic and boolean operators as methods. For instance, `Int` has methods named `+` and `*`, and `Boolean` has methods named `||` and `&&`. Value classes also inherit all methods from class `Any`. You can test this in the interpreter:

¹The only case where `==` does not directly call `equals` is for Java's boxed numeric classes, such as `Integer` or `Long`. In Java, a `new Integer(1)` does not equal a `new Long(1)` even though for primitive values `1 == 1L`. Since Scala is a more regular language than Java, it was necessary to correct this discrepancy by special-casing the `==` method for these classes. Likewise, the `##` method provides a Scala version of hashing that is the same as Java's `hashCode`, except for boxed numeric types, where it works consistently with `==`. For instance `new Integer(1)` and `new Long(1)` hash the same with `##` even though their Java `hashCodes` are different.




Figure 11.1 · Class hierarchy of Scala.

```
scala> 42.toString
res1: String = 42

scala> 42.hashCode
res2: Int = 42

scala> 42.equals 42
res3: Boolean = true
```

Note that the value class space is flat; all value classes are subtypes of `scala.AnyVal`, but they do not subclass each other. Instead there are implicit conversions between different value class types. For example, an instance of class `scala.Int` is automatically widened (by an implicit conversion) to an instance of class `scala.Long` when required.

As mentioned in [Section 5.10](#), implicit conversions are also used to add more functionality to value types. For instance, the type `Int` supports all of the operations below:

```
scala> 42 max 43
res4: Int = 43

scala> 42 min 43
res5: Int = 42

scala> 1 until 5
res6: scala.collection.immutable.Range = Range(1, 2, 3, 4)

scala> 1 to 5
res7: scala.collection.immutable.Range.Inclusive
      = Range(1, 2, 3, 4, 5)

scala> 3.abs
res8: Int = 3

scala> (-3).abs
res9: Int = 3
```

Here's how this works: The methods `min`, `max`, `until`, `to`, and `abs` are all defined in a class `scala.runtime.RichInt`, and there is an implicit conversion from class `Int` to `RichInt`. The conversion is applied whenever a method is invoked on an `Int` that is undefined in `Int` but defined in `RichInt`. Similar “booster classes” and implicit conversions exist for the other value classes. Implicit conversions will be discussed in detail in [Chapter 21](#).

The other subclass of the root class Any is class AnyRef. This is the base class of all *reference classes* in Scala. As mentioned previously, on the Java platform AnyRef is in fact just an alias for class `java.lang.Object`. So classes written in Java, as well as classes written in Scala, all inherit from AnyRef.² One way to think of `java.lang.Object`, therefore, is as the way AnyRef is implemented on the Java platform. Thus, although you can use `Object` and `AnyRef` interchangeably in Scala programs on the Java platform, the recommended style is to use `AnyRef` everywhere.

11.2 How primitives are implemented

How is all this implemented? In fact, Scala stores integers in the same way as Java—as 32-bit words. This is important for efficiency on the JVM and also for interoperability with Java libraries. Standard operations like addition or multiplication are implemented as primitive operations. However, Scala uses the “backup” class `java.lang.Integer` whenever an integer needs to be seen as a (Java) object. This happens for instance when invoking the `toString` method on an integer number or when assigning an integer to a variable of type `Any`. Integers of type `Int` are converted transparently to “boxed integers” of type `java.lang.Integer` whenever necessary.

All this sounds a lot like auto-boxing in Java 5 and it is indeed quite similar. There’s one crucial difference though: Boxing in Scala is much less visible than boxing in Java. Try the following in Java:

```
// This is Java
boolean isEqual(int x, int y) {
    return x == y;
}
System.out.println(isEqual(421, 421));
```

You will surely get `true`. Now, change the argument types of `isEqual` to `java.lang.Integer` (or `Object`, the result will be the same):

²The reason AnyRef alias exists, instead of just using the name `java.lang.Object`, is because Scala was originally designed to work on both the Java and .NET platforms. On .NET, AnyRef was an alias for `System.Object`.

```
// This is Java
boolean isEqual(Integer x, Integer y) {
    return x == y;
}
System.out.println(isEqual(421, 421));
```

You will find that you get `false!` What happens is that the number `421` gets boxed twice, so that the arguments for `x` and `y` are two different objects. Because `==` means reference equality on reference types, and `Integer` is a reference type, the result is `false`. This is one aspect where it shows that Java is not a pure object-oriented language. There is a difference between primitive types and reference types that can be clearly observed.

Now try the same experiment in Scala:

```
scala> def isEqual(x: Int, y: Int) = x == y
isEqual: (x: Int, y: Int)Boolean

scala> isEqual(421, 421)
res10: Boolean = true

scala> def isEqual(x: Any, y: Any) = x == y
isEqual: (x: Any, y: Any)Boolean

scala> isEqual(421, 421)
res11: Boolean = true
```

The equality operation `==` in Scala is designed to be transparent with respect to the type's representation. For value types, it is the natural (numeric or boolean) equality. For reference types other than Java's boxed numeric types, `==` is treated as an alias of the `equals` method inherited from `Object`. That method is originally defined as reference equality, but is overridden by many subclasses to implement their natural notion of equality. This also means that in Scala you never fall into Java's well-known trap concerning string comparisons. In Scala, string comparison works as it should:

```
scala> val x = "abcd".substring(2)
x: String = cd

scala> val y = "abcd".substring(2)
y: String = cd

scala> x == y
res12: Boolean = true
```

In Java, the result of comparing `x` with `y` would be false. The programmer should have used `equals` in this case, but it is easy to forget.

However, there are situations where you need reference equality instead of user-defined equality. For example, in some situations where efficiency is paramount, you would like to *hash cons* with some classes and compare their instances with reference equality.³ For these cases, class `AnyRef` defines an additional `eq` method, which cannot be overridden and is implemented as reference equality (*i.e.*, it behaves like `==` in Java for reference types). There's also the negation of `eq`, which is called `ne`. For example:

```
scala> val x = new String("abc")
x: String = abc
scala> val y = new String("abc")
y: String = abc
scala> x == y
res13: Boolean = true
scala> x eq y
res14: Boolean = false
scala> x ne y
res15: Boolean = true
```

Equality in Scala is discussed further in [Chapter 30](#).

11.3 Bottom types

At the bottom of the type hierarchy in [Figure 11.1](#) you see the two classes `scala.Null` and `scala.Nothing`. These are special types that handle some “corner cases” of Scala’s object-oriented type system in a uniform way.

Class `Null` is the type of the `null` reference; it is a subclass of every reference class (*i.e.*, every class that itself inherits from `AnyRef`). `Null` is not compatible with value types. You cannot, for example, assign a `null` value to an integer variable:

³You hash cons instances of a class by caching all instances you have created in a weak collection. Then, any time you want a new instance of the class, you first check the cache. If the cache already has an element equal to the one you are about to create, you can reuse the existing instance. As a result of this arrangement, any two instances that are equal with `equals()` are also equal with reference equality.

```
scala> val i: Int = null
<console>:7: error: an expression of type Null is ineligible
for implicit conversion
      val i: Int = null
                           ^
```

Type `Nothing` is at the very bottom of Scala's class hierarchy; it is a subtype of every other type. However, there exist no values of this type whatsoever. Why does it make sense to have a type without values? As discussed in [Section 7.4](#), one use of `Nothing` is that it signals abnormal termination.

For instance there's the `error` method in the `Predef` object of Scala's standard library, which is defined like this:

```
def error(message: String): Nothing =
  throw new RuntimeException(message)
```

The return type of `error` is `Nothing`, which tells users that the method will not return normally (it throws an exception instead). Because `Nothing` is a subtype of every other type, you can use methods like `error` in very flexible ways. For instance:

```
def divide(x: Int, y: Int): Int =
  if (y != 0) x / y
  else error("can't divide by zero")
```

The “then” branch of the conditional, `x / y`, has type `Int`, whereas the `else` branch, the call to `error`, has type `Nothing`. Because `Nothing` is a subtype of `Int`, the type of the whole conditional is `Int`, as required.

11.4 Defining your own value classes

As mentioned in [Section 11.1](#), you can define your own value classes to augment the ones that are built in. Like the built-in value classes, an instance of your value class will usually compile to Java bytecode that does not use the wrapper class. In contexts where a wrapper is needed, such as with generic code, the value will get boxed and unboxed automatically.

Only certain classes can be made into value classes. For a class to be a value class, it must have exactly one parameter and it must have nothing inside it except `defs`. Furthermore, no other class can extend a value class, and a value class cannot redefine `equals` or `hashCode`.

To define a value class, make it a subclass of `AnyVal`, and put `val` before the one parameter. Here is an example value class:

```
class Dollars(val amount: Int) extends AnyVal {  
    override def toString() = "$" + amount  
}
```

As described in Section 10.6, the `val` prefix allows the `amount` parameter to be accessed as a field. For example, the following code creates an instance of the value class, then retrieves the amount from it:

```
scala> val money = new Dollars(1000000)  
money: Dollars = $1000000  
scala> money.amount  
res16: Int = 1000000
```

In this example, `money` refers to an instance of the value class. It is of type `Dollars` in Scala source code, but the compiled Java bytecode will use type `Int` directly.

This example defines a `toString` method, and the compiler figures out when to use it. That's why printing `money` gives `$1000000`, with a dollar sign, but printing `money.amount` gives `1000000`. You can even define multiple value types that are all backed by the same `Int` value. For example:

```
class SwissFrancs(val amount: Int) extends AnyVal {  
    override def toString() = amount + " CHF"  
}
```

Even though both `Dollars` and `SwissFrancs` are represented as integers, it works fine to use them in the same scope:

```
scala> val dollars = new Dollars(1000)  
dollars: Dollars = $1000  
scala> val francs = new SwissFrancs(1000)  
francs: SwissFrancs = 1000 CHF
```

Avoiding a types monoculture

To get the most benefit from the Scala class hierarchy, try to define a new class for each domain concept, even when it would be possible to reuse the same class for different purposes. Even if such a class is a so-called *tiny type* with no methods or fields, defining the additional class is a way to help the compiler be helpful to you.

For example, suppose you are writing some code to generate HTML. In HTML, a style name is represented as a string. So are anchor identifiers. HTML itself is also a string, so if you wanted, you could define helper code using strings to represent all of these things, like this:

```
def title(text: String, anchor: String, style: String): String =  
  s"<a id='$anchor'><h1 class='$style'>$text</h1></a>"
```

That type signature has four strings in it! Such *stringly typed* code is technically strongly typed, but since everything in sight is of type `String`, the compiler cannot help you detect the use of one when you meant to write the other. For example, it won't stop you from this travesty:

```
scala> title("chap:vcls", "bold", "Value Classes")  
res17: String = <a id='bold'><h1 class='Value  
Classes'>chap:vcls</h1></a>
```

This HTML is mangled. The intended display text “Value Classes” is being used as a style class, and the text being displayed is “chap.vcls,” which was supposed to be an anchor. To top it off, the actual anchor identifier is “bold,” which is supposed to be a style class. Despite this comedy of errors, the compiler utters not a peep.

The compiler can be more helpful if you define a tiny type for each domain concept. For example, you could define a small class for styles, anchor identifiers, display text, and HTML. Since these classes have one parameter and no members, they can be defined as value classes:

```
class Anchor(val value: String) extends AnyVal  
class Style(val value: String) extends AnyVal  
class Text(val value: String) extends AnyVal  
class Html(val value: String) extends AnyVal
```

Given these classes, it is possible to write a version of `title` that has a less trivial type signature:

```
def title(text: Text, anchor: Anchor, style: Style): Html =  
  new Html(  
    s"<a id='${anchor.value}'>" +  
      s"<h1 class='${style.value}'>" +  
        text.value +  
      "</h1></a>"  
  )
```

If you try to use this version with the arguments in the wrong order, the compiler can now detect the error. For example:

```
scala> title(new Anchor("chap:vcls"), new Style("bold"),  
           new Text("Value Classes"))  
<console>:18: error: type mismatch;  
       found   : Anchor  
       required: Text  
              new Anchor("chap:vcls"),  
              ^  
  
<console>:19: error: type mismatch;  
       found   : Style  
       required: Anchor  
              new Style("bold"),  
              ^  
  
<console>:20: error: type mismatch;  
       found   : Text  
       required: Style  
              new Text("Value Classes"))  
              ^
```

11.5 Conclusion

In this chapter we showed you the classes at the top and bottom of Scala's class hierarchy. Now that you've gotten a good foundation on class inheritance in Scala, you're ready to understand mixin composition. In the next chapter, you'll learn about traits.

Chapter 12

Traits

Traits are a fundamental unit of code reuse in Scala. A trait encapsulates method and field definitions, which can then be reused by mixing them into classes. Unlike class inheritance, in which each class must inherit from just one superclass, a class can mix in any number of traits. This chapter shows you how traits work and shows two of the most common ways they are useful: widening thin interfaces to rich ones, and defining stackable modifications. It also shows how to use the `Ordered` trait and compares traits to the multiple inheritance of other languages.

12.1 How traits work

A trait definition looks just like a class definition except that it uses the keyword `trait`. An example is shown in Listing 12.1:

```
trait Philosophical {
    def philosophize() = {
        println("I consume memory, therefore I am!")
    }
}
```

Listing 12.1 · The definition of trait `Philosophical`.

This trait is named `Philosophical`. It does not declare a superclass, so like a class, it has the default superclass of `AnyRef`. It defines one method, named `philosophize`, which is concrete. It's a simple trait, just enough to show how traits work.

Once a trait is defined, it can be *mixed in* to a class using either the `extends` or `with` keywords. Scala programmers “mix in” traits rather than inherit from them, because mixing in a trait has important differences from the multiple inheritance found in many other languages. This issue is discussed in [Section 12.6](#). For example, [Listing 12.2](#) shows a class that mixes in the `Philosophical` trait using `extends`:

```
class Frog extends Philosophical {  
    override def toString = "green"  
}
```

[Listing 12.2](#) · Mixing in a trait using `extends`.

You can use the `extends` keyword to mix in a trait; in that case you implicitly inherit the trait’s superclass. For instance, in [Listing 12.2](#), class `Frog` subclasses `AnyRef` (the superclass of `Philosophical`) and mixes in `Philosophical`. Methods inherited from a trait can be used just like methods inherited from a superclass. Here’s an example:

```
scala> val frog = new Frog  
frog: Frog = green  
  
scala> frog.philosophize()  
I consume memory, therefore I am!
```

A trait also defines a type. Here’s an example in which `Philosophical` is used as a type:

```
scala> val phil: Philosophical = frog  
phil: Philosophical = green  
  
scala> phil.philosophize()  
I consume memory, therefore I am!
```

The type of `phil` is `Philosophical`, a trait. Thus, variable `phil` could have been initialized with any object whose class mixes in `Philosophical`.

If you wish to mix a trait into a class that explicitly extends a superclass, you use `extends` to indicate the superclass and `with` to mix in the trait. [Listing 12.3](#) shows an example. If you want to mix in multiple traits, you add more `with` clauses. For example, given a trait `HasLegs`, you could mix both `Philosophical` and `HasLegs` into `Frog` as shown in [Listing 12.4](#).

```
class Animal

class Frog extends Animal with Philosophical {
    override def toString = "green"
}
```

Listing 12.3 · Mixing in a trait using with.

```
class Animal

trait HasLegs

class Frog extends Animal with Philosophical with HasLegs {
    override def toString = "green"
}
```

Listing 12.4 · Mixing in multiple traits.

In the examples you've seen so far, class `Frog` has inherited an implementation of `philosophize` from trait `Philosophical`. Alternatively, `Frog` could override `philosophize`. The syntax looks the same as overriding a method declared in a superclass. Here's an example:

```
class Animal

class Frog extends Animal with Philosophical {
    override def toString = "green"
    override def philosophize() = {
        println("It ain't easy being " + toString + "!")
    }
}
```

Because this new definition of `Frog` still mixes in trait `Philosophical`, you can still use it from a variable of that type. But because `Frog` overrides `Philosophical`'s implementation of `philosophize`, you'll get a new behavior when you call it:

```
scala> val phrog: Philosophical = new Frog
phrog: Philosophical = green
scala> phrog.philosophize()
It ain't easy being green!
```

At this point you might philosophize that traits are like Java interfaces with concrete methods, but they can actually do much more. Traits can, for example, declare fields and maintain state. In fact, you can do anything in a trait definition that you can do in a class definition, and the syntax looks exactly the same, with only two exceptions.

First, a trait cannot have any “class” parameters (*i.e.*, parameters passed to the primary constructor of a class). In other words, although you could define a class like this:

```
class Point(x: Int, y: Int)
```

The following attempt to define a trait would not compile:

```
trait NoPoint(x: Int, y: Int) // Does not compile
```

You’ll find out in [Section 20.5](#) how to work around this restriction.

The other difference between classes and traits is that whereas in classes, super calls are statically bound, in traits, they are dynamically bound. If you write “super.toString” in a class, you know exactly which method implementation will be invoked. When you write the same thing in a trait, however, the method implementation to invoke for the super call is undefined when you define the trait. Rather, the implementation to invoke will be determined anew each time the trait is mixed into a concrete class. This curious behavior of super is key to allowing traits to work as *stackable modifications*, which will be described in [Section 12.5](#). The rules for resolving super calls will be given in [Section 12.6](#).

12.2 Thin versus rich interfaces

One major use of traits is to automatically add methods to a class in terms of methods the class already has. That is, traits can enrich a *thin* interface, making it into a *rich* interface.

Thin versus rich interfaces represents a commonly faced trade-off in object-oriented design. The trade-off is between the implementers and the clients of an interface. A rich interface has many methods, which make it convenient for the caller. Clients can pick a method that exactly matches the functionality they need. A thin interface, on the other hand, has fewer methods, and thus is easier on the implementers. Clients calling into a thin interface, however, have to write more code. Given the smaller selection of

methods to call, they may have to choose a less than perfect match for their needs and write extra code to use it.

Java's interfaces are more often thin than rich. For example, interface `CharSequence`, which was introduced in Java 1.4, is a thin interface common to all string-like classes that hold a sequence of characters. Here's its definition when seen as a Scala trait:

```
trait CharSequence {  
    def charAt(index: Int): Char  
    def length: Int  
    def subSequence(start: Int, end: Int): CharSequence  
    def toString(): String  
}
```

Although most of the dozens of methods in class `String` would apply to any `CharSequence`, Java's `CharSequence` interface declares only four methods. Had `CharSequence` instead included the full `String` interface, it would have placed a large burden on implementers of `CharSequence`. Every programmer that implemented `CharSequence` in Java would have had to define dozens more methods. Because Scala traits can contain concrete methods, they make rich interfaces far more convenient.

Adding a concrete method to a trait tilts the thin-rich trade-off heavily towards rich interfaces. Unlike in Java, adding a concrete method to a Scala trait is a one-time effort. You only need to implement the method once, in the trait itself, instead of needing to reimplement it for every class that mixes in the trait. Thus, rich interfaces are less work to provide in Scala than in a language without traits.

To enrich an interface using traits, simply define a trait with a small number of abstract methods—the thin part of the trait's interface—and a potentially large number of concrete methods, all implemented in terms of the abstract methods. Then you can mix the enrichment trait into a class, implement the thin portion of the interface, and end up with a class that has all of the rich interface available.

12.3 Example: Rectangular objects

Graphics libraries often have many different classes that represent something rectangular. Some examples are windows, bitmap images, and regions se-

lected with a mouse. To make these rectangular objects convenient to use, it is nice if the library provides geometric queries, such as `width`, `height`, `left`, `right`, `topLeft`, and so on. However, many such methods exist that would be nice to have, so it can be a large burden on library writers to provide all of them for all rectangular objects in a Java library. If such a library were written in Scala, by contrast, the library writer could use traits to easily supply all of these convenience methods on all the classes they like.

To see how, first imagine what the code would look like without traits. There would be some basic geometric classes like `Point` and `Rectangle`:

```
class Point(val x: Int, val y: Int)

class Rectangle(val topLeft: Point, val bottomRight: Point) {
    def left = topLeft.x
    def right = bottomRight.x
    def width = right - left
    // and many more geometric methods...
}
```

This `Rectangle` class takes two points in its primary constructor: the coordinates of the top-left and bottom-right corners. It then implements many convenience methods, such as `left`, `right`, and `width`, by performing simple calculations on these two points.

Another class a graphics library might have is a 2-D graphical widget:

```
abstract class Component {
    def topLeft: Point
    def bottomRight: Point
    def left = topLeft.x
    def right = bottomRight.x
    def width = right - left
    // and many more geometric methods...
}
```

Notice that the definitions of `left`, `right`, and `width` are exactly the same in the two classes. They will also be the same, aside from minor variations, in any other classes for rectangular objects.

This repetition can be eliminated with an enrichment trait. The trait will have two abstract methods: one that returns the top-left coordinate of the object, and another that returns the bottom-right coordinate. It can then supply

concrete implementations of all the other geometric queries. Listing 12.5 shows what it will look like:

```
trait Rectangular {  
    def topLeft: Point  
    def bottomRight: Point  
  
    def left = topLeft.x  
    def right = bottomRight.x  
    def width = right - left  
    // and many more geometric methods...  
}
```

Listing 12.5 · Defining an enrichment trait.

Class Component can mix in this trait to get all the geometric methods provided by Rectangular:

```
abstract class Component extends Rectangular {  
    // other methods...  
}
```

Similarly, Rectangle itself can mix in the trait:

```
class Rectangle(val topLeft: Point, val bottomRight: Point)  
    extends Rectangular {  
    // other methods...  
}
```

Given these definitions, you can create a Rectangle and call geometric methods such as width and left on it:

```
scala> val rect = new Rectangle(new Point(1, 1),  
        new Point(10, 10))  
rect: Rectangle = Rectangle@5f5da68c  
  
scala> rect.left  
res2: Int = 1  
  
scala> rect.right  
res3: Int = 10
```

```
scala> rect.width
res4: Int = 9
```

12.4 The Ordered trait

Comparison is another domain where a rich interface is convenient. Whenever you compare two objects that are ordered, it is convenient if you use a single method call to ask about the precise comparison you want. If you want “is less than,” you would like to call `<`, and if you want “is less than or equal,” you would like to call `<=`. With a thin comparison interface, you might just have the `<` method, and you would sometimes have to write things like `“(x < y) || (x == y)”`. A rich interface would provide you with all of the usual comparison operators, thus allowing you to directly write things like `“x <= y”`.

Before looking at `Ordered`, imagine what you might do without it. Suppose you took the `Rational` class from [Chapter 6](#) and added comparison operations to it. You would end up with something like this:¹

```
class Rational(n: Int, d: Int) {
    // ...
    def < (that: Rational) =
        this.numer * that.denom < that.numer * this.denom
    def > (that: Rational) = that < this
    def <= (that: Rational) = (this < that) || (this == that)
    def >= (that: Rational) = (this > that) || (this == that)
}
```

This class defines four comparison operators (`<`, `>`, `<=`, and `>=`), and it’s a classic demonstration of the costs of defining a rich interface. First, notice that three of the comparison operators are defined in terms of the first one. For example, `>` is defined as the reverse of `<`, and `<=` is defined as literally “less than or equal.” Next, notice that all three of these methods would be the same for any other class that is comparable. There is nothing special about rational numbers regarding `<=`. In a comparison context, `<=` is *always* used to mean “less than or equals.” Overall, there is quite a lot of boilerplate code

¹This example is based on the `Rational` class shown in [Listing 6.5](#) on [page 151](#), with `equals`, `hashCode`, and modifications to ensure a positive `denom` added.

in this class which would be the same in any other class that implements comparison operations.

This problem is so common that Scala provides a trait to help with it. The trait is called `Ordered`. To use it, you replace all of the individual comparison methods with a single `compare` method. The `Ordered` trait then defines `<`, `>`, `<=`, and `>=` for you in terms of this one method. Thus, trait `Ordered` allows you to enrich a class with comparison methods by implementing only one method, `compare`.

Here is how it looks if you define comparison operations on `Rational` by using the `Ordered` trait:

```
class Rational(n: Int, d: Int) extends Ordered[Rational] {  
    // ...  
    def compare(that: Rational) =  
        (this.numer * that.denom) - (that.numer * this.denom)  
}
```

There are just two things to do. First, this version of `Rational` mixes in the `Ordered` trait. Unlike the traits you have seen so far, `Ordered` requires you to specify a *type parameter* when you mix it in. Type parameters are not discussed in detail until [Chapter 19](#), but for now all you need to know is that when you mix in `Ordered`, you must actually mix in `Ordered[C]`, where `C` is the class whose elements you compare. In this case, `Rational` mixes in `Ordered[Rational]`.

The second thing you need to do is define a `compare` method for comparing two objects. This method should compare the receiver, `this`, with the object passed as an argument to the method. It should return an integer that is zero if the objects are the same, negative if receiver is less than the argument, and positive if the receiver is greater than the argument.

In this case, the comparison method of `Rational` uses a formula based on converting the fractions to a common denominator and then subtracting the resulting numerators. Given this mixin and the definition of `compare`, class `Rational` now has all four comparison methods:

```
scala> val half = new Rational(1, 2)  
half: Rational = 1/2  
  
scala> val third = new Rational(1, 3)  
third: Rational = 1/3
```

```
scala> half < third
res5: Boolean = false

scala> half > third
res6: Boolean = true
```

Any time you implement a class that is ordered by some comparison, you should consider mixing in the `Ordered` trait. If you do, you will provide the class's users with a rich set of comparison methods.

Beware that the `Ordered` trait does not define `equals` for you, because it is unable to do so. The problem is that implementing `equals` in terms of `compare` requires checking the type of the passed object, and because of type erasure, `Ordered` itself cannot do this test. Thus, you need to define `equals` yourself, even if you inherit `Ordered`. You'll find out how to go about this in [Chapter 30](#).

12.5 Traits as stackable modifications

You have now seen one major use of traits: turning a thin interface into a rich one. Now we'll turn to a second major use: providing stackable modifications to classes. Traits let you *modify* the methods of a class, and they do so in a way that allows you to *stack* those modifications with each other.

As an example, consider stacking modifications to a queue of integers. The queue will have two operations: `put`, which places integers in the queue, and `get`, which takes them back out. Queues are first-in, first-out, so `get` should return the integers in the same order they were put in the queue.

Given a class that implements such a queue, you could define traits to perform modifications such as these:

- **Doubling:** double all integers that are put in the queue
- **Incrementing:** increment all integers that are put in the queue
- **Filtering:** filter out negative integers from a queue

These three traits represent *modifications*, because they modify the behavior of an underlying queue class rather than defining a full queue class themselves. The three are also *stackable*. You can select any of the three you like, mix them into a class, and obtain a new class that has all of the modifications you chose.

An abstract `IntQueue` class is shown in Listing 12.6. `IntQueue` has a `put` method that adds new integers to the queue, and a `get` method that removes and returns them. A basic implementation of `IntQueue` that uses an `ArrayBuffer` is shown in Listing 12.7.

```
abstract class IntQueue {  
    def get(): Int  
    def put(x: Int)  
}
```

Listing 12.6 · Abstract class `IntQueue`.

```
import scala.collection.mutable.ArrayBuffer  
  
class BasicIntQueue extends IntQueue {  
    private val buf = new ArrayBuffer[Int]  
    def get() = buf.remove(0)  
    def put(x: Int) = { buf += x }  
}
```

Listing 12.7 · A `BasicIntQueue` implemented with an `ArrayBuffer`.

Class `BasicIntQueue` has a private field holding an array buffer. The `get` method removes an entry from one end of the buffer, while the `put` method adds elements to the other end. Here's how this implementation looks when you use it:

```
scala> val queue = new BasicIntQueue  
queue: BasicIntQueue = BasicIntQueue@23164256  
  
scala> queue.put(10)  
scala> queue.put(20)  
  
scala> queue.get()  
res9: Int = 10  
  
scala> queue.get()  
res10: Int = 20
```

So far so good. Now take a look at using traits to modify this behavior. Listing 12.8 shows a trait that doubles integers as they are put in the queue.

The Doubling trait has two funny things going on. The first is that it declares a superclass, IntQueue. This declaration means that the trait can only be mixed into a class that also extends IntQueue. Thus, you can mix Doubling into BasicIntQueue, but not into Rational.

```
trait Doubling extends IntQueue {  
    abstract override def put(x: Int) = { super.put(2 * x) }  
}
```

Listing 12.8 · The Doubling stackable modification trait.

The second funny thing is that the trait has a `super` call on a method declared abstract. Such calls are illegal for normal classes because they will certainly fail at run time. For a trait, however, such a call can actually succeed. Since `super` calls in a trait are dynamically bound, the `super` call in trait Doubling will work so long as the trait is mixed in *after* another trait or class that gives a concrete definition to the method.

This arrangement is frequently needed with traits that implement stackable modifications. To tell the compiler you are doing this on purpose, you must mark such methods as `abstract override`. This combination of modifiers is only allowed for members of traits, not classes, and it means that the trait must be mixed into some class that has a concrete definition of the method in question.

There is a lot going on with such a simple trait, isn't there! Here's how it looks to use the trait:

```
scala> class MyQueue extends BasicIntQueue with Doubling  
defined class MyQueue  
  
scala> val queue = new MyQueue  
queue: MyQueue = MyQueue@44bbf788  
  
scala> queue.put(10)  
  
scala> queue.get()  
res12: Int = 20
```

In the first line in this interpreter session, we define class `MyQueue`, which extends `BasicIntQueue` and mixes in `Doubling`. We then put a 10 in the queue, but because `Doubling` has been mixed in, the 10 is doubled. When we get an integer from the queue, it is a 20.

Note that `MyQueue` defines no new code. It simply identifies a class and mixes in a trait. In this situation, you could supply “`BasicIntQueue` with `Doubling`” directly to `new` instead of defining a named class. It would look as shown in Listing 12.9:

```
scala> val queue = new BasicIntQueue with Doubling
queue: BasicIntQueue with Doubling = $anon$1@141f05bf
scala> queue.put(10)
scala> queue.get()
res14: Int = 20
```

Listing 12.9 · Mixing in a trait when instantiating with `new`.

To see how to stack modifications, we need to define the other two modification traits, `Incrementing` and `Filtering`. Implementations of these traits are shown in Listing 12.10:

```
trait Incrementing extends IntQueue {
    abstract override def put(x: Int) = { super.put(x + 1) }
}
trait Filtering extends IntQueue {
    abstract override def put(x: Int) = {
        if (x >= 0) super.put(x)
    }
}
```

Listing 12.10: Stackable modification traits `Incrementing` and `Filtering`.

Given these modifications, you can now pick and choose which ones you want for a particular queue. For example, here is a queue that both filters negative numbers and adds one to all numbers that it keeps:

```
scala> val queue = (new BasicIntQueue
                     with Incrementing with Filtering)
queue: BasicIntQueue with Incrementing with Filtering...
scala> queue.put(-1); queue.put(0); queue.put(1)
scala> queue.get()
res16: Int = 1
```

```
scala> queue.get()
res17: Int = 2
```

The order of mixins is significant.² The precise rules are given in the following section, but, roughly speaking, traits further to the right take effect first. When you call a method on a class with mixins, the method in the trait furthest to the right is called first. If that method calls `super`, it invokes the method in the next trait to its left, and so on. In the previous example, `Filtering`'s `put` is invoked first, so it removes integers that were negative to begin with. `Incrementing`'s `put` is invoked second, so it adds one to those integers that remain.

If you reverse the order, first integers will be incremented, and *then* the integers that are still negative will be discarded:

```
scala> val queue = (new BasicIntQueue
                     with Filtering with Incrementing)
queue: BasicIntQueue with Filtering with Incrementing...
scala> queue.put(-1); queue.put(0); queue.put(1)
scala> queue.get()
res19: Int = 0
scala> queue.get()
res20: Int = 1
scala> queue.get()
res21: Int = 2
```

Overall, code written in this style gives you a great deal of flexibility. You can define sixteen different classes by mixing in these three traits in different combinations and orders. That's a lot of flexibility for a small amount of code, so you should keep your eyes open for opportunities to arrange code as stackable modifications.

12.6 Why not multiple inheritance?

Traits are a way to inherit from multiple class-like constructs, but they differ in important ways from the multiple inheritance present in many languages.

²Once a trait is mixed into a class, you can alternatively call it a *mixin*.

One difference is especially important: the interpretation of `super`. With multiple inheritance, the method called by a `super` call can be determined right where the call appears. With traits, the method called is determined by a *linearization* of the classes and traits that are mixed into a class. This is the difference that enables the stacking of modifications described in the previous section.

Before looking at linearization, take a moment to consider how to stack modifications in a language with traditional multiple inheritance. Imagine the following code, but this time interpreted as multiple inheritance instead of trait mixin:

```
// Multiple inheritance thought experiment
val q = new BasicIntQueue with Incrementing with Doubling
q.put(42) // which put would be called?
```

The first question is: Which `put` method would get invoked by this call? Perhaps the rule would be that the last superclass wins, in which case `Doubling` would get called. `Doubling` would double its argument and call `super.put`, and that would be it. No `incrementing` would happen! Likewise, if the rule were that the first superclass wins, the resulting queue would increment integers but not double them. Thus neither ordering would work.

You might also entertain the possibility of allowing programmers to identify exactly which superclass method they want when they say `super`. For example, imagine the following Scala-like code, in which `super` appears to be explicitly invoked on both `Incrementing` and `Doubling`:

```
// Multiple inheritance thought experiment
trait MyQueue extends BasicIntQueue
  with Incrementing with Doubling {
  def put(x: Int) = {
    Incrementing.super.put(x) // (Not real Scala)
    Doubling.super.put(x)
  }
}
```

This approach would give us new problems (with the verbosity of this attempt being the least of its problems). What would happen is that the base class's `put` method would get called *twice*—once with an incremented

value and once with a doubled value, but neither time with an incremented, doubled value.

There is simply no good solution to this problem using multiple inheritance. You would have to back up in your design and factor the code differently. By contrast, the traits solution in Scala is straightforward. You simply mix in Incrementing and Doubling, and Scala's special treatment of super in traits makes it all work out. Something is clearly different here from traditional multiple inheritance, but what?

As hinted previously, the answer is linearization. When you instantiate a class with new, Scala takes the class, and all of its inherited classes and traits, and puts them in a single, *linear* order. Then, whenever you call super inside one of those classes, the invoked method is the next one up the chain. If all of the methods but the last call super, the net result is stackable behavior.

The precise order of the linearization is described in the language specification. It is a little bit complicated, but the main thing you need to know is that, in any linearization, a class is always linearized in front of *all* its superclasses and mixed in traits. Thus, when you write a method that calls super, that method is definitely modifying the behavior of the superclasses and mixed in traits, not the other way around.

Note

The remainder of this section describes the details of linearization. You can safely skip the rest of this section if you are not interested in understanding those details right now.

The main properties of Scala's linearization are illustrated by the following example: Say you have a class Cat, which inherits from a superclass Animal and two supertraits Furry and FourLegged. FourLegged extends in turn another trait HasLegs:

```
class Animal
trait Furry extends Animal
trait HasLegs extends Animal
trait FourLegged extends HasLegs
class Cat extends Animal with Furry with FourLegged
```

Class Cat's inheritance hierarchy and linearization are shown in Figure 12.1. Inheritance is indicated using traditional UML notation:³ arrows

³Rumbaugh, et al., *The Unified Modeling Language Reference Manual*. [Rum04]




Figure 12.1 · Inheritance hierarchy and linearization of class `Cat`.

with white, triangular arrowheads indicate inheritance, with the arrowhead pointing to the supertype. The arrows with darkened, non-triangular arrowheads depict linearization. The darkened arrowheads point in the direction in which super calls will be resolved.

The linearization of `Cat` is computed from back to front as follows. The *last* part of the linearization of `Cat` is the linearization of its superclass, `Animal`. This linearization is copied over without any changes. (The linearization of each of these types is shown in [Table 12.1 on page 274](#).) Because `Animal` doesn't explicitly extend a superclass or mix in any supertraits, it by default extends `AnyRef`, which extends `Any`. `Animal`'s linearization, therefore, looks like:

`Animal → AnyRef → Any`

The second to last part is the linearization of the first mixin, trait `Furry`, but all classes that are already in the linearization of `Animal` are left out now, so that each class appears only once in `Cat`'s linearization. The result is:

`Furry → Animal → AnyRef → Any`

This is preceded by the linearization of `FourLegged`, where again any classes that have already been copied in the linearizations of the superclass or the first mixin are left out:

`FourLegged → HasLegs → Furry → Animal → AnyRef → Any`

Table 12.1 · Linearization of types in Cat's hierarchy

Type	Linearization
Animal	Animal, AnyRef, Any
Furry	Furry, Animal, AnyRef, Any
FourLegged	FourLegged, HasLegs, Animal, AnyRef, Any
HasLegs	HasLegs, Animal, AnyRef, Any
Cat	Cat, FourLegged, HasLegs, Furry, Animal, AnyRef, Any

Finally, the first class in the linearization of Cat is Cat itself:

Cat → FourLegged → HasLegs → Furry → Animal → AnyRef → Any

When any of these classes and traits invokes a method via `super`, the implementation invoked will be the first implementation to its right in the linearization.

12.7 To trait or not to trait?

Whenever you implement a reusable collection of behavior, you will have to decide whether you want to use a trait or an abstract class. There is no firm rule, but this section contains a few guidelines to consider.

If the behavior will not be reused, then make it a concrete class. It is not reusable behavior after all.

If it might be reused in multiple, unrelated classes, make it a trait. Only traits can be mixed into different parts of the class hierarchy.

If you want to inherit from it in Java code, use an abstract class. Since traits with code do not have a close Java analog, it tends to be awkward to inherit from a trait in a Java class. Inheriting from a Scala class, meanwhile, is exactly like inheriting from a Java class. As one exception, a Scala trait with only abstract members translates directly to a Java interface, so you should feel free to define such traits even if you expect Java code to inherit from it. See [Chapter 31](#) for more information on working with Java and Scala together.

If you plan to distribute it in compiled form, and you expect outside groups to write classes inheriting from it, you might lean towards using an abstract class. The issue is that when a trait gains or loses a member, any classes that inherit from it must be recompiled, even if they have not changed.

If outside clients will only call into the behavior, instead of inheriting from it, then using a trait is fine.

If you still do not know, after considering the above, then start by making it as a trait. You can always change it later, and in general using a trait keeps more options open.

12.8 Conclusion

This chapter has shown you how traits work and how to use them in several common idioms. You saw that traits are similar to multiple inheritance. But because traits interpret super using linearization, they both avoid some of the difficulties of traditional multiple inheritance and allow you to stack behaviors. You also saw the Ordered trait and learned how to write your own enrichment traits.

Now that you have seen all of these facets, it is worth stepping back and taking another look at traits as a whole. Traits do not merely support the idioms described in this chapter; they are a fundamental unit of code that is reusable through inheritance. As such, many experienced Scala programmers start with traits when they are at the early stages of implementation. Each trait can hold less than an entire concept, a mere fragment of a concept. As the design solidifies, the fragments can be combined into more complete concepts through trait mixin.

Chapter 13

Packages and Imports

When working on a program, especially a large one, it is important to minimize *coupling*—the extent to which the various parts of the program rely on the other parts. Low coupling reduces the risk that a small, seemingly innocuous change in one part of the program will have devastating consequences in another part. One way to minimize coupling is to write in a modular style. You divide the program into a number of smaller modules, each of which has an inside and an outside. When working on the inside of a module—its *implementation*—you need only coordinate with other programmers working on that very same module. Only when you must change the outside of a module—its *interface*—is it necessary to coordinate with developers working on other modules.

This chapter shows several constructs that help you program in a modular style. It shows how to place things in packages, make names visible through imports, and control the visibility of definitions through access modifiers. The constructs are similar in spirit to constructs in Java, but there are some differences—usually ways that are more consistent—so it's worth reading this chapter even if you already know Java.

13.1 Putting code in packages

Scala code resides in the Java platform's global hierarchy of packages. The example code you've seen so far in this book has been in the *unnamed* package. You can place code into named packages in Scala in two ways. First, you can place the contents of an entire file into a package by putting a package clause at the top of the file, as shown in [Listing 13.1](#).

```
package bobsrockets.navigation
class Navigator
```

Listing 13.1 · Placing the contents of an entire file into a package.

The package clause of Listing 13.1 places class `Navigator` into the package named `bobsrockets.navigation`. Presumably, this is the navigation software developed by Bob’s Rockets, Inc.

Note

Because Scala code is part of the Java ecosystem, it is recommended to follow Java’s reverse-domain-name convention for Scala packages that you release to the public. Thus, a better name for `Navigator`’s package might be `com.bobsrockets.navigation`. In this chapter, however, we’ll leave off the “`com.`” to make the examples easier to understand.

The other way you can place code into packages in Scala is more like C# namespaces. You follow a package clause by a section in curly braces that contains the definitions that go into the package. This syntax is called a *packaging*. The packaging shown in Listing 13.2 has the same effect as the code in Listing 13.1:

```
package bobsrockets.navigation {
    class Navigator
}
```

Listing 13.2 · Long form of a simple package declaration.

For such simple examples, you might as well use the syntactic sugar shown in Listing 13.1. However, one use of the more general notation is to have different parts of a file in different packages. For example, you might include a class’s tests in the same file as the original code, but put the tests in a different package, as shown in Listing 13.3.

13.2 Concise access to related code

When code is divided into a package hierarchy, it doesn’t just help people browse through the code. It also tells the compiler that code in the same

```
package bobsrockets {
    package navigation {
        // In package bobsrockets.navigation
        class Navigator
    }
    package tests {
        // In package bobsrockets.navigation.tests
        class NavigatorSuite
    }
}
```

Listing 13.3 · Multiple packages in the same file.

```
package bobsrockets {
    package navigation {
        class Navigator {
            // No need to say bobsrockets.navigation.StarMap
            val map = new StarMap
        }
        class StarMap
    }
    class Ship {
        // No need to say bobsrockets.navigation.Navigator
        val nav = new navigation.Navigator
    }
    package fleets {
        class Fleet {
            // No need to say bobsrockets.Ship
            def addShip() = { new Ship }
        }
    }
}
```

Listing 13.4 · Concise access to classes and packages.

```
package bobsrockets {
    class Ship
}

package bobsrockets.fleets {
    class Fleet {
        // Doesn't compile! Ship is not in scope.
        def addShip() = { new Ship }
    }
}
```

Listing 13.5 · Symbols in enclosing packages not automatically available.

```
// In file launch.scala
package launch {
    class Booster3
}

// In file bobsrockets.scala
package bobsrockets {
    package navigation {
        package launch {
            class Booster1
        }
        class MissionControl {
            val booster1 = new launch.Booster1
            val booster2 = new bobsrockets.launch.Booster2
            val booster3 = new _root_.launch.Booster3
        }
    }
    package launch {
        class Booster2
    }
}
```

Listing 13.6 · Accessing hidden package names.

package is related in some way to each other. Scala takes advantage of this relatedness by allowing short, unqualified names when accessing code that is in the same package.

[Listing 13.4](#) gives three simple examples. First, as you would expect, a class can be accessed from within its own package without needing a prefix. That's why new StarMap compiles. Class StarMap is in the same package, bobsrockets.navigation, as the new expression that accesses it, so the package name doesn't need to be prefixed.

Second, a package itself can be accessed from its containing package without needing a prefix. In [Listing 13.4](#), look at how class Navigator is instantiated. The new expression appears in package bobsrockets, which is the containing package of bobsrockets.navigation. Thus, it can access package bobsrockets.navigation as simply navigation.

Third, when using the curly-braces packaging syntax, all names accessible in scopes outside the packaging are also available inside it. An example in [Listing 13.4](#) is the way addShip() creates a new Ship. The method is defined within two packagings: an outer one for bobsrockets, and an inner one for bobsrockets.fleets. Since Ship is accessible in the outer packaging, it can be referenced from within addShip().

Note that this kind of access is only available if you explicitly nest the packagings. If you stick to one package per file, then—like in Java—the only names available will be the ones defined in the current package. In [Listing 13.5](#), the packaging of bobsrockets.fleets has been moved to the top level. Since it is no longer enclosed in a packaging for bobsrockets, names from bobsrockets are not immediately in scope. As a result, new Ship gives a compile error. If nesting packages with braces shifts your code uncomfortably to the right, you can also use multiple package clauses without the braces.¹ For instance, the code below also defines class Fleet in two nested packages bobrockets and fleets, just like you saw it in [Listing 13.4](#):

```
package bobsrockets
package fleets
class Fleet {
    // No need to say bobsrockets.Ship
    def addShip() = { new Ship }
}
```

¹This style of multiple package clauses without braces is called *chained package clauses*.

One final trick is important to know. Sometimes, you end up coding in a heavily crowded scope where package names are hiding each other. In Listing 13.6, the scope of class `MissionControl` includes three separate packages named `launch!` There's one `launch` in `bobsrockets.navigation`, one in `bobsrockets`, and one at the top level. How would you reference each of `Booster1`, `Booster2`, and `Booster3`?

Accessing the first one is easiest. A reference to `launch` by itself will get you to package `bobsrockets.navigation.launch`, because that is the `launch` package defined in the closest enclosing scope. Thus, you can refer to the first booster class as simply `launch.Booster1`. Referring to the second one also is not tricky. You can write `bobrockets.launch.Booster2` and be clear about which one you are referencing. That leaves the question of the third booster class: How can you access `Booster3`, considering that a nested `launch` package shadows the top-level one?

To help in this situation, Scala provides a package named `_root_` that is outside any package a user can write. Put another way, every top-level package you can write is treated as a member of package `_root_`. For example, both `launch` and `bobsrockets` of Listing 13.6 are members of package `_root_`. As a result, `_root_.launch` gives you the top-level `launch` package, and `_root_.launch.Booster3` designates the outermost booster class.

13.3 Imports

In Scala, packages and their members can be imported using `import` clauses. Imported items can then be accessed by a simple name like `File`, as opposed to requiring a qualified name like `java.io.File`. For example, consider the code shown in Listing 13.7.

An `import` clause makes members of a package or object available by their names alone without needing to prefix them by the package or object name. Here are some simple examples:

```
// easy access to Fruit
import bobsdelights.Fruit

// easy access to all members of bobsdelights
import bobsdelights._

// easy access to all members of Fruits
import bobsdelights.Fruits._
```

```
package bobsdelights
abstract class Fruit(
    val name: String,
    val color: String
)
object Fruits {
    object Apple extends Fruit("apple", "red")
    object Orange extends Fruit("orange", "orange")
    object Pear extends Fruit("pear", "yellowish")
    val menu = List(Apple, Orange, Pear)
}
```

Listing 13.7 · Bob’s delightful fruits, ready for import.

The first of these corresponds to Java’s single type import and the second to Java’s *on-demand* import. The only difference is that Scala’s on-demand imports are written with a trailing underscore (_) instead of an asterisk (*). (After all, * is a valid identifier in Scala!) The third import clause above corresponds to Java’s import of static class fields.

These three imports give you a taste of what imports can do, but Scala imports are actually much more general. For one, imports in Scala can appear anywhere, not just at the beginning of a compilation unit. Also, they can refer to arbitrary values. For instance, the import shown in Listing 13.8 is possible:

```
def showFruit(fruit: Fruit) = {
    import fruit._
    println(name + "s are " + color)
}
```

Listing 13.8 · Importing the members of a regular (not singleton) object.

Method `showFruit` imports all members of its parameter `fruit`, which is of type `Fruit`. The subsequent `println` statement can refer to `name` and `color` directly. These two references are equivalent to `fruit.name` and `fruit.color`. This syntax is particularly useful when you use objects as modules, which will be described in Chapter 29.

Scala's flexible imports

Scala's `import` clauses are quite a bit more flexible than Java's. There are three principal differences. In Scala, imports:

- may appear anywhere
- may refer to objects (singleton or regular) in addition to packages
- let you rename and hide some of the imported members

Another way Scala's imports are flexible is that they can import packages themselves, not just their non-package members. This is only natural if you think of nested packages being contained in their surrounding package. For example, in [Listing 13.9](#), the package `java.util.regex` is imported. This makes `regex` usable as a simple name. To access the `Pattern` singleton object from the `java.util.regex` package, you can just say, `regex.Pattern`, as shown in [Listing 13.9](#):

```
import java.util.regex
class AStarB {
    // Accesses java.util.regex.Pattern
    val pat = regex.Pattern.compile("a*b")
}
```

[Listing 13.9 · Importing a package name.](#)

Imports in Scala can also rename or hide members. This is done with an *import selector clause* enclosed in braces, which follows the object from which members are imported. Here are some examples:

```
import Fruits.{Apple, Orange}
```

This imports just members `Apple` and `Orange` from object `Fruits`.

```
import Fruits.{Apple => McIntosh, Orange}
```

This imports the two members `Apple` and `Orange` from object `Fruits`. However, the `Apple` object is renamed to `McIntosh`, so this object can be

accessed with either `Fruits.Apple` or `McIntosh`. A renaming clause is always of the form “`<original-name> => <new-name>`”.

```
import java.sql.{Date => SDate}
```

This imports the SQL date class as `SDate`, so that you can simultaneously import the normal Java date class as simply `Date`.

```
import java.{sql => S}
```

This imports the `java.sql` package as `S`, so that you can write things like `S.Date`.

```
import Fruits._
```

This imports all members from object `Fruits`. It means the same thing as `import Fruits._`.

```
import Fruits.{Apple => McIntosh, _}
```

This imports all members from object `Fruits` but renames `Apple` to `McIntosh`.

```
import Fruits.{Pear => _, _}
```

This imports all members of `Fruits` *except* `Pear`. A clause of the form “`<original-name> => _`” excludes `<original-name>` from the names that are imported. In a sense, renaming something to ‘`_`’ means hiding it altogether. This is useful to avoid ambiguities. Say you have two packages, `Fruits` and `Notebooks`, which both define a class `Apple`. If you want to get just the notebook named `Apple`, and not the fruit, you could still use two imports on demand like this:

```
import Notebooks._  
import Fruits.{Apple => _, _}
```

This would import all `Notebooks` and all `Fruits`, except for `Apple`.

These examples demonstrate the great flexibility Scala offers when it comes to importing members selectively and possibly under different names. In summary, an import selector can consist of the following:

- A simple name `x`. This includes `x` in the set of imported names.

- A renaming clause `x => y`. This makes the member named `x` visible under the name `y`.
- A hiding clause `x => _`. This excludes `x` from the set of imported names.
- A *catch-all* ‘`_`’. This imports all members except those members mentioned in a preceding clause. If a catch-all is given, it must come last in the list of import selectors.

The simpler import clauses shown at the beginning of this section can be seen as special abbreviations of import clauses with a selector clause. For example, “`import p._`” is equivalent to “`import p.{_}`” and “`import p.n`” is equivalent to “`import p.{n}`”.

13.4 Implicit imports

Scala adds some imports implicitly to every program. In essence, it is as if the following three import clauses had been added to the top of every source file with extension “`.scala`”:

```
import java.lang._ // everything in the java.lang package
import scala._      // everything in the scala package
import Predef._     // everything in the Predef object
```

The `java.lang` package contains standard Java classes. It is always implicitly imported in Scala source files.² Because `java.lang` is imported implicitly, you can write `Thread` instead of `java.lang.Thread`, for instance.

As you have no doubt realized by now, the `scala` package contains the standard Scala library, with many common classes and objects. Because `scala` is imported implicitly, you can write `List` instead of `scala.List`, for instance.

The `Predef` object contains many definitions of types, methods, and implicit conversions that are commonly used on Scala programs. For example, because `Predef` is imported implicitly, you can write `assert` instead of `Predef.assert`.

²Scala also originally had an implementation on .NET., where namespace `System`, the .NET analogue of package `java.lang`, was imported instead.

These three import clauses are treated a bit specially in that later imports overshadow earlier ones. For instance, the `StringBuilder` class is defined both in package `scala` and, from Java version 1.5 on, also in package `java.lang`. Because the `scala` import overshadows the `java.lang` import, the simple name `StringBuilder` will refer to `scala.StringBuilder`, not `java.lang.StringBuilder`.

13.5 Access modifiers

Members of packages, classes, or objects can be labeled with the access modifiers `private` and `protected`. These modifiers restrict access to the members to certain regions of code. Scala's treatment of access modifiers roughly follows Java's but there are some important differences which are explained in this section.

Private members

Private members in Scala are treated similarly to Java. A member labeled `private` is visible only inside the class or object that contains the member definition. In Scala, this rule applies also for inner classes. This treatment is more consistent, but differs from Java. Consider the example shown in Listing 13.10.

```
class Outer {
    class Inner {
        private def f() = { println("f") }
        class InnerMost {
            f() // OK
        }
    }
    (new Inner).f() // error: f is not accessible
}
```

Listing 13.10 · How private access differs in Scala and Java.

In Scala, the access `(new Inner).f()` is illegal because `f` is declared `private` in `Inner` and the access is not from within class `Inner`. By contrast, the first access to `f` in class `InnerMost` is OK, because that access

is contained in the body of class Inner. Java would permit both accesses because it lets an outer class access private members of its inner classes.

Protected members

Access to protected members in Scala is also a bit more restrictive than in Java. In Scala, a protected member is only accessible from subclasses of the class in which the member is defined. In Java such accesses are also possible from other classes in the same package. In Scala, there is another way to achieve this effect³ so protected is free to be left as is. The example shown in Listing 13.11 illustrates protected accesses.

```
package p {
    class Super {
        protected def f() = { println("f") }
    }
    class Sub extends Super {
        f()
    }
    class Other {
        (new Super).f() // error: f is not accessible
    }
}
```

Listing 13.11 · How protected access differs in Scala and Java.

In Listing 13.11, the access to f in class Sub is OK because f is declared protected in Super and Sub is a subclass of Super. By contrast the access to f in Other is not permitted, because Other does not inherit from Super. In Java, the latter access would be still permitted because Other is in the same package as Sub.

Public members

Scala has no explicit modifier for public members: Any member not labeled private or protected is public. Public members can be accessed from anywhere.

³Using *qualifiers*, described in “Scope of protection” on page 288.

```
package bobsrockets
package navigation {
    private[bobsrockets] class Navigator {
        protected[navigation] def useStarChart() = {}
        class LegOfJourney {
            private[Navigator] val distance = 100
        }
        private[this] var speed = 200
    }
}
package launch {
    import navigation.-
    object Vehicle {
        private[launch] val guide = new Navigator
    }
}
```

Listing 13.12 · Flexible scope of protection with access qualifiers.

Scope of protection

Access modifiers in Scala can be augmented with qualifiers. A modifier of the form `private[X]` or `protected[X]` means that access is private or protected “up to” X, where X designates some enclosing package, class or singleton object.

Qualified access modifiers give you very fine-grained control over visibility. In particular they enable you to express Java’s accessibility notions, such as package private, package protected, or private up to outermost class, which are not directly expressible with simple modifiers in Scala. But they also let you express accessibility rules that cannot be expressed in Java.

[Listing 13.12](#) presents an example with many access qualifiers being used. In this listing, class `Navigator` is labeled `private[bobsrockets]`. This means that this class is visible in all classes and objects that are contained in package `bobsrockets`. In particular, the access to `Navigator` in object `Vehicle` is permitted because `Vehicle` is contained in package `launch`, which is contained in `bobsrockets`. On the other hand, all code outside the package `bobsrockets` cannot access class `Navigator`.

This technique is quite useful in large projects that span several packages. It allows you to define things that are visible in several sub-packages of your project but that remain hidden from clients external to your project. The same technique is not possible in Java. There, once a definition escapes its immediate package boundary, it is visible to the world at large.

Of course, the qualifier of a `private` may also be the directly enclosing package. An example is the access modifier of `guide` in object `Vehicle` in Listing 13.12. Such an access modifier is equivalent to Java's package-private access.

Table 13.1 · Effects of private qualifiers on `LegOfJourney.distance`

<i>no access modifier</i>	public access
<code>private[bobsrockets]</code>	access within outer package
<code>private[navigation]</code>	same as package visibility in Java
<code>private[Navigator]</code>	same as <code>private</code> in Java
<code>private[LegOfJourney]</code>	same as <code>private</code> in Scala
<code>private[this]</code>	access only from same object

All qualifiers can also be applied to `protected`, with the same meaning as `private`. That is, a modifier `protected[X]` in a class C allows access to the labeled definition in all subclasses of C and also within the enclosing package, class, or object X. For instance, the `useStarChart` method in Listing 13.12 is accessible in all subclasses of `Navigator` and also in all code contained in the enclosing package `navigation`. It thus corresponds exactly to the meaning of `protected` in Java.

The qualifiers of `private` can also refer to an enclosing class or object. For instance the `distance` variable in class `LegOfJourney` in Listing 13.12 is labeled `private[Navigator]`, so it is visible from everywhere in class `Navigator`. This gives the same access capabilities as for private members of inner classes in Java. A `private[C]` where C is the outermost enclosing class is the same as just `private` in Java.

Finally, Scala also has an access modifier that is even more restrictive than `private`. A definition labeled `private[this]` is accessible only from within the same object that contains the definition. Such a definition is called *object-private*. For instance, the definition of `speed` in class `Navigator` in Listing 13.12 is object-private. This means that any access must not only be within class `Navigator`, it must also be made from the very same instance of

Navigator. Thus the accesses “speed” and “this.speed” would be legal from within Navigator.

The following access, though, would not be allowed, even if it appeared inside class Navigator:

```
val other = new Navigator  
other.speed // this line would not compile
```

Marking a member `private[this]` is a guarantee that it will not be seen from other objects of the same class. This can be useful for documentation. It also sometimes lets you write more general variance annotations (see [Section 19.7](#) for details).

To summarize, [Table 13.1](#) on [page 289](#) lists the effects of private qualifiers. Each line shows a qualified private modifier and what it would mean if such a modifier were attached to the `distance` variable declared in class `LegOfJourney` in [Listing 13.12](#).

Visibility and companion objects

In Java, static members and instance members belong to the same class, so access modifiers apply uniformly to them. You have already seen that in Scala there are no static members; instead you can have a companion object that contains members that exist only once. For instance, in [Listing 13.13](#) object `Rocket` is a companion of class `Rocket`.

Scala’s access rules privilege companion objects and classes when it comes to private or protected accesses. A class shares all its access rights with its companion object and *vice versa*. In particular, an object can access all private members of its companion class, just as a class can access all private members of its companion object.

For instance, the `Rocket` class in [Listing 13.13](#) can access method `fuel`, which is declared `private` in object `Rocket`. Analogously, the `Rocket` object can access the private method `canGoHomeAgain` in class `Rocket`.

One exception where the similarity between Scala and Java breaks down concerns `protected static` members. A `protected static` member of a Java class `C` can be accessed in all subclasses of `C`. By contrast, a `protected` member in a companion object makes no sense, as singleton objects don’t have any subclasses.

```
class Rocket {  
    import Rocket.fuel  
    private def canGoHomeAgain = fuel > 20  
}  
  
object Rocket {  
    private def fuel = 10  
    def chooseStrategy(rocket: Rocket) = {  
        if (rocket.canGoHomeAgain)  
            goHome()  
        else  
            pickAStar()  
    }  
    def goHome() = {}  
    def pickAStar() = {}  
}
```

Listing 13.13: Accessing private members of companion classes and objects.

13.6 Package objects

So far, the only code you have seen added to packages are classes, traits, and standalone objects. These are by far the most common definitions that are placed at the top level of a package. But Scala doesn't limit you to just those—Any kind of definition that you can put inside a class can also be at the top level of a package. If you have some helper method you'd like to be in scope for an entire package, go ahead and put it right at the top level of the package.

To do so, put the definitions in a *package object*. Each package is allowed to have one package object. Any definitions placed in a package object are considered members of the package itself.

An example is shown in Listing 13.14. File `package.scala` holds a package object for package `bobsdelights`. Syntactically, a package object looks much like one of the curly-braces packagings shown earlier in the chapter. The only difference is that it includes the `object` keyword. It's a *package object*, not a *package*. The contents of the curly braces can include any definitions you like. In this case, the package object includes the `showFruit` utility method from Listing 13.8.

Given that definition, any other code in any package can import the method just like it would import a class. For example, Listing 13.14 also shows the standalone object PrintMenu, which is located in a different package. PrintMenu can import the utility method showFruit in the same way it would import the class Fruit.

```
// In file bobsdelights/package.scala
package object bobsdelights {
    def showFruit(fruit: Fruit) = {
        import fruit._
        println(name + "s are " + color)
    }
}

// In file PrintMenu.scala
package printmenu
import bobsdelights.Fruits
import bobsdelights.showFruit

object PrintMenu {
    def main(args: Array[String]) = {
        for (fruit <- Fruits.menu) {
            showFruit(fruit)
        }
    }
}
```

Listing 13.14 · A package object.

Looking ahead, there are other uses of package objects for kinds of definitions you haven't seen yet. Package objects are frequently used to hold package-wide type aliases (Chapter 20) and implicit conversions (Chapter 21). The top-level `scala` package has a package object, and its definitions are available to all Scala code.

Package objects are compiled to class files named `package.class` that are located in the directory of the package that they augment. It's useful to keep the same convention for source files. So you would typically put the source file of the package object `bobsdelights` of Listing 13.14 into a file named `package.scala` that resides in the `bobsdelights` directory.

13.7 Conclusion

In this chapter, you saw the basic constructs for dividing a program into packages. This gives you a simple and useful kind of modularity, so that you can work with very large bodies of code without different parts of the code trampling on each other. Scala's system is the same in spirit as Java's packages, but there are some differences where Scala chooses to be more consistent or more general.

Looking ahead, [Chapter 29](#) describes a more flexible module system than division into packages. In addition to letting you separate code into several namespaces, that approach allows modules to be parameterized and inherit from each other. In the next chapter, we'll turn our attention to assertions and unit testing.

Chapter 14

Assertions and Tests

Assertions and tests are two important ways you can check that the software you write behaves as you expect. In this chapter, we'll show you several options you have in Scala to write and run them.

14.1 Assertions

Assertions in Scala are written as calls of a predefined method `assert`.¹ The expression `assert(condition)` throws an `AssertionError` if `condition` does not hold. There's also a two-argument version of `assert`: The expression `assert(condition, explanation)` tests `condition` and, if it does not hold, throws an `AssertionError` that contains the given explanation. The type of explanation is `Any`, so you can pass any object as the explanation. The `assert` method will call `toString` on it to get a string explanation to place inside the `AssertionError`. For example, in the method named “above” of class `Element`, shown in [Listing 10.13](#) on [page 243](#), you might place an `assert` after the calls to `widen` to make sure that the widened elements have equal widths. This is shown in [Listing 14.1](#).

Another way you might choose to do this is to check the widths at the end of the `widen` method, right before you return the value. You can accomplish this by storing the result in a `val`, performing an assertion on the result, then mentioning the `val` last so the result is returned if the assertion succeeds. However, you can do this more concisely with a convenience method in `Predef` named `ensuring`, as shown in [Listing 14.2](#).

¹The `assert` method is defined in the `Predef` singleton object, whose members are automatically imported into every Scala source file.

```
def above(that: Element): Element = {
    val this1 = this widen that.width
    val that1 = that widen this.width
    assert(this1.width == that1.width)
    elem(this1.contents ++ that1.contents)
}
```

Listing 14.1 · Using an assertion.

The `ensuring` method can be used with any result type because of an implicit conversion. Although it looks in this code as if we’re invoking `ensuring` on `widen`’s result, which is type `Element`, we’re actually invoking `ensuring` on a type to which `Element` is implicitly converted. The `ensuring` method takes one argument, a predicate function that takes a result type and returns Boolean, and passes the result to the predicate. If the predicate returns true, `ensuring` will return the result; otherwise, `ensuring` will throw an `AssertionError`.

In this example, the predicate is “`w <= _.width`”. The underscore is a placeholder for the one argument passed to the predicate, the `Element` result of the `widen` method. If the width passed as `w` to `widen` is less than or equal to the `width` of the result `Element`, the predicate will result in true, and `ensuring` will result in the `Element` on which it was invoked. Because this is the last expression of the `widen` method, `widen` itself will then result in the `Element`.

Assertions can be enabled and disabled using the JVM’s `-ea` and `-da`

```
private def widen(w: Int): Element =
  if (w <= width)
    this
  else {
    val left = elem(' ', (w - width) / 2, height)
    var right = elem(' ', w - width - left.width, height)
    left beside this beside right
  } ensuring (w <= _.width)
```

Listing 14.2 · Using `ensuring` to assert a function’s result.

command-line flags. When enabled, each assertion serves as a little test that uses the actual data encountered as the software runs. In the remainder of this chapter, we'll focus on the writing of external tests, which provide their own test data and run independently from the application.

14.2 Testing in Scala

You have many options for testing in Scala, from established Java tools, such as JUnit and TestNG, to tools written in Scala, such as ScalaTest, specs2, and ScalaCheck. For the remainder of this chapter, we'll give you a quick tour of these tools. We'll start with ScalaTest.

ScalaTest is the most flexible Scala test framework: it can be easily customized to solve different problems. ScalaTest's flexibility means teams can use whatever testing style fits their needs best. For example, for teams familiar with JUnit, the `FunSuite` style will feel comfortable and familiar. Listing 14.3 shows an example.

```
import org.scalatest.FunSuite
import Element.elem

class ElementSuite extends FunSuite {
    test("elem result should have passed width") {
        val ele = elem('x', 2, 3)
        assert(ele.width == 2)
    }
}
```

Listing 14.3 · Writing tests with `FunSuite`.

The central concept in ScalaTest is the *suite*, a collection of tests. A *test* can be anything with a name that can start and either succeed, fail, be pending, or canceled. Trait `Suite` is the central unit of composition in ScalaTest. `Suite` declares “lifecycle” methods defining a default way to run tests, which can be overridden to customize how tests are written and run.

ScalaTest offers *style traits* that extend `Suite` and override lifecycle methods to support different testing styles. It also provides *mixin traits* that override lifecycle methods to address particular testing needs. You define

test classes by composing Suite style and mixin traits, and define test suites by composing Suite instances.

FunSuite, which is extended by the test class shown in Listing 14.3, is an example of a testing style. The “Fun” in FunSuite stands for function; “test” is a method defined in FunSuite, which is invoked by the primary constructor of ElementSuite. You specify the name of the test as a string between the parentheses and the test code itself between curly braces. The test code is a function passed as a by-name parameter to test, which registers it for later execution.

ScalaTest is integrated into common build tools (such as sbt and Maven) and IDEs (such as IntelliJ IDEA and Eclipse). You can also run a Suite directly via ScalaTest’s Runner application or from the Scala interpreter simply by invoking execute on it. Here’s an example:

```
scala> (new ElementSuite).execute()
ElementSuite:
- elem result should have passed width
```

All ScalaTest styles, including FunSuite, are designed to encourage the writing of focused tests with descriptive names. In addition, all styles generate specification-like output that can facilitate communication among stakeholders. The style you choose dictates only how the declarations of your tests will look. Everything else in ScalaTest works consistently the same way no matter what style you choose.²

14.3 Informative failure reports

The test in Listing 14.3 attempts to create an element of width 2 and assert that the width of the resulting element is indeed 2. Were this assertion to fail, the failure report would include the filename and line number of the offending assertion, and an informative error message:

```
scala> val width = 3
width: Int = 3

scala> assert(width == 2)
org.scalatest.exceptions.TestFailedException:
  3 did not equal 2
```

²More detail on ScalaTest is available from <http://www.scalatest.org/>.

To provide descriptive error messages when assertions fail, ScalaTest analyzes the expressions passed to each `assert` invocation at compile time. If you prefer to see even more detailed information about assertion failures, you can use ScalaTest's `DiagrammedAssertions`, whose error messages display a diagram of the expression passed to `assert`:

```
scala> assert(List(1, 2, 3).contains(4))
org.scalatest.exceptions.TestFailedException:
  assert(List(1, 2, 3).contains(4))
  |   |   |   |   |
  |   1   2   3   false    4
List(1, 2, 3)
```

ScalaTest's `assert` methods do not differentiate between the actual and expected result in error messages. They just indicate that the left operand did not equal the right operand, or show the values in a diagram. If you wish to emphasize the distinction between actual and expected, you can alternatively use ScalaTest's `assertResult` method, like this:

```
assertResult(2) {
  ele.width
}
```

With this expression you indicate that you expect the code between the curly braces to result in 2. Were the code between the braces to result in 3, you'd see the message, "Expected 2, but got 3" in the test failure report.

If you want to check that a method throws an expected exception, you can use ScalaTest's `assertThrows` method, like this:

```
assertThrows[IllegalArgumentException] {
  elem('x', -2, 3)
}
```

If the code between the curly braces throws a different exception than expected, or throws no exception, `assertThrows` will complete abruptly with a `TestFailedException`. You'll get a helpful error message in the failure report, such as:

```
Expected IllegalArgumentException to be thrown,
but NegativeArraySizeException was thrown.
```

On the other hand, if the code completes abruptly with an instance of the passed exception class, `assertThrows` will return normally. If you wish to inspect the expected exception further, you can use `intercept` instead of `assertThrows`. The `intercept` method works the same as `assertThrows`, except if the expected exception is thrown, `intercept` returns it:

```
val caught =  
  intercept[ArithException] {  
    1 / 0  
}  
  
assert(caught.getMessage == "/ by zero")
```

In short, ScalaTest's assertions work hard to provide useful failure messages that will help you diagnose and fix problems in your code.

14.4 Tests as specifications

In the *behavior-driven development* (BDD) testing style, the emphasis is on writing human-readable specifications of the expected behavior of code and accompanying tests that verify the code has the specified behavior. ScalaTest includes several traits that facilitate this style of testing. An example using one such trait, `FlatSpec`, is shown in Listing 14.4.

In a `FlatSpec`, you write tests as *specifier clauses*. You start by writing a name for the *subject* under test as a string ("A `UniformElement`" in Listing 14.4), then `should` (or `must` or `can`), then a string that specifies a bit of behavior required of the subject, then `in`. In the curly braces following `in`, you write code that tests the specified behavior. In subsequent clauses you can write `it` to refer to the most recently given subject. When a `FlatSpec` is executed, it will run each specifier clause as a ScalaTest test. `FlatSpec` (and ScalaTest's other specification traits) generate output that reads like a specification when run. For example, here's what the output will look like if you run `ElementSpec` from Listing 14.4 in the interpreter:

```
scala> (new ElementSpec).execute()  
A UniformElement  
- should have a width equal to the passed value  
- should have a height equal to the passed value  
- should throw an IAE if passed a negative width
```

```
import org.scalatest.FlatSpec
import org.scalatest.Matchers
import Element.elem

class ElementSpec extends FlatSpec with Matchers {

  "A UniformElement" should
    "have a width equal to the passed value" in {
      val ele = elem('x', 2, 3)
      ele.width should be (2)
    }

  it should "have a height equal to the passed value" in {
    val ele = elem('x', 2, 3)
    ele.height should be (3)
  }

  it should "throw an IAE if passed a negative width" in {
    an [IllegalArgumentException] should be thrownBy {
      elem('x', -2, 3)
    }
  }
}
```

Listing 14.4 · Specifying and testing behavior with a ScalaTest FlatSpec.

[Listing 14.4](#) also illustrates ScalaTest’s *matchers* domain-specific language (DSL). By mixing in trait `Matchers`, you can write assertions that read more like natural language. ScalaTest provides many matchers in its DSL, and also enables you to define new matchers with custom failure messages. The matchers shown in [Listing 14.4](#) include the “should be” and “`an [...] should be thrownBy {...}`” syntax. You can alternatively mix in `MustMatchers` if you prefer `must` to `should`. For example, mixing in `MustMatchers` would allow you to write expressions such as:

```
result must be >= 0
map must contain key 'c'
```

If the last assertion failed, you’d see an error message similar to:

```
Map('a' -> 1, 'b' -> 2) did not contain key 'c'
```

The specs2 testing framework, an open source tool written in Scala by Eric Torreborre, also supports the BDD style of testing but with a different syntax. For example, you could use specs2 to write the test shown in Listing 14.5:

```
import org.specs2._
import Element.elem

object ElementSpecification extends Specification {
    "A UniformElement" should {
        "have a width equal to the passed value" in {
            val ele = elem('x', 2, 3)
            ele.width must be==(2)
        }
        "have a height equal to the passed value" in {
            val ele = elem('x', 2, 3)
            ele.height must be==(3)
        }
        "throw an IAE if passed a negative width" in {
            elem('x', -2, 3) must
                throwA[IllegalArgumentException]
        }
    }
}
```

Listing 14.5 · Specifying and testing behavior with the specs2 framework.

Like ScalaTest, specs2 provides a matchers DSL. You can see some examples of specs2 matchers in action in Listing 14.5 in the lines that contain “must be==” and “must throwA”.³ You can use specs2 standalone, but it is also integrated with ScalaTest and JUnit, so you can run specs2 tests with those tools as well.

One of the big ideas of BDD is that tests can be used to facilitate communication between the people who decide what a software system should do, the people who implement the software, and the people who determine whether the software is finished and working. Although any of ScalaTest’s

³You can download specs2 from <http://specs2.org/>.

or specs2's styles can be used in this manner, ScalaTest's FeatureSpec in particular is designed for it. Listing 14.6 shows an example:

```
import org.scalatest._

class TVSetSpec extends FeatureSpec with GivenWhenThen {

    feature("TV power button") {
        scenario("User presses power button when TV is off") {
            Given("a TV set that is switched off")
            When("the power button is pressed")
            Then("the TV should switch on")
            pending
        }
    }
}
```

Listing 14.6 · Using tests to facilitate communication among stakeholders.

FeatureSpec is designed to guide conversations about software requirements: You must identify specific *features*, then specify those features in terms of *scenarios*. The Given, When, and Then methods (provided by trait GivenWhenThen) can help focus the conversation on the specifics of individual scenarios. The pending call at the end indicates that neither the test nor the actual behavior has been implemented—just the specification. Once all the tests and specified behavior have been implemented, the tests will pass and the requirements can be deemed to have been met.

14.5 Property-based testing

Another useful testing tool for Scala is ScalaCheck, an open source framework written by Rickard Nilsson. ScalaCheck enables you to specify properties that the code under test must obey. For each property, ScalaCheck will generate data and execute assertions that check whether the property holds. Listing 14.7 shows an example of using ScalaCheck from a ScalaTest WordSpec that mixes in trait PropertyChecks.

WordSpec is a ScalaTest style class. The PropertyChecks trait provides several forAll methods that allow you to mix property-based tests with traditional assertion-based or matcher-based tests. In this example, we

```
import org.scalatest.WordSpec
import org.scalatest.prop.PropertyChecks
import org.scalatest.MustMatchers._
import Element.elem

class ElementSpec extends WordSpec with PropertyChecks {
    "elem result" must {
        "have passed width" in {
            forAll { (w: Int) =>
                whenever (w > 0) {
                    elem('x', w, 3).width must equal (w)
                }
            }
        }
    }
}
```

Listing 14.7 · Writing property-based tests with ScalaCheck.

check a property that the `elem` factory should obey. ScalaCheck properties are expressed as function values that take as parameters the data needed by the property's assertions. This data will be generated by ScalaCheck. In the property shown in Listing 14.7, the data is an integer named `w` that represents a width. Inside the body of the function, you see this code:

```
whenever (w > 0) {
    elem('x', w, 3).width must equal (w)
}
```

The `whenever` clause indicates that whenever the left hand expression is true, the expression on the right must hold true. Thus in this case, the expression in the block must hold true whenever `w` is greater than 0. The right-hand expression in this case will yield true if the width passed to the `elem` factory is the same as the width of the `Element` returned by the factory.

With this small amount of code, ScalaCheck will generate possibly hundreds of values for `w` and test each one, looking for a value for which the property doesn't hold. If the property holds true for every value ScalaCheck tries, the test will pass. Otherwise, the test will complete abruptly with a

`TestFailedException` that contains information including the value that caused the failure.

14.6 Organizing and running tests

Each framework mentioned in this chapter provides some mechanism for organizing and running tests. In this section, we'll give a quick overview of ScalaTest's approach. To get the full story on any of these frameworks, however, you'll need to consult their documentation.

In ScalaTest, you organize large test suites by nesting Suites inside Suites. When a Suite is executed, it will execute its nested Suites as well as its tests. The nested Suites will in turn execute their nested Suites, and so on. A large test suite, therefore, is represented as a tree of Suite objects. When you execute the root Suite in the tree, all Suites in the tree will be executed.

You can nest suites manually or automatically. To nest manually, you either override the `nestedSuites` method on your Suites or pass the Suites you want to nest to the constructor of class `Suites`, which ScalaTest provides for this purpose. To nest automatically, you provide package names to ScalaTest's Runner, which will discover Suites automatically, nest them under a root Suite, and execute the root Suite.


You can invoke ScalaTest's Runner application from the command line or via a build tool, such as sbt, maven, or ant. The simplest way to invoke Runner on the command line is via the `org.scalatest.run` application. This application expects a fully qualified test class name. For example, to run the test class shown in [Listing 14.6](#), you must compile it with:

```
$ scalac -cp scalatest.jar TVSetSpec.scala
```

Then you can run it with:

```
$ scala -cp scalatest.jar org.scalatest.run TVSetSpec
```

With `-cp` you place ScalaTest's JAR file on the class path. (When downloaded, the JAR file name will include embedded Scala and ScalaTest version numbers.) The next token, `org.scalatest.run`, is the fully qualified application name. Scala will run this application and pass the remaining tokens as command line arguments. The `TVSetSpec` argument specifies the suite to execute. The result is shown in [Figure 14.1](#).



The screenshot shows a terminal window titled "ScalaTest Output". The output of the command \$ scala -cp scalatest_2.11-2.2.4.jar org.scalatest.run TVSetSpec is displayed. The output includes the run starting message, the feature definition (TVSetSpec), the scenario (User presses power button when TV is off), and the pending status (pending). It also shows the run completed in 92 milliseconds, total tests run (0), suites completed (1), and tests succeeded (0). A note at the bottom states "No tests were executed."

Figure 14.1 · The output of `org.scalatest.run`.

14.7 Conclusion

In this chapter you saw examples of mixing assertions directly in production code, as well as writing them externally in tests. You saw that as a Scala programmer, you can take advantage of popular testing tools from the Java community, such as JUnit and TestNG, as well as newer tools designed explicitly for Scala, such as ScalaTest, ScalaCheck, and specs2. Both in-code assertions and external tests can help you achieve your software quality goals. We felt that these techniques are important enough to justify the short detour from the Scala tutorial that this chapter represented. In the next chapter, however, we'll return to the language tutorial and cover a very useful aspect of Scala: pattern matching.

Chapter 15

Case Classes and Pattern Matching

This chapter introduces **case classes** and **pattern matching**, twin constructs that support you when writing regular, non-encapsulated data structures. These two constructs are particularly helpful for tree-like recursive data.

If you have programmed in a functional language before, then you will probably recognize pattern matching. But case classes will be new to you. Case classes are Scala's way to allow pattern matching on objects without requiring a large amount of boilerplate. Generally, all you need to do is add a single `case` keyword to each class that you want to be pattern matchable.

This chapter starts with a simple example of case classes and pattern matching. It then goes through all of the kinds of patterns that are supported, talks about the role of **sealed classes**, discusses the `Option` type, and shows some non-obvious places in the language where pattern matching is used. Finally, a larger, more realistic example of pattern matching is shown.

15.1 A simple example

Before delving into all the rules and nuances of pattern matching, it is worth looking at a simple example to get the general idea. Let's say you need to write a library that manipulates arithmetic expressions, perhaps as part of a domain-specific language you are designing.

A first step to tackling this problem is the definition of the input data. To keep things simple, we'll concentrate on arithmetic expressions consisting of variables, numbers, and unary and binary operations. This is expressed by the hierarchy of Scala classes shown in [Listing 15.1](#).

```
abstract class Expr
case class Var(name: String) extends Expr
case class Number(num: Double) extends Expr
case class UnOp(operator: String, arg: Expr) extends Expr
case class BinOp(operator: String,
                  left: Expr, right: Expr) extends Expr
```

Listing 15.1 · Defining case classes.

The hierarchy includes an abstract base class `Expr` with four subclasses, one for each kind of expression being considered.¹ The bodies of all five classes are empty. As mentioned previously, in Scala you can leave out the braces around an empty class body if you wish, so `class C` is the same as `class C {}`.

Case classes

The other noteworthy thing about the declarations of Listing 15.1 is that each subclass has a `case` modifier. Classes with such a modifier are called **case classes**. Using the modifier makes the Scala compiler add some syntactic conveniences to your class.

First, it adds a factory method with the name of the class. This means that, for instance, you can write `Var("x")` to construct a `Var` object, instead of the slightly longer `new Var("x")`:

```
scala> val v = Var("x")
v: Var = Var(x)
```

The factory methods are particularly nice when you nest them. Because there are no noisy `new` keywords sprinkled throughout the code, you can take in the expression's structure at a glance:

```
scala> val op = BinOp("+", Number(1), v)
op: BinOp = BinOp(+,Number(1.0),Var(x))
```

The second syntactic convenience is that all arguments in the parameter list of a case class implicitly get a `val` prefix, so they are maintained as fields:

¹Instead of an abstract class, we could have also chosen to model the root of that class hierarchy as a trait. Modeling it as an abstract class may be slightly more efficient.

```
scala> v.name
res0: String = x

scala> op.left
res1: Expr = Number(1.0)
```

Third, the compiler adds “natural” implementations of methods `toString`, `hashCode`, and `equals` to your class. They will print, hash, and compare a whole tree consisting of the class and (recursively) all its arguments. Since `==` in Scala always delegates to `equals`, this means that elements of case classes are always compared structurally:

```
scala> println(op)
BinOp(+,Number(1.0),Var(x))

scala> op.right == Var("x")
res3: Boolean = true
```

Finally, the compiler adds a `copy` method to your class for making modified copies. This method is useful for making a new instance of the class that is the same as another one except that one or two attributes are different. The method works by using named and default parameters (see [Section 8.8](#)). You specify the changes you’d like to make by using named parameters. For any parameter you don’t specify, the value from the old object is used. As an example, here is how you can make an operation just like `op` except that the operator has changed:

```
scala> op.copy(operator = "-")
res4: BinOp = BinOp(-,Number(1.0),Var(x))
```

```
case class BinOp(operator: String,
left: Expr, right: Expr) extends Expr
```

← Reminder

```
scala> val op = BinOp("+", Number(1), v)
op: BinOp = BinOp(+,Number(1.0),Var(x))
```

All these conventions add a lot of convenience—at a small price. You have to write the `case` modifier, and your classes and objects become a bit larger. They are larger because additional methods are generated and an implicit field is added for each constructor parameter. However, the biggest advantage of case classes is that they support pattern matching.

Pattern matching

Say you want to simplify arithmetic expressions of the kinds just presented. There is a multitude of possible simplification rules. The following three rules just serve as an illustration:

```

UnOp("−", UnOp("−", e)) => e // Double negation
BinOp("+", e, Number(0)) => e // Adding zero
BinOp("∗", e, Number(1)) => e // Multiplying by one

```

Using pattern matching, these rules can be taken almost as they are to form the core of a simplification function in Scala, as shown in Listing 15.2. The function, `simplifyTop`, can be used like this:

```
scala> simplifyTop(UnOp("−", UnOp("−", Var("x"))))
res4: Expr = Var(x)
```

Listing 15.2 · The `simplifyTop` function, which does a pattern match.

The right-hand side of `simplifyTop` consists of a `match expression`. `match` corresponds to `switch` in Java, but it's written after the selector expression. In other words, it's:

```
selector match { alternatives }
```

instead of:

```
switch (selector) { alternatives }
```

A pattern match includes a `sequence of alternatives`, each starting with the keyword `case`. Each alternative includes a `pattern` and one or more `expressions`, which will be evaluated if the pattern matches. An `arrow symbol =>` separates the pattern from the expressions.

A `match expression` is evaluated by trying each of the patterns in the order they are written. The first pattern that matches is selected, and the part following the arrow is selected and executed.

A `constant pattern` like `"+"` or `1` matches values that are equal to the constant with respect to `==`. A `variable pattern` like `e` matches every value.

The variable then refers to that value in the right hand side of the case clause. In this example, note that the first three alternatives evaluate to `e`, a variable that is bound within the associated pattern. The *wildcard pattern* (`_`) also matches every value, but it does not introduce a variable name to refer to that value. In Listing 15.2, notice how the match ends with a default case that does nothing to the expression. Instead, it just results in `expr`, the expression matched upon.

A *constructor pattern* looks like `UnOp("-", e)`. This pattern matches all values of type `UnOp` whose first argument matches `"-"` and whose second argument matches `e`. Note that the arguments to the constructor are themselves patterns. This allows you to write deep patterns using a concise notation. Here's an example:

```
UnOp("-", UnOp("-", e))
```

Imagine trying to implement this same functionality using the visitor design pattern!² Almost as awkward, imagine implementing it as a long sequence of `if` statements, type tests, and type casts.

match compared to switch

Match expressions can be seen as a generalization of Java-style switches. A Java-style switch can be naturally expressed as a match expression, where each pattern is a constant and the last pattern may be a wildcard (which represents the default case of the switch).

However, there are three differences to keep in mind: First, `match` is an *expression* in Scala (*i.e.*, it always results in a value). Second, Scala's alternative expressions never "fall through" into the next case. Third, if none of the patterns match, an exception named `MatchError` is thrown. This means you always have to make sure that all cases are covered, even if it means adding a default case where there's nothing to do.

Listing 15.3 shows an example. The second case is necessary because without it, the match expression would throw a `MatchError` for every `expr` argument that is not a `BinOp`. In this example, no code is specified for that second case, so if that case runs it does nothing. The result of either case is the unit value '`()`', which is also the result of the entire match expression.

²Gamma, et al., *Design Patterns* [Gam95]

```
expr match {
    case BinOp(op, left, right) =>
        println(expr + " is a binary operation")
    case _ =>
}
```

Listing 15.3 · A pattern match with an empty “default” case.

15.2 Kinds of patterns

The previous example showed several kinds of patterns in quick succession. Now take a minute to look at each pattern in detail.

The syntax of patterns is easy, so do not worry about that too much. All patterns look exactly like the corresponding expression. For instance, given the hierarchy of Listing 15.1, the pattern `Var(x)` matches any variable expression, binding `x` to the name of the variable. Used as an expression, `Var(x)`—exactly the same syntax—recreates an equivalent object, assuming `x` is already bound to the variable’s name. Since the syntax of patterns is so transparent, the main thing to pay attention to is just what kinds of patterns are possible.

Wildcard patterns

The wildcard pattern `(_)` matches any object whatsoever. You have already seen it used as a default, catch-all alternative, like this:

```
expr match {
    case BinOp(op, left, right) =>
        println(expr + " is a binary operation")
    case _ => // handle the default case
}
```

Wildcards can also be used to ignore parts of an object that you do not care about. For example, the previous example does not actually care what the elements of a binary operation are; it just checks whether or not it is a binary operation. Thus, the code can just as well use the wildcard pattern for the elements of the `BinOp`, as shown in Listing 15.4.

```
expr match {
  case BinOp(_, _, _) => println(expr + " is a binary operation")
  case _ => println("It's something else")
}
```

Listing 15.4 · A pattern match with wildcard patterns.

Constant patterns

A **constant pattern** matches only itself. Any literal may be used as a constant. For example, 5, true, and "hello" are all constant patterns. Also, any **val** or **singleton object** can be used as a constant. For example, Nil, a singleton object, is a pattern that matches only the empty list. Listing 15.5 shows some examples of constant patterns:

```
def describe(x: Any) = x match {
  case 5 => "five"
  case true => "truth"
  case "hello" => "hi!"
  case Nil => "the empty list"
  case _ => "something else"
}
```

Listing 15.5 · A pattern match with constant patterns.

Here is how the pattern match shown in Listing 15.5 looks in action:

```
scala> describe(5)
res6: String = five

scala> describe(true)
res7: String = truth

scala> describe("hello")
res8: String = hi!

scala> describe(Nil)
res9: String = the empty list

scala> describe(List(1,2,3))
res10: String = something else
```

Variable patterns

A variable pattern matches any object, just like a wildcard. But unlike a wildcard, Scala binds the variable to whatever the object is. You can then use this variable to act on the object further. For example, Listing 15.6 shows a pattern match that has a special case for zero, and a default case for all other values. The default case uses a variable pattern so that it has a name for the value, no matter what it is.

```
expr match {
    case 0 => "zero"
    case somethingElse => "not zero: " + somethingElse
}
```

Listing 15.6 · A pattern match with a variable pattern.

Variable or constant?

Constant patterns can have symbolic names. You saw this already when we used `Nil` as a pattern. Here is a related example, where a pattern match involves the constants `E` (`2.71828...`) and `Pi` (`3.14159...`):

```
scala> import math.{E, Pi}
import math.{E, Pi}

scala> E match {
    case Pi => "strange math? Pi = " + Pi
    case _ => "OK"
}
res11: String = OK
```

As expected, `E` does not match `Pi`, so the “strange math” case is not used.

How does the Scala compiler know that `Pi` is a constant imported from `scala.math`, and not a variable that stands for the selector value itself? Scala uses a simple lexical rule for disambiguation: a simple name starting with a lowercase letter is taken to be a pattern variable; all other references are taken to be constants. To see the difference, create a lowercase alias for `pi` and try with that:

```
scala> val pi = math.Pi
pi: Double = 3.141592653589793

scala> E match {
    case pi => "strange math? Pi = " + pi
}
res12: String = strange math? Pi = 2.718281828459045
```

Here the compiler will not even let you add a default case at all. Since `pi` is a variable pattern, it will match all inputs, and so no cases following it can be reached:

```
scala> E match {
    case pi => "strange math? Pi = " + pi
    case _ => "OK"
}
<console>:12: warning: unreachable code
    case _ => "OK"
               ^
```

You can still use a lowercase name for a pattern constant, if you need to, by using one of two tricks. First, if the constant is a field of some object, you can prefix it with a qualifier. For instance, `pi` is a variable pattern, but `this.pi` or `obj.pi` are constants even though they start with lowercase letters. If that does not work (because `pi` is a local variable, say), you can alternatively enclose the variable name in back ticks. For instance, ``pi`` would again be interpreted as a constant, not as a variable:

```
scala> E match {
    case `pi` => "strange math? Pi = " + pi
    case _ => "OK"
}
res14: String = OK
```

As you can see, the back-tick syntax for identifiers is used for two different purposes in Scala to help you code your way out of unusual circumstances. Here you see that it can be used to treat a lowercase identifier as a constant in a pattern match. Earlier on, in [Section 6.10](#), you saw that it can also be used to treat a keyword as an ordinary identifier, *e.g.*, writing `Thread.`yield`()` treats `yield` as an identifier rather than a keyword.

Constructor patterns

Constructors are where pattern matching becomes really powerful. A constructor pattern looks like “BinOp(“+”, e, Number(0))”. It consists of a name (BinOp) and then a number of patterns within parentheses: “+”, e, and Number(0). Assuming the name designates a case class, such a pattern means to first check that the object is a member of the named case class, and then to check that the constructor parameters of the object match the extra patterns supplied.

These extra patterns mean that Scala patterns support *deep matches*. Such patterns not only check the top-level object supplied, but also the contents of the object against further patterns. Since the extra patterns can themselves be constructor patterns, you can use them to check arbitrarily deep into an object. For example, the pattern shown in Listing 15.7 checks that the top-level object is a BinOp, that its third constructor parameter is a Number, and that the value field of that number is 0. This pattern is one line long yet checks three levels deep.

```
expr match {
    case BinOp("+", e, Number(0)) => println("a deep match")
    case _ =>
}
```

Listing 15.7 · A pattern match with a constructor pattern.

Sequence patterns

You can match against sequence types, like List or Array, just like you match against case classes. Use the same syntax, but now you can specify any number of elements within the pattern. Listing 15.8 shows a pattern that checks for a three-element list starting with zero.

```
expr match {
    case List(0, _, _) => println("found it")
    case _ =>
}
```

Listing 15.8 · A sequence pattern with a fixed length.

If you want to match against a sequence without specifying how long it can be, you can specify `_*` as the last element of the pattern. This funny-looking pattern matches any number of elements within a sequence, including zero elements. Listing 15.9 shows an example that matches any list that starts with zero, regardless of how long the list is.

```
expr match {
    case List(0, _) => println("found it")
    case _ =>
}
```

Listing 15.9 · A sequence pattern with an arbitrary length.

Tuple patterns

You can match against tuples too. A pattern like `(a, b, c)` matches an arbitrary 3-tuple. An example is shown in Listing 15.10.

```
def tupleDemo(expr: Any) =
expr match {
    case (a, b, c) => println("matched " + a + b + c)
    case _ =>
}
```

Listing 15.10 · A pattern match with a tuple pattern.

If you load the `tupleDemo` method shown in Listing 15.10 into the interpreter, and pass to it a tuple with three elements, you'll see:

```
scala> tupleDemo(("a ", 3, "-tuple"))
matched a 3-tuple
```

Typed patterns

You can use a *typed pattern* as a convenient replacement for type tests and type casts. Listing 15.11 shows an example.

```
def generalSize(x: Any) = x match {
    case s: String => s.length
    case m: Map[_, _] => m.size
    case _ => -1
}
```

Listing 15.11 · A pattern match with typed patterns.

Here are a few examples of using `generalSize` in the Scala interpreter:

```
scala> generalSize("abc")
res16: Int = 3

scala> generalSize(Map(1 -> 'a', 2 -> 'b'))
res17: Int = 2

scala> generalSize(math.Pi)
res18: Int = -1
```

The `generalSize` method returns the size or length of objects of various types. Its argument is of type `Any`, so it could be any value. If the argument is a `String`, the method returns the string's length. The pattern "`s: String`" is a typed pattern; it matches every (non-null) instance of `String`. The pattern variable `s` then refers to that string.

Note that even though `s` and `x` refer to the same value, the type of `x` is `Any`, while the type of `s` is `String`. So you can write `s.length` in the alternative expression that corresponds to the pattern, but you could not write `x.length`, because the type `Any` does not have a `length` member.

An equivalent but more long-winded way that achieves the effect of a match against a typed pattern employs a type test followed by a type cast. Scala uses a different syntax than Java for these. To test whether an expression `expr` has type `String`, say, you write:

```
expr.isInstanceOf[String]
```

To cast the same expression to type `String`, you use:

```
expr.asInstanceOf[String]
```

Using a type test and cast, you could rewrite the first case of the previous match expression as shown in Listing 15.12.

```
if (x.isInstanceOf[String]) {  
    val s = x.asInstanceOf[String]  
    s.length  
} else ...
```

Listing 15.12 · Using `isInstanceOf` and `asInstanceOf` (poor style).

The operators `isInstanceOf` and `asInstanceOf` are treated as predefined methods of class `Any` that take a type parameter in square brackets. In fact, `x.asInstanceOf[String]` is a special case of a method invocation with an explicit type parameter `String`.

As you will have noted by now, writing type tests and casts is rather verbose in Scala. That's intentional because it is not encouraged practice. You are usually better off using a pattern match with a typed pattern. That's particularly true if you need to do both a type test and a type cast, because both operations are then rolled into a single pattern match.

The second case of the `match` expression in Listing 15.11 contains the typed pattern “`m: Map[_, _]`”. This pattern matches any value that is a `Map` of some arbitrary key and value types, and lets `m` refer to that value. Therefore, `m.size` is well typed and returns the size of the map. The underscores in the type pattern³ are like wildcards in other patterns. You could have also used (lowercase) type variables instead.

Type erasure

Can you also test for a map with specific element types? This would be handy, say, for testing whether a given value is a map from type `Int` to type `Int`. Let's try:

```
scala> def isIntIntMap(x: Any) = x match {  
    case m: Map[Int, Int] => true  
    case _ => false  
}  
<console>:9: warning: non-variable type argument Int in type  
pattern scala.collection.immutable.Map[Int,Int] (the  
underlying of Map[Int,Int]) is unchecked since it is
```

³In the typed pattern, `m: Map[_, _]`, the “`Map[_, _]`” portion is called a *type pattern*.

eliminated by erasure

```
case m: Map[Int, Int] => true
```

^

Scala uses the *erasure* model of generics, just like Java does. This means that no information about type arguments is maintained at runtime. Consequently, there is no way to determine at runtime whether a given Map object has been created with two Int arguments, rather than with arguments of different types. All the system can do is determine that a value is a Map of some arbitrary type parameters. You can verify this behavior by applying `isIntIntMap` to arguments of different instances of class `Map`:

```
scala> isIntIntMap(Map(1 -> 1))
res19: Boolean = true

scala> isIntIntMap(Map("abc" -> "abc"))
res20: Boolean = true
```

The first application returns `true`, which looks correct, but the second application also returns `true`, which might be a surprise. To alert you to the possibly non-intuitive runtime behavior, the compiler emits unchecked warnings like the one shown previously.

The only exception to the erasure rule is arrays, because they are handled specially in Java as well as in Scala. The element type of an array is stored with the array value, so you can pattern match on it. Here's an example:

```
scala> def isStringArray(x: Any) = x match {
    case a: Array[String] => "yes"
    case _ => "no"
  }
isStringArray: (x: Any)String

scala> val as = Array("abc")
as: Array[String] = Array(abc)

scala> isStringArray(as)
res21: String = yes

scala> val ai = Array(1, 2, 3)
ai: Array[Int] = Array(1, 2, 3)

scala> isStringArray(ai)
res22: String = no
```

Variable binding

In addition to the standalone variable patterns, you can also add a variable to any other pattern. You simply write the variable name, an at sign (@), and then the pattern. This gives you a variable-binding pattern, which means the pattern is to perform the pattern match as normal, and if the pattern succeeds, set the variable to the matched object just as with a simple variable pattern.

As an example, Listing 15.13 shows a pattern match that looks for the absolute value operation being applied twice in a row. Such an expression can be simplified to only take the absolute value one time.

```
expr match {
    case UnOp("abs", e @ UnOp("abs", _)) => e
    case _ =>
}
```

Listing 15.13 · A pattern with a variable binding (via the @ sign).

The example shown in Listing 15.13 includes a variable-binding pattern with `e` as the variable and `UnOp("abs", _)` as the pattern. If the entire pattern match succeeds, then the portion that matched the `UnOp("abs", _)` part is made available as variable `e`. The result of the case is just `e`, because `e` has the same value as `expr` but with one less absolute value operation.

15.3 Pattern guards

Sometimes, syntactic pattern matching is not precise enough. For instance, say you are given the task of formulating a simplification rule that replaces sum expressions with two identical operands, such as $e + e$, by multiplications of two (e.g., $e * 2$). In the language of Expr trees, an expression like:

`BinOp("+", Var("x"), Var("x"))`

would be transformed by this rule to:

`BinOp("*", Var("x"), Number(2))`

You might try to define this rule as follows:

```
scala> def simplifyAdd(e: Expr) = e match {
    case BinOp("+", x, x) => BinOp("*", x, Number(2))
    case _ => e
}
<console>:14: error: x is already defined as value x
           case BinOp("+", x, x) => BinOp("*", x, Number(2))
                                         ^

```

This fails because Scala restricts patterns to be *linear*: a pattern variable may only appear once in a pattern. However, you can re-formulate the match with a *pattern guard*, as shown in Listing 15.14:

```
scala> def simplifyAdd(e: Expr) = e match {
    case BinOp("+", x, y) if x == y =>
        BinOp("*", x, Number(2))
    case _ => e
}
simplifyAdd: (e: Expr)Expr
```

Listing 15.14 · A match expression with a pattern guard.

A pattern guard comes after a pattern and starts with an `if`. The guard can be an arbitrary boolean expression, which typically refers to variables in the pattern. If a pattern guard is present, the match succeeds only if the guard evaluates to `true`. Hence, the first case above would only match binary operations with two equal operands.

Some other examples of guarded patterns are:

```
// match only positive integers
case n: Int if 0 < n => ...
// match only strings starting with the letter 'a'
case s: String if s(0) == 'a' => ...
```

15.4 Pattern overlaps

Patterns are tried in the order in which they are written. The version of `simplify` shown in Listing 15.15 presents an example where the order of the cases matters.

```
def simplifyAll(expr: Expr): Expr = expr match {
    case UnOp("-", UnOp("-", e)) =>
        simplifyAll(e) // '-' is its own inverse
    case BinOp("+", e, Number(0)) =>
        simplifyAll(e) // '0' is a neutral element for '+'
    case BinOp("*", e, Number(1)) =>
        simplifyAll(e) // '1' is a neutral element for '*'
    case UnOp(op, e) =>
        UnOp(op, simplifyAll(e))
    case BinOp(op, l, r) =>
        BinOp(op, simplifyAll(l), simplifyAll(r))
    case _ => expr
}
```

Listing 15.15 · Match expression in which case order matters.

The version of `simplify` shown in Listing 15.15 will apply simplification rules everywhere in an expression, not just at the top, as `simplifyTop` did. It can be derived from `simplifyTop` by adding two more cases for general unary and binary expressions (cases four and five in Listing 15.15).

The fourth case has the pattern `UnOp(op, e)`; *i.e.*, it matches every unary operation. The operator and operand of the unary operation can be arbitrary. They are bound to the pattern variables `op` and `e`, respectively. The alternative in this case applies `simplifyAll` recursively to the operand `e` and then rebuilds the same unary operation with the (possibly) simplified operand. The fifth case for `BinOp` is analogous: it is a “catch-all” case for arbitrary binary operations, which recursively applies the simplification method to its two operands.

In this example, it is important that the catch-all cases come *after* the more specific simplification rules. If you wrote them in the other order, then the catch-all case would be run in favor of the more specific rules. In many cases, the compiler will even complain if you try. For example, here’s a match expression that won’t compile because the first case will match anything that would be matched by the second case:

```
scala> def simplifyBad(expr: Expr) = expr match {  
    case UnOp(op, e) => UnOp(op, simplifyBad(e))  
    case UnOp("-", UnOp("-", e)) => e  
}  
<console>:21: warning: unreachable code  
    case UnOp("-", UnOp("-", e)) => e  
                                         ^
```

15.5 Sealed classes

Whenever you write a pattern match, you need to make sure you have covered all of the possible cases. Sometimes you can do this by adding a default case at the end of the match, but that only applies if there is a sensible default behavior. What do you do if there is no default? How can you ever feel safe that you covered all the cases?

You can enlist the help of the Scala compiler in detecting missing combinations of patterns in a `match` expression. To do this, the compiler needs to be able to tell which are the possible cases. In general, this is impossible in Scala because new case classes can be defined at any time and in arbitrary compilation units. For instance, nothing would prevent you from adding a fifth case class to the `Expr` class hierarchy in a different compilation unit from the one where the other four cases are defined.

The alternative is to make the superclass of your case classes `sealed`. A sealed class cannot have any new subclasses added except the ones in the same file. This is very useful for pattern matching because it means you only need to worry about the subclasses you already know about. What's more, you get better compiler support as well. If you match against case classes that inherit from a sealed class, the compiler will flag missing combinations of patterns with a warning message.

If you write a hierarchy of classes intended to be pattern matched, you should consider sealing them. Simply put the `sealed` keyword in front of the class at the top of the hierarchy. Programmers using your class hierarchy will then feel confident in pattern matching against it. The `sealed` keyword, therefore, is often a license to pattern match. Listing 15.16 shows an example in which `Expr` is turned into a sealed class.

```
sealed abstract class Expr
case class Var(name: String) extends Expr
case class Number(num: Double) extends Expr
case class UnOp(operator: String, arg: Expr) extends Expr
case class BinOp(operator: String,
                  left: Expr, right: Expr) extends Expr
```

Listing 15.16 · A sealed hierarchy of case classes.

Now define a pattern match where some of the possible cases are left out:

```
def describe(e: Expr): String = e match {
    case Number(_) => "a number"
    case Var(_)      => "a variable"
}
```

You will get a compiler warning like the following:

```
warning: match is not exhaustive!
missing combination          UnOp
missing combination          BinOp
```

Such a warning tells you that there's a risk your code might produce a `MatchError` exception because some possible patterns (`UnOp`, `BinOp`) are not handled. The warning points to a potential source of runtime faults, so it is usually a welcome help in getting your program right.

However, at times you might encounter a situation where the compiler is too picky in emitting the warning. For instance, you might know from the context that you will only ever apply the `describe` method above to expressions that are either `Numbers` or `Vars`, so you know that no `MatchError` will be produced. To make the warning go away, you could add a third catch-all case to the method, like this:

```
def describe(e: Expr): String = e match {
    case Number(_) => "a number"
    case Var(_)     => "a variable"
    case _          => throw new RuntimeException // Should not happen
}
```

That works, but it is not ideal. You will probably not be very happy that you were forced to add code that will never be executed (or so you think), just to make the compiler shut up.

A more lightweight alternative is to add an `@unchecked` annotation to the selector expression of the match. This is done as follows:

```
def describe(e: Expr): String = (e: @unchecked) match {  
    case Number(_) => "a number"  
    case Var(_)      => "a variable"  
}
```

Annotations are described in [Chapter 27](#). In general, you can add an annotation to an expression in the same way you add a type: follow the expression with a colon and the name of the annotation (preceded by an at sign). For example, in this case you add an `@unchecked` annotation to the variable `e`, with “`e: @unchecked`”. The `@unchecked` annotation has a special meaning for pattern matching. If a `match`’s selector expression carries this annotation, exhaustivity checking for the patterns that follow will be suppressed.

15.6 The Option type

Scala has a standard type named `Option` for optional values. Such a value can be of two forms: `Some(x)`, where `x` is the actual value, or the `None` object, which represents a missing value.

Optional values are produced by some of the standard operations on Scala’s collections. For instance, the `get` method of Scala’s `Map` produces `Some(value)` if a value corresponding to a given key has been found, or `None` if the given key is not defined in the `Map`. Here’s an example:

```
scala> val capitals =  
        Map("France" -> "Paris", "Japan" -> "Tokyo")  
capitals: scala.collection.immutable.Map[String,String] =  
Map(France -> Paris, Japan -> Tokyo)  
  
scala> capitals get "France"  
res23: Option[String] = Some(Paris)  
  
scala> capitals get "North Pole"  
res24: Option[String] = None
```

The most common way to take optional values apart is through a pattern match. For instance:

```
scala> def show(x: Option[String]) = x match {
    case Some(s) => s
    case None => "?"
}
show: (x: Option[String])String
scala> show(capitals get "Japan")
res25: String = Tokyo
scala> show(capitals get "France")
res26: String = Paris
scala> show(capitals get "North Pole")
res27: String = ?
```

The `Option` type is used frequently in Scala programs. Compare this to the dominant idiom in Java of using `null` to indicate no value. For example, the `get` method of `java.util.HashMap` returns either a value stored in the `HashMap` or `null` if no value was found. This approach works for Java but is error prone because it is difficult in practice to keep track of which variables in a program are allowed to be `null`.

If a variable is allowed to be `null`, then you must remember to check it for `null` every time you use it. When you forget to check, you open the possibility that a `NullPointerException` may result at runtime. Because such exceptions may not happen very often, it can be difficult to discover the bug during testing. For Scala, the approach would not work at all because it is possible to store value types in hash maps, and `null` is not a legal element for a value type. For instance, a `HashMap[Int, Int]` cannot return `null` to signify “no element.”

By contrast, Scala encourages the use of `Option` to indicate an optional value. This approach to optional values has several advantages over Java’s. First, it is far more obvious to readers of code that a variable whose type is `Option[String]` is an optional `String` than a variable of type `String`, which may sometimes be `null`. But most importantly, that programming error described earlier of using a variable that may be `null` without first checking it for `null` becomes a type error in Scala. If a variable is of type `Option[String]` and you try to use it as a `String`, your Scala program will not compile.

15.7 Patterns everywhere

Patterns are allowed in many parts of Scala, not just in standalone `match` expressions. Take a look at some other places you can use patterns.

Patterns in variable definitions

Anytime you define a `val` or a `var`, you can use a pattern instead of a simple identifier. For example, you can take apart a tuple and assign each of its parts to its own variable, as shown in Listing 15.17:

```
scala> val myTuple = (123, "abc")
myTuple: (Int, String) = (123,abc)
scala> val (number, string) = myTuple
number: Int = 123
string: String = abc
```

Listing 15.17 · Defining multiple variables with one assignment.

This construct is quite useful when working with case classes. If you know the precise case class you are working with, then you can deconstruct it with a pattern. Here's an example:

```
scala> val exp = new BinOp("*", Number(5), Number(1))
exp: BinOp = BinOp(*,Number(5.0),Number(1.0))

scala> val BinOp(op, left, right) = exp
op: String = *
left: Expr = Number(5.0)
right: Expr = Number(1.0)
```

Case sequences as partial functions

A sequence of cases (*i.e.*, alternatives) in curly braces can be used anywhere a function literal can be used. Essentially, a case sequence *is* a function literal, only more general. Instead of having a single entry point and list of parameters, a case sequence has multiple entry points, each with their own list of parameters. Each case is an entry point to the function, and the

parameters are specified with the pattern. The body of each entry point is the right-hand side of the case.

Here is a simple example:

```
val withDefault: Option[Int] => Int = {  
    case Some(x) => x  
    case None => 0  
}
```

The body of this function has two cases. The first case matches a Some, and returns the number inside the Some. The second case matches a None, and returns a default value of zero. Here is this function in use:

```
scala> withDefault(Some(10))  
res28: Int = 10  
  
scala> withDefault(None)  
res29: Int = 0
```

This facility is quite useful for the Akka actors library, because it allows its receive method to be defined as a series of cases:

```
var sum = 0  
  
def receive = {  
    case Data(byte) =>  
        sum += byte  
  
    case GetChecksum(requester) =>  
        val checksum = ~(sum & 0xFF) + 1  
        requester ! checksum  
}
```

One other generalization is worth noting: a sequence of cases gives you a *partial* function. If you apply such a function on a value it does not support, it will generate a run-time exception. For example, here is a partial function that returns the second element of a list of integers:

```
val second: List[Int] => Int = {  
    case x :: y :: _ => y  
}
```

When you compile this, the compiler will correctly warn that the match is not exhaustive:

```
<console>:17: warning: match is not exhaustive!
  missing combination           Nil
```

This function will succeed if you pass it a three-element list, but not if you pass it an empty list:

```
scala> second(List(5, 6, 7))
res24: Int = 6

scala> second(List())
scala.MatchError: List()
    at $anonfun$1.apply(<console>:17)
    at $anonfun$1.apply(<console>:17)
```

If you want to check whether a partial function is defined, you must first tell the compiler that you know you are working with partial functions. The type `List[Int] => Int` includes all functions from lists of integers to integers, whether or not the functions are partial. The type that only includes *partial* functions from lists of integers to integers is written `PartialFunction[List[Int], Int]`. Here is the `second` function again, this time written with a partial function type:

```
val second: PartialFunction[List[Int], Int] = {
  case x :: y :: _ => y
}
```

Partial functions have a method `isDefinedAt`, which can be used to test whether the function is defined at a particular value. In this case, the function is defined for any list that has at least two elements:

```
scala> second.isDefinedAt(List(5,6,7))
res30: Boolean = true

scala> second.isDefinedAt(List())
res31: Boolean = false
```

The typical example of a partial function is a pattern matching function literal like the one in the previous example. In fact, such an expression gets

translated by the Scala compiler to a partial function by translating the patterns twice—once for the implementation of the real function, and once to test whether the function is defined or not.

For instance, the function literal `{ case x :: y :: _ => y }` gets translated to the following partial function value:

```
new PartialFunction[List[Int], Int] {  
    def apply(xs: List[Int]) = xs match {  
        case x :: y :: _ => y  
    }  
    def isDefinedAt(xs: List[Int]) = xs match {  
        case x :: y :: _ => true  
        case _ => false  
    }  
}
```

This translation takes effect whenever the declared type of a function literal is `PartialFunction`. If the declared type is just `Function1`, or is missing, the function literal is instead translated to a *complete function*.

In general, you should try to work with complete functions whenever possible, because using partial functions allows for runtime errors that the compiler cannot help you with. Sometimes partial functions are really helpful though. You might be sure that an unhandled value will never be supplied. Alternatively, you might be using a framework that expects partial functions and so will always check `isDefinedAt` before calling the function. An example of the latter is the `react` example given above, where the argument is a partially defined function, defined precisely for those messages that the caller wants to handle.

Patterns in for expressions

You can also use a pattern in a `for` expression, as shown in Listing 15.18. This `for` expression retrieves all key/value pairs from the `capitals` map. Each pair is matched against the pattern `(country, city)`, which defines the two variables `country` and `city`.

The pair pattern shown in Listing 15.18 was special because the match against it can never fail. Indeed, `capitals` yields a sequence of pairs, so you can be sure that every generated pair can be matched against a pair pattern.

```
scala> for ((country, city) <- capitals)
           println("The capital of " + country + " is " + city)
The capital of France is Paris
The capital of Japan is Tokyo
```

Listing 15.18 · A for expression with a tuple pattern.

But it is equally possible that a pattern might not match a generated value. Listing 15.19 shows an example where that is the case.

```
scala> val results = List(Some("apple"), None,
           Some("orange"))
results: List[Option[String]] = List(Some(apple), None,
Some(orange))

scala> for (Some(fruit) <- results) println(fruit)
apple
orange
```

Listing 15.19 · Picking elements of a list that match a pattern.

As you can see from this example, generated values that do not match the pattern are discarded. For instance, the second element `None` in the `results` list does not match the pattern `Some(fruit)`; therefore it does not show up in the output.

15.8 A larger example

After having learned the different forms of patterns, you might be interested in seeing them applied in a larger example. The proposed task is to write an expression formatter class that displays an arithmetic expression in a two-dimensional layout. Divisions such as “ $x / (x + 1)$ ” should be printed vertically, by placing the numerator on top of the denominator, like this:

$$\frac{x}{x + 1}$$

As another example, here's the expression $((a / (b * c) + 1 / n) / 3)$ in two dimensional layout:

$$\begin{array}{rcl} a & & 1 \\ \hline b * c & n & \\ \hline & & 3 \end{array}$$

From these examples it looks like the class (we'll call it `ExprFormatter`) will have to do a fair bit of layout juggling, so it makes sense to use the layout library developed in [Chapter 10](#). We'll also use the `Expr` family of case classes you saw previously in this chapter, and place both [Chapter 10](#)'s layout library and this chapter's expression formatter into named packages. The full code for the example will be shown in [Listings 15.20](#) and [15.21](#).

A useful first step is to concentrate on horizontal layout. A structured expression like:

```
BinOp("+",
      BinOp("*",
            BinOp("+", Var("x"), Var("y")),
            Var("z")),
      Number(1))
```

should print $(x + y) * z + 1$. Note that parentheses are mandatory around $x + y$, but would be optional around $(x + y) * z$. To keep the layout as legible as possible, your goal should be to omit parentheses wherever they are redundant, while ensuring that all necessary parentheses are present.

To know where to put parentheses, the code needs to know about the relative precedence of each operator, so it's a good idea to tackle this first. You could express the relative precedence directly as a map literal of the following form:

```
Map(
  "| " -> 0, "||" -> 0,
  "&" -> 1, "&&" -> 1, ...
)
```

However, this would involve some amount of pre-computation of precedences on your part. A more convenient approach is to just define groups

of operators of increasing precedence and then calculate the precedence of each operator from that. [Listing 15.20](#) shows the code.

The precedence variable is a map from operators to their precedences, which are integers starting with 0. It is calculated using a for expression with two generators. The first generator produces every index i of the `opGroups` array. The second generator produces every operator `op` in `opGroups(i)`. For each such operator the for expression yields an association from the operator `op` to its index i . Hence, the relative position of an operator in the array is taken to be its precedence.

Associations are written with an infix arrow, *e.g.*, `op -> i`. So far you have seen associations only as part of map constructions, but they are also values in their own right. In fact, the association `op -> i` is nothing else but the pair `(op, i)`.

Now that you have fixed the precedence of all binary operators except `/`, it makes sense to generalize this concept to also cover unary operators. The precedence of a unary operator is higher than the precedence of every binary operator. Thus we can set `unaryPrecedence` (shown in [Listing 15.20](#)) to the length of the `opGroups` array, which is one more than the precedence of the `*` and `%` operators. The precedence of a fraction is treated differently from the other operators because fractions use vertical layout. However, it will prove convenient to assign to the division operator the special precedence value `-1`, so we'll initialize `fractionPrecedence` to `-1` (shown in [Listing 15.20](#)).

After these preparations, you are ready to write the main `format` method. This method takes two arguments: an expression `e`, of type `Expr`, and the precedence `enclPrec` of the operator directly enclosing the expression `e`. (If there's no enclosing operator, `enclPrec` should be zero.) The method yields a layout element that represents a two-dimensional array of characters.

[Listing 15.21](#) shows the remainder of class `ExprFormatter`, which includes three methods. The first method, `stripDot`, is a helper method. The next method, the private `format` method, does most of the work to format expressions. The last method, also named `format`, is the lone public method in the library, which takes an expression to format. The private `format` method does its work by performing a pattern match on the kind of expression. The match expression has five cases. We'll discuss each case individually.

```
package org.stairwaybook.expr
import org.stairwaybook.layout.Element.elem

sealed abstract class Expr
case class Var(name: String) extends Expr
case class Number(num: Double) extends Expr
case class UnOp(operator: String, arg: Expr) extends Expr
case class BinOp(operator: String,
                  left: Expr, right: Expr) extends Expr

class ExprFormatter {

    // Contains operators in groups of increasing precedence
    private val opGroups =
        Array(
            Set("|", "|"),
            Set("&", "&&"),
            Set("^"),
            Set("==", "!="),
            Set("<", "<=", ">", ">="),
            Set("+", "-"),
            Set("*", "%")
        )

    // A mapping from operators to their precedence
    private val precedence = {
        val assocs =
            for {
                i <- 0 until opGroups.length
                op <- opGroups(i)
            } yield op -> i
        assocs.toMap
    }

    private val unaryPrecedence = opGroups.length
    private val fractionPrecedence = -1

    // continued in Listing 15.21...
}
```

Listing 15.20 · The top half of the expression formatter.

```
// ...continued from Listing 15.20
import org.stairwaybook.layout.Element
private def format(e: Expr, enclPrec: Int): Element =
  e match {
    case Var(name) =>
      elem(name)
    case Number(num) =>
      def stripDot(s: String) =
        if (s endsWith ".0") s.substring(0, s.length - 2)
        else s
      elem(stripDot(num.toString()))
    case UnOp(op, arg) =>
      elem(op) beside format(arg, unaryPrecedence)
    case BinOp("/", left, right) =>
      val top = format(left, fractionPrecedence)
      val bot = format(right, fractionPrecedence)
      val line = elem('—', top.width max bot.width, 1)
      val frac = top above line above bot
      if (enclPrec != fractionPrecedence) frac
      else elem(" ") beside frac beside elem(" ")
    case BinOp(op, left, right) =>
      val opPrec = precedence(op)
      val l = format(left, opPrec)
      val r = format(right, opPrec + 1)
      val oper = l beside elem(" " + op + " ") beside r
      if (enclPrec <= opPrec) oper
      else elem("(") beside oper beside elem(")")
  }
  def format(e: Expr): Element = format(e, 0)
}
```

Listing 15.21 · The bottom half of the expression formatter.

The first case is:

```
case Var(name) =>
    elem(name)
```

If the expression is a variable, the result is an element formed from the variable's name.

The second case is:

```
case Number(num) =>
    def stripDot(s: String) =
        if (s endsWith ".0") s.substring(0, s.length - 2)
        else s
    elem(stripDot(num.toString))
```

If the expression is a number, the result is an element formed from the number's value. The `stripDot` function cleans up the display of a floating-point number by stripping any ".0" suffix from a string.

The third case is:

```
case UnOp(op, arg) =>
    elem(op) beside format(arg, unaryPrecedence)
```

If the expression is a unary operation `UnOp(op, arg)` the result is formed from the operation `op` and the result of formatting the argument `arg` with the highest-possible environment precedence.⁴ This means that if `arg` is a binary operation (but not a fraction) it will always be displayed in parentheses.

The fourth case is:

```
case BinOp("/", left, right) =>
    val top = format(left, fractionPrecedence)
    val bot = format(right, fractionPrecedence)
    val line = elem('—', top.width max bot.width, 1)
    val frac = top above line above bot
    if (enclPrec != fractionPrecedence) frac
    else elem(" ") beside frac beside elem(" ")
```

⁴The value of `unaryPrecedence` is the highest possible precedence, because it was initialized to one more than the precedence of the * and % operators.

If the expression is a fraction, an intermediate result `frac` is formed by placing the formatted operands `left` and `right` on top of each other, separated by an horizontal line element. The width of the horizontal line is the maximum of the widths of the formatted operands. This intermediate result is also the final result unless the fraction appears itself as an argument of another fraction. In the latter case, a space is added on each side of `frac`. To see the reason why, consider the expression “ $(a / b) / c$ ”.

Without the widening correction, formatting this expression would give:

a
—
b
—
c

The problem with this layout is evident—it’s not clear where the top-level fractional bar is. The expression above could mean either “ $(a / b) / c$ ” or “ $a / (b / c)$ ”. To disambiguate, a space should be added on each side to the layout of the nested fraction “ a / b ”.

Then the layout becomes unambiguous:

a
—
b

c

The fifth and last case is:

```
case BinOp(op, left, right) =>
  val opPrec = precedence(op)
  val l = format(left, opPrec)
  val r = format(right, opPrec + 1)
  val oper = l beside elem(" " + op + " ") beside r
  if (enclPrec <= opPrec) oper
  else elem("(") beside oper beside elem(")")
```

This case applies for all other binary operations. Since it comes after the case starting with:

```
case BinOp("/", left, right) => ...
```

you know that the operator op in the pattern `BinOp(op, left, right)` cannot be a division. To format such a binary operation, one needs to format first its operands `left` and `right`. The precedence parameter for formatting the left operand is the precedence `opPrec` of the operator `op`, while for the right operand it is one more than that. This scheme ensures that parentheses also reflect the correct associativity.

For instance, the operation:

```
BinOp("-", Var("a"), BinOp("-", Var("b"), Var("c"))))
```

would be correctly parenthesized as “`a - (b - c)`”. The intermediate result `oper` is then formed by placing the formatted left and right operands side-by-side, separated by the operator. If the precedence of the current operator is smaller than the precedence of the enclosing operator, `oper` is placed between parentheses; otherwise, it is returned as is.

```
import org.stairwaybook.expr._

object Express extends App {

    val f = new ExprFormatter

    val e1 = BinOp("*", BinOp("/", Number(1), Number(2)),
                  BinOp("+", Var("x"), Number(1)))

    val e2 = BinOp("+", BinOp("/", Var("x"), Number(2)),
                  BinOp("/", Number(1.5), Var("x")))

    val e3 = BinOp("/", e1, e2)

    def show(e: Expr) = println(f.format(e)+ "\n\n")

    for (e <- Array(e1, e2, e3)) show(e)
}
```

Listing 15.22 · An application that prints formatted expressions.

This finishes the design of the private `format` function. The only remaining method is the public `format` method, which allows client programmers to format a top-level expression without passing a precedence argument. [Listing 15.22](#) shows a demo program that exercises `ExprFormatter`.

Note that, even though this program does not define a `main` method, it is still a runnable application because it inherits from the `App` trait. You can run the `Express` program with the command:

```
scala Express
```

This will give the following output:

```
1
- * (x + 1)
2
```

```
x 1.5
- + ---
2 x
```

```
1
- * (x + 1)
2
-----
x 1.5
- + ---
2 x
```

15.9 Conclusion

In this chapter, you learned about Scala’s case classes and pattern matching in detail. By using them, you can take advantage of several concise idioms not normally available in object-oriented languages. However, Scala’s pattern matching goes further than this chapter describes. If you want to use pattern matching on one of your classes, but you do not want to open access to your classes the way case classes do, you can use the *extractors* described in [Chapter 26](#). In the next chapter, we’ll turn our attention to lists.

Chapter 16

Working with Lists

Lists are probably the most commonly used data structure in Scala programs. This chapter explains lists in detail. We will present many common operations that can be performed on lists. We'll also cover some important design principles for programs working on lists.

16.1 List literals

You saw lists already in the preceding chapters, so you know that a list containing the elements 'a', 'b', and 'c' is written `List('a', 'b', 'c')`. Here are some other examples:

```
val fruit = List("apples", "oranges", "pears")
val nums = List(1, 2, 3, 4)
val diag3 =
  List(
    List(1, 0, 0),
    List(0, 1, 0),
    List(0, 0, 1)
  )
val empty = List()
```

Lists are quite similar to arrays, but there are two important differences. First, lists are immutable. That is, elements of a list cannot be changed by assignment. Second, lists have a recursive structure (*i.e.*, a *linked list*)¹, whereas arrays are flat.

¹For a graphical depiction of the structure of a `List`, see [Figure 22.2 on page 504](#).

16.2 The List type

Like arrays, lists are *homogeneous*: the elements of a list all have the same type. The type of a list that has elements of type T is written `List[T]`. For instance, here are the same four lists with explicit types added:

```
val fruit: List[String] = List("apples", "oranges", "pears")
val nums: List[Int] = List(1, 2, 3, 4)
val diag3: List[List[Int]] =
  List(
    List(1, 0, 0),
    List(0, 1, 0),
    List(0, 0, 1)
  )
val empty: List[Nothing] = List()
```

The list type in Scala is *covariant*. This means that for each pair of types S and T, if S is a subtype of T, then `List[S]` is a subtype of `List[T]`. For instance, `List[String]` is a subtype of `List[Object]`. This is natural because every list of strings can also be seen as a list of objects.²

Note that the empty list has type `List[Nothing]`. You saw in [Section 11.3](#) that `Nothing` is the bottom type in Scala's class hierarchy. It is a subtype of every other Scala type. Because lists are covariant, it follows that `List[Nothing]` is a subtype of `List[T]` for any type T. So the empty list object, which has type `List[Nothing]`, can also be seen as an object of every other list type of the form `List[T]`. That's why it is permissible to write code like:

```
// List() is also of type List[String]!
val xs: List[String] = List()
```

16.3 Constructing lists

All lists are built from two fundamental building blocks, `Nil` and `::` (pronounced “cons”). `Nil` represents the empty list. The infix operator, `::`, expresses list extension at the front. That is, `x :: xs` represents a list whose

²[Chapter 19](#) gives more details on covariance and other kinds of variance.

first element is `x`, followed by (the elements of) list `xs`. Hence, the previous list values could also have been defined as follows:

```
val fruit = "apples" :: ("oranges" :: ("pears" :: Nil))
val nums  = 1 :: (2 :: (3 :: (4 :: Nil)))
val diag3 = (1 :: (0 :: (0 :: Nil))) :: 
             (0 :: (1 :: (0 :: Nil))) :: 
             (0 :: (0 :: (1 :: Nil))) :: Nil
val empty = Nil
```

In fact the previous definitions of `fruit`, `nums`, `diag3`, and `empty` in terms of `List(...)` are just wrappers that expand to these definitions. For instance, `List(1, 2, 3)` creates the list `1 :: (2 :: (3 :: Nil))`.

Because it ends in a colon, the `::` operation associates to the right: `A :: B :: C` is interpreted as `A :: (B :: C)`. Therefore, you can drop the parentheses in the previous definitions. For instance:

```
val nums = 1 :: 2 :: 3 :: 4 :: Nil
```

is equivalent to the previous definition of `nums`.

16.4 Basic operations on lists

All operations on lists can be expressed in terms of the following three:

<code>head</code>	returns the first element of a list
<code>tail</code>	returns a list consisting of all elements except the first
<code>isEmpty</code>	returns <code>true</code> if the list is empty

These operations are defined as methods of class `List`. Some examples are shown in [Table 16.1](#). The `head` and `tail` methods are defined only for non-empty lists. When selected from an empty list, they throw an exception:

```
scala> Nil.head
java.util.NoSuchElementException: head of empty list
```

As an example of how lists can be processed, consider sorting the elements of a list of numbers into ascending order. One simple way to do so is *insertion sort*, which works as follows: To sort a non-empty list `x :: xs`, sort the remainder `xs` and insert the first element `x` at the right position in the result.

Table 16.1 · Basic list operations

What it is	What it does
<code>empty.isEmpty</code>	returns true
<code>fruit.isEmpty</code>	returns false
<code>fruit.head</code>	returns "apples"
<code>fruit.tail.head</code>	returns "oranges"
<code>diag3.head</code>	returns <code>List(1, 0, 0)</code>

Sorting an empty list yields the empty list. Expressed as Scala code, the insertion sort algorithm looks like:

```
def isort(xs: List[Int]): List[Int] =
  if (xs.isEmpty) Nil
  else insert(xs.head, isort(xs.tail))

def insert(x: Int, xs: List[Int]): List[Int] =
  if (xs.isEmpty || x <= xs.head) x :: xs
  else xs.head :: insert(x, xs.tail)
```

16.5 List patterns

Lists can also be taken apart using pattern matching. List patterns correspond one-by-one to list expressions. You can either match on all elements of a list using a pattern of the form `List(...)`, or you take lists apart bit by bit using patterns composed from the `::` operator and the `Nil` constant.

Here's an example of the first kind of pattern:

```
scala> val List(a, b, c) = fruit
a: String = apples
b: String = oranges
c: String = pears
```

The pattern `List(a, b, c)` matches lists of length 3, and binds the three elements to the pattern variables `a`, `b`, and `c`. If you don't know the number of list elements beforehand, it's better to match with `::` instead. For instance, the pattern `a :: b :: rest` matches lists of length 2 or greater:

About pattern matching on Lists

If you review the possible forms of patterns explained in [Chapter 15](#), you might find that neither `List(...)` nor `::` look like it fits the kinds of patterns defined there. In fact, `List(...)` is an instance of a library-defined *extractor* pattern. Such patterns will be discussed in [Chapter 26](#). The “cons” pattern `x :: xs` is a special case of an infix operation pattern. As an expression, an infix operation is equivalent to a method call. For patterns, the rules are different: As a pattern, an infix operation such as `p op q` is equivalent to `op(p, q)`. That is, the infix operator `op` is treated as a constructor pattern. In particular, a cons pattern such as `x :: xs` is treated as `::(x, xs)`.

This hints that there should be a class named `::` that corresponds to the pattern constructor. Indeed, there is such a class—it is named `scala.::` and is exactly the class that builds non-empty lists. So `::` exists twice in Scala, once as a name of a class in package `scala` and again as a method in class `List`. The effect of the method `::` is to produce an instance of the class `scala.::`. You’ll find out more details about how the `List` class is implemented in [Chapter 22](#).

```
scala> val a :: b :: rest = fruit
a: String = apples
b: String = oranges
rest: List[String] = List(pears)
```

Taking lists apart with patterns is an alternative to taking them apart with the basic methods `head`, `tail`, and `isEmpty`. For instance, here’s insertion sort again, this time written with pattern matching:

```
def isort(xs: List[Int]): List[Int] = xs match {
  case List()    => List()
  case x :: xs1 => insert(x, isort(xs1))
}

def insert(x: Int, xs: List[Int]): List[Int] = xs match {
  case List()  => List(x)
  case y :: ys => if (x <= y) x :: xs
                  else y :: insert(x, ys)
}
```

Often, pattern matching over lists is clearer than decomposing them with methods, so pattern matching should be a part of your list processing toolbox.

This is all you need to know about lists in Scala to use them correctly. However, there are also a large number of methods that capture common patterns of operations over lists. These methods make list processing programs more concise and often clearer. The next two sections present the most important methods defined in the `List` class.

16.6 First-order methods on class `List`

This section explains most first-order methods defined in the `List` class. A method is *first-order* if it does not take any functions as arguments. We will also introduce some recommended techniques to structure programs that operate on lists by using two examples.

Concatenating two lists

An operation similar to `::` is list concatenation, written `::::`. Unlike `::`, `::::` takes two lists as operands. The result of `xs :::: ys` is a new list that contains all the elements of `xs`, followed by all the elements of `ys`.

Here are some examples:

```
scala> List(1, 2) :::: List(3, 4, 5)
res0: List[Int] = List(1, 2, 3, 4, 5)

scala> List() :::: List(1, 2, 3)
res1: List[Int] = List(1, 2, 3)

scala> List(1, 2, 3) :::: List(4)
res2: List[Int] = List(1, 2, 3, 4)
```

Like cons, list concatenation associates to the right. An expression like this:

```
xs :::: ys :::: zs
```

is interpreted like this:

```
xs :::: (ys :::: zs)
```

The Divide and Conquer principle

Concatenation (`:::`) is implemented as a method in class `List`. It would also be possible to implement concatenation “by hand,” using pattern matching on lists. It’s instructive to try to do that yourself, because it shows a common way to implement algorithms using lists. First, we’ll settle on a signature for the concatenation method, which we’ll call `append`. In order not to mix things up too much, assume that `append` is defined outside the `List` class, so it will take the two lists to be concatenated as parameters. These two lists must agree on their element type, but that element type can be arbitrary. This can be expressed by giving `append` a type parameter³ that represents the element type of the two input lists:

```
def append[T](xs: List[T], ys: List[T]): List[T]
```

To design the implementation of `append`, it pays to remember the “divide and conquer” design principle for programs over recursive data structures such as lists. Many algorithms over lists first split an input list into simpler cases using a pattern match. That’s the *divide* part of the principle. They then construct a result for each case. If the result is a non-empty list, some of its parts may be constructed by recursive invocations of the same algorithm. That’s the *conquer* part of the principle.

To apply this principle to the implementation of the `append` method, the first question to ask is on which list to match. This is less trivial in the case of `append` than for many other methods because there are two choices. However, the subsequent “conquer” phase tells you that you need to construct a list consisting of all elements of both input lists. Since lists are constructed from the back towards the front, `ys` can remain intact, whereas `xs` will need to be taken apart and prepended to `ys`. Thus, it makes sense to concentrate on `xs` as a source for a pattern match. The most common pattern match over lists simply distinguishes an empty from a non-empty list. So this gives the following outline of an `append` method:

```
def append[T](xs: List[T], ys: List[T]): List[T] =  
  xs match {  
    case List() => ???  
    case x :: xs1 => ???  
  }
```

³Type parameters will be explained in more detail in Chapter 19.

All that remains is to fill in the two places marked with ???.⁴ The first such place is the alternative where the input list `xs` is empty. In this case concatenation yields the second list:

```
case List() => ys
```

The second place left open is the alternative where the input list `xs` consists of some head `x` followed by a tail `xs1`. In this case the result is also a non-empty list. To construct a non-empty list you need to know what the head and the tail of that list should be. You know that the first element of the result list is `x`. As for the remaining elements, these can be computed by appending the second list, `ys`, to the rest of the first list, `xs1`.

This completes the design and gives:

```
def append[T](xs: List[T], ys: List[T]): List[T] =  
  xs match {  
    case List() => ys  
    case x :: xs1 => x :: append(xs1, ys)  
  }
```

The computation of the second alternative illustrated the “conquer” part of the divide and conquer principle: Think first what the shape of the desired output should be, then compute the individual parts of that shape, using recursive invocations of the algorithm where appropriate. Finally, construct the output from these parts.

Taking the length of a list: `length`

The `length` method computes the length of a list.

```
scala> List(1, 2, 3).length  
res3: Int = 3
```

On lists, unlike arrays, `length` is a relatively expensive operation. It needs to traverse the whole list to find its end, and therefore takes time proportional to the number of elements in the list. That’s why it’s not a good idea to replace a test such as `xs.isEmpty` by `xs.length == 0`. The result of the two tests is equivalent, but the second one is slower, in particular if the list `xs` is long.

⁴The `???` method, which throws `scala.NotImplementedError` and has result type `Nothing`, can be used as a temporary implementation during development.

Accessing the end of a list: `init` and `last`

You know already the basic operations `head` and `tail`, which respectively take the first element of a list, and the rest of the list except the first element. They each have a dual operation: `last` returns the last element of a (non-empty) list, whereas `init` returns a list consisting of all elements except the last one:

```
scala> val abcde = List('a', 'b', 'c', 'd', 'e')
abcde: List[Char] = List(a, b, c, d, e)

scala> abcde.last
res4: Char = e

scala> abcde.init
res5: List[Char] = List(a, b, c, d)
```

Like `head` and `tail`, these methods throw an exception when applied to an empty list:

```
scala> List().init
java.lang.UnsupportedOperationException: Nil.init
      at scala.List.init(List.scala:544)
      at ...

scala> List().last
java.util.NoSuchElementException: Nil.last
      at scala.List.last(List.scala:563)
      at ...
```

Unlike `head` and `tail`, which both run in constant time, `init` and `last` need to traverse the whole list to compute their result. As a result, they take time proportional to the length of the list.

It's a good idea to organize your data so that most accesses are at the head of a list, rather than the last element.

Reversing lists: reverse

If at some point in the computation an algorithm demands frequent accesses to the end of a list, it's sometimes better to reverse the list first and work with the result instead. Here's how to do the reversal:

```
scala> abcde.reverse
res6: List[Char] = List(e, d, c, b, a)
```

Like all other list operations, `reverse` creates a new list rather than changing the one it operates on. Since lists are immutable, such a change would not be possible anyway. To verify this, check that the original value of `abcde` is unchanged after the `reverse` operation:

```
scala> abcde
res7: List[Char] = List(a, b, c, d, e)
```

The `reverse`, `init`, and `last` operations satisfy some laws that can be used for reasoning about computations and for simplifying programs.

1. `reverse` is its own inverse:

```
xs.reverse.reverse equals xs
```

2. `reverse` turns `init` to `tail` and `last` to `head`, except that the elements are reversed:

```
xs.reverse.init equals xs.tail.reverse
xs.reverse.tail equals xs.init.reverse
xs.reverse.head equals xs.last
xs.reverse.last equals xs.head
```

Reverse could be implemented using concatenation (`:::`), like in the following method, `rev`:

```
def rev[T](xs: List[T]): List[T] = xs match {
  case List() => xs
  case x :: xs1 => rev(xs1) :: List(x)
}
```

However, this method is less efficient than one would hope for. To study the complexity of `rev`, assume that the list `xs` has length n . Notice that there are n recursive calls to `rev`. Each call except the last involves a list concatenation. List concatenation `xs :: ys` takes time proportional to the length of its first argument `xs`. Hence, the total complexity of `rev` is:

$$n + (n - 1) + \dots + 1 = (1 + n) * n / 2$$

In other words, `rev`'s complexity is quadratic in the length of its input argument. This is disappointing when compared to the standard reversal of a mutable, linked list, which has linear complexity. However, the current implementation of `rev` is not the best implementation possible. In the example starting on [page 363](#), you will see how to speed it up.

Prefixes and suffixes: `drop`, `take`, and `splitAt`

The `drop` and `take` operations generalize `tail` and `init` in that they return arbitrary prefixes or suffixes of a list. The expression “`xs take n`” returns the first n elements of the list `xs`. If n is greater than `xs.length`, the whole list `xs` is returned. The operation “`xs drop n`” returns all elements of the list `xs`, except for the first n ones. If n is greater than `xs.length`, the empty list is returned.

The `splitAt` operation splits the list at a given index, returning a pair of two lists.⁵ It is defined by the equality:

$$\text{xs splitAt } n \text{ equals } (\text{xs take } n, \text{xs drop } n)$$

However, `splitAt` avoids traversing the list `xs` twice. Here are some examples of these three methods:

```
scala> abcde take 2
res8: List[Char] = List(a, b)
scala> abcde drop 2
res9: List[Char] = List(c, d, e)
scala> abcde splitAt 2
res10: (List[Char], List[Char]) = (List(a, b), List(c, d, e))
```

⁵As mentioned in [Section 10.12](#), the term *pair* is an informal name for `Tuple2`.

Element selection: apply and indices

Random element selection is supported through the `apply` method; however it is a less common operation for lists than it is for arrays.

```
scala> abcde apply 2 // rare in Scala
res11: Char = c
```

As for all other types, `apply` is implicitly inserted when an object appears in the function position in a method call. So the line above can be shortened to:

```
scala> abcde(2)      // rare in Scala
res12: Char = c
```

One reason why random element selection is less popular for lists than for arrays is that `xs(n)` takes time proportional to the index `n`. In fact, `apply` is simply defined by a combination of `drop` and `head`:

$$\text{xs apply } n \text{ equals } (\text{xs drop } n).\text{head}$$

This definition also makes clear that list indices range from 0 up to the length of the list minus one, the same as for arrays. The `indices` method returns a list consisting of all valid indices of a given list:

```
scala> abcde.indices
res13: scala.collection.immutable.Range
= Range(0, 1, 2, 3, 4)
```

Flattening a list of lists: flatten

The `flatten` method takes a list of lists and flattens it out to a single list:

```
scala> List(List(1, 2), List(3), List(), List(4, 5)).flatten
res14: List[Int] = List(1, 2, 3, 4, 5)
scala> fruit.map(_.toCharArray).flatten
res15: List[Char] = List(a, p, p, l, e, s, o, r, a, n, g, e,
s, p, e, a, r, s)
```

It can only be applied to lists whose elements are all lists. Trying to flatten any other list will give a compilation error:

```
scala> List(1, 2, 3).flatten
<console>:8: error: No implicit view available from Int =>
  scala.collection.GenTraversableOnce[B].
                                         ^
                                         List(1, 2, 3).flatten
```

Zipping lists: `zip` and `unzip`

The `zip` operation takes two lists and forms a list of pairs:

```
scala> abcde.indices zip abcde
res17: scala.collection.immutable.IndexedSeq[(Int, Char)] =
Vector((0,a), (1,b), (2,c), (3,d), (4,e))
```

If the two lists are of different length, any unmatched elements are dropped:

```
scala> val zipped = abcde zip List(1, 2, 3)
zipped: List[(Char, Int)] = List((a,1), (b,2), (c,3))
```

A useful special case is to zip a list with its index. This is done most efficiently with the `zipWithIndex` method, which pairs every element of a list with the position where it appears in the list.

```
scala> abcde.zipWithIndex
res18: List[(Char, Int)] = List((a,0), (b,1), (c,2), (d,3),
(e,4))
```

Any list of tuples can also be changed back to a tuple of lists by using the `unzip` method:

```
scala> zipped.unzip
res19: (List[Char], List[Int])
= (List(a, b, c), List(1, 2, 3))
```

The `zip` and `unzip` methods provide one way to operate on multiple lists together. See [Section 16.9](#) for a more concise way to do this.

Displaying lists: `toString` and `mkString`

The `toString` operation returns the canonical string representation of a list:

```
scala> abcde.toString
res20: String = List(a, b, c, d, e)
```

If you want a different representation you can use the `mkString` method. The operation `xs mkString (pre, sep, post)` involves four operands: the list `xs` to be displayed, a prefix string `pre` to be displayed in front of all elements, a separator string `sep` to be displayed between successive elements, and a postfix string `post` to be displayed at the end.

The result of the operation is the string:

```
pre + xs(0) + sep + ... + sep + xs(xs.length - 1) + post
```

The `mkString` method has two overloaded variants that let you drop some or all of its arguments. The first variant only takes a separator string:

```
xs.mkString(sep) equals xs.mkString("", sep, "")
```

The second variant lets you omit all arguments:

```
xs.mkString equals xs.mkString("")
```

Here are some examples:

```
scala> abcde.mkString("[", ", ", "]")
res21: String = [a,b,c,d,e]

scala> abcde.mkString ""
res22: String = abcde

scala> abcde.mkString
res23: String = abcde

scala> abcde.mkString("List(", ", ", ")")
res24: String = List(a, b, c, d, e)
```

There are also variants of the `mkString` methods called `addString` which append the constructed string to a `StringBuilder` object,⁶ rather than returning them as a result:

⁶This is class `scala.StringBuilder`, not `java.lang.StringBuilder`.

```
scala> val buf = new StringBuilder  
buf: StringBuilder =  
scala> abcde addString (buf, "(", ";", ")")  
res25: StringBuilder = (a;b;c;d;e)
```

The `mkString` and `addString` methods are inherited from `List`'s super trait `Traversable`, so they are applicable to all other collections as well.

Converting lists: `iterator`, `toArray`, `copyToArray`

To convert data between the flat world of arrays and the recursive world of lists, you can use method `toArray` in class `List` and `toList` in class `Array`:

```
scala> val arr = abcde.toArray  
arr: Array[Char] = Array(a, b, c, d, e)  
scala> arr.toList  
res26: List[Char] = List(a, b, c, d, e)
```

There's also a method `copyToArray`, which copies list elements to successive array positions within some destination array. The operation:

```
xs copyToArray (arr, start)
```

copies all elements of the list `xs` to the array `arr`, beginning with position `start`. You must ensure that the destination array `arr` is large enough to hold the list in full. Here's an example:

```
scala> val arr2 = new Array[Int](10)  
arr2: Array[Int] = Array(0, 0, 0, 0, 0, 0, 0, 0, 0, 0)  
scala> List(1, 2, 3) copyToArray (arr2, 3)  
scala> arr2  
res28: Array[Int] = Array(0, 0, 0, 1, 2, 3, 0, 0, 0, 0)
```

Finally, if you need to access list elements via an iterator, you can use the `iterator` method:

```
scala> val it = abcde.iterator  
it: Iterator[Char] = non-empty iterator
```

```
scala> it.next
res29: Char = a
scala> it.next
res30: Char = b
```

Example: Merge sort

The insertion sort presented earlier is concise to write, but it is not very efficient. Its average complexity is proportional to the square of the length of the input list. A more efficient algorithm is *merge sort*.

The fast track

This example provides another illustration of the divide and conquer principle and currying, as well as a useful discussion of algorithmic complexity. If you prefer to move a bit faster on your first pass through this book, however, you can safely skip to [Section 16.7](#).

Merge sort works as follows: First, if the list has zero or one elements, it is already sorted, so the list can be returned unchanged. Longer lists are split into two sub-lists, each containing about half the elements of the original list. Each sub-list is sorted by a recursive call to the sort function, and the resulting two sorted lists are then combined in a merge operation.

For a general implementation of merge sort, you want to leave open the type of list elements to be sorted and the function to be used for the comparison of elements. You obtain a function of maximal generality by passing these two items as parameters. This leads to the implementation shown in [Listing 16.1](#).

The complexity of `msort` is order ($n \log(n)$), where n is the length of the input list. To see why, note that splitting a list in two and merging two sorted lists each take time proportional to the length of the argument list(s). Each recursive call of `msort` halves the number of elements in its input, so there are about $\log(n)$ consecutive recursive calls until the base case of lists of length 1 is reached. However, for longer lists each call spawns off two further calls. Adding everything up, we obtain at each of the $\log(n)$ call levels, every element of the original lists takes part in one split operation and one merge operation.

Hence, every call level has a total cost proportional to n . Since there are $\log(n)$ call levels, we obtain an overall cost proportional to $n \log(n)$. That

```
def msort[T](less: (T, T) => Boolean)
  (xs: List[T]): List[T] = {
  def merge(xs: List[T], ys: List[T]): List[T] =
    (xs, ys) match {
      case (Nil, _) => ys
      case (_, Nil) => xs
      case (x :: xs1, y :: ys1) =>
        if (less(x, y)) x :: merge(xs1, ys)
        else y :: merge(xs, ys1)
    }
  val n = xs.length / 2
  if (n == 0) xs
  else {
    val (ys, zs) = xs splitAt n
    merge(msort(less)(ys), msort(less)(zs))
  }
}
```

Listing 16.1 · A merge sort function for Lists.

cost does not depend on the initial distribution of elements in the list, so the worst case cost is the same as the average case cost. This property makes merge sort an attractive algorithm for sorting lists.

Here is an example of how `msort` is used:

```
scala> msort((x: Int, y: Int) => x < y)(List(5, 7, 1, 3))
res31: List[Int] = List(1, 3, 5, 7)
```

The `msort` function is a classical example of the currying concept discussed in Section 9.3. Currying makes it easy to specialize the function for particular comparison functions. Here's an example:

```
scala> val intSort = msort((x: Int, y: Int) => x < y) _
intSort: List[Int] => List[Int] = <function1>
```

The `intSort` variable refers to a function that takes a list of integers and sorts them in numerical order. As described in Section 8.6, an underscore stands for a missing argument list. In this case, the missing argument is the

list that should be sorted. As another example, here's how you could define a function that sorts a list of integers in reverse numerical order:

```
scala> val reverseIntSort = msort((x: Int, y: Int) => x > y) _  
reverseIntSort: (List[Int]) => List[Int] = <function>
```

Because you provided the comparison function already via currying, you now need only provide the list to sort when you invoke the `intSort` or `reverseIntSort` functions. Here are some examples:

```
scala> val mixedInts = List(4, 1, 9, 0, 5, 8, 3, 6, 2, 7)  
mixedInts: List[Int] = List(4, 1, 9, 0, 5, 8, 3, 6, 2, 7)  
scala> intSort(mixedInts)  
res0: List[Int] = List(0, 1, 2, 3, 4, 5, 6, 7, 8, 9)  
scala> reverseIntSort(mixedInts)  
res1: List[Int] = List(9, 8, 7, 6, 5, 4, 3, 2, 1, 0)
```

16.7 Higher-order methods on class List

Many operations over lists have a similar structure. Several patterns appear time and time again. Some examples are: transforming every element of a list in some way, verifying whether a property holds for all elements of a list, extracting from a list elements satisfying a certain criterion, or combining the elements of a list using some operator. In Java, such patterns would usually be expressed by idiomatic combinations of `for` or `while` loops. In Scala, they can be expressed more concisely and directly using higher-order operators,⁷ which are implemented as methods in class `List`. These higher-order operators are discussed in this section.

Mapping over lists: `map`, `flatMap` and `foreach`

The operation `xs map f` takes as operands a list `xs` of type `List[T]` and a function `f` of type `T => U`. It returns the list that results from applying the function `f` to each list element in `xs`. For instance:

⁷By *higher-order operators*, we mean higher-order functions used in operator notation. As mentioned in [Section 9.1](#), a function is “higher-order” if it takes one or more other functions as parameters.

```
scala> List(1, 2, 3) map (_ + 1)
res32: List[Int] = List(2, 3, 4)

scala> val words = List("the", "quick", "brown", "fox")
words: List[String] = List(the, quick, brown, fox)

scala> words map (_.length)
res33: List[Int] = List(3, 5, 5, 3)

scala> words map (_.toList.reverse.mkString)
res34: List[String] = List(eht, kciuq, nworb, xof)
```

The `flatMap` operator is similar to `map`, but it takes a function returning a list of elements as its right operand. It applies the function to each list element and returns the concatenation of all function results. The difference between `map` and `flatMap` is illustrated in the following example:

```
scala> words map (_.toList)
res35: List[List[Char]] = List(List(t, h, e), List(q, u, i,
    c, k), List(b, r, o, w, n), List(f, o, x))

scala> words flatMap (_.toList)
res36: List[Char] = List(t, h, e, q, u, i, c, k, b, r, o, w,
    n, f, o, x)
```

You see that where `map` returns a list of lists, `flatMap` returns a single list in which all element lists are concatenated.

The differences and interplay between `map` and `flatMap` are also demonstrated by the following expression, which constructs a list of all pairs (i, j) such that $1 \leq j < i < 5$:

```
scala> List.range(1, 5) flatMap (
    i => List.range(1, i) map (j => (i, j))
)
res37: List[(Int, Int)] = List((2,1), (3,1), (3,2), (4,1),
    (4,2), (4,3))
```

`List.range` is a utility method that creates a list of all integers in some range. It is used twice in this example: once to generate a list of integers from 1 (including) until 5 (excluding), and a second time to generate a list of integers from 1 until i , for each value of i taken from the first list. The `map` in this expression generates a list of tuples (i, j) where $j < i$. The outer `flatMap`

in this example generates this list for each `i` between 1 and 5, and then concatenates all the results. Alternatively, the same list can be constructed with a `for` expression:

```
for (i <- List.range(1, 5); j <- List.range(1, i)) yield (i, j)
```

You'll learn more about the interplay of `for` expressions and list operations in [Chapter 23](#).

The third map-like operation is `foreach`. Unlike `map` and `flatMap`, however, `foreach` takes a procedure (a function with result type `Unit`) as right operand. It simply applies the procedure to each list element. The result of the operation itself is again `Unit`; no list of results is assembled. As an example, here is a concise way of summing up all numbers in a list:

```
scala> var sum = 0
sum: Int = 0
scala> List(1, 2, 3, 4, 5) foreach (sum += _)
scala> sum
res39: Int = 15
```

Filtering lists: `filter`, `partition`, `find`, `takeWhile`, `dropWhile`, and `span`

The operation “`xs filter p`” takes as operands a list `xs` of type `List[T]` and a predicate function `p` of type `T => Boolean`. It yields the list of all elements `x` in `xs` for which `p(x)` is true. For instance:

```
scala> List(1, 2, 3, 4, 5) filter (_ % 2 == 0)
res40: List[Int] = List(2, 4)
scala> words filter (_ .length == 3)
res41: List[String] = List(the, fox)
```

The `partition` method is like `filter` but returns a pair of lists. One list contains all elements for which the predicate is true, while the other contains all elements for which the predicate is false. It is defined by the equality:

$$\text{xs partition } p \quad \text{equals} \quad (\text{xs filter } p, \text{xs filter } (!p(_)))$$

Here's an example:

```
scala> List(1, 2, 3, 4, 5) partition (_ % 2 == 0)
res42: (List[Int], List[Int]) = (List(2, 4),List(1, 3, 5))
```

The `find` method is also similar to `filter`, but it returns the first element satisfying a given predicate, rather than all such elements. The operation `xs find p` takes a list `xs` and a predicate `p` as operands. It returns an optional value. If there is an element `x` in `xs` for which `p(x)` is true, `Some(x)` is returned. Otherwise, `p` is false for all elements, and `None` is returned. Here are some examples:

```
scala> List(1, 2, 3, 4, 5) find (_ % 2 == 0)
res43: Option[Int] = Some(2)

scala> List(1, 2, 3, 4, 5) find (_ <= 0)
res44: Option[Int] = None
```

The `takeWhile` and `dropWhile` operators also take a predicate as their right operand. The operation `xs takeWhile p` takes the longest prefix of list `xs` such that every element in the prefix satisfies `p`. Analogously, the operation `xs dropWhile p` removes the longest prefix from list `xs` such that every element in the prefix satisfies `p`. Here are some examples:

```
scala> List(1, 2, 3, -4, 5) takeWhile (_ > 0)
res45: List[Int] = List(1, 2, 3)

scala> words dropWhile (_ startsWith "t")
res46: List[String] = List(quick, brown, fox)
```

The `span` method combines `takeWhile` and `dropWhile` in one operation, just like `splitAt` combines `take` and `drop`. It returns a pair of two lists, defined by the equality:

$$\text{xs span } p \text{ equals } (\text{xs takeWhile } p, \text{xs dropWhile } p)$$

Like `splitAt`, `span` avoids traversing the list `xs` twice:

```
scala> List(1, 2, 3, -4, 5) span (_ > 0)
res47: (List[Int], List[Int]) = (List(1, 2, 3),List(-4, 5))
```

Predicates over lists: `forall` and `exists`

The operation `xs forall p` takes as arguments a list `xs` and a predicate `p`. Its result is true if all elements in the list satisfy `p`. Conversely, the operation `xs exists p` returns true if there is an element in `xs` that satisfies the predicate `p`. For instance, to find out whether a matrix represented as a list of lists has a row with only zeroes as elements:

```
scala> def hasZeroRow(m: List[List[Int]]) =  
        m exists (row => row forall (_ == 0))  
hasZeroRow: (m: List[List[Int]])Boolean  
  
scala> hasZeroRow(diag3)  
res48: Boolean = false
```

Folding lists: `/:` and `:\ \\`

Another common kind of operation combines the elements of a list with some operator. For instance:

$$\text{sum}(\text{List}(a, b, c)) \text{ equals } 0 + a + b + c$$

This is a special instance of a fold operation:

```
scala> def sum(xs: List[Int]): Int = (0 /: xs) (_ + _)  
sum: (xs: List[Int])Int
```

Similarly:

$$\text{product}(\text{List}(a, b, c)) \text{ equals } 1 * a * b * c$$


is a special instance of this fold operation:

```
scala> def product(xs: List[Int]): Int = (1 /: xs) (_ * _)  
product: (xs: List[Int])Int
```

A *fold left* operation “`(z /: xs) (op)`” involves three objects: a start value `z`, a list `xs`, and a binary operation `op`. The result of the fold is `op` applied between successive elements of the list prefixed by `z`. For instance:

$$(z /: \text{List}(a, b, c)) (\text{op}) \text{ equals } \text{op}(\text{op}(\text{op}(z, a), b), c)$$

Or, graphically:



Here's another example that illustrates how `/:` is used. To concatenate all words in a list of strings with spaces between them and in front, you can write this:

```
scala> (" " /: words) (_ + " " + _)
res49: String = " the quick brown fox"
```


This gives an extra space at the beginning. To remove the space, you can use this slight variation:

```
scala> (words.head /: words.tail) (_ + " " + _)
res50: String = the quick brown fox
```

The `/:` operator produces left-leaning operation trees (its syntax with the slash rising forward is intended to be a reflection of that). The operator has `:\
:` as an analog that produces right-leaning trees. For instance:

`(List(a, b, c) :\
z) (op) equals op(a, op(b, op(c, z)))`

Or, graphically:



The `:\
:` operator is pronounced *fold right*. It involves the same three operands as fold left, but the first two appear in reversed order: The first operand is the list to fold, the second is the start value.

For associative operations, fold left and fold right are equivalent, but there might be a difference in efficiency. Consider for instance an operation corresponding to the `flatten` method, which concatenates all elements in a list of lists. This could be implemented with either fold left or fold right:

```
def flattenLeft[T](xss: List[List[T]]) =  
  (List[T]() /: xss) (_ ::: _)  
  
def flattenRight[T](xss: List[List[T]]) =  
  (xss :\ List[T]()) (_ ::: _)
```

Because list concatenation, `xs ::: ys`, takes time proportional to its first argument `xs`, the implementation in terms of fold right in `flattenRight` is more efficient than the fold left implementation in `flattenLeft`. The problem is that `flattenLeft(xss)` copies the first element list `xss.head` $n - 1$ times, where n is the length of the list `xss`.

Note that both versions of `flatten` require a type annotation on the empty list that is the start value of the fold. This is due to a limitation in Scala's type inferencer, which fails to infer the correct type of the list automatically. If you try to leave out the annotation, you get the following:

```
scala> def flattenRight[T](xss: List[List[T]]) =  
        (xss :\ List()) (_ ::: _)  
<console>:8: error: type mismatch;  
   found   : List[T]  
   required: List[Nothing]  
           (xss :\ List()) (_ ::: _)^
```

To find out why the type inferencer goes wrong, you'll need to know about the types of the fold methods and how they are implemented. More on this in [Section 16.10](#).

Lastly, although the `/:` and `:\` operators have the advantage that the direction of the slash resembles the graphical depiction of their respective left or right-leaning trees, and the associativity of the colon character places the start value in the same position in the expression as it is in the tree, some may find the resulting code less than intuitive. If you prefer, you can use the methods named `foldLeft` and `foldRight` instead, which are also defined on class `List`.

Example: List reversal using fold

Earlier in the chapter you saw an implementation of method `reverse`, named `rev`, whose running time was quadratic in the length of the list to be reversed. Here is a different implementation of `reverse` that has linear cost. The idea is to use a fold left operation based on the following scheme:

```
def reverseLeft[T](xs: List[T]) = (startvalue /: xs)(operation)
```

What remains is to fill in the *startvalue* and *operation* parts. In fact, you can try to deduce these parts from some simple examples. To deduce the correct value of *startvalue*, you can start with the smallest possible list, `List()`, and calculate as follows:

```
List()  
  equals (by the properties of reverseLeft)  
reverseLeft(List())  
  equals (by the template for reverseLeft)  
(startvalue /: List())(operation)  
  equals (by the definition of /:)  
  startvalue
```

Hence, *startvalue* must be `List()`. To deduce the second operand, you can pick the next smallest list as an example case. You know already that *startvalue* is `List()`, so you can calculate as follows:

```
List(x)  
  equals (by the properties of reverseLeft)  
reverseLeft(List(x))  
  equals (by the template for reverseLeft, with startvalue = List())  
(List() /: List(x)) (operation)  
  equals (by the definition of /:)  
  operation(List(), x)
```

Hence, `operation(List(), x)` equals `List(x)`, which can also be written as `x :: List()`. This suggests taking as *operation* the `::` operator with its operands exchanged. (This operation is sometimes called “snoc,” in reference to `::`, which is called `cons`.) We arrive then at the following implementation for `reverseLeft`:

```
def reverseLeft[T](xs: List[T]) =  
  (List[T]() /: xs) { (ys, y) => y :: ys}
```

Again, the type annotation in `List[T]()` is needed to make the type inferencer work. If you analyze the complexity of `reverseLeft`, you’ll find that

it applies a constant-time operation (“snoc”) n times, where n is the length of the argument list. Thus, the complexity of `reverseLeft` is linear.

Sorting lists: `sortWith`

The operation `xs sortWith before`, where “`xs`” is a list and “`before`” is a function that can be used to compare two elements, sorts the elements of list `xs`. The expression `x before y` should return `true` if `x` should come before `y` in the intended ordering for the sort. For instance:

```
scala> List(1, -3, 4, 2, 6) sortWith (_ < _)
res51: List[Int] = List(-3, 1, 2, 4, 6)

scala> words sortWith (_.length > _.length)
res52: List[String] = List(quick, brown, the, fox)
```

Note that `sortWith` performs a merge sort similar to the `msort` algorithm shown in the last section. But `sortWith` is a method of class `List`, whereas `msort` is defined outside lists.

16.8 Methods of the `List` object

So far, all operations you have seen in this chapter are implemented as methods of class `List`, so you invoke them on individual list objects. There are also a number of methods in the globally accessible object `scala.List`, which is the companion object of class `List`. Some of these operations are factory methods that create lists. Others are operations that work on lists of some specific shape. Both kinds of methods will be presented in this section.

Creating lists from their elements: `List.apply`

You’ve already seen on several occasions list literals such as `List(1, 2, 3)`. There’s nothing special about their syntax. A literal like `List(1, 2, 3)` is simply the application of the object `List` to the elements 1, 2, 3. That is, it is equivalent to `List.apply(1, 2, 3)`:

```
scala> List.apply(1, 2, 3)
res53: List[Int] = List(1, 2, 3)
```

Creating a range of numbers: `List.range`

The `range` method, which you saw briefly earlier in the discussion of `map` and `flatmap`, creates a list consisting of a range of numbers. Its simplest form is `List.range(from, until)`, which creates a list of all numbers starting at `from` and going up to `until` minus one. So the end value, `until`, does not form part of the range.

There's also a version of `range` that takes a `step` value as third parameter. This operation will yield list elements that are `step` values apart, starting at `from`. The `step` can be positive or negative:

```
scala> List.range(1, 5)
res54: List[Int] = List(1, 2, 3, 4)

scala> List.range(1, 9, 2)
res55: List[Int] = List(1, 3, 5, 7)

scala> List.range(9, 1, -3)
res56: List[Int] = List(9, 6, 3)
```

Creating uniform lists: `List.fill`

The `fill` method creates a list consisting of zero or more copies of the same element. It takes two parameters: the length of the list to be created, and the element to be repeated. Each parameter is given in a separate list:

```
scala> List.fill(5)('a')
res57: List[Char] = List(a, a, a, a, a)

scala> List.fill(3)("hello")
res58: List[String] = List(hello, hello, hello)
```

If `fill` is given more than two arguments, then it will make multi-dimensional lists. That is, it will make lists of lists, lists of lists of lists, etc. The additional arguments go in the first argument list.

```
scala> List.fill(2, 3)('b')
res59: List[List[Char]] = List(List(b, b, b), List(b, b, b))
```

Tabulating a function: `List.tabulate`

The `tabulate` method creates a list whose elements are computed according to a supplied function. Its arguments are just like those of `List.fill`: the first argument list gives the dimensions of the list to create, and the second describes the elements of the list. The only difference is that instead of the elements being fixed, they are computed from a function:

```
scala> val squares = List.tabulate(5)(n => n * n)
squares: List[Int] = List(0, 1, 4, 9, 16)
scala> val multiplication = List.tabulate(5,5) (_ * _)
multiplication: List[List[Int]] = List(List(0, 0, 0, 0, 0),
  List(0, 1, 2, 3, 4), List(0, 2, 4, 6, 8),
  List(0, 3, 6, 9, 12), List(0, 4, 8, 12, 16))
```

Concatenating multiple lists: `List.concat`

The `concat` method concatenates a number of element lists. The lists to be concatenated are supplied as direct arguments to `concat`:

```
scala> List.concat(List('a', 'b'), List('c'))
res60: List[Char] = List(a, b, c)
scala> List.concat(List(), List('b'), List('c'))
res61: List[Char] = List(b, c)
scala> List.concat()
res62: List[Nothing] = List()
```

16.9 Processing multiple lists together

The `zipped` method on tuples generalizes several common operations to work on multiple lists instead of just one. One such operation is `map`. The `map` method for two zipped lists maps pairs of elements rather than individual elements. One pair is for the first element of each list, another pair is for the second element of each list, and so on—as many pairs as the lists are long. Here is an example of its use:

```
scala> (List(10, 20), List(3, 4, 5)).zipped.map(_ * _)
res63: List[Int] = List(30, 80)
```

Notice that the third element of the second list is discarded. The `zipped` method zips up only as many elements as appear in all the lists together. Any extra elements on the end are discarded.

There are also zipped analogs to `exists` and `forall`. They are just like the single-list versions of those methods except they operate on elements from multiple lists instead of just one:

```
scala> (List("abc", "de"), List(3, 2)).zipped.  
       forall(_.length == _)  
res64: Boolean = true  
scala> (List("abc", "de"), List(3, 2)).zipped.  
       exists(_.length != _)  
res65: Boolean = false
```

The fast track

In the next (and final) section of this chapter, we provide insight into Scala's type inference algorithm. If you're not interested in such details right now, you can skip the entire section and go straight to the conclusion on [page 372](#).

16.10 Understanding Scala's type inference algorithm

One difference between the previous uses of `sortWith` and `msort` concerns the admissible syntactic forms of the comparison function.

Compare:

```
scala> msort((x: Char, y: Char) => x > y)(abcde)  
res66: List[Char] = List(e, d, c, b, a)
```

with:

```
scala> abcde sortWith (_ > _)  
res67: List[Char] = List(e, d, c, b, a)
```

The two expressions are equivalent, but the first uses a longer form of comparison function with named parameters and explicit types. The second uses the concise form, `(_ > _)`, where named parameters are replaced by underscores. Of course, you could also use the first, longer form of comparison with `sortWith`.

However, the short form cannot be used with `msort`.

```
scala> msort(_ > _)(abcde)
<console>:12: error: missing parameter type for expanded
  function ((x$1, x$2) => x$1.$greater(x$2))
           msort(_ > _)(abcde)
                           ^
```

To understand why, you need to know some details of Scala's type inference algorithm. Type inference in Scala is flow based. In a method application `m(args)`, the inferencer first checks whether the method `m` has a known type. If it does, that type is used to infer the expected type of the arguments. For instance, in `abcde.sortWith(_ > _)`, the type of `abcde` is `List[Char]`. Hence, `sortWith` is known to be a method that takes an argument of type `(Char, Char) => Boolean` and produces a result of type `List[Char]`. Since the parameter types of the function arguments are known, they need not be written explicitly. With what it knows about `sortWith`, the inferencer can deduce that `(_ > _)` should expand to `((x: Char, y: Char) => x > y)` where `x` and `y` are some arbitrary fresh names.

Now consider the second case, `msort(_ > _)(abcde)`. The type of `msort` is a curried, polymorphic method type that takes an argument of type `(T, T) => Boolean` to a function from `List[T]` to `List[T]` where `T` is some as-yet unknown type. The `msort` method needs to be instantiated with a type parameter before it can be applied to its arguments.

Because the precise instance type of `msort` in the application is not yet known, it cannot be used to infer the type of its first argument. The type inferencer changes its strategy in this case; it first type checks method arguments to determine the proper instance type of the method. However, when tasked to type check the short-hand function literal, `(_ > _)`, it fails because it has no information about the types of the implicit function parameters that are indicated by underscores.

One way to resolve the problem is to pass an explicit type parameter to `msort`, as in:

```
scala> msort[Char](_ > _)(abcde)
res68: List[Char] = List(e, d, c, b, a)
```

Because the correct instance type of `msort` is now known, it can be used to infer the type of the arguments. Another possible solution is to rewrite the `msort` method so that its parameters are swapped:

```
def msortSwapped[T](xs: List[T])(less:
    (T, T) => Boolean): List[T] = {
    // same implementation as msort,
    // but with arguments swapped
}
```

Now type inference would succeed:

```
scala> msortSwapped(abcde)(_ > _)
res69: List[Char] = List(e, d, c, b, a)
```

What has happened is that the inferencer used the known type of the first parameter `abcde` to determine the type parameter of `msortSwapped`. Once the precise type of `msortSwapped` was known, it could be used in turn to infer the type of the second parameter, `(_ > _)`.

Generally, when tasked to infer the type parameters of a polymorphic method, the type inferencer consults the types of all value arguments in the first parameter list but no arguments beyond that. Since `msortSwapped` is a curried method with two parameter lists, the second argument (*i.e.*, the function value) did not need to be consulted to determine the type parameter of the method.

This inference scheme suggests the following library design principle: When designing a polymorphic method that takes some non-function arguments and a function argument, place the function argument last in a curried parameter list on its own. That way, the method's correct instance type can be inferred from the non-function arguments, and that type can in turn be used to type check the function argument. The net effect is that users of the method will be able to give less type information and write function literals in more compact ways.

Now to the more complicated case of a *fold* operation. Why is there the need for an explicit type parameter in an expression like the body of the `flattenRight` method shown on [page 363](#)?

```
(xss :\ List[T]()) (_ ::: _)
```

The type of the fold-right operation is polymorphic in two type variables. Given an expression:

```
(xs :\ z) (op)
```

The type of `xs` must be a list of some arbitrary type `A`, say `xs: List[A]`. The start value `z` can be of some other type `B`. The operation `op` must then take two arguments of type `A` and `B`, and return a result of type `B`, *i.e.*, `op: (A, B) => B`. Because the type of `z` is not related to the type of the list `xs`, type inference has no context information for `z`.

Now consider the expression in the erroneous version of `flattenRight`, also shown on [page 363](#):

```
(xs: List()) _ ::_ // this won't compile
```

The start value `z` in this fold is an empty list, `List()`, so without additional type information its type is inferred to be a `List[Nothing]`. Hence, the inferencer will infer that the `B` type of the fold is `List[Nothing]`. Therefore, the operation `(_ ::_)` of the fold is expected to be of the following type:

```
(List[T], List[Nothing]) => List[Nothing]
```

This is indeed a possible type for the operation in that fold but it is not a very useful one! It says that the operation always takes an empty list as second argument and always produces an empty list as result.

In other words, the type inference settled too early on a type for `List()`; it should have waited until it had seen the type of the operation `op`. So the (otherwise very useful) rule to only consider the first argument section in a curried method application for determining the method's type is at the root of the problem here. On the other hand, even if that rule were relaxed, the inferencer still could not come up with a type for `op` because its parameter types are not given. Hence, there is a Catch-22 situation that can only be resolved by an explicit type annotation from the programmer.

This example highlights some limitations of the local, flow-based type inference scheme of Scala. It is not present in the more global Hindley-Milner style of type inference used in functional languages, such as ML or Haskell. However, Scala's local type inference deals much more gracefully with object-oriented subtyping than the Hindley-Milner style does. Fortunately, the limitations show up only in some corner cases, and are usually easily fixed by adding an explicit type annotation.

Adding type annotations is also a useful debugging technique when you get confused by type error messages related to polymorphic methods. If you are unsure what caused a particular type error, just add some type arguments or other type annotations, which you think are correct. Then you should be able to quickly see where the real problem is.

16.11 Conclusion

Now you have seen many ways to work with lists. You have seen the basic operations like `head` and `tail`, the first-order operations like `reverse`, the higher-order operations like `map`, and the utility methods in the `List` object. Along the way, you learned a bit about how Scala's type inference works.

Lists are a real work horse in Scala, so you will benefit from knowing how to use them. For that reason, this chapter has delved deeply into how to use lists. Lists are just one kind of collection that Scala supports, however. The next chapter is broad, rather than deep, and shows you how to use a variety of Scala's collection types.

Chapter 17

Working with Other Collections

Scala has a rich collection library. This chapter gives you a tour of the most commonly used collection types and operations, showing just the parts you will use most frequently. [Chapter 24](#) will provide a more comprehensive tour of what's available, and [Chapter 25](#) will show how Scala's composition constructs are used to provide such a rich API.

17.1 Sequences

Sequence types let you work with groups of data lined up in order. Because the elements are ordered, you can ask for the first element, second element, 103rd element, and so on. In this section, we'll give you a quick tour of the most important sequences.

Lists

Perhaps the most important sequence type to know about is class `List`, the immutable linked-list described in detail in the previous chapter. Lists support fast addition and removal of items to the beginning of the list, but they do not provide fast access to arbitrary indexes because the implementation must iterate through the list linearly.

This combination of features might sound odd, but they hit a sweet spot that works well for many algorithms. The fast addition and removal of initial elements means that pattern matching works well, as described in [Chapter 15](#). The immutability of lists helps you develop correct, efficient algorithms because you never need to make copies of a list.

Here's a short example showing how to initialize a list, and access its head and tail:

```
scala> val colors = List("red", "blue", "green")
colors: List[String] = List(red, blue, green)

scala> colors.head
res0: String = red

scala> colors.tail
res1: List[String] = List(blue, green)
```

For a refresher on lists, see [Step 8](#) in [Chapter 3](#). You can find details on using lists in [Chapter 16](#). Lists will also be discussed in [Chapter 22](#), which provides insight into how lists are implemented in Scala.

Arrays

Arrays allow you to hold a sequence of elements and efficiently access an element at an arbitrary position, either to get or update the element, with a zero-based index. Here's how you create an array whose size you know, but for which you don't yet know the element values:

```
scala> val fiveInts = new Array[Int](5)
fiveInts: Array[Int] = Array(0, 0, 0, 0, 0)
```

Here's how you initialize an array when you do know the element values:

```
scala> val fiveToOne = Array(5, 4, 3, 2, 1)
fiveToOne: Array[Int] = Array(5, 4, 3, 2, 1)
```

As mentioned previously, arrays are accessed in Scala by placing an index in parentheses, not square brackets as in Java. Here's an example of both accessing and updating an array element:

```
scala> fiveInts(0) = fiveToOne(4)
scala> fiveInts
res3: Array[Int] = Array(1, 0, 0, 0, 0)
```

Scala arrays are represented in the same way as Java arrays. So, you can seamlessly use existing Java methods that return arrays.¹

¹The difference in variance of Scala's and Java's arrays—*i.e.*, whether `Array[String]` is a subtype of `Array[AnyRef]`—will be discussed in [Section 19.3](#).

You have seen arrays in action many times in previous chapters. The basics are in [Step 7 in Chapter 3](#). Several examples of iterating through the elements of an array with a `for` expression are shown in [Section 7.3](#). Arrays also figure prominently in the two-dimensional layout library of [Chapter 10](#).

List buffers

Class `List` provides fast access to the head of the list, but not the end. Thus, when you need to build a list by appending to the end, consider building the list backwards by prepending elements to the front. Then when you're done, call `reverse` to get the elements in the order you need.

Another alternative, which avoids the `reverse` operation, is to use a `ListBuffer`. A `ListBuffer` is a mutable object (contained in package `scala.collection.mutable`), which can help you build lists more efficiently when you need to append. `ListBuffer` provides constant time append and prepend operations. You append elements with the `+=` operator, and prepend them with the `+=:` operator. When you're done building, you can obtain a `List` by invoking `toList` on the `ListBuffer`. Here's an example:

```
scala> import scala.collection.mutable.ListBuffer
import scala.collection.mutable.ListBuffer

scala> val buf = new ListBuffer[Int]
buf: scala.collection.mutable.ListBuffer[Int] = ListBuffer()

scala> buf += 1
res4: buf.type = ListBuffer(1)

scala> buf += 2
res5: buf.type = ListBuffer(1, 2)

scala> buf
res6: scala.collection.mutable.ListBuffer[Int] =
ListBuffer(1, 2)

scala> 3 +=: buf
res7: buf.type = ListBuffer(3, 1, 2)

scala> buf.toList
res8: List[Int] = List(3, 1, 2)
```

Another reason to use `ListBuffer` instead of `List` is to prevent the potential for stack overflow. If you can build a list in the desired order by

prepend, but the recursive algorithm that would be required is not tail recursive, you can use a `for` expression or `while` loop and a `ListBuffer` instead. You'll see `ListBuffer` being used in this way in [Section 22.2](#).

Array buffers

An `ArrayBuffer` is like an array, except that you can additionally add and remove elements from the beginning and end of the sequence. All `Array` operations are available, though they are a little slower due to a layer of wrapping in the implementation. The new addition and removal operations are constant time on average, but occasionally require linear time due to the implementation needing to allocate a new array to hold the buffer's contents.

To use an `ArrayBuffer`, you must first import it from the mutable collections package:

```
scala> import scala.collection.mutable.ArrayBuffer  
import scala.collection.mutable.ArrayBuffer
```

When you create an `ArrayBuffer`, you must specify a type parameter, but you don't need to specify a length. The `ArrayBuffer` will adjust the allocated space automatically as needed:

```
scala> val buf = new ArrayBuffer[Int]()  
buf: scala.collection.mutable.ArrayBuffer[Int] =  
ArrayBuffer()
```

You can append to an `ArrayBuffer` using the `+=` method:

```
scala> buf += 12  
res9: buf.type = ArrayBuffer(12)  
  
scala> buf += 15  
res10: buf.type = ArrayBuffer(12, 15)  
  
scala> buf  
res11: scala.collection.mutable.ArrayBuffer[Int] =  
ArrayBuffer(12, 15)
```

All the normal array methods are available. For example, you can ask an `ArrayBuffer` its length or you can retrieve an element by its index:

```
scala> buf.length
res12: Int = 2

scala> buf(0)
res13: Int = 12
```

Strings (via StringOps)

One other sequence to be aware of is `StringOps`, which implements many sequence methods. Because `Predef` has an implicit conversion from `String` to `StringOps`, you can treat any string like a sequence. Here's an example:

```
scala> def hasUpperCase(s: String) = s.exists(_.isUpper)
hasUpperCase: (s: String)Boolean

scala> hasUpperCase("Robert Frost")
res14: Boolean = true

scala> hasUpperCase("e e cummings")
res15: Boolean = false
```

In this example, the `exists` method is invoked on the string named `s` in the `hasUpperCase` method body. Because no method named “`exists`” is declared in class `String` itself, the Scala compiler will implicitly convert `s` to `StringOps`, which has the method. The `exists` method treats the string as a sequence of characters, and will return true if any of the characters are upper case.²

17.2 Sets and maps

You have already seen the basics of sets and maps in previous chapters, starting with [Step 10 in Chapter 3](#). In this section, we'll offer more insight into their use and show you a few more examples.

As mentioned previously, the Scala collections library offers both mutable and immutable versions of sets and maps. The hierarchy for sets is shown in [Figure 3.2 on page 88](#), and the hierarchy for maps is shown in [Figure 3.3 on page 90](#). As these diagrams show, the simple names `Set` and `Map` are used by three traits each, residing in different packages.

²The code given on [page 57 of Chapter 1](#) presents a similar example.

By default when you write “Set” or “Map” you get an immutable object. If you want the mutable variant, you need to do an explicit import. Scala gives you easier access to the immutable variants, as a gentle encouragement to prefer them over their mutable counterparts. The easy access is provided via the `Predef` object, which is implicitly imported into every Scala source file. Listing 17.1 shows the relevant definitions:

```
object Predef {  
    type Map[A, +B] = collection.immutable.Map[A, B]  
    type Set[A] = collection.immutable.Set[A]  
    val Map = collection.immutable.Map  
    val Set = collection.immutable.Set  
    // ...  
}
```

Listing 17.1 · Default map and set definitions in `Predef`.

The “type” keyword is used in `Predef` to define `Set` and `Map` as aliases³ for the longer fully qualified names of the immutable set and map traits.³ The vals named `Set` and `Map` are initialized to refer to the singleton objects for the immutable `Set` and `Map`. So `Map` is the same as `Predef.Map`, which is defined to be the same as `scala.collection.immutable.Map`. This holds both for the `Map` type and `Map` object.

If you want to use both mutable and immutable sets or maps in the same source file, one approach is to import the name of the package that contains the mutable variants:

```
scala> import scala.collection.mutable  
import scala.collection.mutable
```

You can continue to refer to the immutable set as `Set`, as before, but can now refer to the mutable set as `mutable.Set`. Here’s an example:

```
scala> val mutaSet = mutable.Set(1, 2, 3)  
mutaSet: scala.collection.mutable.Set[Int] = Set(1, 2, 3)
```

³The type keyword will be explained in more detail in Section 20.6.

Using sets

The key characteristic of sets is that they will ensure that at most one of each object, as determined by `==`, will be contained in the set at any one time. As an example, we'll use a set to count the number of different words in a string.

The `split` method on `String` can separate a string into words, if you specify spaces and punctuation as word separators. The regular expression “[!, .]+” will suffice: It indicates the string should be split at each place that one or more space and/or punctuation characters exist.

```
scala> val text = "See Spot run. Run, Spot. Run!"  
text: String = See Spot run. Run, Spot. Run!  
  
scala> val wordsArray = text.split("[ !, . ]+")  
wordsArray: Array[String]  
= Array(See, Spot, run, Run, Spot, Run)
```

To count the distinct words, you can convert them to the same case and then add them to a set. Because sets exclude duplicates, each distinct word will appear exactly one time in the set.

First, you can create an empty set using the `empty` method provided on the `Set` companion objects:

```
scala> val words = mutable.Set.empty[String]  
words: scala.collection.mutable.Set[String] = Set()
```

Then, just iterate through the words with a `for` expression, convert each word to lower case, and add it to the mutable set with the `+=` operator:

```
scala> for (word <- wordsArray)  
      words += word.toLowerCase  
  
scala> words  
res17: scala.collection.mutable.Set[String] =  
Set(see, run, spot)
```

Thus, the text contained exactly three distinct words: spot, run, and see. The most commonly used methods on both mutable and immutable sets are shown in Table 17.1.

Table 17.1 · Common operations for sets

What it is	What it does
<code>val nums = Set(1, 2, 3)</code>	Creates an immutable set (<code>nums.toString</code> returns <code>Set(1, 2, 3)</code>)
<code>nums + 5</code>	Adds an element (returns <code>Set(1, 2, 3, 5)</code>)
<code>nums - 3</code>	Removes an element (returns <code>Set(1, 2)</code>)
<code>nums ++ List(5, 6)</code>	Adds multiple elements (returns <code>Set(1, 2, 3, 5, 6)</code>)
<code>nums -- List(1, 2)</code>	Removes multiple elements (returns <code>Set(3)</code>)
<code>nums & Set(1, 3, 5, 7)</code>	Takes the intersection of two sets (returns <code>Set(1, 3)</code>)
<code>nums.size</code>	Returns the size of the set (returns 3)
<code>nums.contains(3)</code>	Checks for inclusion (returns <code>true</code>)
<code>import scala.collection.mutable</code>	Makes the mutable collections easy to access
<code>val words = mutable.Set.empty[String]</code>	Creates an empty, mutable set (<code>words.toString</code> returns <code>Set()</code>)
<code>words += "the"</code>	Adds an element (<code>words.toString</code> returns <code>Set(the)</code>)
<code>words -= "the"</code>	Removes an element, if it exists (<code>words.toString</code> returns <code>Set()</code>)
<code>words ++= List("do", "re", "mi")</code>	Adds multiple elements (<code>words.toString</code> returns <code>Set(do, re, mi)</code>)
<code>words --- List("do", "re")</code>	Removes multiple elements (<code>words.toString</code> returns <code>Set(mi)</code>)
<code>words.clear</code>	Removes all elements (<code>words.toString</code> returns <code>Set()</code>)

Using maps

Maps let you associate a value with each element of a set. Using a map looks similar to using an array, except instead of indexing with integers counting from 0, you can use any kind of key. If you import the `mutable` package name, you can create an empty mutable map like this:

```
scala> val map = mutable.Map.empty[String, Int]
map: scala.collection.mutable.Map[String,Int] = Map()
```

Note that when you create a map, you must specify two types. The first type is for the *keys* of the map, the second for the *values*. In this case, the keys are strings and the values are integers. Setting entries in a map looks similar to setting entries in an array:

```
scala> map("hello") = 1
scala> map("there") = 2
scala> map
res20: scala.collection.mutable.Map[String,Int] =
Map(hello -> 1, there -> 2)
```

Likewise, reading a map is similar to reading an array:

```
scala> map("hello")
res21: Int = 1
```

Putting it all together, here is a method that counts the number of times each word occurs in a string:

```
scala> def countWords(text: String) = {
    val counts = mutable.Map.empty[String, Int]
    for (rawWord <- text.split("[ ,!.]+")) {
        val word = rawWord.toLowerCase
        val oldCount =
            if (counts.contains(word)) counts(word)
            else 0
        counts += (word -> (oldCount + 1))
    }
    counts
}
```

```
countWords: (text:  
String)scala.collection.mutable.Map[String,Int]  
scala> countWords("See Spot run! Run, Spot. Run!")  
res22: scala.collection.mutable.Map[String,Int] =  
Map(spot -> 2, see -> 1, run -> 3)
```

Given these counts, you can see that this text talks a lot about running, but not so much about seeing.

The way this code works is that a mutable map, named `counts`, maps each word to the number of times it occurs in the text. For each word in the text, the word's old count is looked up, that count is incremented by one, and the new count is saved back into `counts`. Note the use of `contains` to check whether a word has been seen yet or not. If `counts.contains(word)` is not true, then the word has not yet been seen and zero is used for the count.

Many of the most commonly used methods on both mutable and immutable maps are shown in [Table 17.2](#).

Table 17.2 · Common operations for maps

What it is	What it does
<code>val nums = Map("i" -> 1, "ii" -> 2)</code>	Creates an immutable map (<code>nums.toString</code> returns <code>Map(i -> 1, ii -> 2)</code>)
<code>nums + ("vi" -> 6)</code>	Adds an entry (returns <code>Map(i -> 1, ii -> 2, vi -> 6)</code>)
<code>nums - "ii"</code>	Removes an entry (returns <code>Map(i -> 1)</code>)
<code>nums ++ List("iii" -> 3, "v" -> 5)</code>	Adds multiple entries (returns <code>Map(i -> 1, ii -> 2, iii -> 3, v -> 5)</code>)
<code>nums -- List("i", "ii")</code>	Removes multiple entries (returns <code>Map()</code>)
<code>nums.size</code>	Returns the size of the map (returns 2)
<code>nums.contains("ii")</code>	Checks for inclusion (returns true)
<code>nums("ii")</code>	Retrieves the value at a specified key (returns 2)
<code>nums.keys</code>	Returns the keys (returns an Iterable over the strings "i" and "ii")

Table 17.2 · continued

<code>nums.keySet</code>	Returns the keys as a set (returns <code>Set(i, ii)</code>)
<code>nums.values</code>	Returns the values (returns an <code>Iterable</code> over the integers 1 and 2)
<code>nums.isEmpty</code>	Indicates whether the map is empty (returns <code>false</code>)
<code>import scala.collection.mutable</code>	Makes the mutable collections easy to access
<code>val words = mutable.Map.empty[String, Int]</code>	Creates an empty, mutable map
<code>words += ("one" -> 1)</code>	Adds a map entry from "one" to 1 (<code>words.toString</code> returns <code>Map(one -> 1)</code>)
<code>words --= "one"</code>	Removes a map entry, if it exists (<code>words.toString</code> returns <code>Map()</code>)
<code>words ++= List("one" -> 1, "two" -> 2, "three" -> 3)</code>	Adds multiple map entries (<code>words.toString</code> returns <code>Map(one -> 1, two -> 2, three -> 3)</code>)
<code>words ---= List("one", "two")</code>	Removes multiple objects (<code>words.toString</code> returns <code>Map(three -> 3)</code>)

Default sets and maps

For most uses, the implementations of mutable and immutable sets and maps provided by the `Set()`, `scala.collection.mutable.Map()`, etc., factories will likely be sufficient. The implementations provided by these factories use a fast lookup algorithm, usually involving a hash table, so they can quickly decide whether or not an object is in the collection.

The `scala.collection.mutable.Set()` factory method, for example, returns a `scala.collection.mutable.HashSet`, which uses a hash table internally. Similarly, the `scala.collection.mutable.Map()` factory returns a `scala.collection.mutable.HashMap`.

The story for immutable sets and maps is a bit more involved. The class

Table 17.3 · Default immutable set implementations

Number of elements	Implementation
0	<code>scala.collection.immutable.EmptySet</code>
1	<code>scala.collection.immutable.Set1</code>
2	<code>scala.collection.immutable.Set2</code>
3	<code>scala.collection.immutable.Set3</code>
4	<code>scala.collection.immutable.Set4</code>
5 or more	<code>scala.collection.immutable.HashSet</code>

returned by the `scala.collection.immutable.Set()` factory method, for example, depends on how many elements you pass to it, as shown in [Table 17.3](#). For sets with fewer than five elements, a special class devoted exclusively to sets of each particular size is used to maximize performance. Once you request a set that has five or more elements in it, however, the factory method will return an implementation that uses hash tries.

Similarly, the `scala.collection.immutable.Map()` factory method will return a different class depending on how many key-value pairs you pass to it, as shown in [Table 17.4](#). As with sets, for immutable maps with fewer than five elements, a special class devoted exclusively to maps of each particular size is used to maximize performance. Once a map has five or more key-value pairs in it, however, an immutable `HashMap` is used.

The default immutable implementation classes shown in [Tables 17.3](#) and [17.4](#) work together to give you maximum performance. For example, if you add an element to an `EmptySet`, it will return a `Set1`. If you add an element to that `Set1`, it will return a `Set2`. If you then remove an element from the `Set2`, you'll get another `Set1`.

Table 17.4 · Default immutable map implementations

Number of elements	Implementation
0	<code>scala.collection.immutable.EmptyMap</code>
1	<code>scala.collection.immutable.Map1</code>
2	<code>scala.collection.immutable.Map2</code>
3	<code>scala.collection.immutable.Map3</code>
4	<code>scala.collection.immutable.Map4</code>
5 or more	<code>scala.collection.immutable.HashMap</code>

Sorted sets and maps

On occasion you may need a set or map whose iterator returns elements in a particular order. For this purpose, the Scala collections library provides traits `SortedSet` and `SortedMap`. These traits are implemented by classes `TreeSet` and `TreeMap`, which use a red-black tree to keep elements (in the case of `TreeSet`) or keys (in the case of `TreeMap`) in order. The order is determined by the `Ordered` trait, which the element type of the set, or key type of the map, must either mix in or be implicitly convertible to. These classes only come in immutable variants. Here are some `TreeSet` examples:

```
scala> import scala.collection.immutable.TreeSet
import scala.collection.immutable.TreeSet
scala> val ts = TreeSet(9, 3, 1, 8, 0, 2, 7, 4, 6, 5)
ts: scala.collection.immutable.TreeSet[Int] =
TreeSet(0, 1, 2, 3, 4, 5, 6, 7, 8, 9)
scala> val cs = TreeSet('f', 'u', 'n')
cs: scala.collection.immutable.TreeSet[Char] =
TreeSet(f, n, u)
```

And here are a few `TreeMap` examples:

```
scala> import scala.collection.immutable.TreeMap
import scala.collection.immutable.TreeMap
scala> var tm = TreeMap(3 -> 'x', 1 -> 'x', 4 -> 'x')
tm: scala.collection.immutable.TreeMap[Int,Char] =
Map(1 -> x, 3 -> x, 4 -> x)
scala> tm += (2 -> 'x')
scala> tm
res30: scala.collection.immutable.TreeMap[Int,Char] =
Map(1 -> x, 2 -> x, 3 -> x, 4 -> x)
```

17.3 Selecting mutable versus immutable collections

For some problems, mutable collections work better, while for others, immutable collections work better. When in doubt, it is better to start with an

immutable collection and change it later, if you need to, because immutable collections can be easier to reason about than mutable ones.

Also, it can be worthwhile to go the opposite way sometimes. If you find some code that uses mutable collections becoming complicated and hard to reason about, consider whether it would help to change some of the collections to immutable alternatives. In particular, if you find yourself worrying about making copies of mutable collections in just the right places, or thinking a lot about who “owns” or “contains” a mutable collection, consider switching some of the collections to their immutable counterparts.

Besides being potentially easier to reason about, immutable collections can usually be stored more compactly than mutable ones if the number of elements stored in the collection is small. For instance an empty mutable map in its default representation of `HashMap` takes up about 80 bytes, and about 16 more are added for each entry that’s added to it. An empty immutable `Map` is a single object that’s shared between all references, so referring to it essentially costs just a single pointer field.

What’s more, the Scala collections library currently stores immutable maps and sets with up to four entries in a single object, which typically takes up between 16 and 40 bytes, depending on the number of entries stored in the collection.⁴ So for small maps and sets, the immutable versions are much more compact than the mutable ones. Given that many collections are small, switching them to be immutable can bring important space savings and performance advantages.

To make it easier to switch from immutable to mutable collections, and vice versa, Scala provides some syntactic sugar. Even though immutable sets and maps do not support a true `+=` method, Scala gives a useful alternate interpretation to `+=`. Whenever you write `a += b`, and `a` does not support a method named `+=`, Scala will try interpreting it as `a = a + b`.

For example, immutable sets do not support a `+=` operator:

```
scala> val people = Set("Nancy", "Jane")
people: scala.collection.immutable.Set[String] =
Set(Nancy, Jane)

scala> people += "Bob"
<console>:14: error: value += is not a member of
```

⁴The “single object” is an instance of `Set1` through `Set4`, or `Map1` through `Map4`, as shown in [Tables 17.3 and 17.4](#).

```
scala.collection.immutable.Set[String]
    people += "Bob"
        ^
```

However, if you declare `people` as a `var`, instead of a `val`, then the collection can be “updated” with a `+=` operation, even though it is immutable. First, a new collection will be created, and then `people` will be reassigned to refer to the new collection:

```
scala> var people = Set("Nancy", "Jane")
people: scala.collection.immutable.Set[String] =
Set(Nancy, Jane)
scala> people += "Bob"
scala> people
res34: scala.collection.immutable.Set[String] =
Set(Nancy, Jane, Bob)
```

After this series of statements, the `people` variable refers to a new immutable set, which contains the added string, “Bob”. The same idea applies to any method ending in `=`, not just the `+=` method. Here’s the same syntax used with the `--` operator, which removes an element from a set, and the `++=` operator, which adds a collection of elements to a set:

```
scala> people --= "Jane"
scala> people ++= List("Tom", "Harry")
scala> people
res37: scala.collection.immutable.Set[String] =
Set(Nancy, Bob, Tom, Harry)
```

To see how this is useful, consider again the following `Map` example from Section 1.1:

```
var capital = Map("US" -> "Washington", "France" -> "Paris")
capital += ("Japan" -> "Tokyo")
println(capital("France"))
```

This code uses immutable collections. If you want to try using mutable collections instead, all that is necessary is to import the mutable version of `Map`, thus overriding the default import of the immutable `Map`:

```
import scala.collection.mutable.Map // only change needed!
var capital = Map("US" -> "Washington", "France" -> "Paris")
capital += ("Japan" -> "Tokyo")
println(capital("France"))
```

Not all examples are quite that easy to convert, but the special treatment of methods ending in an equals sign will often reduce the amount of code that needs changing.

By the way, this syntactic treatment works on any kind of value, not just collections. For example, here it is being used on floating-point numbers:

```
scala> var roughlyPi = 3.0
roughlyPi: Double = 3.0
scala> roughlyPi += 0.1
scala> roughlyPi += 0.04
scala> roughlyPi
res40: Double = 3.14
```

The effect of this expansion is similar to Java's assignment operators (`+=`, `-=`, `*=`, etc.), but it is more general because every operator ending in `=` can be converted.

17.4 Initializing collections

As you've seen previously, the most common way to create and initialize a collection is to pass the initial elements to a factory method on the companion object of your chosen collection. You just place the elements in parentheses after the companion object name, and the Scala compiler will transform that to an invocation of an `apply` method on that companion object:

```
scala> List(1, 2, 3)
res41: List[Int] = List(1, 2, 3)
scala> Set('a', 'b', 'c')
res42: scala.collection.immutable.Set[Char] = Set(a, b, c)
scala> import scala.collection.mutable
import scala.collection.mutable
```

```
scala> mutable.Map("hi" -> 2, "there" -> 5)
res43: scala.collection.mutable.Map[String,Int] =
Map(hi -> 2, there -> 5)

scala> Array(1.0, 2.0, 3.0)
res44: Array[Double] = Array(1.0, 2.0, 3.0)
```

Although most often you can let the Scala compiler infer the element type of a collection from the elements passed to its factory method, sometimes you may want to create a collection but specify a different type from the one the compiler would choose. This is especially an issue with mutable collections. Here's an example:

```
scala> import scala.collection.mutable
import scala.collection.mutable

scala> val stuff = mutable.Set(42)
stuff: scala.collection.mutable.Set[Int] = Set(42)

scala> stuff += "abracadabra"
<console>:16: error: type mismatch;
 found   : String("abracadabra")
 required: Int
           stuff += "abracadabra"
                           ^
```

The problem here is that `stuff` was given an element type of `Int`. If you want it to have an element type of `Any`, you need to say so explicitly by putting the element type in square brackets, like this:

```
scala> val stuff = mutable.Set[Any](42)
stuff: scala.collection.mutable.Set[Any] = Set(42)
```

Another special situation is if you want to initialize a collection with another collection. For example, imagine you have a list, but you want a `TreeSet` containing the elements in the list. Here's the list:

```
scala> val colors = List("blue", "yellow", "red", "green")
colors: List[String] = List(blue, yellow, red, green)
```

You cannot pass the `colors` list to the factory method for `TreeSet`:

```
scala> import scala.collection.immutable.TreeSet
import scala.collection.immutable.TreeSet
scala> val treeSet = TreeSet(colors)
<console>:16: error: No implicit Ordering defined for
List[String].
      val treeSet = TreeSet(colors)
                           ^
```

Instead, you'll need to create an empty `TreeSet[String]` and add to it the elements of the list with the `TreeSet`'s `++` operator:

```
scala> val treeSet = TreeSet[String]() ++ colors
treeSet: scala.collection.immutable.TreeSet[String] =
TreeSet(blue, green, red, yellow)
```

Converting to array or list

If you need to initialize a list or array with another collection, on the other hand, it is quite straightforward. As you've seen previously, to initialize a new list with another collection, simply invoke `toList` on that collection:

```
scala> treeSet.toList
res50: List[String] = List(blue, green, red, yellow)
```

Or, if you need an array, invoke `toArray`:

```
scala> treeSet.toArray
res51: Array[String] = Array(blue, green, red, yellow)
```

Note that although the original `colors` list was not sorted, the elements in the list produced by invoking `toList` on the `TreeSet` are in alphabetical order. When you invoke `toList` or `toArray` on a collection, the order of the elements in the resulting list or array will be the same as the order of elements produced by an iterator obtained by invoking `elements` on that collection. Because a `TreeSet[String]`'s iterator will produce strings in alphabetical order, those strings will appear in alphabetical order in the list resulting from invoking `toList` on that `TreeSet`.

Keep in mind, however, that conversion to lists or arrays usually requires copying all of the elements of the collection, and thus may be slow for large collections. Sometimes you need to do it, though, due to an existing API.

Further, many collections only have a few elements anyway, in which case there is only a small speed penalty.

Converting between mutable and immutable sets and maps

Another situation that arises occasionally is the need to convert a mutable set or map to an immutable one, or *vice versa*. To accomplish this, you can use the technique shown on the previous page to initialize a TreeSet with the elements of a list. Create a collection of the new type using the `empty` method and then add the new elements using either `++` or `++=`, whichever is appropriate for the target collection type. Here's how you'd convert the immutable TreeSet from the previous example to a mutable set, and back again to an immutable one:

```
scala> import scala.collection.mutable  
import scala.collection.mutable  
  
scala> treeSet  
res52: scala.collection.immutable.TreeSet[String] =  
  TreeSet(blue, green, red, yellow)  
  
scala> val mutaSet = mutable.Set.empty ++= treeSet  
mutaSet: scala.collection.mutable.Set[String] =  
  Set(red, blue, green, yellow)  
  
scala> val immutaSet = Set.empty ++ mutaSet  
immutaSet: scala.collection.immutable.Set[String] =  
  Set(red, blue, green, yellow)
```

You can use the same technique to convert between mutable and immutable maps:

```
scala> val muta = mutable.Map("i" -> 1, "ii" -> 2)  
muta: scala.collection.mutable.Map[String,Int] =  
  Map(ii -> 2, i -> 1)  
  
scala> val immu = Map.empty ++ muta  
immu: scala.collection.immutable.Map[String,Int] =  
  Map(ii -> 2, i -> 1)
```

17.5 Tuples

As described in [Step 9](#) in [Chapter 3](#), a tuple combines a fixed number of items together so that they can be passed around as a whole. Unlike an array or list, a tuple can hold objects with different types. Here is an example of a tuple holding an integer, a string, and the console:

```
(1, "hello", Console)
```

Tuples save you the tedium of defining simplistic data-heavy classes. Even though defining a class is already easy, it does require a certain minimum effort, which sometimes serves no purpose. Tuples save you the effort of choosing a name for the class, choosing a scope to define the class in, and choosing names for the members of the class. If your class simply holds an integer and a string, there is no clarity added by defining a class named `AnIntegerAndAString`.

Because tuples can combine objects of different types, tuples do not inherit from `Traversable`. If you find yourself wanting to group exactly one integer and exactly one string, then you want a tuple, not a `List` or `Array`.

A common application of tuples is returning multiple values from a method. For example, here is a method that finds the longest word in a collection and also returns its index:

```
def longestWord(words: Array[String]) = {  
    var word = words(0)  
    var idx = 0  
    for (i <- 1 until words.length) {  
        if (words(i).length > word.length) {  
            word = words(i)  
            idx = i  
        }  
    }  
    (word, idx)  
}
```

Here is an example use of the method:

```
scala> val longest =  
         longestWord("The quick brown fox".split(" "))  
longest: (String, Int) = (quick,1)
```

The `longestWord` function here computes two items: `word`, the longest word in the array, and `idx`, the index of that word. To keep things simple, the function assumes there is at least one word in the list, and it breaks ties by choosing the word that comes earlier in the list. Once the function has chosen which word and index to return, it returns both of them together using the tuple syntax (`word, idx`).

To access elements of a tuple, you can use method `_1` to access the first element, `_2` to access the second, and so on:

```
scala> longest._1
res53: String = quick
scala> longest._2
res54: Int = 1
```

Additionally, you can assign each element of the tuple to its own variable,⁵ like this:

```
scala> val (word, idx) = longest
word: String = quick
idx: Int = 1
scala> word
res55: String = quick
```

By the way, if you leave off the parentheses you get a different result:

```
scala> val word, idx = longest
word: (String, Int) = (quick,1)
idx: (String, Int) = (quick,1)
```

This syntax gives *multiple definitions* of the same expression. Each variable is initialized with its own evaluation of the expression on the right-hand side. That the expression evaluates to a tuple in this case does not matter. Both variables are initialized to the tuple in its entirety. See [Chapter 18](#) for some examples where multiple definitions are convenient.

As a note of warning, tuples are almost too easy to use. Tuples are great when you combine data that has no meaning beyond “an A and a B.” However, whenever the combination has some meaning, or you want to add some

⁵This syntax is actually a special case of *pattern matching*, as described in detail in [Section 15.7](#).

methods to the combination, it is better to go ahead and create a class. For example, do not use a 3-tuple for the combination of a month, a day, and a year. Make a Date class. It makes your intentions explicit, which both clears up the code for human readers and gives the compiler and language opportunities to help you catch mistakes.

17.6 Conclusion

This chapter has given an overview of the Scala collections library and the most important classes and traits in it. With this foundation you should be able to work effectively with Scala collections, and know where to look in Scaladoc when you need more information. For more detailed information about Scala collections, look ahead to [Chapter 24](#) and [Chapter 25](#). For now, in the next chapter, we'll turn our attention from the Scala library back to the language and discuss Scala's support for mutable objects.

Chapter 18

Mutable Objects

In previous chapters, we put the spotlight on functional (immutable) objects. We did so because the idea of objects without any mutable state deserves to be better known. However, it is also perfectly possible to define objects with mutable state in Scala. Such mutable objects often come up naturally when you want to model objects in the real world that change over time.

This chapter explains what mutable objects are and what Scala provides in terms of syntax to express them. We will also introduce a larger case study on discrete event simulation, which involves mutable objects, as well as building an internal DSL for defining digital circuits to simulate.

18.1 What makes an object mutable?

You can observe the principal difference between a purely functional object and a mutable one even without looking at the object's implementation. When you invoke a method or dereference a field on some purely functional object, you will always get the same result.

For instance, given a list of characters:

```
val cs = List('a', 'b', 'c')
```

an application of `cs.head` will always return '`a`'. This is the case even if there is an arbitrary number of operations on the list `cs` between the point where it is defined and the point where the access `cs.head` is made.

For a mutable object, on the other hand, the result of a method call or field access may depend on what operations were previously performed on the

object. A good example of a mutable object is a bank account. Listing 18.1 shows a simplified implementation of bank accounts:

```
class BankAccount {  
    private var bal: Int = 0  
  
    def balance: Int = bal  
  
    def deposit(amount: Int) = {  
        require(amount > 0)  
        bal += amount  
    }  
  
    def withdraw(amount: Int): Boolean =  
        if (amount > bal) false  
        else {  
            bal -= amount  
            true  
        }  
}
```

Listing 18.1 · A mutable bank account class.

The `BankAccount` class defines a private variable, `bal`, and three public methods: `balance` returns the current balance; `deposit` adds a given amount to `bal`; and `withdraw` tries to subtract a given amount from `bal` while assuring that the remaining balance won't be negative. The return value of `withdraw` is a Boolean indicating whether the requested funds were successfully withdrawn.

Even if you know nothing about the inner workings of the `BankAccount` class, you can still tell that `BankAccounts` are mutable objects:

```
scala> val account = new BankAccount  
account: BankAccount = BankAccount@21cf775d  
  
scala> account deposit 100  
  
scala> account withdraw 80  
res1: Boolean = true  
  
scala> account withdraw 80  
res2: Boolean = false
```

Note that the two final withdrawals in the previous interaction returned different results. The first withdraw operation returned true because the bank account contained sufficient funds to allow the withdrawal. The second operation, although the same as the first one, returned false because the balance of the account had been reduced so that it no longer covered the requested funds. So, clearly, bank accounts have mutable state, because the same operation can return different results at different times.

You might think that the mutability of `BankAccount` is immediately apparent because it contains a `var` definition. Mutation and `vars` usually go hand in hand, but things are not always so clear cut. For instance, a class might be mutable without defining or inheriting any `vars` because it forwards method calls to other objects that have mutable state. The reverse is also possible: A class might contain `vars` and still be purely functional. An example would be a class that caches the result of an expensive operation in a field for optimization purposes. To pick an example, assume the following unoptimized class `Keyed` with an expensive operation `computeKey`:

```
class Keyed {  
    def computeKey: Int = ... // this will take some time  
    ...  
}
```

Provided that `computeKey` neither reads nor writes any `vars`, you can make `Keyed` more efficient by adding a cache:

```
class MemoKeyed extends Keyed {  
    private var keyCache: Option[Int] = None  
    override def computeKey: Int = {  
        if (!keyCache.isDefined) keyCache = Some(super.computeKey)  
        keyCache.get  
    }  
}
```

Using `MemoKeyed` instead of `Keyed` can speed things up because the second time the result of the `computeKey` operation is requested, the value stored in the `keyCache` field can be returned instead of running `computeKey` once again. But except for this speed gain, the behavior of class `Keyed` and `MemoKeyed` is exactly the same. Consequently, if `Keyed` is purely functional, then so is `MemoKeyed`, even though it contains a reassignable variable.

18.2 Reassignable variables and properties

You can perform two fundamental operations on a reassignable variable: get its value or set it to a new value. In libraries such as JavaBeans, these operations are often encapsulated in separate getter and setter methods, which need to be defined explicitly.

In Scala, every `var` that is a non-private member of some object implicitly defines a getter and a setter method with it. These getters and setters are named differently from the Java convention, however. The getter of a `var` `x` is just named “`x`”, while its setter is named “`x_=`”.

For example, if it appears in a class, the `var` definition:

```
var hour = 12
```

generates a getter, “`hour`”, and setter, “`hour_=`”, in addition to a reassignable field. The field is always marked `private[this]`, which means it can be accessed only from the object that contains it. The getter and setter, on the other hand, get the same visibility as the original `var`. If the `var` definition is public, so are its getter and setter. If it is protected, they are also protected, and so on.

For instance, consider the class `Time` shown in [Listing 18.2](#), which defines two public `vars` named `hour` and `minute`:

```
class Time {  
    var hour = 12  
    var minute = 0  
}
```

[Listing 18.2](#) · A class with public vars.

This implementation is exactly equivalent to the class definition shown in [Listing 18.3](#). In the definitions shown in [Listing 18.3](#), the names of the local fields `h` and `m` are arbitrarily chosen so as not to clash with any names already in use.

An interesting aspect about this expansion of `vars` into getters and setters is that you can also choose to define a getter and a setter directly, instead of defining a `var`. By defining these access methods directly you can interpret the operations of variable access and variable assignment as you like. For in-

```
class Time {  
    private[this] var h = 12  
    private[this] var m = 0  
    def hour: Int = h  
    def hour_=(x: Int) = { h = x }  
    def minute: Int = m  
    def minute_=(x: Int) = { m = x }  
}
```

Listing 18.3 · How public vars are expanded into getter and setter methods.

stance, the variant of class Time shown in Listing 18.4 contains requirements that catch all assignments to hour and minute with illegal values.

```
class Time {  
    private[this] var h = 12  
    private[this] var m = 0  
    def hour: Int = h  
    def hour_=(x: Int) = {  
        require(0 <= x && x < 24)  
        h = x  
    }  
    def minute = m  
    def minute_=(x: Int) = {  
        require(0 <= x && x < 60)  
        m = x  
    }  
}
```

Listing 18.4 · Defining getter and setter methods directly.

Some languages have a special syntactic construct for these variable-like quantities that are not plain variables in that their getter or setter can be redefined. For instance, C# has properties, which fulfill this role. In effect, Scala's convention of always interpreting a variable as a pair of setter and getter methods gives you the same capabilities as C# properties without

requiring special syntax.

Properties can serve many different purposes. In the example shown in Listing 18.4, the setters enforced an invariant, thus protecting the variable from being assigned illegal values. You could also use a property to log all accesses to getters or setters of a variable. Or you could integrate variables with events, for instance by notifying some subscriber methods each time a variable is modified (you'll see examples of this in Chapter 35).

It's also possible, and sometimes useful, to define a getter and a setter without an associated field. For example, Listing 18.5 shows a Thermometer class, which encapsulates a temperature variable that can be read and updated. Temperatures can be expressed in Celsius or Fahrenheit degrees. This class allows you to get and set the temperature in either measure.

```
class Thermometer {  
    var celsius: Float = _  
  
    def fahrenheit = celsius * 9 / 5 + 32  
    def fahrenheit_= (f: Float) = {  
        celsius = (f - 32) * 5 / 9  
    }  
    override def toString = fahrenheit + "F/" + celsius + "C"  
}
```

Listing 18.5 · Defining a getter and setter without an associated field.

The first line in the body of this class defines a var, celsius, which will contain the temperature in degrees Celsius. The celsius variable is initially set to a default value by specifying ‘_’ as the “initializing value” of the variable. More precisely, an initializer “=_” of a field assigns a zero value to that field. The zero value depends on the field’s type. It is 0 for numeric types, false for booleans, and null for reference types. This is the same as if the same variable was defined in Java without an initializer.

Note that you cannot simply leave off the “=_” initializer in Scala. If you had written:

```
var celsius: Float
```

this would declare an abstract variable, not an uninitialized one.¹

¹Abstract variables will be explained in Chapter 20.

The `celsius` variable definition is followed by a getter, “`fahrenheit`”, and a setter, “`fahrenheit_=`”, which access the same temperature, but in degrees Fahrenheit. There is no separate field that contains the current temperature value in Fahrenheit. Instead the getter and setter methods for Fahrenheit values automatically convert from and to degrees Celsius, respectively. Here’s an example of interacting with a `Thermometer` object:

```
scala> val t = new Thermometer
t: Thermometer = 32.0F/0.0C

scala> t.celsius = 100
t.celsius: Float = 100.0

scala> t
res3: Thermometer = 212.0F/100.0C

scala> t.fahrenheit = -40
t.fahrenheit: Float = -40.0

scala> t
res4: Thermometer = -40.0F/-40.0C
```

18.3 Case study: Discrete event simulation

The rest of this chapter shows by way of an extended example how mutable objects can be combined with first-class function values in interesting ways. You’ll see the design and implementation of a simulator for digital circuits. This task is broken down into several subproblems, each of which is interesting individually.

First, you’ll see a little language for digital circuits. The definition of this language will highlight a general method for embedding domain-specific languages (DSL) in a host language like Scala. Second, we’ll present a simple but general framework for discrete event simulation. Its main task will be to keep track of actions that are performed in simulated time. Finally, we’ll show how discrete simulation programs can be structured and built. The idea of such simulations is to model physical objects by simulated objects, and use the simulation framework to model physical time.

The example is taken from the classic textbook *Structure and Interpretation of Computer Programs* by Abelson and Sussman [Abe96]. What’s different here is that the implementation language is Scala instead of Scheme,




Figure 18.1 · Basic gates.

and that the various aspects of the example are structured into four software layers: one for the simulation framework, another for the basic circuit simulation package, a third for a library of user-defined circuits, and the last layer for each simulated circuit itself. Each layer is expressed as a class, and more specific layers inherit from more general ones.

The fast track

Understanding the discrete event simulation example presented in this chapter will take some time. If you feel you want to get on with learning more Scala instead, it's safe to skip ahead to the next chapter.

18.4 A language for digital circuits

We'll start with a “little language” to describe digital circuits. A digital circuit is built from *wires* and *function boxes*. Wires carry *signals*, which are transformed by function boxes. Signals are represented by booleans: `true` for signal-on and `false` for signal-off.

Figure 18.1 shows three basic function boxes (or *gates*):

- An *inverter*, which negates its signal.
- An *and-gate*, which sets its output to the conjunction of its inputs.
- An *or-gate*, which sets its output to the disjunction of its inputs.

These gates are sufficient to build all other function boxes. Gates have *delays*, so an output of a gate will change only some time after its inputs change.

We'll describe the elements of a digital circuit by the following set of Scala classes and functions. First, there is a class `Wire` for wires. We can construct wires like this:

```
val a = new Wire
val b = new Wire
val c = new Wire
```

or, equivalent but shorter, like this:

```
val a, b, c = new Wire
```

Second, there are three procedures which “make” the basic gates we need:

```
def inverter(input: Wire, output: Wire)
def andGate(a1: Wire, a2: Wire, output: Wire)
def orGate(o1: Wire, o2: Wire, output: Wire)
```

What’s unusual, given the functional emphasis of Scala, is that these procedures construct the gates as a side effect, instead of returning the constructed gates as a result. For instance, an invocation of `inverter(a, b)` places an inverter between the wires `a` and `b`. It turns out that this side-effecting construction makes it easier to construct complicated circuits gradually. Also, although methods most often have verb names, these have noun names that indicate which gate they are making. This reflects the declarative nature of the DSL: it should describe a circuit, not the actions of making one.

More complicated function boxes can be built from the basic gates. For instance, the method shown in Listing 18.6 constructs a half-adder. The `halfAdder` method takes two inputs, `a` and `b`, and produces a sum, `s`, defined by “ $s = (a + b) \% 2$ ” and a carry, `c`, defined by “ $c = (a + b) / 2$ ”. A diagram of the half-adder is shown in Figure 18.2.

```
def halfAdder(a: Wire, b: Wire, s: Wire, c: Wire) = {
    val d, e = new Wire
    orGate(a, b, d)
    andGate(a, b, c)
    inverter(c, e)
    andGate(d, e, s)
}
```

Listing 18.6 · The `halfAdder` method.

Note that `halfAdder` is a parameterized function box just like the three methods that construct the primitive gates. You can use the `halfAdder`




Figure 18.2 · A half-adder circuit.

method to construct more complicated circuits. For instance, Listing 18.7 defines a full, one-bit adder, shown in Figure 18.3, which takes two inputs, a and b , as well as a carry-in, cin , and which produces a sum output defined by “ $\text{sum} = (\text{a} + \text{b} + \text{cin}) \% 2$ ” and a carry-out output defined by “ $\text{cout} = (\text{a} + \text{b} + \text{cin}) / 2$ ”.

```
def fullAdder(a: Wire, b: Wire, cin: Wire,
    sum: Wire, cout: Wire) = {
    val s, c1, c2 = new Wire
    halfAdder(a, cin, s, c1)
    halfAdder(b, s, sum, c2)
    orGate(c1, c2, cout)
}
```

Listing 18.7 · The fullAdder method.

Class `Wire` and functions `inverter`, `andGate`, and `orGate` represent a little language with which users can define digital circuits. It's a good example of an *internal DSL*, a domain-specific language defined as a library in a host language instead of being implemented on its own.

The implementation of the circuit DSL still needs to be worked out. Since the purpose of defining a circuit in the DSL is simulating the circuit, it makes sense to base the DSL implementation on a general API for discrete event simulation. The next two sections will present first the simulation API and then the implementation of the circuit DSL on top of it.




Figure 18.3 · A full-adder circuit.

18.5 The Simulation API

The simulation API is shown in [Listing 18.8](#). It consists of class `Simulation` in package `org.stairwaybook.simulation`. Concrete simulation libraries inherit this class and augment it with domain-specific functionality. The elements of the `Simulation` class are presented in this section.

A discrete event simulation performs user-defined *actions* at specified *times*. The actions, which are defined by concrete simulation subclasses, all share a common type:

```
type Action = () => Unit
```

This statement defines `Action` to be an alias of the type of procedure that takes an empty parameter list and returns `Unit`. `Action` is a *type member* of class `Simulation`. You can think of it as a more readable name for type `() => Unit`. Type members will be described in detail in [Section 20.6](#).

The time at which an action is performed is simulated time; it has nothing to do with the actual “wall clock” time. Simulated times are represented simply as integers. The current simulated time is kept in a private variable:

```
private var curtime: Int = 0
```

The variable has a public accessor method, which retrieves the current time:

```
def currentTime: Int = curtime
```

This combination of private variable with public accessor is used to make sure that the current time cannot be modified outside the `Simulation` class. After all, you don’t usually want your simulation objects to manipulate the current time, except possibly if your simulation models time travel.

```
abstract class Simulation {  
    type Action = () => Unit  
    case class WorkItem(time: Int, action: Action)  
    private var curtime = 0  
    def currentTime: Int = curtime  
    private var agenda: List[WorkItem] = List()  
    private def insert(ag: List[WorkItem],  
                      item: WorkItem): List[WorkItem] = {  
        if (ag.isEmpty || item.time < ag.head.time) item :: ag  
        else ag.head :: insert(ag.tail, item)  
    }  
    def afterDelay(delay: Int)(block: => Unit) = {  
        val item = WorkItem(currentTime + delay, () => block)  
        agenda = insert(agenda, item)  
    }  
    private def next() = {  
        (agenda: @unchecked) match {  
            case item :: rest =>  
                agenda = rest  
                curtime = item.time  
                item.action()  
        }  
    }  
    def run() = {  
        afterDelay(0) {  
            println("*** simulation started, time = " +  
                   currentTime + " ***")  
        }  
        while (!agenda.isEmpty) next()  
    }  
}
```

Listing 18.8 · The `Simulation` class.

An action that needs to be executed at a specified time is called a *work item*. Work items are implemented by the following class:

```
case class WorkItem(time: Int, action: Action)
```

We made the `WorkItem` class a case class because of the syntactic conveniences this entails: You can use the factory method, `WorkItem`, to create instances of the class, and you get accessors for the constructor parameters `time` and `action` for free. Note also that class `WorkItem` is nested inside class `Simulation`. Nested classes in Scala are treated similarly to Java. [Section 20.7](#) will give more details.

The `Simulation` class keeps an *agenda* of all remaining work items that have not yet been executed. The work items are sorted by the simulated time at which they have to be run:

```
private var agenda: List[WorkItem] = List()
```

The agenda list will be kept in the proper sorted order by the `insert` method, which updates it. You can see `insert` being called from `afterDelay`, which is the only way to add a work item to the agenda:

```
def afterDelay(delay: Int)(block: => Unit) = {
    val item = WorkItem(currentTime + delay, () => block)
    agenda = insert(agenda, item)
}
```

As the name implies, this method inserts an action (given by `block`) into the agenda so that it is scheduled for execution `delay` time units after the current simulation time. For instance, the following invocation would create a new work item to be executed at the simulated time, `currentTime + delay`:

```
afterDelay(1) { count += 1 }
```

The code to be executed is contained in the method's second argument. The formal parameter for this argument has type “`=> Unit`” (*i.e.*, it is a computation of type `Unit` which is passed by name). Recall that by-name parameters are not evaluated when passed to a method. So in the call above, `count` would be incremented only when the simulation framework calls the action stored in the work item. Note that `afterDelay` is a curried function. It's a good example of the principle set forward in [Section 9.5](#) that currying can be used to make method calls look more like built-in syntax.

The created work item still needs to be inserted into the agenda. This is done by the `insert` method, which maintains the invariant that the agenda is time-sorted:

```
private def insert(ag: List[WorkItem],  
                  item: WorkItem): List[WorkItem] = {  
    if (ag.isEmpty || item.time < ag.head.time) item :: ag  
    else ag.head :: insert(ag.tail, item)  
}
```

The core of the `Simulation` class is defined by the `run` method:

```
def run() = {  
    afterDelay(0) {  
        println("*** simulation started, time = " +  
               currentTime + " ***")  
    }  
    while (!agenda.isEmpty) next()  
}
```

This method repeatedly takes the first item in the agenda, removes it from the agenda and executes it. It does this until there are no more items left in the agenda to execute. Each step is performed by calling the `next` method, which is defined as follows:

```
private def next() = {  
    (agenda: @unchecked) match {  
        case item :: rest =>  
            agenda = rest  
            curtime = item.time  
            item.action()  
    }  
}
```

The `next` method decomposes the current agenda with a pattern match into a front item, `item`, and a remaining list of work items, `rest`. It removes the front item from the current agenda, sets the simulated time `curtime` to the work item's time, and executes the work item's action.

Note that `next` can be called only if the agenda is non-empty. There's no case for an empty list, so you would get a `MatchError` exception if you tried to run `next` on an empty agenda.

In fact, the Scala compiler would normally warn you that you missed one of the possible patterns for a list:

```
Simulator.scala:19: warning: match is not exhaustive!
missing combination           Nil

agenda match {
^
one warning found
```

In this case, the missing case is not a problem because you know that `next` is called only on a non-empty agenda. Therefore, you might want to disable the warning. You saw in [Section 15.5](#) that this can be done by adding an `@unchecked` annotation to the selector expression of the pattern match. That's why the `Simulation` code uses "`(agenda: @unchecked) match`", not "`agenda match`".

That's it. This might look like surprisingly little code for a simulation framework. You might wonder how this framework could possibly support interesting simulations, if all it does is execute a list of work items? In fact the power of the simulation framework comes from the fact that actions stored in work items can themselves install further work items into the agenda when they are executed. That makes it possible to have long-running simulations evolve from simple beginnings.

18.6 Circuit Simulation

The next step is to use the simulation framework to implement the domain-specific language for circuits shown in [Section 18.4](#). Recall that the circuit DSL consists of a class for wires and methods that create and-gates, or-gates, and inverters. These are all contained in a `BasicCircuitSimulation` class, which extends the simulation framework. This class is shown in [Listings 18.9 and 18.10](#).

Class `BasicCircuitSimulation` declares three abstract methods that represent the delays of the basic gates: `InverterDelay`, `AndGateDelay`, and `OrGateDelay`. The actual delays are not known at the level of this class

```
package org.stairwaybook.simulation

abstract class BasicCircuitSimulation extends Simulation {

    def InverterDelay: Int
    def AndGateDelay: Int
    def OrGateDelay: Int

    class Wire {

        private var sigVal = false
        private var actions: List[Action] = List()

        def getSignal = sigVal

        def setSignal(s: Boolean) =
            if (s != sigVal) {
                sigVal = s
                actions foreach (_ ())
            }

        def addAction(a: Action) = {
            actions = a :: actions
            a()
        }
    }

    def inverter(input: Wire, output: Wire) = {
        def invertAction() = {
            val inputSig = input.getSignal
            afterDelay(InverterDelay) {
                output setSignal !inputSig
            }
        }
        input addAction invertAction
    }

    // continued in Listing 18.10...
}
```

Listing 18.9 · The first half of the `BasicCircuitSimulation` class.

```
// ...continued from Listing 18.9
def andGate(a1: Wire, a2: Wire, output: Wire) = {
    def andAction() = {
        val a1Sig = a1.getSignal
        val a2Sig = a2.getSignal
        afterDelay(AndGateDelay) {
            output setSignal (a1Sig & a2Sig)
        }
    }
    a1 addAction andAction
    a2 addAction andAction
}

def orGate(o1: Wire, o2: Wire, output: Wire) = {
    def orAction() = {
        val o1Sig = o1.getSignal
        val o2Sig = o2.getSignal
        afterDelay(OrGateDelay) {
            output setSignal (o1Sig | o2Sig)
        }
    }
    o1 addAction orAction
    o2 addAction orAction
}

def probe(name: String, wire: Wire) = {
    def probeAction() = {
        println(name + " " + currentTime +
            " new-value = " + wire.getSignal)
    }
    wire addAction probeAction
}
```

Listing 18.10 · The second half of the `BasicCircuitSimulation` class.

because they depend on the technology of circuits that are simulated. That's why the delays are left abstract in class `BasicCircuitSimulation`, so that their concrete definition is delegated to a subclass.² The implementation of class `BasicCircuitSimulation`'s other members is described next.

The `Wire` class

A wire needs to support three basic actions:

`getSignal: Boolean`: returns the current signal on the wire.

`setSignal(sig: Boolean)`: sets the wire's signal to `sig`.

`addAction(p: Action)`: attaches the specified procedure `p` to the *actions* of the wire. The idea is that all action procedures attached to some wire will be executed every time the signal of the wire changes. Typically actions are added to a wire by components connected to the wire. An attached action is executed once at the time it is added to a wire, and after that, every time the signal of the wire changes.

Here is the implementation of the `Wire` class:

```
class Wire {  
    private var sigVal = false  
    private var actions: List[Action] = List()  
  
    def getSignal = sigVal  
  
    def setSignal(s: Boolean) =  
        if (s != sigVal) {  
            sigVal = s  
            actions foreach (_ ())  
        }  
  
    def addAction(a: Action) = {  
        actions = a :: actions  
        a()  
    }  
}
```

²The names of these “delay” methods start with a capital letter because they represent constants. They are methods so they can be overridden in subclasses. You'll find out how to do the same thing with `vals` in [Section 20.3](#).

Two private variables make up the state of a wire. The variable `sigVal` represents the current signal, and the variable `actions` represents the action procedures currently attached to the wire. The only interesting method implementation is the one for `setSignal`: When the signal of a wire changes, the new value is stored in the variable `sigVal`. Furthermore, all actions attached to a wire are executed. Note the shorthand syntax for doing this: “`actions foreach (_())`” applies the function, “`_()`”, to each element in the `actions` list. As described in [Section 8.5](#), the function “`_()`” is a shorthand for “`f => f()`”—*i.e.*, it takes a function (we’ll call it `f`) and applies it to the empty parameter list.

The inverter method

The only effect of creating an inverter is that an action is installed on its input wire. This action is invoked once at the time the action is installed, and thereafter every time the signal on the input changes. The effect of the action is that the value of the inverter’s output value is set (via `setSignal`) to the inverse of its input value. Since inverter gates have delays, this change should take effect only `InverterDelay` units of simulated time after the input value has changed and the action was executed. This suggests the following implementation:

```
def inverter(input: Wire, output: Wire) = {
    def invertAction() = {
        val inputSig = input.getSignal
        afterDelay(InverterDelay) {
            output setSignal !inputSig
        }
    }
    input addAction invertAction
}
```

The effect of the `inverter` method is to add `invertAction` to the input wire. This action, when invoked, gets the input signal and installs another action that inverts the output signal into the simulation agenda. This other action is to be executed after `InverterDelay` units of simulated time. Note how the method uses the `afterDelay` method of the simulation framework to create a new work item that’s going to be executed in the future.

The andGate and orGate methods

The implementation of and-gates is analogous to the implementation of inverters. The purpose of an and-gate is to output the conjunction of its input signals. This should happen at AndGateDelay simulated time units after any one of its two inputs changes. Hence, the following implementation:

```
def andGate(a1: Wire, a2: Wire, output: Wire) = {
    def andAction() = {
        val a1Sig = a1.getSignal
        val a2Sig = a2.getSignal
        afterDelay(AndGateDelay) {
            output setSignal (a1Sig & a2Sig)
        }
    }
    a1 addAction andAction
    a2 addAction andAction
}
```

The effect of the andGate method is to add andAction to both of its input wires a1 and a2. This action, when invoked, gets both input signals and installs another action that sets the output signal to the conjunction of both input signals. This other action is to be executed after AndGateDelay units of simulated time. Note that the output has to be recomputed if either of the input wires changes. That's why the same andAction is installed on each of the two input wires a1 and a2. The orGate method is implemented similarly, except it performs a logical-or instead of a logical-and.

Simulation output

To run the simulator, you need a way to inspect changes of signals on wires. To accomplish this, you can simulate the action of putting a probe on a wire:

```
def probe(name: String, wire: Wire) = {
    def probeAction() = {
        println(name + " " + currentTime +
            " new-value = " + wire.getSignal)
    }
    wire addAction probeAction
}
```

The effect of the `probe` procedure is to install a `probeAction` on a given wire. As usual, the installed action is executed every time the wire's signal changes. In this case it simply prints the name of the wire (which is passed as first parameter to `probe`), as well as the current simulated time and the wire's new value.

Running the simulator

After all these preparations, it's time to see the simulator in action. To define a concrete simulation, you need to inherit from a simulation framework class. To see something interesting, we'll create an abstract simulation class that extends `BasicCircuitSimulation` and contains method definitions for half-adders and full-adders as they were presented earlier in this chapter in [Listings 18.6 and 18.7](#), respectively. This class, which we'll call `CircuitSimulation`, is shown in [Listing 18.11](#).

```
package org.stairwaybook.simulation
abstract class CircuitSimulation
  extends BasicCircuitSimulation {
  def halfAdder(a: Wire, b: Wire, s: Wire, c: Wire) = {
    val d, e = new Wire
    orGate(a, b, d)
    andGate(a, b, c)
    inverter(c, e)
    andGate(d, e, s)
  }
  def fullAdder(a: Wire, b: Wire, cin: Wire,
    sum: Wire, cout: Wire) = {
    val s, c1, c2 = new Wire
    halfAdder(a, cin, s, c1)
    halfAdder(b, s, sum, c2)
    orGate(c1, c2, cout)
  }
}
```

[Listing 18.11 · The `CircuitSimulation` class.](#)

A concrete circuit simulation will be an object that inherits from class `CircuitSimulation`. The object still needs to fix the gate delays according to the circuit implementation technology that's simulated. Finally, you will also need to define the concrete circuit that's going to be simulated.

You can do these steps interactively in the Scala interpreter:

```
scala> import org.stairwaybook.simulation._  
import org.stairwaybook.simulation._
```

First, the gate delays. Define an object (call it `MySimulation`) that provides some numbers:

```
scala> object MySimulation extends CircuitSimulation {  
    def InverterDelay = 1  
    def AndGateDelay = 3  
    def OrGateDelay = 5  
}  
defined module MySimulation
```

Because you are going to access the members of the `MySimulation` object repeatedly, an import of the object keeps the subsequent code shorter:

```
scala> import MySimulation._  
import MySimulation._
```

Next, the circuit. Define four wires, and place probes on two of them:

```
scala> val input1, input2, sum, carry = new Wire  
input1: MySimulation.Wire =  
    BasicCircuitSimulation$Wire@111089b  
input2: MySimulation.Wire =  
    BasicCircuitSimulation$Wire@14c352e  
sum: MySimulation.Wire =  
    BasicCircuitSimulation$Wire@37a04c  
carry: MySimulation.Wire =  
    BasicCircuitSimulation$Wire@1fd10fa  
  
scala> probe("sum", sum)  
sum 0 new-value = false  
  
scala> probe("carry", carry)  
carry 0 new-value = false
```

Note that the probes immediately print an output. This is because every action installed on a wire is executed a first time when the action is installed.

Now define a half-adder connecting the wires:

```
scala> halfAdder(input1, input2, sum, carry)
```

Finally, set the signals, one after another, on the two input wires to true and run the simulation:

```
scala> input1 setSignal true
scala> run()
*** simulation started, time = 0 ***
sum 8 new-value = true

scala> input2 setSignal true
scala> run()
*** simulation started, time = 8 ***
carry 11 new-value = true
sum 15 new-value = false
```

18.7 Conclusion

This chapter brought together two techniques that seem disparate at first: mutable state and higher-order functions. Mutable state was used to simulate physical entities whose state changes over time. Higher-order functions were used in the simulation framework to execute actions at specified points in simulated time. They were also used in the circuit simulations as *triggers* that associate actions with state changes. Along the way, you saw a simple way to define a domain-specific language as a library. That's probably enough for one chapter!

If you feel like staying a bit longer, you might want to try more simulation examples. You can combine half-adders and full-adders to create larger circuits, or design new circuits from the basic gates defined so far and simulate them. In the next chapter, you'll learn about type parameterization in Scala, and see another example in which a combination of functional and imperative approaches yields a good solution.

Chapter 19

Type Parameterization

In this chapter, we'll explain the details of type parameterization in Scala. Along the way we'll demonstrate some of the techniques for information hiding introduced in [Chapter 13](#) by using a concrete example: the design of a class for purely functional queues. We're presenting type parameterization and information hiding together, because information hiding can be used to obtain more general type parameterization variance annotations.

Type parameterization allows you to write generic classes and traits. For example, sets are generic and take a type parameter: they are defined as `Set[T]`. As a result, any particular set instance might be a `Set[String]`, a `Set[Int]`, *etc.*, but it must be a set of *something*. Unlike Java, which allows raw types, Scala requires that you specify type parameters. Variance defines inheritance relationships of parameterized types, such as whether a `Set[String]`, for example, is a subtype of `Set[AnyRef]`.

The chapter contains three parts. The first part develops a data structure for purely functional queues. The second part develops techniques to hide internal representation details of this structure. The final part explains variance of type parameters and how it interacts with information hiding.

19.1 Functional queues

A functional queue is a data structure with three operations:

<code>head</code>	returns the first element of the queue
<code>tail</code>	returns a queue without its first element
<code>enqueue</code>	returns a new queue with a given element appended at the end

Unlike a mutable queue, a functional queue does not change its contents when an element is appended. Instead, a new queue is returned that contains the element. The goal of this chapter will be to create a class, which we'll name `Queue`, that works like this:

```
scala> val q = Queue(1, 2, 3)
q: Queue[Int] = Queue(1, 2, 3)

scala> val q1 = q enqueue 4
q1: Queue[Int] = Queue(1, 2, 3, 4)

scala> q
res0: Queue[Int] = Queue(1, 2, 3)
```

If `Queue` were a mutable implementation, the `enqueue` operation in the second input line above would affect the contents of `q`; in fact both the result, `q1`, and the original queue, `q`, would contain the sequence 1, 2, 3, 4 after the operation. But for a functional queue, the appended value shows up only in the result, `q1`, not in the queue, `q`, being operated on.

Purely functional queues also have some similarity with lists. Both are so called *fully persistent* data structures, where old versions remain available even after extensions or modifications. Both support `head` and `tail` operations. But where a list is usually extended at the front, using a `:::` operation, a queue is extended at the end, using `enqueue`.

How can this be implemented efficiently? Ideally, a functional (immutable) queue should not have a fundamentally higher overhead than an imperative (mutable) one. That is, all three operations, `head`, `tail`, and `enqueue`, should operate in constant time.

One simple approach to implement a functional queue would be to use a list as representation type. Then `head` and `tail` would just translate into the same operations on the list, whereas `enqueue` would be concatenation.

This would give the following implementation:

```
class SlowAppendQueue[T](elems: List[T]) { // Not efficient
    def head = elems.head
    def tail = new SlowAppendQueue(elems.tail)
    def enqueue(x: T) = new SlowAppendQueue(elems :: List(x))
}
```

The problem with this implementation is in the `enqueue` operation. It takes time proportional to the number of elements stored in the queue. If you want

constant time append, you could also try to reverse the order of the elements in the representation list, so that the last element that's appended comes first in the list. This would lead to the following implementation:

```
class SlowHeadQueue[T](smele: List[T]) { // Not efficient
    // smelete is elems reversed
    def head = smelete.last
    def tail = new SlowHeadQueue(smelete.init)
    def enqueue(x: T) = new SlowHeadQueue(x :: smelete)
}
```

Now enqueue is constant time, but head and tail are not. They now take time proportional to the number of elements stored in the queue.

Looking at these two examples, it does not seem easy to come up with an implementation that's constant time for all three operations. In fact, it looks doubtful that this is even possible! However, by combining the two operations you can get very close. The idea is to represent a queue by two lists, called `leading` and `trailing`. The `leading` list contains elements towards the front, whereas the `trailing` list contains elements towards the back of the queue in reversed order. The contents of the whole queue are at each instant equal to “`leading :::: trailing.reverse`”.

Now, to append an element, you just cons it to the `trailing` list using the `::` operator, so `enqueue` is constant time. This means that, when an initially empty queue is constructed from successive `enqueue` operations, the `trailing` list will grow whereas the `leading` list will stay empty. Then, before the first `head` or `tail` operation is performed on an empty `leading` list, the whole `trailing` list is copied to `leading`, reversing the order of the elements. This is done in an operation called `mirror`. Listing 19.1 shows an implementation of queues that uses this approach.

What is the complexity of this implementation of queues? The `mirror` operation might take time proportional to the number of queue elements, but only if list `leading` is empty. It returns directly if `leading` is non-empty. Because `head` and `tail` call `mirror`, their complexity might be linear in the size of the queue, too. However, the longer the queue gets, the less often `mirror` is called.

Indeed, assume a queue of length n with an empty `leading` list. Then `mirror` has to reverse-copy a list of length n . However, the next time `mirror` will have to do any work is once the `leading` list is empty again, which will

```
class Queue[T](  
    private val leading: List[T],  
    private val trailing: List[T]  
) {  
    private def mirror =  
        if (leading.isEmpty)  
            new Queue(trailing.reverse, Nil)  
        else  
            this  
  
    def head = mirror.leading.head  
  
    def tail = {  
        val q = mirror  
        new Queue(q.leading.tail, q.trailing)  
    }  
  
    def enqueue(x: T) =  
        new Queue(leading, x :: trailing)  
}
```

Listing 19.1 · A basic functional queue.

be the case after n `tail` operations. This means you can “charge” each of these n `tail` operations with one n ’th of the complexity of `mirror`, which means a constant amount of work. Assuming that `head`, `tail`, and `enqueue` operations appear with about the same frequency, the *amortized* complexity is hence constant for each operation. So functional queues are asymptotically just as efficient as mutable ones.

Now, there are some caveats that need to be attached to this argument. First, the discussion was only about asymptotic behavior; the constant factors might well be somewhat different. Second, the argument rested on the fact that `head`, `tail` and `enqueue` are called with about the same frequency. If `head` is called much more often than the other two operations, the argument is not valid, as each call to `head` might involve a costly re-organization of the list with `mirror`. The second caveat can be avoided; it is possible to design functional queues so that in a sequence of successive `head` operations only the first one might require a re-organization. You will find out at the end of this chapter how this is done.

19.2 Information hiding

The implementation of Queue shown in Listing 19.1 is now quite good with regards to efficiency. You might object, though, that this efficiency is paid for by exposing a needlessly detailed implementation. The Queue constructor, which is globally accessible, takes two lists as parameters, where one is reversed—hardly an intuitive representation of a queue. What’s needed is a way to hide this constructor from client code. In this section, we’ll show you some ways to accomplish this in Scala.

Private constructors and factory methods

In Java, you can hide a constructor by making it `private`. In Scala, the primary constructor does not have an explicit definition; it is defined implicitly by the class parameters and body. Nevertheless, it is still possible to hide the primary constructor by adding a `private` modifier in front of the class parameter list, as shown in Listing 19.2:

```
class Queue[T] private (
    private val leading: List[T],
    private val trailing: List[T]
)
```

Listing 19.2 · Hiding a primary constructor by making it private.

The `private` modifier between the class name and its parameters indicates that the constructor of Queue is private: it can be accessed only from within the class itself and its companion object. The class name Queue is still public, so you can use it as a type, but you cannot call its constructor:

```
scala> new Queue(List(1, 2), List(3))
<console>:9: error: constructor Queue in class Queue cannot
be accessed in object $iw
          new Queue(List(1, 2), List(3))
                           ^
```

Now that the primary constructor of class Queue can no longer be called from client code, there needs to be some other way to create new queues. One possibility is to add an auxiliary constructor, like this:

```
def this() = this(Nil, Nil)
```

The auxiliary constructor shown in the previous example builds an empty queue. As a refinement, the auxiliary constructor could take a list of initial queue elements:

```
def this(elems: T*) = this(elems.toList, Nil)
```

Recall that T^* is the notation for repeated parameters, as described in [Section 8.8](#).

Another possibility is to add a factory method that builds a queue from such a sequence of initial elements. A neat way to do this is to define an object Queue that has the same name as the class being defined and contains an apply method, as shown in [Listing 19.3](#):

```
object Queue {  
    // constructs a queue with initial elements 'xs'  
    def apply[T](xs: T*) = new Queue[T](xs.toList, Nil)  
}
```

[Listing 19.3](#) · An apply factory method in a companion object.

By placing this object in the same source file as class Queue, you make the object a companion object of the class. You saw in [Section 13.5](#) that a companion object has the same access rights as its class. Because of this, the apply method in object Queue can create a new Queue object, even though the constructor of class Queue is private.

Note that, because the factory method is called apply, clients can create queues with an expression such as Queue(1, 2, 3). This expression expands to Queue.apply(1, 2, 3) since Queue is an object instead of a function. As a result, Queue looks to clients as if it was a globally defined factory method. In reality, Scala has no globally visible methods; every method must be contained in an object or a class. However, using methods named apply inside global objects, you can support usage patterns that look like invocations of global methods.

An alternative: private classes

Private constructors and private members are one way to hide the initialization and representation of a class. Another more radical way is to hide the class itself and only export a trait that reveals the public interface of the

```
trait Queue[T] {
    def head: T
    def tail: Queue[T]
    def enqueue(x: T): Queue[T]
}

object Queue {
    def apply[T](xs: T*): Queue[T] =
        new QueueImpl[T](xs.toList, Nil)

    private class QueueImpl[T](
        private val leading: List[T],
        private val trailing: List[T])
        extends Queue[T] {

        def mirror =
            if (leading.isEmpty)
                new QueueImpl(trailing.reverse, Nil)
            else
                this

        def head: T = mirror.leading.head

        def tail: QueueImpl[T] = {
            val q = mirror
            new QueueImpl(q.leading.tail, q.trailing)
        }

        def enqueue(x: T) =
            new QueueImpl(leading, x :: trailing)
    }
}
```

Listing 19.4 · Type abstraction for functional queues.

class. The code in Listing 19.4 implements this design. There’s a trait Queue, which declares the methods head, tail, and enqueue. All three methods are implemented in a subclass QueueImpl, which is itself a private inner class of object Queue. This exposes to clients the same information as before, but using a different technique. Instead of hiding individual constructors and methods, this version hides the whole implementation class.

19.3 Variance annotations

Queue, as defined in Listing 19.4, is a trait, but not a type. Queue is not a type because it takes a type parameter.

As a result, you cannot create variables of type Queue:

```
scala> def doesNotCompile(q: Queue) = {}
<console>:8: error: class Queue takes type parameters
          def doesNotCompile(q: Queue) = {}
                           ^
```

Instead, trait Queue enables you to specify *parameterized* types, such as Queue[String], Queue[Int], or Queue[AnyRef]:

```
scala> def doesCompile(q: Queue[AnyRef]) = {}
doesCompile: (q: Queue[AnyRef])Unit
```

Thus, Queue is a trait and Queue[String] is a type. Queue is also called a *type constructor* because you can construct a type with it by specifying a type parameter. (This is analogous to constructing an object instance with a plain-old constructor by specifying a value parameter.) The type constructor Queue “generates” a family of types, which includes Queue[Int], Queue[String], and Queue[AnyRef].

You can also say that Queue is a *generic* trait. (Classes and traits that take type parameters are “generic,” but the types they generate are “parameterized,” not generic.) The term “generic” means that you are defining many specific types with one generically written class or trait. For example, trait Queue in Listing 19.4 defines a generic queue. Queue[Int] and Queue[String], *etc.*, would be the specific queues.

The combination of type parameters and subtyping poses some interesting questions. For example, are there any special subtyping relationships between members of the family of types generated by Queue[T]? More specifically, should a Queue[String] be considered a subtype of Queue[AnyRef]?

Or more generally, if S is a subtype of type T , then should $\text{Queue}[S]$ be considered a subtype of $\text{Queue}[T]$? If so, you could say that trait Queue is *covariant* (or “flexible”) in its type parameter T . Or, since it just has one type parameter, you could say simply that Queues are covariant. Covariant Queues would mean, for example, that you could pass a $\text{Queue}[\text{String}]$ to the `doesCompile` method shown previously, which takes a value parameter of type $\text{Queue}[\text{AnyRef}]$.

Intuitively, all this seems OK, since a queue of Strings looks like a special case of a queue of AnyRefs . In Scala, however, generic types have by default *nonvariant* (or “rigid”) subtyping. That is, with Queue defined as in Listing 19.4, queues with different element types would never be in a subtype relationship. A $\text{Queue}[\text{String}]$ would not be usable as a $\text{Queue}[\text{AnyRef}]$. However, you can demand covariant (flexible) subtyping of queues by changing the first line of the definition of class Queue like this:

```
trait Queue[+T] { ... }
```

Prefixing a formal type parameter with a $+$ indicates that subtyping is covariant (flexible) in that parameter. By adding this single character, you are telling Scala that you want $\text{Queue}[\text{String}]$, for example, to be considered a subtype of $\text{Queue}[\text{AnyRef}]$. The compiler will check that Queue is defined in a way that this subtyping is sound.

Besides $+$, there is also a prefix $-$, which indicates *contravariant* subtyping. If Queue were defined like this:

```
trait Queue[-T] { ... }
```

then if T is a subtype of type S , this would imply that $\text{Queue}[S]$ is a subtype of $\text{Queue}[T]$ (which in the case of queues would be rather surprising!). Whether a type parameter is covariant, contravariant, or nonvariant is called the parameter’s *variance*. The $+$ and $-$ symbols you can place next to type parameters are called *variance annotations*.

In a purely functional world, many types are naturally covariant (flexible). However, the situation changes once you introduce mutable data. To find out why, consider the simple type of one-element cells that can be read or written, shown in Listing 19.5.

The `Cell` type of Listing 19.5 is declared nonvariant (rigid). For the sake of argument, assume for a moment that `Cell` was declared covariant instead—*i.e.*, it was declared `class Cell[+T]`—and that this passed the

```
class Cell[T](init: T) {  
    private[this] var current = init  
    def get = current  
    def set(x: T) = { current = x }  
}
```

Listing 19.5 · A nonvariant (rigid) Cell class.

Scala compiler. (It doesn't, and we'll explain why shortly.) Then you could construct the following problematic statement sequence:

```
val c1 = new Cell[String]("abc")  
val c2: Cell[Any] = c1  
c2.set(1)  
val s: String = c1.get
```

Seen by itself, each of these four lines looks OK. The first line creates a cell of strings and stores it in a `val` named `c1`. The second line defines a new `val`, `c2`, of type `Cell[Any]`, which initialized with `c1`. This is OK since Cells are assumed to be covariant. The third line sets the value of cell `c2` to 1. This is also OK because the assigned value 1 is an instance of `c2`'s element type `Any`. Finally, the last line assigns the element value of `c1` into a string. Nothing strange here, as both the sides are of the same type. But taken together, these four lines end up assigning the integer 1 to the string `s`. This is clearly a violation of type soundness.

Which operation is to blame for the runtime fault? It must be the second one, which uses covariant subtyping. The other statements are too simple and fundamental. Thus, a `Cell` of `String` is *not* also a `Cell` of `Any`, because there are things you can do with a `Cell` of `Any` that you cannot do with a `Cell` of `String`. You cannot use `set` with an `Int` argument on a `Cell` of `String`, for example.

In fact, were you to pass the covariant version of `Cell` to the Scala compiler, you would get a compile-time error:

```
Cell.scala:7: error: covariant type T occurs in  
contravariant position in type T of value x  
def set(x: T) = current = x  
          ^
```

Variance and arrays

It's interesting to compare this behavior with arrays in Java. In principle, arrays are just like cells except that they can have more than one element. Nevertheless, arrays are treated as covariant in Java.

You can try an example analogous to the cell interaction described here with Java arrays:

```
// this is Java
String[] a1 = { "abc" };
Object[] a2 = a1;
a2[0] = new Integer(17);
String s = a1[0];
```

If you try out this example, you will find that it compiles. But executing the program will cause an `ArrayStore` exception to be thrown when `a2[0]` is assigned to an `Integer`:

```
Exception in thread "main" java.lang.ArrayStoreException:
java.lang.Integer
at JavaArrays.main(JavaArrays.java:8)
```

What happens here is that Java stores the element type of the array at run-time. Then, every time an array element is updated, the new element value is checked against the stored type. If it is not an instance of that type, an `ArrayStore` exception is thrown.

You might ask why Java adopted this design, which seems both unsafe and expensive. When asked this question, James Gosling, the principal inventor of the Java language, answered that they wanted to have a simple means to treat arrays generically. For instance, they wanted to be able to write a method to sort all elements of an array, using a signature like the following that takes an array of `Object`:

```
void sort(Object[] a, Comparator cmp) { ... }
```

Covariance of arrays was needed so that arrays of arbitrary reference types could be passed to this `sort` method. Of course, with the arrival of Java generics, such a `sort` method can now be written with a type parameter, so the covariance of arrays is no longer necessary. For compatibility reasons, though, it has persisted in Java to this day.

Scala tries to be purer than Java in not treating arrays as covariant. Here's what you get if you translate the first two lines of the array example to Scala:

```
scala> val a1 = Array("abc")
a1: Array[String] = Array(abc)

scala> val a2: Array[Any] = a1
<console>:8: error: type mismatch;
         found   : Array[String]
         required: Array[Any]
              val a2: Array[Any] = a1
                           ^
```

What happened here is that Scala treats arrays as nonvariant (rigid), so an `Array[String]` is not considered to conform to an `Array[Any]`. However, sometimes it is necessary to interact with legacy methods in Java that use an `Object` array as a means to emulate a generic array. For instance, you might want to call a `sort` method like the one described previously with an array of `Strings` as argument. To make this possible, Scala lets you cast an array of `Ts` to an array of any supertype of `T`:

```
scala> val a2: Array[Object] =
           a1.asInstanceOf[Array[Object]]
a2: Array[Object] = Array(abc)
```

The cast is always legal at compile-time, and it will always succeed at run-time because the JVM's underlying run-time model treats arrays as covariant, just as Java the language does. But you might get `ArrayStore` exceptions afterwards, again just as you would in Java.

19.4 Checking variance annotations

Now that you have seen some examples where variance is unsound, you may be wondering which kind of class definitions need to be rejected and which can be accepted. So far, all violations of type soundness involved some reassignable field or array element. The purely functional implementation of queues, on the other hand, looks like a good candidate for covariance. However, the following example shows that you can "engineer" an unsound situation even if there is no reassignable field.

To set up the example, assume that queues as defined in Listing 19.4 are covariant. Then, create a subclass of queues that specializes the element type to Int and overrides the enqueue method:

```
class StrangeIntQueue extends Queue[Int] {  
    override def enqueue(x: Int) = {  
        println(math.sqrt(x))  
        super.enqueue(x)  
    }  
}
```

The enqueue method in StrangeIntQueue prints out the square root of its (integer) argument before doing the append proper.

Now, you can write a counterexample in two lines:

```
val x: Queue[Any] = new StrangeIntQueue  
x.enqueue("abc")
```

The first of these two lines is valid because StrangeIntQueue is a subclass of Queue[Int] and, assuming covariance of queues, Queue[Int] is a subtype of Queue[Any]. The second line is valid because you can append a String to a Queue[Any]. However, taken together, these two lines have the effect of applying a square root method to a string, which makes no sense.

Clearly it's not just mutable fields that make covariant types unsound. The problem is more general. It turns out that as soon as a generic parameter type appears as the type of a method parameter, the containing class or trait may not be covariant in that type parameter.

For queues, the enqueue method violates this condition:

```
class Queue[+T] {  
    def enqueue(x: T) =  
    ...  
}
```

Running a modified queue class like the one above through a Scala compiler would yield:

```
Queues.scala:11: error: covariant type T occurs in  
contravariant position in type T of value x  
def enqueue(x: T) =  
^
```

Reassignable fields are a special case of the rule that disallows type parameters annotated with `+` from being used as method parameter types. As mentioned in [Section 18.2](#), a reassignable field, “`var x: T`”, is treated in Scala as a getter method, “`def x: T`”, and a setter method, “`def x_=(y: T)`”. As you can see, the setter method has a parameter of the field’s type `T`. So that type may not be covariant.

The fast track

In the rest of this section, we’ll describe the mechanism by which the Scala compiler checks variance annotations. If you’re not interested in such detail right now, you can safely skip to [Section 19.5](#). The most important thing to understand is that the Scala compiler will check any variance annotations you place on type parameters. For example, if you try to declare a type parameter to be covariant (by adding a `+`), but that could lead to potential runtime errors, your program won’t compile.

To verify correctness of variance annotations, the Scala compiler classifies all positions in a class or trait body as *positive*, *negative* or *neutral*. A “position” is any location in the class or trait (but from now on we’ll just write “class”) body where a type parameter may be used. For example, every method value parameter is a position because a method value parameter has a type. Therefore a type parameter could appear in that position.

The compiler checks each use of each of the class’s type parameters. Type parameters annotated with `+` may only be used in positive positions, while type parameters annotated with `-` may only be used in negative positions. A type parameter with no variance annotation may be used in any position, and is, therefore, the only kind of type parameter that can be used in neutral positions of the class body.

To classify the positions, the compiler starts from the declaration of a type parameter and then moves inward through deeper nesting levels. Positions at the top level of the declaring class are classified as positive. By default, positions at deeper nesting levels are classified the same as that at enclosing levels, but there are a handful of exceptions where the classification changes. Method value parameter positions are classified to the *flipped* classification relative to positions outside the method, where the flip of a positive classification is negative, the flip of a negative classification is positive, and the flip of a neutral classification is still neutral.

Besides method value parameter positions, the current classification is also flipped at the type parameters of methods. A classification is sometimes

flipped at the type argument position of a type, such as the Arg in C[Arg], depending on the variance of the corresponding type parameter. If C's type parameter is annotated with a + then the classification stays the same. If C's type parameter is annotated with a -, then the current classification is flipped. If C's type parameter has no variance annotation then the current classification is changed to neutral.

As a somewhat contrived example, consider the following class definition, where several positions are annotated with their classifications, $^+$ (for positive) or $^-$ (for negative):

```
abstract class Cat[-T, +U] {  
    def meow[W^-](volume: T^-, listener: Cat[U^+, T^-]^-)  
        : Cat[Cat[U^+, T^-]^-, U^+]^+  
}
```

The positions of the type parameter, W, and the two value parameters, volume and listener, are all negative. Looking at the result type of meow, the position of the first Cat[U, T] argument is negative because Cat's first type parameter, T, is annotated with a -. The type U inside this argument is again in positive position (two flips), whereas the type T inside that argument is still in negative position.

You see from this discussion that it's quite hard to keep track of variance positions. That's why it's a welcome relief that the Scala compiler does this job for you.

Once the classifications are computed, the compiler checks that each type parameter is only used in positions that are classified appropriately. In this case, T is only used in negative positions, and U is only used in positive positions. So class Cat is type correct.

19.5 Lower bounds

Back to the Queue class. You saw that the previous definition of Queue[T] shown in [Listing 19.4](#) cannot be made covariant in T because T appears as a type of a parameter of the enqueue method, and that's a negative position.

Fortunately, there's a way to get unstuck: you can generalize enqueue by making it polymorphic (*i.e.*, giving the enqueue method itself a type parameter) and using a *lower bound* for its type parameter. [Listing 19.6](#) shows a new formulation of Queue that implements this idea.

```
class Queue[+T] (private val leading: List[T],  
    private val trailing: List[T] ) {  
  def enqueue[U >: T](x: U) =  
    new Queue[U](leading, x :: trailing) // ...  
}
```

Listing 19.6 · A type parameter with a lower bound.

The new definition gives `enqueue` a type parameter `U`, and with the syntax, “`U >: T`”, defines `T` as the lower bound for `U`. As a result, `U` is required to be a supertype of `T`.¹ The parameter to `enqueue` is now of type `U` instead of type `T`, and the return value of the method is now `Queue[U]` instead of `Queue[T]`.

For example, suppose there is a class `Fruit` with two subclasses, `Apple` and `Orange`. With the new definition of class `Queue`, it is possible to append an `Orange` to a `Queue[Apple]`. The result will be a `Queue[Fruit]`.

This revised definition of `enqueue` is type correct. Intuitively, if `T` is a more specific type than expected (for example, `Apple` instead of `Fruit`), a call to `enqueue` will still work because `U` (`Fruit`) will still be a supertype of `T` (`Apple`).²

The new definition of `enqueue` is arguably better than the old, because it is more general. Unlike the old version, the new definition allows you to append an arbitrary supertype `U` of the queue element type `T`. The result is then a `Queue[U]`. Together with queue covariance, this gives the right kind of flexibility for modeling queues of different element types in a natural way.

This shows that variance annotations and lower bounds play well together. They are a good example of *type-driven design*, where the types of an interface guide its detailed design and implementation. In the case of queues, it’s likely you would not have thought of the refined implementation of `enqueue` with a lower bound. But you might have decided to make queues covariant, in which case, the compiler would have pointed out the variance error for `enqueue`. Correcting the variance error by adding a lower bound makes `enqueue` more general and queues as a whole more usable.

¹Supertype and subtype relationships are reflexive, which means a type is both a supertype and a subtype of itself. Even though `T` is a lower bound for `U`, you could still pass in a `T` to `enqueue`.

²Technically, what happens is a flip occurs for lower bounds. The type parameter `U` is in a negative position (1 flip), while the lower bound (`>: T`) is in a positive position (2 flips).

This observation is also the main reason that Scala prefers declaration-site variance over use-site variance as it is found in Java's wildcards. With use-site variance, you are on your own designing a class. It will be the clients of the class that need to put in the wildcards, and if they get it wrong, some important instance methods will no longer be applicable. Variance being a tricky business, users usually get it wrong, and they come away thinking that wildcards and generics are overly complicated. With definition-side variance, you express your intent to the compiler, and the compiler will double check that the methods you want available will indeed be available.

19.6 Contravariance

So far in this chapter, all examples you've seen were either covariant or non-variant. But there are also cases where contravariance is natural. For instance, consider the trait of output channels shown in [Listing 19.7](#):

```
trait OutputChannel[-T] {  
    def write(x: T)  
}
```

[Listing 19.7](#) · A contravariant output channel.

Here, `OutputChannel` is defined to be contravariant in `T`. So an output channel of `AnyRefs`, say, is a subtype of an output channel of `Strings`. Although it may seem non-intuitive, it actually makes sense. To see why, consider what you can do with an `OutputChannel[String]`. The only supported operation is writing a `String` to it. The same operation can also be done on an `OutputChannel[AnyRef]`. So it is safe to substitute an `OutputChannel[AnyRef]` for an `OutputChannel[String]`. By contrast, it would not be safe to substitute an `OutputChannel[String]` where an `OutputChannel[AnyRef]` is required. After all, you can send any object to an `OutputChannel[AnyRef]`, whereas an `OutputChannel[String]` requires that the written values are all strings.

This reasoning points to a general principle in type system design: It is safe to assume that a type `T` is a subtype of a type `U` if you can substitute a value of type `T` wherever a value of type `U` is required. This is called the *Liskov Substitution Principle*. The principle holds if `T` supports the same operations as `U`, and all of `T`'s operations require less and provide more

```
trait Function1[-S, +T] {  
    def apply(x: S): T  
}
```

Listing 19.8 · Covariance and contravariance of Function1s.

than the corresponding operations in U. In the case of output channels, an `OutputChannel[AnyRef]` can be a subtype of an `OutputChannel[String]` because the two support the same `write` operation, and this operation requires less in `OutputChannel[AnyRef]` than in `OutputChannel[String]`. “Less” means the argument is only required to be an `AnyRef` in the first case, whereas it is required to be a `String` in the second case.

Sometimes covariance and contravariance are mixed in the same type. A prominent example is Scala’s function traits. For instance, whenever you write the function type `A => B`, Scala expands this to `Function1[A, B]`. The definition of `Function1` in the standard library uses both covariance and contravariance: the `Function1` trait is contravariant in the function argument type `S` and covariant in the result type `T`, as shown in Listing 19.8. This satisfies the Liskov Substitution Principle because arguments are something that’s required, whereas results are something that’s provided.

As an example, consider the application shown in Listing 19.9. Here, class `Publication` contains one parametric field, `title`, of type `String`. Class `Book` extends `Publication` and forwards its string `title` parameter to the constructor of its superclass. The `Library` singleton object defines a set of books and a method `printBookList`, which takes a function, named `info`, of type `Book => AnyRef`. In other words, the type of the lone parameter to `printBookList` is a function that takes one `Book` argument and returns an `AnyRef`. The `Customer` application defines a method, `getTitle`, which takes a `Publication` as its lone parameter and returns a `String`, the title of the passed `Publication`.

Now take a look at the last line in `Customer`. This line invokes `Library`’s `printBookList` method and passes `getTitle`, wrapped in a function value:

```
Library.printBookList(getTitle)
```

This line of code type checks even though `String`, the function’s result type, is a subtype of `AnyRef`, the result type of `printBookList`’s `info` parameter. This code passes the compiler because function result types are de-

```
class Publication(val title: String)
class Book(title: String) extends Publication(title)

object Library {
    val books: Set[Book] =
        Set(
            new Book("Programming in Scala"),
            new Book("Walden")
        )
    def printBookList(info: Book => AnyRef) = {
        for (book <- books) println(info(book))
    }
}

object Customer extends App {
    def getTitle(p: Publication): String = p.title
    Library.printBookList(getTitle)
}
```

Listing 19.9 · Demonstration of function type parameter variance.

clared to be covariant (the +T in Listing 19.8). If you look inside the body of `printBookList`, you can get a glimpse of why this makes sense.

The `printBookList` method iterates through its book list and invokes the passed function on each book. It passes the `AnyRef` result returned by `info` to `println`, which invokes `toString` on it and prints the result. This activity will work with `String` as well as any other subclass of `AnyRef`, which is what covariance of function result types means.

Now consider the parameter type of the function being passed to the `printBookList` method. Although `printBookList`'s parameter type is declared as `Book`, the `getTitle` we're passing in takes a `Publication`, a *supertype* of `Book`. The reason this works is that since `printBookList`'s parameter type is `Book`, the body of the `printBookList` method will only be allowed to pass a `Book` into the function. And because `getTitle`'s parameter type is `Publication`, the body of that function will only be able to access on its parameter, `p`, members that are declared in class `Publication`. Because any method declared in `Publication` is also available on its subclass `Book`, everything should work, which is what contravariance of function parameter




Figure 19.1 · Covariance and contravariance in function type parameters.

types means. You can see all this graphically in [Figure 19.1](#).

The code in [Listing 19.9](#) compiles because `Publication => String` is a subtype of `Book => AnyRef`, as shown in the center of the [Figure 19.1](#). Because the result type of a `Function1` is defined as covariant, the inheritance relationship of the two result types, shown at the right of the diagram, is in the same direction as that of the two functions shown in the center. By contrast, because the parameter type of a `Function1` is defined as contravariant, the inheritance relationship of the two parameter types, shown at the left of the diagram, is in the opposite direction as that of the two functions.

19.7 Object private data

The `Queue` class seen so far has a problem in that the `mirror` operation will repeatedly copy the `trailing` into the `leading` list if `head` is called several times in a row on a list where `leading` is empty. The wasteful copying could be avoided by adding some judicious side effects. [Listing 19.10](#) presents a new implementation of `Queue`, which performs at most one `trailing` to `leading` adjustment for any sequence of `head` operations.

What's different with respect to the previous version is that now `leading` and `trailing` are reassignable variables, and `mirror` performs the reverse copy from `trailing` to `leading` as a side effect on the current queue instead of returning a new queue. This side effect is purely internal to the implementation of the `Queue` operation; since `leading` and `trailing` are private variables, the effect is not visible to clients of `Queue`. So by the terminology established in [Chapter 18](#), the new version of `Queue` still defines purely functional objects, in spite of the fact that they now contain reassignable fields.

```
class Queue[+T] private {
    private[this] var leading: List[T],
    private[this] var trailing: List[T]
} {

    private def mirror() =
        if (leading.isEmpty) {
            while (!trailing.isEmpty) {
                leading = trailing.head :: leading
                trailing = trailing.tail
            }
        }

    def head: T = {
        mirror()
        leading.head
    }

    def tail: Queue[T] = {
        mirror()
        new Queue(leading.tail, trailing)
    }

    def enqueue[U >: T](x: U) =
        new Queue[U](leading, x :: trailing)
}
```

Listing 19.10 · An optimized functional queue.

You might wonder whether this code passes the Scala type checker. After all, queues now contain two reassignable fields of the covariant parameter type `T`. Is this not a violation of the variance rules? It would be indeed, except for the detail that `leading` and `trailing` have a `private[this]` modifier, and are thus declared to be object private.

As mentioned in [Section 13.5](#), object private members can be accessed only from within the object in which they are defined. It turns out that accesses to variables from the same object in which they are defined do not cause problems with variance. The intuitive explanation is that, in order to construct a case where variance would lead to type errors, you need to have a reference to a containing object that has a statically weaker type than the type

the object was defined with. For accesses to object private values, however, this is impossible.

Scala's variance checking rules contain a special case for object private definitions. Such definitions are omitted when it is checked that a type parameter with either a + or - annotation occurs only in positions that have the same variance classification. Therefore, the code in [Listing 19.10](#) compiles without error. On the other hand, if you had left out the [this] qualifiers from the two private modifiers, you would see two type errors:

```
Queues.scala:1: error: covariant type T occurs in
contravariant position in type List[T] of parameter of
setter leading_=
class Queue[+T] private (private var leading: List[T],
^
Queues.scala:1: error: covariant type T occurs in
contravariant position in type List[T] of parameter of
setter trailing_=
                    private var trailing: List[T]) {
^
```

19.8 Upper bounds

In [Listing 16.1](#) on page 356, we showed a merge sort function for lists that took a comparison function as a first argument and a list to sort as a second, curried argument. Another way you might want to organize such a sort function is by requiring the type of the list to mix in the `Ordered` trait. As mentioned in [Section 12.4](#), by mixing `Ordered` into a class and implementing `Ordered`'s one abstract method, `compare`, you enable clients to compare instances of that class with `<`, `>`, `<=`, and `>=`. For example, [Listing 19.11](#) shows `Ordered` being mixed into a `Person` class.

As a result, you can compare two people like this:

```
scala> val robert = new Person("Robert", "Jones")
robert: Person = Robert Jones

scala> val sally = new Person("Sally", "Smith")
sally: Person = Sally Smith

scala> robert < sally
res0: Boolean = true
```

```
class Person(val firstName: String, val lastName: String)
    extends Ordered[Person] {

    def compare(that: Person) = {
        val lastNameComparison =
            lastName.compareToIgnoreCase(that.lastName)
        if (lastNameComparison != 0)
            lastNameComparison
        else
            firstName.compareToIgnoreCase(that.firstName)
    }

    override def toString = firstName + " " + lastName
}
```

Listing 19.11 · A Person class that mixes in the Ordered trait.

```
def orderedMergeSort[T <: Ordered[T]](xs: List[T]): List[T] = {
    def merge(xs: List[T], ys: List[T]): List[T] =
        (xs, ys) match {
            case (Nil, _) => ys
            case (_, Nil) => xs
            case (x :: xs1, y :: ys1) =>
                if (x < y) x :: merge(xs1, ys)
                else y :: merge(xs, ys1)
        }
    val n = xs.length / 2
    if (n == 0) xs
    else {
        val (ys, zs) = xs splitAt n
        merge(orderedMergeSort(ys), orderedMergeSort(zs))
    }
}
```

Listing 19.12 · A merge sort function with an upper bound.

To require that the type of the list passed to your new sort function mixes in `Ordered`, you need to use an *upper bound*. An upper bound is specified similar to a lower bound, except instead of the `>`: symbol used for lower bounds, you use a `<:` symbol, as shown in Listing 19.12.

With the “`T <: Ordered[T]`” syntax, you indicate that the type parameter, `T`, has an upper bound, `Ordered[T]`. This means that the element type of the list passed to `orderedMergeSort` must be a subtype of `Ordered`. Thus, you could pass a `List[Person]` to `orderedMergeSort` because `Person` mixes in `Ordered`.

For example, consider this list:

```
scala> val people = List(  
    new Person("Larry", "Wall"),  
    new Person("Anders", "Hejlsberg"),  
    new Person("Guido", "van Rossum"),  
    new Person("Alan", "Kay"),  
    new Person("Yukihiro", "Matsumoto")  
)  
people: List[Person] = List(Larry Wall, Anders Hejlsberg,  
    Guido van Rossum, Alan Kay, Yukihiro Matsumoto)
```

Because the element type of this list, `Person`, mixes in (and is therefore a subtype of) `Ordered[People]`, you can pass the list to `orderedMergeSort`:

```
scala> val sortedPeople = orderedMergeSort(people)  
sortedPeople: List[Person] = List(Anders Hejlsberg, Alan Kay,  
    Yukihiro Matsumoto, Guido van Rossum, Larry Wall)
```

Now, although the sort function shown in Listing 19.12 serves as a useful illustration of upper bounds, it isn’t actually the most general way in Scala to design a sort function that takes advantage of the `Ordered` trait.

For example, you couldn’t use the `orderedMergeSort` function to sort a list of integers, because class `Int` is not a subtype of `Ordered[Int]`:

```
scala> val wontCompile = orderedMergeSort(List(3, 2, 1))  
<console>:5: error: inferred type arguments [Int] do  
    not conform to method orderedMergeSort's type  
        parameter bounds [T <: Ordered[T]]  
            val wontCompile = orderedMergeSort(List(3, 2, 1))  
                           ^
```

In Section 21.6, we'll show you how to use *implicit parameters* and *context bounds* to achieve a more general solution.

19.9 Conclusion

In this chapter you saw several techniques for information hiding: private constructors, factory methods, type abstraction, and object private members. You also learned how to specify data type variance and what it implies for class implementation. Finally, you saw two techniques which help in obtaining flexible variance annotations: lower bounds for method type parameters and `private[this]` annotations for local fields and methods.

Chapter 20

Abstract Members

A member of a class or trait is *abstract* if the member does not have a complete definition in the class. Abstract members are intended to be implemented in subclasses of the class in which they are declared. This idea is found in many object-oriented languages. For instance, Java lets you declare abstract methods. Scala also lets you declare such methods, as you saw in [Section 10.2](#). But Scala goes beyond that and implements the idea in its full generality: Besides methods, you can declare abstract fields and even abstract types as members of classes and traits.

In this chapter we'll describe all four kinds of abstract member: `vals`, `vars`, methods, and types. Along the way we'll discuss pre-initialized fields, lazy `vals`, path-dependent types, and enumerations.

20.1 A quick tour of abstract members

The following trait declares one of each kind of abstract member: an abstract type (`T`), method (`transform`), `val` (`initial`), and `var` (`current`):

```
trait Abstract {  
    type T  
    def transform(x: T): T  
    val initial: T  
    var current: T  
}
```

A concrete implementation of `Abstract` needs to fill in definitions for each of its abstract members. Here is an example implementation that provides

these definitions:

```
class Concrete extends Abstract {  
    type T = String  
    def transform(x: String) = x + x  
    val initial = "hi"  
    var current = initial  
}
```

The implementation gives a concrete meaning to the type name T by defining it as an alias of type String. The transform operation concatenates a given string with itself, and the initial and current values are both set to "hi".

This example gives you a rough first idea of what kinds of abstract members exist in Scala. The remainder of the chapter will present the details and explain what the new forms of abstract members, as well as type members in general, are good for.

20.2 Type members

As you can see from the example in the previous section, the term *abstract type* in Scala means a type declared (with the “type” keyword) to be a member of a class or trait, without specifying a definition. Classes themselves may be abstract, and traits are by definition abstract, but neither of these are what are referred to as *abstract types* in Scala. An abstract type in Scala is always a member of some class or trait, such as type T in trait Abstract.

You can think of a non-abstract (or “concrete”) type member, such as type T in class Concrete, as a way to define a new name, or *alias*, for a type. In class Concrete, for example, the type String is given the alias T. As a result, anywhere T appears in the definition of class Concrete, it means String. This includes the parameter and result types of transform, initial, and current, which mention T when they are declared in super-trait Abstract. Thus, when class Concrete implements these methods, those Ts are interpreted to mean String.

One reason to use a type member is to define a short, descriptive alias for a type whose real name is more verbose, or less obvious in meaning, than the alias. Such type members can help clarify the code of a class or trait. The other main use of type members is to declare abstract types that must

be defined in subclasses. This use, which was demonstrated in the previous section, will be described in detail later in this chapter.

20.3 Abstract vals

An abstract val declaration has a form like:

```
val initial: String
```

It gives a name and type for a val, but not its value. This value has to be provided by a concrete val definition in a subclass. For instance, class Concrete implemented the val using:

```
val initial = "hi"
```

You use an abstract val declaration in a class when you do not know the correct value in the class, but you do know that the variable will have an unchangeable value in each instance of the class.

An abstract val declaration resembles an abstract parameterless method declaration such as:

```
def initial: String
```

Client code would refer to both the val and the method in exactly the same way (*i.e.*, `obj.initial`). However, if `initial` is an abstract val, the client is guaranteed that `obj.initial` will yield the same value every time it is referenced. If `initial` were an abstract method, that guarantee would not hold because, in that case, `initial` could be implemented by a concrete method that returns a different value every time it's called.

In other words, an abstract val constrains its legal implementation: Any implementation must be a val definition; it may not be a var or a def. Abstract method declarations, on the other hand, may be implemented by both concrete method definitions and concrete val definitions. Given the abstract class `Fruit` shown in Listing 20.1, class `Apple` would be a legal subclass implementation, but class `BadApple` would not.

```
abstract class Fruit {  
    val v: String // 'v' for value  
    def m: String // 'm' for method  
}  
  
abstract class Apple extends Fruit {  
    val v: String  
    val m: String // OK to override a 'def' with a 'val'  
}  
  
abstract class BadApple extends Fruit {  
    def v: String // ERROR: cannot override a 'val' with a 'def'  
    def m: String  
}
```

Listing 20.1 · Overriding abstract vals and parameterless methods.

20.4 Abstract vars

Like an abstract val, an abstract var declares just a name and a type, but not an initial value. For instance, Listing 20.2 shows a trait `AbstractTime`, which declares two abstract variables named `hour` and `minute`:

```
trait AbstractTime {  
    var hour: Int  
    var minute: Int  
}
```

Listing 20.2 · Declaring abstract vars.

What is the meaning of abstract vars like `hour` and `minute`? You saw in Section 18.2 that vars declared as members of classes come equipped with getter and setter methods. This holds for abstract vars as well. If you declare an abstract var named `hour`, for example, you implicitly declare an abstract getter method, `hour`, and an abstract setter method, `hour_=`. There's no reassignable field to be defined—that will come in subclasses that define the concrete implementation of the abstract var. For instance, the definition of `AbstractTime` shown in Listing 20.2 is exactly equivalent to the definition shown in Listing 20.3.

```
trait AbstractTime {  
    def hour: Int          // getter for 'hour'  
    def hour_=(x: Int)     // setter for 'hour'  
    def minute: Int        // getter for 'minute'  
    def minute_=(x: Int)   // setter for 'minute'  
}
```

Listing 20.3 · How abstract vars are expanded into getters and setters.

20.5 Initializing abstract vals

Abstract `vals` sometimes play a role analogous to superclass parameters: they let you provide details in a subclass that are missing in a superclass. This is particularly important for traits, because traits don't have a constructor to which you could pass parameters. So the usual notion of parameterizing a trait works via abstract `vals` that are implemented in subclasses.

As an example, consider a reformulation of class `Rational` from [Chapter 6](#), as shown in [Listing 6.5 on page 151](#), as a trait:

```
trait RationalTrait {  
    val numerArg: Int  
    val denomArg: Int  
}
```

The `Rational` class from [Chapter 6](#) had two parameters: `n` for the numerator of the rational number, and `d` for the denominator. The `RationalTrait` trait given here defines instead two abstract `vals`: `numerArg` and `denomArg`. To instantiate a concrete instance of that trait, you need to implement the abstract `val` definitions. Here's an example:

```
new RationalTrait {  
    val numerArg = 1  
    val denomArg = 2  
}
```

Here the keyword `new` appears in front of a trait name, `RationalTrait`, which is followed by a class body in curly braces. This expression yields an instance of an [*anonymous class*](#) that mixes in the trait and is defined by the

body. This particular anonymous class instantiation has an effect analogous to the instance creation new Rational(1, 2).

The analogy is not perfect, however. There's a subtle difference concerning the order in which expressions are initialized. When you write:

```
new Rational(expr1, expr2)
```

the two expressions, expr1 and expr2, are evaluated before class Rational is initialized, so the values of expr1 and expr2 are available for the initialization of class Rational.

For traits, the situation is the opposite. When you write:

```
new RationalTrait {  
    val numerArg = expr1  
    val denomArg = expr2  
}
```

the expressions, expr1 and expr2, are evaluated as part of the initialization of the anonymous class, but the anonymous class is initialized *after* the RationalTrait. So the values of numerArg and denomArg are not available during the initialization of RationalTrait (more precisely, a selection of either value would yield the default value for type Int, 0). For the definition of RationalTrait given previously, this is not a problem, because the trait's initialization does not make use of values numerArg or denomArg. However, it becomes a problem in the variant of RationalTrait shown in Listing 20.4, which defines normalized numerators and denominators.

If you try to instantiate this trait with some numerator and denominator expressions that are not simple literals, you'll get an exception:

```
scala> val x = 2  
x: Int = 2  
  
scala> new RationalTrait {  
    val numerArg = 1 * x  
    val denomArg = 2 * x  
}  
  
java.lang.IllegalArgumentException: requirement failed  
  at scala.Predef$.require(Predef.scala:207)  
  at RationalTrait$class.$init$(<console>:10)  
... 28 elided
```

```
trait RationalTrait {
    val numerArg: Int
    val denomArg: Int
    require(denomArg != 0)
    private val g = gcd(numerArg, denomArg)
    val numer = numerArg / g
    val denom = denomArg / g
    private def gcd(a: Int, b: Int): Int =
        if (b == 0) a else gcd(b, a % b)
    override def toString = numer + "/" + denom
}
```

Listing 20.4 · A trait that uses its abstract vals.

The exception in this example was thrown because `denomArg` still had its default value of 0 when class `RationalTrait` was initialized, which caused the `require` invocation to fail.

This example demonstrates that initialization order is not the same for class parameters and abstract fields. A class parameter argument is evaluated *before* it is passed to the class constructor (unless the parameter is by-name). An implementing `val` definition in a subclass, by contrast, is evaluated only *after* the superclass has been initialized.

Now that you understand why abstract `vals` behave differently from parameters, it would be good to know what can be done about this. Is it possible to define a `RationalTrait` that can be initialized robustly, without fearing errors due to uninitialized fields? In fact, Scala offers two alternative solutions to this problem, *pre-initialized fields* and *lazy vals*. They are presented in the remainder of this section.

Pre-initialized fields

The first solution, pre-initialized fields, lets you initialize a field of a subclass before the superclass is called. To do this, simply place the field definition in braces before the superclass constructor call. As an example, Listing 20.5 shows another attempt to create an instance of `RationalTrait`. As you see from this example, the initialization section comes before the mention of the supertrait `RationalTrait`. Both are separated by a `with`.

```
scala> new {
    val numerArg = 1 * x
    val denomArg = 2 * x
} with RationalTrait
res1: RationalTrait = 1/2
```

Listing 20.5 · Pre-initialized fields in an anonymous class expression.

Pre-initialized fields are not restricted to anonymous classes; they can also be used in objects or named subclasses. Two examples are shown in [Listings 20.6 and 20.7](#). As you can see from these examples, the pre-initialization section comes in each case after the `extends` keyword of the defined object or class. Class `RationalClass`, shown in [Listing 20.7](#), exemplifies a general schema of how class parameters can be made available for the initialization of a supertrait.

```
object twoThirds extends {
    val numerArg = 2
    val denomArg = 3
} with RationalTrait
```

Listing 20.6 · Pre-initialized fields in an object definition.

```
class RationalClass(n: Int, d: Int) extends {
    val numerArg = n
    val denomArg = d
} with RationalTrait {
    def + (that: RationalClass) = new RationalClass(
        numer * that.denom + that.numer * denom,
        denom * that.denom
    )
}
```

Listing 20.7 · Pre-initialized fields in a class definition.

Because pre-initialized fields are initialized before the superclass constructor is called, their initializers cannot refer to the object that's being con-

structed. Consequently, if such an initializer refers to `this`, the reference goes to the object containing the class or object that's being constructed, not the constructed object itself.

Here's an example:

```
scala> new {
    val numerArg = 1
    val denomArg = this.numerArg * 2
} with RationalTrait
<console>:11: error: value numerArg is not a member of object
$iw
    val denomArg = this.numerArg * 2
               ^
```

The example did not compile because the reference `this.numerArg` was looking for a `numerArg` field in the object containing the `new` (which in this case was the synthetic object named `$iw`, into which the interpreter puts user input lines). Once more, pre-initialized fields behave in this respect like class constructor arguments.

Lazy vals

You can use pre-initialized fields to simulate precisely the initialization behavior of class constructor arguments. Sometimes, however, you might prefer to let the system itself sort out how things should be initialized. This can be achieved by making your `val` definitions *lazy*. If you prefix a `val` definition with a `lazy` modifier, the initializing expression on the right-hand side will only be evaluated the first time the `val` is used.

For an example, define an object `Demo` with a `val` as follows:

```
scala> object Demo {
    val x = { println("initializing x"); "done" }
}
defined object Demo
```

Now, first refer to `Demo`, then to `Demo.x`:

```
scala> Demo
initializing x
res3: Demo.type = Demo@2129a843
```

```
scala> Demo.x
res4: String = done
```

As you can see, the moment you use `Demo`, its `x` field becomes initialized. The initialization of `x` forms part of the initialization of `Demo`. The situation changes, however, if you define the `x` field to be `lazy`:

```
scala> object Demo {
    lazy val x = { println("initializing x"); "done" }
}
defined object Demo

scala> Demo
res5: Demo.type = Demo$@5b1769c

scala> Demo.x
initializing x
res6: String = done
```

Now, initializing `Demo` does not involve initializing `x`. The initialization of `x` will be deferred until the first time `x` is used. This is similar to the situation where `x` is defined as a parameterless method, using a `def`. However, unlike a `def`, a `lazy val` is never evaluated more than once. In fact, after the first evaluation of a `lazy val` the result of the evaluation is stored, to be reused when the same `val` is used subsequently.

Looking at this example, it seems that objects like `Demo` themselves behave like `lazy vals`, in that they are also initialized on demand, the first time they are used. This is correct. In fact an object definition can be seen as a shorthand for the definition of a `lazy val` with an anonymous class that describes the object's contents.

Using `lazy vals`, you could reformulate `RationalTrait` as shown in [Listing 20.8](#). In the new trait definition, all concrete fields are defined `lazy`. Another change with respect to the previous definition of `RationalTrait`, shown in [Listing 20.4](#), is that the `require` clause was moved from the body of the trait to the initializer of the private field, `g`, which computes the greatest common divisor of `numerArg` and `denomArg`. With these changes, there's nothing that remains to be done when `LazyRationalTrait` is initialized; all initialization code is now part of the right-hand side of a `lazy val`. Thus, it is safe to initialize the abstract fields of `LazyRationalTrait` after the class is defined.

```
trait LazyRationalTrait {
    val numerArg: Int
    val denomArg: Int
    lazy val numer = numerArg / g
    lazy val denom = denomArg / g
    override def toString = numer + "/" + denom
    private lazy val g = {
        require(denomArg != 0)
        gcd(numerArg, denomArg)
    }
    private def gcd(a: Int, b: Int): Int =
        if (b == 0) a else gcd(b, a % b)
}
```

Listing 20.8 · Initializing a trait with lazy vals.

Here's an example:

```
scala> val x = 2
x: Int = 2
scala> new LazyRationalTrait {
    val numerArg = 1 * x
    val denomArg = 2 * x
}
res7: LazyRationalTrait = 1/2
```

No pre-initialization is needed. It's instructive to trace the sequence of initializations that lead to the string 1/2 to be printed in the code above:

1. A fresh instance of `LazyRationalTrait` gets created and the initialization code of `LazyRationalTrait` is run. This initialization code is empty; none of the fields of `LazyRationalTrait` is initialized yet.
2. Next, the primary constructor of the anonymous subclass defined by the `new` expression is executed. This involves the initialization of `numerArg` with 2 and `denomArg` with 4.
3. Next, the `toString` method is invoked on the constructed object by the interpreter, so that the resulting value can be printed.

4. Next, the `numer` field is accessed for the first time by the `toString` method in trait `LazyRationalTrait`, so its initializer is evaluated.
5. The initializer of `numer` accesses the private field, `g`, so `g` is evaluated next. This evaluation accesses `numerArg` and `denomArg`, which were defined in Step 2.
6. Next, the `toString` method accesses the value of `denom`, which causes `denom`'s evaluation. The evaluation of `denom` accesses the values of `denomArg` and `g`. The initializer of the `g` field is not re-evaluated, because it was already evaluated in Step 5.
7. Finally, the result string "1/2" is constructed and printed.

Note that the definition of `g` comes textually after the definitions of `numer` and `denom` in class `LazyRationalTrait`. Nevertheless, because all three values are lazy, `g` gets initialized before the initialization of `numer` and `denom` is completed.

This shows an important property of lazy `vals`: The textual order of their definitions does not matter because values get initialized on demand. Thus, lazy `vals` can free you as a programmer from having to think hard how to arrange `val` definitions to ensure that everything is defined when it is needed.

However, this advantage holds only as long as the initialization of lazy `vals` neither produces side effects nor depends on them. In the presence of side effects, initialization order starts to matter. And then it can be quite difficult to trace in what order initialization code is run, as the previous example has demonstrated. So lazy `vals` are an ideal complement to functional objects, where the order of initializations does not matter, as long as everything gets initialized eventually. They are less well suited for code that's predominantly imperative.

Lazy functional languages

Scala is by no means the first language to have exploited the perfect match of lazy definitions and functional code. In fact, there is a category of “lazy functional programming languages” in which *every* value and parameter is initialized lazily. The best known member of this class of languages is Haskell [SPJ02].

20.6 Abstract types

In the beginning of this chapter, you saw, “type T”, an abstract type declaration. The rest of this chapter discusses what such an abstract type declaration means and what it’s good for. Like all other abstract declarations, an abstract type declaration is a placeholder for something that will be defined concretely in subclasses. In this case, it is a type that will be defined further down the class hierarchy. So T above refers to a type that is as yet unknown at the point where it is declared. Different subclasses can provide different realizations of T.

Here is a well-known example where abstract types show up naturally. Suppose you are given the task of modeling the eating habits of animals. You might start with a class Food and a class Animal with an eat method:

```
class Food
abstract class Animal {
    def eat(food: Food)
}
```

You might then attempt to specialize these two classes to a class of Cows that eat Grass:

```
class Grass extends Food
class Cow extends Animal {
    override def eat(food: Grass) = {} // This won't compile
}
```

However, if you tried to compile the new classes, you’d get the following compilation errors:

```
BuggyAnimals.scala:7: error: class Cow needs to be
abstract, since method eat in class Animal of type
    (Food)Unit is not defined
class Cow extends Animal {
    ^
BuggyAnimals.scala:8: error: method eat overrides nothing
    override def eat(food: Grass) = {}
    ^
```

What happened is that the `eat` method in class `Cow` did not override the `eat` method in class `Animal` because its parameter type is different: it's `Grass` in class `Cow` vs. `Food` in class `Animal`.

Some people have argued that the type system is unnecessarily strict in refusing these classes. They have said that it should be OK to specialize a parameter of a method in a subclass. However, if the classes were allowed as written, you could get yourself in unsafe situations very quickly.

For instance, the following script would pass the type checker:

```
class Food
abstract class Animal {
    def eat(food: Food)
}
class Grass extends Food
class Cow extends Animal {
    override def eat(food: Grass) = {} // This won't compile,
}                                         // but if it did, ...
class Fish extends Food
val bessy: Animal = new Cow
bessy eat (new Fish)      // ...you could feed fish to cows.
```

The program would compile if the restriction were eased, because Cows are Animals and Animals do have an `eat` method that accepts any kind of Food, including Fish. But surely it would do a cow no good to eat a fish!

What you need to do instead is apply some more precise modeling. Animals do eat Food, but what kind of Food each Animal eats depends on the Animal. This can be neatly expressed with an abstract type, as shown in Listing 20.9:

```
class Food
abstract class Animal {
    type SuitableFood <: Food
    def eat(food: SuitableFood)
}
```

Listing 20.9 · Modeling suitable food with an abstract type.

With the new class definition, an `Animal` can eat only food that's suitable. What food is suitable cannot be determined at the level of the `Animal` class.

That's why `SuitableFood` is modeled as an abstract type. The type has an upper bound, `Food`, which is expressed by the “`<: Food`” clause. This means that any concrete instantiation of `SuitableFood` (in a subclass of `Animal`) must be a subclass of `Food`. For example, you would not be able to instantiate `SuitableFood` with class `IOException`.

With `Animal` defined, you can now progress to cows, as shown in Listing 20.10. Class `Cow` fixes its `SuitableFood` to be `Grass` and also defines a concrete `eat` method for this kind of food.

```
class Grass extends Food
class Cow extends Animal {
    type SuitableFood = Grass
    override def eat(food: Grass) = {}
}
```

Listing 20.10 · Implementing an abstract type in a subclass.

These new class definitions compile without errors. If you tried to run the “cows-that-eat-fish” counterexample with the new class definitions, you would get the following compiler error:

```
scala> class Fish extends Food
defined class Fish

scala> val bessy: Animal = new Cow
bessy: Animal = Cow@1515d8a6

scala> bessy eat (new Fish)
<console>:14: error: type mismatch;
 found   : Fish
 required: bessy.SuitableFood
           bessy eat (new Fish)
                           ^
```

20.7 Path-dependent types

Have a look at the last error message again. What's interesting about it is the type required by the `eat` method: `bessy.SuitableFood`. This type consists of an object reference, `bessy`, followed by a type field, `SuitableFood`, of

the object. So this shows that objects in Scala can have types as members. The meaning of `bessy.SuitableFood` is “the type `SuitableFood` that is a member of the object referenced from `bessy`” or, alternatively, the type of food that’s suitable for `bessy`.

A type like `bessy.SuitableFood` is called a *path-dependent type*. The word “path” here means a reference to an object. It could be a single name, such as `bessy`, or a longer access path, such as `farm.barn.bessy`, where each of `farm`, `barn`, and `bessy` are variables (or singleton object names) that refer to objects.

As the term “path-dependent type” implies, the type depends on the path; in general, different paths give rise to different types. For instance, say you defined classes `DogFood` and `Dog`, like this:

```
class DogFood extends Food
class Dog extends Animal {
    type SuitableFood = DogFood
    override def eat(food: DogFood) = {}
}
```

If you attempted to feed a dog with food fit for a cow, your code would not compile:

```
scala> val bessy = new Cow
bessy: Cow = Cow@713e7e09
scala> val lassie = new Dog
lassie: Dog = Dog@6eaf2c57
scala> lassie eat (new bessy.SuitableFood)
<console>:16: error: type mismatch;
  found   : Grass
  required: DogFood
                     lassie eat (new bessy.SuitableFood)
                                         ^
```

The problem here is that the type of the `SuitableFood` object passed to the `eat` method, `bessy.SuitableFood`, is incompatible with the parameter type of `eat`, `lassie.SuitableFood`.

The case would be different for two Dogs. Because `Dog`’s `SuitableFood` type is defined to be an alias for class `DogFood`, the `SuitableFood` types of two Dogs are in fact the same. As a result, the `Dog` instance named `lassie`

could actually eat the suitable food of a different Dog instance (which we'll name bootsie):

```
scala> val bootsie = new Dog  
bootsie: Dog = Dog@13a7c48c  
scala> lassie eat (new bootsie.SuitableFood)
```

A path-dependent type resembles the syntax for an inner class type in Java, but there is a crucial difference: a path-dependent type names an outer *object*, whereas an inner class type names an outer *class*. Java-style inner class types can also be expressed in Scala, but they are written differently. Consider these two classes, Outer and Inner:

```
class Outer {  
    class Inner  
}
```

In Scala, the inner class is addressed using the expression Outer#Inner instead of Java's Outer.Inner. The '.' syntax is reserved for objects. For example, imagine you instantiate two objects of type Outer, like this:

```
val o1 = new Outer  
val o2 = new Outer
```

Here o1.Inner and o2.Inner are two path-dependent types (and they are different types). Both of these types conform to (are subtypes of) the more general type Outer#Inner, which represents the Inner class with an *arbitrary* outer object of type Outer. By contrast, type o1.Inner refers to the Inner class with a *specific* outer object (the one referenced from o1). Likewise, type o2.Inner refers to the Inner class with a different, specific outer object (the one referenced from o2).

In Scala, as in Java, inner class instances hold a reference to an enclosing outer class instance. This allows an inner class, for example, to access members of its outer class. Thus you can't instantiate an inner class without in some way specifying an outer class instance. One way to do this is to instantiate the inner class inside the body of the outer class. In this case, the current outer class instance (referenced from this) will be used.

Another way is to use a path-dependent type. For example, because the type, o1.Inner, names a specific outer object, you can instantiate it:

```
scala> new o1.Inner  
res11: o1.Inner = Outer$Inner@1ae1e03f
```

The resulting inner object will contain a reference to its outer object, the object referenced from o1. By contrast, because the type Outer#Inner does not name any specific instance of Outer, you can't create an instance of it:

```
scala> new Outer#Inner  
<console>:9: error: Outer is not a legal prefix for a  
constructor  
      new Outer#Inner  
               ^
```

20.8 Refinement types

When a class inherits from another, the first class is said to be a *nominal* subtype of the other one. It's a *nominal* subtype because each type has a *name*, and the names are explicitly declared to have a subtyping relationship. Scala additionally supports *structural* subtyping, where you get a subtyping relationship simply because two types have compatible members. To get structural subtyping in Scala, use Scala's *refinement types*.

Nominal subtyping is usually more convenient, so you should try nominal types first with any new design. A name is a single short identifier and thus is more concise than an explicit listing of member types. Further, structural subtyping is often more flexible than you want. A widget can `draw()`, and a Western cowboy can `draw()`, but they aren't really substitutable. You'd typically prefer to get a compilation error if you tried to substitute a cowboy for a widget.

Nonetheless, structural subtyping has its own advantages. One is that sometimes there really is no more to a type than its members. For example, suppose you want to define a `Pasture` class that can contain animals that eat grass. One option would be to define a trait `AnimalThatEatsGrass` and mix it into every class where it applies. It would be verbose, however. Class `Cow` has already declared that it's an animal and that it eats grass, and now it would have to declare that it is also an animal-that-eats-grass.

Instead of defining `AnimalThatEatsGrass`, you can use a refinement type. Simply write the base type, `Animal`, followed by a sequence of members listed in curly braces. The members in the curly braces further specify—or refine, if you will—the types of members from the base class.

Here is how you write the type, “animal that eats grass”:

```
Animal { type SuitableFood = Grass }
```

Given this type, you can now write the pasture class like this:

```
class Pasture {  
    var animals: List[Animal { type SuitableFood = Grass }] = Nil  
    // ...  
}
```

20.9 Enumerations

An interesting application of path-dependent types is found in Scala’s support for enumerations. Some other languages, including Java and C#, have enumerations as a built-in language construct to define new types. Scala does not need special syntax for enumerations. Instead, there’s a class in its standard library, `scala.Enumeration`.

To create a new enumeration, you define an object that extends this class, as in the following example, which defines a new enumeration of Colors:

```
object Color extends Enumeration {  
    val Red = Value  
    val Green = Value  
    val Blue = Value  
}
```

Scala lets you also shorten several successive `val` or `var` definitions with the same right-hand side. Equivalently to the above you could write:

```
object Color extends Enumeration {  
    val Red, Green, Blue = Value  
}
```

This object definition provides three values: `Color.Red`, `Color.Green`, and `Color.Blue`. You could also import everything in `Color` with:

```
import Color._
```

and then just use Red, Green, and Blue. But what is the type of these values?

Enumeration defines an inner class named Value, and the same-named parameterless Value method returns a fresh instance of that class. In other words, a value such as Color.Red is of type Color.Value; Color.Value is the type of all enumeration values defined in object Color. It's a path-dependent type, with Color being the path and Value being the dependent type. What's significant about this is that it is a completely new type, different from all other types.

In particular, if you define another enumeration, such as:

```
object Direction extends Enumeration {  
    val North, East, South, West = Value  
}
```

then Direction.Value would be different from Color.Value because the path parts of the two types differ.

Scala's Enumeration class also offers many other features found in the enumeration designs of other languages. You can associate names with enumeration values by using a different overloaded variant of the Value method:

```
object Direction extends Enumeration {  
    val North = Value("North")  
    val East = Value("East")  
    val South = Value("South")  
    val West = Value("West")  
}
```

You can iterate over the values of an enumeration via the set returned by the enumeration's values method:

```
scala> for (d <- Direction.values) print(d + " ")  
North East South West
```

Values of an enumeration are numbered from 0, and you can find out the number of an enumeration value by its id method:

```
scala> Direction.East.id  
res14: Int = 1
```

It's also possible to go the other way, from a non-negative integer number to the value that has this number as id in an enumeration:

```
scala> Direction(1)
res15: Direction.Value = East
```

This should be enough to get you started with enumerations. You can find more information in the Scaladoc comments of class `scala.Enumeration`.

20.10 Case study: Currencies

The rest of this chapter presents a case study that explains how abstract types can be used in Scala. The task is to design a class `Currency`. A typical instance of `Currency` would represent an amount of money in dollars, euros, yen, or some other currency. It should be possible to do some arithmetic on currencies. For instance, you should be able to add two amounts of the same currency. Or you should be able to multiply a currency amount by a factor representing an interest rate.

These thoughts lead to the following first design for a currency class:

```
// A first (faulty) design of the Currency class
abstract class Currency {
    val amount: Long
    def designation: String
    override def toString = amount + " " + designation
    def + (that: Currency): Currency = ...
    def * (x: Double): Currency = ...
}
```

The `amount` of a currency is the number of currency units it represents. This is a field of type `Long` so that very large amounts of money, such as the market capitalization of Google or Apple, can be represented. It's left abstract here, waiting to be defined when a subclass talks about concrete amounts of money. The `designation` of a currency is a string that identifies it. The `toString` method of class `Currency` indicates an amount and a designation. It would yield results such as:

```
79 USD
11000 Yen
99 Euro
```

Finally, there are methods `+` for adding currencies and `*` for multiplying a currency with a floating-point number. You can create a concrete currency value by supplying concrete amount and designation values, like this:

```
new Currency {  
    val amount = 79L  
    def designation = "USD"  
}
```

This design would be OK if all we wanted to model was a single currency, like only dollars or only euros. But it fails if we need to deal with several currencies. Assume that you model dollars and euros as two subclasses of class `Currency`:

```
abstract class Dollar extends Currency {  
    def designation = "USD"  
}  
abstract class Euro extends Currency {  
    def designation = "Euro"  
}
```

At first glance this looks reasonable. But it would let you add dollars to euros. The result of such an addition would be of type `Currency`. But it would be a funny currency that was made up of a mix of euros and dollars. What you want instead is a more specialized version of the `+` method. When implemented in class `Dollar`, it should take `Dollar` arguments and yield a `Dollar` result; when implemented in class `Euro`, it should take `Euro` arguments and yield a `Euro` result. So the type of the addition method would change depending on which class you are in. Nonetheless, you would like to write the addition method just once, not each time a new currency is defined.

In Scala, there's a simple technique to deal with situations like this. If something is not known at the point where a class is defined, make it abstract in the class. This applies to both values and types. In the case of currencies, the exact argument and result type of the addition method are not known, so it is a good candidate for an abstract type.

This would lead to the following sketch of class `AbstractCurrency`:

```
// A second (still imperfect) design of the Currency class
abstract class AbstractCurrency {
    type Currency <: AbstractCurrency
    val amount: Long
    def designation: String
    override def toString = amount + " " + designation
    def + (that: Currency): Currency = ...
    def * (x: Double): Currency = ...
}
```

The only differences from the previous situation are that the class is now called `AbstractCurrency`, and that it contains an abstract type `Currency`, which represents the real currency in question. Each concrete subclass of `AbstractCurrency` would need to fix the `Currency` type to refer to the concrete subclass itself, thereby “tying the knot.”

For instance, here is a new version of class `Dollar`, which now extends class `AbstractCurrency`:

```
abstract class Dollar extends AbstractCurrency {
    type Currency = Dollar
    def designation = "USD"
}
```

This design is workable, but it is still not perfect. One problem is hidden by the ellipses that indicate the missing method definitions of `+` and `*` in class `AbstractCurrency`. In particular, how should addition be implemented in this class? It’s easy enough to calculate the correct amount of the new currency as `this.amount + that.amount`, but how would you convert the amount into a currency of the right type?

You might try something like:

```
def + (that: Currency): Currency = new Currency {
    val amount = this.amount + that.amount
}
```

However, this would not compile:

```
error: class type required
def + (that: Currency): Currency = new Currency {
```

One of the restrictions of Scala’s treatment of abstract types is that you can neither create an instance of an abstract type nor have an abstract type as a supertype of another class.¹ So the compiler would refuse the example code here that attempted to instantiate `Currency`.

However, you can work around this restriction using a *factory method*. Instead of creating an instance of an abstract type directly, declare an abstract method that does it. Then, wherever the abstract type is fixed to be some concrete type, you also need to give a concrete implementation of the factory method. For class `AbstractCurrency`, this would look as follows:

```
abstract class AbstractCurrency {  
    type Currency <: AbstractCurrency // abstract type  
    def make(amount: Long): Currency // factory method  
    ... // rest of class  
}
```

A design like this could be made to work, but it looks rather suspicious. Why place the factory method *inside* class `AbstractCurrency`? This looks dubious for at least two reasons. First, if you have some amount of currency (say, one dollar), you also hold in your hand the ability to make more of the same currency, using code such as:

```
myDollar.make(100) // here are a hundred more!
```

In the age of color copying this might be a tempting scenario, but hopefully not one which you would be able to do for very long without being caught. The second problem with this code is that you can make more `Currency` objects if you already have a reference to a `Currency` object. But how do you get the first object of a given `Currency`? You’d need another creation method, which does essentially the same job as `make`. So you have a case of code duplication, which is a sure sign of a code smell.

The solution, of course, is to move the abstract type and the factory method outside class `AbstractCurrency`. You need to create another class that contains the `AbstractCurrency` class, the `Currency` type, and the `make` factory method.

We’ll call this a `CurrencyZone`:

¹ There’s some promising recent research on *virtual classes*, which would allow this, but virtual classes are not currently supported in Scala.

```
abstract class CurrencyZone {  
    type Currency <: AbstractCurrency  
    def make(x: Long): Currency  
    abstract class AbstractCurrency {  
        val amount: Long  
        def designation: String  
        override def toString = amount + " " + designation  
        def + (that: Currency): Currency =  
            make(this.amount + that.amount)  
        def *(x: Double): Currency =  
            make((this.amount * x).toLong)  
    }  
}
```

An example concrete `CurrencyZone` is the US, which could be defined as:

```
object US extends CurrencyZone {  
    abstract class Dollar extends AbstractCurrency {  
        def designation = "USD"  
    }  
    type Currency = Dollar  
    def make(x: Long) = new Dollar { val amount = x }  
}
```

Here, `US` is an object that extends `CurrencyZone`. It defines a class `Dollar`, which is a subclass of `AbstractCurrency`. So the type of money in this zone is `US.Dollar`. The `US` object also fixes the type `Currency` to be an alias for `Dollar`, and it gives an implementation of the `make` factory method to return a dollar amount.

This is a workable design. There are only a few refinements to be added. The first refinement concerns subunits. So far, every currency was measured in a single unit: dollars, euros, or yen. However, most currencies have subunits: For instance, in the US, it's dollars and cents. The most straightforward way to model cents is to have the `amount` field in `US.Currency` represent cents instead of dollars. To convert back to dollars, it's useful to introduce a field `CurrencyUnit` into class `CurrencyZone`, which contains the amount of one standard unit in that currency:

```
class CurrencyZone {  
    ...  
    val CurrencyUnit: Currency  
}
```

As shown in Listing 20.11, The US object could define the quantities Cent, Dollar, and CurrencyUnit. This definition is just like the previous definition of the US object, except that it adds three new fields. The field Cent represents an amount of 1 US.Currency. It's an object analogous to a one-cent coin. The field Dollar represents an amount of 100 US.Currency. So the US object now defines the name Dollar in two ways. The *type* Dollar (defined by the abstract inner class named Dollar) represents the generic name of the Currency valid in the US currency zone. By contrast, the *value* Dollar (referenced from the val field named Dollar) represents a single US dollar, analogous to a one-dollar bill. The third field definition of CurrencyUnit specifies that the standard currency unit in the US zone is the Dollar (*i.e.*, the value Dollar, referenced from the field, not the type Dollar).

The `toString` method in class `Currency` also needs to be adapted to take subunits into account. For instance, the sum of ten dollars and twenty three cents should print as a decimal number: 10.23 USD. To achieve this, you could implement `Currency`'s `toString` method as follows:

```
override def toString =  
    ((amount.toDouble / CurrencyUnit.amount.toDouble)  
     formatted ("%." + decimals(CurrencyUnit.amount) + "f")  
     + " " + designation)
```

Here, `formatted` is a method that Scala makes available on several classes, including `Double`.² The `formatted` method returns the string that results from formatting the original string on which `formatted` was invoked according to a format string passed as the `formatted` method's right-hand operand. The syntax of format strings passed to `formatted` is the same as that of Java's `String.format` method.

For instance, the format string `%.2f` formats a number with two decimal digits. The format string used in the `toString` shown previously is assembled by calling the `decimals` method on `CurrencyUnit.amount`. This

²Scala uses rich wrappers, described in Section 5.10, to make `formatted` available.

```
object US extends CurrencyZone {
    abstract class Dollar extends AbstractCurrency {
        def designation = "USD"
    }
    type Currency = Dollar
    def make(cents: Long) = new Dollar {
        val amount = cents
    }
    val Cent = make(1)
    val Dollar = make(100)
    val CurrencyUnit = Dollar
}
```

Listing 20.11 · The US currency zone.

method returns the number of decimal digits of a decimal power minus one. For instance, `decimals(10)` is 1, `decimals(100)` is 2, and so on. The `decimals` method is implemented by a simple recursion:

```
private def decimals(n: Long): Int =
    if (n == 1) 0 else 1 + decimals(n / 10)
```

Listing 20.12 shows some other currency zones. As another refinement, you can add a currency conversion feature to the model. First, you could write a `Converter` object that contains applicable exchange rates between currencies, as shown in Listing 20.13. Then, you could add a conversion method, `from`, to class `Currency`, which converts from a given source currency into the current `Currency` object:

```
def from(other: CurrencyZone#AbstractCurrency): Currency =
    make(math.round(
        other.amount.toDouble * Converter.exchangeRate
        (other.designation)(this.designation)))
```

The `from` method takes an arbitrary currency as argument. This is expressed by its formal parameter type, `CurrencyZone#AbstractCurrency`, which indicates that the argument passed as `other` must be an `AbstractCurrency` type in some arbitrary and unknown `CurrencyZone`. It produces its result

```
object Europe extends CurrencyZone {
    abstract class Euro extends AbstractCurrency {
        def designation = "EUR"
    }
    type Currency = Euro
    def make(cents: Long) = new Euro {
        val amount = cents
    }
    val Cent = make(1)
    val Euro = make(100)
    val CurrencyUnit = Euro
}

object Japan extends CurrencyZone {
    abstract class Yen extends AbstractCurrency {
        def designation = "JPY"
    }
    type Currency = Yen
    def make(yen: Long) = new Yen {
        val amount = yen
    }
    val Yen = make(1)
    val CurrencyUnit = Yen
}
```

Listing 20.12 · Currency zones for Europe and Japan.

by multiplying the amount of the other currency with the exchange rate between the other and the current currency.³

The final version of the `CurrencyZone` class is shown in Listing 20.14. You can test the class in the Scala command shell. We'll assume that the `CurrencyZone` class and all concrete `CurrencyZone` objects are defined in a package `org.stairwaybook.currencies`. The first step is to import “`org.stairwaybook.currencies._`” into the command shell. Then you can do some currency conversions:

³By the way, in case you think you're getting a bad deal on Japanese yen, the exchange rates convert currencies based on their `CurrencyZone` amounts. Thus, 1.211 is the exchange rate between US cents and Japanese yen.

```
object Converter {
    var exchangeRate = Map(
        "USD" -> Map("USD" -> 1.0, "EUR" -> 0.7596,
                      "JPY" -> 1.211, "CHF" -> 1.223),
        "EUR" -> Map("USD" -> 1.316, "EUR" -> 1.0,
                      "JPY" -> 1.594, "CHF" -> 1.623),
        "JPY" -> Map("USD" -> 0.8257, "EUR" -> 0.6272,
                      "JPY" -> 1.0, "CHF" -> 1.018),
        "CHF" -> Map("USD" -> 0.8108, "EUR" -> 0.6160,
                      "JPY" -> 0.982, "CHF" -> 1.0)
    )
}
```

Listing 20.13 · A converter object with an exchange rates map.

```
scala> Japan.Yen from US.Dollar * 100
res16: Japan.Currency = 12110 JPY

scala> Europe.Euro from res16
res17: Europe.Currency = 75.95 EUR

scala> US.Dollar from res17
res18: US.Currency = 99.95 USD
```

The fact that we obtain almost the same amount after three conversions implies that these are some pretty good exchange rates! You can also add up values of the same currency:

```
scala> US.Dollar * 100 + res18
res19: US.Currency = 199.95 USD
```

On the other hand, you cannot add amounts of different currencies:

```
scala> US.Dollar + Europe.Euro
<console>:12: error: type mismatch;
 found   : Europe.Euro
 required: US.Currency
          (which expands to)  US.Dollar
                           US.Dollar + Europe.Euro
                                ^
```

```
abstract class CurrencyZone {  
    type Currency <: AbstractCurrency  
    def make(x: Long): Currency  
  
    abstract class AbstractCurrency {  
  
        val amount: Long  
        def designation: String  
  
        def + (that: Currency): Currency =  
            make(this.amount + that.amount)  
        def * (x: Double): Currency =  
            make((this.amount * x).toLong)  
        def - (that: Currency): Currency =  
            make(this.amount - that.amount)  
        def / (that: Double) =  
            make((this.amount / that).toLong)  
        def / (that: Currency) =  
            this.amount.toDouble / that.amount  
  
        def from(other: CurrencyZone#AbstractCurrency): Currency =  
            make(math.round(  
                other.amount.toDouble * Converter.exchangeRate  
                (other.designation)(this.designation)))  
  
        private def decimals(n: Long): Int =  
            if (n == 1) 0 else 1 + decimals(n / 10)  
  
        override def toString =  
            ((amount.toDouble / CurrencyUnit.amount.toDouble)  
             formatted ("%." + decimals(CurrencyUnit.amount) + "f")  
             + " " + designation)  
    }  
    val CurrencyUnit: Currency  
}
```

Listing 20.14 · The full code of class `CurrencyZone`.

By preventing the addition of two values with different units (in this case, currencies), the type abstraction has done its job. It prevents us from performing calculations that are unsound. Failures to convert correctly between different units may seem like trivial bugs, but they have caused many serious systems faults. An example is the crash of the Mars Climate Orbiter spacecraft on September 23, 1999, which was caused because one engineering team used metric units while another used English units. If units had been coded in the same way as currencies are coded in this chapter, this error would have been detected by a simple compilation run. Instead, it caused the crash of the orbiter after a near ten-month voyage.

20.11 Conclusion

Scala offers systematic and very general support for object-oriented abstraction. It enables you to not only abstract over methods, but also over values, variables, and types. This chapter has shown how to take advantage of abstract members. They support a simple yet effective principle for systems structuring: when designing a class, make everything that is not yet known into an abstract member. The type system will then drive the development of your model, just as you saw with the currency case study. It does not matter whether the unknown is a type, method, variable or value. In Scala, all of these can be declared abstract.

Chapter 21

Implicit Conversions and Parameters

There's a fundamental difference between your own code and other people's libraries: You can change or extend your own code as you wish, but if you want to use someone else's libraries, you usually have to take them as they are. A number of constructs have sprung up in programming languages to alleviate this problem. Ruby has modules, and Smalltalk lets packages add to each other's classes. These are very powerful but also dangerous, in that you can modify the behavior of a class for an entire application, some parts of which you might not know. C# 3.0 has static extension methods, which are more local but also more restrictive, in that you can only add methods, not fields, to a class, and you can't make a class implement new interfaces.

Scala's answer is implicit conversions and parameters. These can make existing libraries much more pleasant to deal with by letting you leave out tedious, obvious details that obscure the interesting parts of your code. Used tastefully, this results in code that is focused on the interesting, non-trivial parts of your program. This chapter shows you how implicits work, and it presents some of the most common ways they are used.

21.1 Implicit conversions

Before delving into the details of implicit conversions, take a look at a typical example of their use. Implicit conversions are often helpful for working with two bodies of software that were developed without each other in mind. Each library has its own way to encode a concept that is essentially the same thing. Implicit conversions help by reducing the number of explicit conversions that are needed from one type to another.

Java includes a library named Swing for implementing cross-platform user interfaces. One of the things Swing does is process events from the operating system, convert them to platform-independent event objects, and pass those events to parts of an application called event listeners.

If Swing had been written with Scala in mind, event listeners would probably have been represented by a function type. Callers could then use the function literal syntax as a lightweight way to specify what should happen for a certain class of events. Since Java doesn't have function literals, Swing uses the next best thing, an inner class that implements a one-method interface. In the case of action listeners, the interface is `ActionListener`.

Without the use of implicit conversions, a Scala program that uses Swing must use inner classes just like in Java. Here's an example that creates a button and hooks up an action listener to it. The action listener is invoked whenever the button is pressed, at which point it prints the string "pressed!":

```
val button = new JButton
button.addActionListener(
  new ActionListener {
    def actionPerformed(event: ActionEvent) = {
      println("pressed!")
    }
  }
)
```

This code has a lot of information-free boilerplate. The fact that this listener is an `ActionListener`, the fact that the callback method is named `actionPerformed`, and the fact that the argument is an `ActionEvent` are all implied for any argument to `addActionListener`. The only new information here is the code to be performed, namely the call to `println`. This new information is drowned out by the boilerplate. Someone reading this code will need to have an eagle's eye to pick through the noise and find the informative part.

A more Scala-friendly version would take a function as an argument, greatly reducing the amount of boilerplate:

```
button.addActionListener( // Type mismatch!
  (_: ActionEvent) => println("pressed!")
)
```

As written so far, this code doesn't work.¹ The `addActionListener` method wants an action listener but is getting a function. With implicit conversions, however, this code can be made to work.

The first step is to write an implicit conversion between the two types. Here is an implicit conversion from functions to action listeners:

```
implicit def function2ActionListener(f: ActionEvent => Unit) =  
    new ActionListener {  
        def actionPerformed(event: ActionEvent) = f(event)  
    }
```

This is a one-argument method that takes a function and returns an action listener. Like any other one-argument method, it can be called directly and have its result passed on to another expression:

```
button.addActionListener(  
    function2ActionListener(  
        (_: ActionEvent) => println("pressed!")  
    )  
)
```

This is already an improvement on the version with the inner class. Note how arbitrary amounts of boilerplate end up replaced by a function literal and a call to a method. It gets better, though, with implicit conversions. Because `function2ActionListener` is marked as implicit, it can be left out and the compiler will insert it automatically. Here is the result:

```
// Now this works  
button.addActionListener(  
    (_: ActionEvent) => println("pressed!")  
)
```

The way this code works is that the compiler first tries to compile it as is, but it sees a type error. Before giving up, it looks for an implicit conversion that can repair the problem. In this case, it finds `function2ActionListener`. It tries that conversion method, sees that it works, and moves on. The compiler works hard here so that the developer can ignore one more fiddly detail.

¹ As will be explained in [Section 31.5](#), it does work in Scala 2.12.

Action listener? Action event function? Either one will work—use the one that's more convenient.

In this section, we illustrated some of the power of implicit conversions and how they let you dress up existing libraries. In the next sections, you'll learn the rules that determine when implicit conversions are tried and how they are found.

21.2 Rules for implicits

Implicit definitions are those that the compiler is allowed to insert into a program in order to fix any of its type errors. For example, if $x + y$ does not type check, then the compiler might change it to $\text{convert}(x) + y$, where convert is some available implicit conversion. If convert changes x into something that has a $+$ method, then this change might fix a program so that it type checks and runs correctly. If convert really is just a simple conversion function, then leaving it out of the source code can be a clarification.

Implicit conversions are governed by the following general rules:

Marking rule: Only definitions marked `implicit` are available. The `implicit` keyword is used to mark which declarations the compiler may use as implicits. You can use it to mark any variable, function, or object definition. Here's an example of an implicit function definition:²

```
implicit def intToString(x: Int) = x.toString
```

The compiler will only change $x + y$ to $\text{convert}(x) + y$ if convert is marked as `implicit`. This way, you avoid the confusion that would result if the compiler picked random functions that happen to be in scope and inserted them as “conversions.” The compiler will only select among the definitions you have explicitly marked as `implicit`.

Scope rule: An inserted implicit conversion must be in scope as a single identifier, or be associated with the source or target type of the conversion. The Scala compiler will only consider implicit conversions that are in scope. To make an implicit conversion available, therefore, you must in

²Variables and singleton objects marked `implicit` can be used as *implicit parameters*. This use case will be described later in this chapter.

some way bring it into scope. Moreover, with one exception, the implicit conversion must be in scope *as a single identifier*. The compiler will not insert a conversion of the form `someVariable.convert`. For example, it will not expand `x + y` to `someVariable.convert(x) + y`. If you want to make `someVariable.convert` available as an implicit, you would need to import it, which would make it available as a single identifier. Once imported, the compiler would be free to apply it as `convert(x) + y`. In fact, it is common for libraries to include a `Preamble` object including a number of useful implicit conversions. Code that uses the library can then do a single “`import Preamble._`” to access the library’s implicit conversions.

There’s one exception to the “single identifier” rule. The compiler will also look for implicit definitions in the companion object of the source or expected target types of the conversion. For example, if you’re attempting to pass a `Dollar` object to a method that takes a `Euro`, the source type is `Dollar` and the target type is `Euro`. You could, therefore, package an implicit conversion from `Dollar` to `Euro` in the companion object of either class, `Dollar` or `Euro`.

Here’s an example in which the implicit definition is placed in `Dollar`’s companion object:

```
object Dollar {  
    implicit def dollarToEuro(x: Dollar): Euro = ...  
}  
class Dollar { ... }
```

In this case, the conversion `dollarToEuro` is said to be *associated* to the type `Dollar`. The compiler will find such an associated conversion every time it needs to convert from an instance of type `Dollar`. There’s no need to import the conversion separately into your program.

The Scope Rule helps with modular reasoning. When you read code in a file, the only things you need to consider from other files are those that are either imported or are explicitly referenced through a fully qualified name. This benefit is at least as important for implicits as for explicitly written code. If implicits took effect system-wide, then to understand a file you would have to know about every implicit introduced anywhere in the program!

One-at-a-time rule: Only one implicit is inserted. The compiler will never rewrite `x + y` to `convert1(convert2(x)) + y`. Doing so would cause

compile times to increase dramatically on erroneous code, and it would increase the difference between what the programmer writes and what the program actually does. For sanity's sake, the compiler does not insert further implicit conversions when it is already in the middle of trying another implicit. However, it's possible to circumvent this restriction by having implicits take implicit parameters, which will be described later in this chapter.

Explicit-first rule: Whenever code type checks as it is written, no implicits are attempted. The compiler will not change code that already works. A corollary of this rule is that you can always replace implicit identifiers by explicit ones, thus making the code longer but with less apparent ambiguity. You can trade between these choices on a case-by-case basis. Whenever you see code that seems repetitive and verbose, implicit conversions can help you decrease the tedium. Whenever code seems terse to the point of obscurity, you can insert conversions explicitly. The amount of implicits you leave the compiler to insert is ultimately a matter of style.

Naming an implicit conversion

Implicit conversions can have arbitrary names. The name of an implicit conversion matters only in two situations: If you want to write it explicitly in a method application and for determining which implicit conversions are available at any place in the program. To illustrate the second point, say you have an object with two implicit conversions:

```
object MyConversions {  
    implicit def stringWrapper(s: String):  
        IndexedSeq[Char] = ...  
    implicit def intToString(x: Int): String = ...  
}
```

In your application, you want to make use of the `stringWrapper` conversion, but you don't want integers to be converted automatically to strings by means of the `intToString` conversion. You can achieve this by importing only one conversion, but not the other:

```
import MyConversions.stringWrapper  
... // code making use of stringWrapper
```

In this example, it was important that the implicit conversions had names, because only that way could you selectively import one and not the other.

Where implicits are tried

There are three places implicits are used in the language: conversions to an expected type, conversions of the receiver of a selection, and implicit parameters. Implicit conversions to an expected type let you use one type in a context where a different type is expected. For example, you might have a `String` and want to pass it to a method that requires an `IndexedSeq[Char]`. Conversions of the receiver let you adapt the receiver of a method call (*i.e.*, the object on which a method is invoked), if the method is not applicable on the original type. An example is `"abc".exists`, which is converted to `stringWrapper("abc").exists` because the `exists` method is not available on `Strings` but is available on `IndexedSeqs`. Implicit parameters, on the other hand, are usually used to provide more information to the called function about what the caller wants. Implicit parameters are especially useful with generic functions, where the called function might otherwise know nothing at all about the type of one or more arguments. We will examine each of these three kinds of implicits in the next sections.

21.3 Implicit conversion to an expected type

Implicit conversion to an expected type is the first place the compiler will use implicits. The rule is simple. Whenever the compiler sees an X, but needs a Y, it will look for an implicit function that converts X to Y. For example, normally a double cannot be used as an integer because it loses precision:

```
scala> val i: Int = 3.5
<console>:7: error: type mismatch;
           found   : Double(3.5)
           required: Int
                  val i: Int = 3.5
                           ^
```

However, you can define an implicit conversion to smooth this over:

```
scala> implicit def doubleToInt(x: Double) = x.toInt
doubleToInt: (x: Double)Int
```

```
scala> val i: Int = 3.5
i: Int = 3
```

What happens here is that the compiler sees a Double, specifically 3.5, in a context where it requires an Int. So far, the compiler is looking at an ordinary type error. Before giving up, though, it searches for an implicit conversion from Double to Int. In this case, it finds one: doubleToInt, because doubleToInt is in scope as a single identifier. (Outside the interpreter, you might bring doubleToInt into scope via an import or possibly through inheritance.) The compiler then inserts a call to doubleToInt automatically. Behind the scenes, the code becomes:

```
val i: Int = doubleToInt(3.5)
```

This is literally an *implicit* conversion. You did not explicitly ask for conversion. Instead, you marked doubleToInt as an available implicit conversion by bringing it into scope as a single identifier, and then the compiler automatically used it when it needed to convert from a Double to an Int.

Converting Doubles to Ints might raise some eyebrows because, it's a dubious idea to have something that causes a loss in precision happen invisibly. So this is not really a conversion we recommend. It makes much more sense to go the other way, from some more constrained type to a more general one. For instance, an Int can be converted without loss of precision to a Double, so an implicit conversion from Int to Double makes sense. In fact, that's exactly what happens. The `scala.Predef` object, which is implicitly imported into every Scala program, defines implicit conversions that convert “smaller” numeric types to “larger” ones. For instance, you will find in `Predef` the following conversion:

```
implicit def int2double(x: Int): Double = x.toDouble
```

That's why in Scala Int values can be stored in variables of type Double. There's no special rule in the type system for this; it's just an implicit conversion that gets applied.³

³The Scala compiler backend will treat the conversion specially, however, translating it to a special “i2d” bytecode. So the compiled image is the same as in Java.

21.4 Converting the receiver

Implicit conversions also apply to the receiver of a method call, the object on which the method is invoked. This kind of implicit conversion has two main uses. First, receiver conversions allow smoother integration of a new class into an existing class hierarchy. And second, they support writing domain-specific languages (DSLs) within the language.

To see how it works, suppose you write down `obj.doIt`, and `obj` does not have a member named `doIt`. The compiler will try to insert conversions before giving up. In this case, the conversion needs to apply to the receiver, `obj`. The compiler will act as if the expected “type” of `obj` was “has a member named `doIt`.” This “has a `doIt`” type is not a normal Scala type, but it is there conceptually and is why the compiler will insert an implicit conversion in this case.

Interoperating with new types

As mentioned previously, one major use of receiver conversions is allowing smoother integration of new types with existing types. In particular, they allow you to enable client programmers to use instances of existing types as if they were instances of your new type. Take, for example, class `Rational` shown in Listing 6.5 on page 151. Here’s a snippet of that class again:

```
class Rational(n: Int, d: Int) {  
    ...  
    def + (that: Rational): Rational = ...  
    def + (that: Int): Rational = ...  
}
```

Class `Rational` has two overloaded variants of the `+` method, which take `Rationals` and `Ints`, respectively, as arguments. So you can either add two rational numbers or a rational number and an integer:

```
scala> val oneHalf = new Rational(1, 2)  
oneHalf: Rational = 1/2  
  
scala> oneHalf + oneHalf  
res0: Rational = 1/1  
  
scala> oneHalf + 1  
res1: Rational = 3/2
```

What about an expression like `1 + oneHalf`? This expression is tricky because the receiver, `1`, does not have a suitable `+` method. So the following gives an error:

```
scala> 1 + oneHalf
<console>:6: error: overloaded method value +
         alternatives (Double)Double <and> ... cannot be applied
                           to (Rational)
          1 + oneHalf
          ^
```

To allow this kind of mixed arithmetic, you need to define an implicit conversion from `Int` to `Rational`:

```
scala> implicit def intToRational(x: Int) =
           new Rational(x, 1)
intToRational: (x: Int)Rational
```

With the conversion in place, converting the receiver does the trick:

```
scala> 1 + oneHalf
res2: Rational = 3/2
```

What happens behind the scenes here is that the Scala compiler first tries to type check the expression `1 + oneHalf` as it is. This fails because `Int` has several `+` methods, but none that takes a `Rational` argument. Next, the compiler searches for an implicit conversion from `Int` to another type that has a `+` method which can be applied to a `Rational`. It finds your conversion and applies it, which yields:

```
intToRational(1) + oneHalf
```

In this case, the compiler found the implicit conversion function because you entered its definition into the interpreter, which brought it into scope for the remainder of the interpreter session.

Simulating new syntax

The other major use of implicit conversions is to simulate adding new syntax. Recall that you can make a `Map` using syntax like this:

```
Map(1 -> "one", 2 -> "two", 3 -> "three")
```

Have you wondered how the `->` is supported? It's not syntax! Instead, `->` is a method of the class `ArrowAssoc`, a class defined inside the standard Scala preamble (`scala.Predef`). The preamble also defines an implicit conversion from `Any` to `ArrowAssoc`. When you write `1 -> "one"`, the compiler inserts a conversion from `1` to `ArrowAssoc` so that the `->` method can be found. Here are the relevant definitions:

```
package scala
object Predef {
    class ArrowAssoc[A](x: A) {
        def -> [B](y: B): Tuple2[A, B] = Tuple2(x, y)
    }
    implicit def any2ArrowAssoc[A](x: A): ArrowAssoc[A] =
        new ArrowAssoc(x)
    ...
}
```

This “rich wrappers” pattern is common in libraries that provide syntax-like extensions to the language, so you should be ready to recognize the pattern when you see it. Whenever you see someone calling methods that appear not to exist in the receiver class, they are probably using implicits. Similarly, if you see a class named `RichSomething` (*e.g.*, `RichInt` or `RichBoolean`), that class is likely adding syntax-like methods to type `Something`.

You have already seen this rich wrappers pattern for the basic types described in [Chapter 5](#). As you can now see, these rich wrappers apply more widely, often letting you get by with an internal DSL defined as a library where programmers in other languages might feel the need to develop an external DSL.

Implicit classes

Implicit classes were added in Scala 2.10 to make it easier to write rich wrapper classes. An implicit class is a class that is preceded by the `implicit` keyword. For any such class, the compiler generates an implicit conversion from the class’s constructor parameter to the class itself. Such a conversion is just what you need if you plan to use the class for the rich wrappers pattern.

For example, suppose you have a class named `Rectangle` for representing the width and height of a rectangle on the screen:

```
case class Rectangle(width: Int, height: Int)
```

If you use this class very frequently, you might want to use the rich wrappers pattern so you can more easily construct it. Here's one way to do so.

```
implicit class RectangleMaker(width: Int) {  
    def x(height: Int) = Rectangle(width, height)  
}
```

The above definition defines a `RectangleMaker` class in the usual manner. In addition, it causes the following conversion to be automatically generated:

```
// Automatically generated  
implicit def RectangleMaker(width: Int) =  
    new RectangleMaker(width)
```

As a result, you can create points by putting an `x` in between two integers:

```
scala> val myRectangle = 3 x 4  
myRectangle: Rectangle = Rectangle(3,4)
```

This is how it works: Since type `Int` has no method named `x`, the compiler will look for an implicit conversion from `Int` to something that does. It will find the generated `RectangleMaker` conversion, and `RectangleMaker` does have a method named `x`. The compiler inserts a call to this conversion, after which the call to `x` type checks and does what is desired.

As a warning to the adventurous, it might be tempting to think that any class can have `implicit` put in front of it. It's not so. An implicit class cannot be a case class, and its constructor must have exactly one parameter. Also, an implicit class must be located within some other object, class, or trait. In practice, so long as you use implicit classes as rich wrappers to add a few methods onto an existing class, these restrictions should not matter.

21.5 Implicit parameters

The remaining place the compiler inserts implicits is within argument lists. The compiler will sometimes replace `someCall(a)` with `someCall(a)(b)`, or `new SomeClass(a)` with `new SomeClass(a)(b)`, thereby adding a missing parameter list to complete a function call. It is the entire last curried parameter list that's supplied, not just the last parameter. For example, if

someCall's missing last parameter list takes three parameters, the compiler might replace someCall(a) with someCall(a)(b, c, d). For this usage, not only must the inserted identifiers, such as b, c, and d in (b, c, d), be marked `implicit` where they are defined, but also the last parameter list in someCall's or someClass's definition must be marked `implicit`.

Here's a simple example. Suppose you have a class `PreferredPrompt`, which encapsulates a shell prompt string (such as, say "\$ " or "> ") that is preferred by a user:

```
class PreferredPrompt(val preference: String)
```

Also, suppose you have a `Greeter` object with a `greet` method, which takes two parameter lists. The first parameter list takes a string user name, and the second parameter list takes a `PreferredPrompt`:

```
object Greeter {  
    def greet(name: String)(implicit prompt: PreferredPrompt) = {  
        println("Welcome, " + name + ". The system is ready.")  
        println(prompt.preference)  
    }  
}
```

The last parameter list is marked `implicit`, which means it can be supplied implicitly. But you can still provide the `prompt` explicitly, like this:

```
scala> val bobsPrompt = new PreferredPrompt("> ")  
bobsPrompt: PreferredPrompt = PreferredPrompt@714d36d6  
  
scala> Greeter.greet("Bob")(bobsPrompt)  
Welcome, Bob. The system is ready.  
relax>
```

To let the compiler supply the parameter implicitly, you must first define a variable of the expected type, which in this case is `PreferredPrompt`. You could do this, for example, in a preferences object:

```
object JoesPrefs {  
    implicit val prompt = new PreferredPrompt("Yes, master> ")  
}
```

Note that the `val` itself is marked `implicit`. If it wasn't, the compiler would not use it to supply the missing parameter list. It will also not use it if it isn't in scope as a single identifier, as shown in this example:

```
scala> Greeter.greet("Joe")
<console>:13: error: could not find implicit value for
parameter prompt: PreferredPrompt
        Greeter.greet("Joe")
               ^
```

Once you bring it into scope via an import, however, it will be used to supply the missing parameter list:

```
scala> import JoesPrefs._
import JoesPrefs._

scala> Greeter.greet("Joe")
Welcome, Joe. The system is ready.
Yes, master>
```

Note that the `implicit` keyword applies to an entire parameter list, not to individual parameters. Listing 21.1 shows an example in which the last parameter list of Greeter's `greet` method, which is again marked `implicit`, has two parameters: `prompt` (of type `PreferredPrompt`) and `drink` (of type `PreferredDrink`).

Singleton object `JoesPrefs` declares two implicit `vals`, `prompt` of type `PreferredPrompt` and `drink` of type `PreferredDrink`. As before, however, so long as these are not in scope as single identifiers, they won't be used to fill in a missing parameter list to `greet`:

```
scala> Greeter.greet("Joe")
<console>:19: error: could not find implicit value for
parameter prompt: PreferredPrompt
        Greeter.greet("Joe")
               ^
```

You can bring both implicit `vals` into scope with an import:

```
scala> import JoesPrefs._
import JoesPrefs._
```

Because both `prompt` and `drink` are now in scope as single identifiers, you can use them to supply the last parameter list explicitly, like this:

```
class PreferredPrompt(val preference: String)
class PreferredDrink(val preference: String)

object Greeter {
    def greet(name: String)(implicit prompt: PreferredPrompt,
                           drink: PreferredDrink) = {
        println("Welcome, " + name + ". The system is ready.")
        print("But while you work, ")
        println("why not enjoy a cup of " + drink.preference + "?")
        println(prompt.preference)
    }
}

object JoesPrefs {
    implicit val prompt = new PreferredPrompt("Yes, master> ")
    implicit val drink = new PreferredDrink("tea")
}
```

Listing 21.1 · An implicit parameter list with multiple parameters.

```
scala> Greeter.greet("Joe")(prompt, drink)
Welcome, Joe. The system is ready.
But while you work, why not enjoy a cup of tea?
Yes, master>
```

And because all the rules for implicit parameters are now met, you can alternatively let the Scala compiler supply `prompt` and `drink` for you by leaving off the last parameter list:

```
scala> Greeter.greet("Joe")
Welcome, Joe. The system is ready.
But while you work, why not enjoy a cup of tea?
Yes, master>
```

One thing to note about the previous examples is that we didn't use `String` as the type of `prompt` or `drink`, even though ultimately it was a `String` that each of them provided through their `preference` fields. Because the compiler selects implicit parameters by matching types of parameters against types of values in scope, implicit parameters usually have “rare”

or “special” enough types that accidental matches are unlikely. For example, the types PreferredPrompt and PreferredDrink in Listing 21.1 were defined solely to serve as implicit parameter types. As a result, it is unlikely that implicit variables of these types will be in scope if they aren’t intended to be used as implicit parameters to Greeter.greet.

Another thing to know about implicit parameters is that they are perhaps most often used to provide information about a type mentioned *explicitly* in an earlier parameter list, similar to the type classes of Haskell.

As an example, consider the maxListOrdering function shown in Listing 21.2, which returns the maximum element of the passed list.

```
def maxListOrdering[T](elements: List[T])
  (ordering: Ordering[T]): T =
  elements match {
    case List() =>
      throw new IllegalArgumentException("empty list!")
    case List(x) => x
    case x :: rest =>
      val maxRest = maxListOrdering(rest)(ordering)
      if (ordering.gt(x, maxRest)) x
      else maxRest
  }
```

Listing 21.2 · A function with an upper bound.

The signature of maxListOrdering is similar to that of orderedMergeSort, shown in Listing 19.12 on page 440: It takes a List[T] as its argument, and now it takes an additional argument of type Ordering[T]. This additional argument specifies which ordering to use when comparing elements of type T. As such, this version can be used for types that don’t have a built-in ordering. Additionally, this version can be used for types that *do* have a built-in ordering, but for which you occasionally want to use some other ordering.

This version is more general, but it’s also more cumbersome to use. Now a caller must specify an explicit ordering even if T is something like String or Int that has an obvious default ordering. To make the new method more convenient, it helps to make the second argument implicit. This approach is shown in Listing 21.3.

The ordering parameter in this example is used to describe the ordering

```
def maxListImpParm[T](elements: List[T])
    (implicit ordering: Ordering[T]): T =
  elements match {
    case List() =>
      throw new IllegalArgumentException("empty list!")
    case List(x) => x
    case x :: rest =>
      val maxRest = maxListImpParm(rest)(ordering)
      if (ordering.gt(x, maxRest)) x
      else maxRest
  }
```

Listing 21.3 · A function with an implicit parameter.

of Ts. In the body of `maxListImpParm`, this ordering is used in two places: a recursive call to `maxListImpParm`, and an `if` expression that checks whether the head of the list is larger than the maximum element of the rest of the list.

The `maxListImpParm` function is an example of an implicit parameter used to provide more information about a type mentioned explicitly in an earlier parameter list. To be specific, the implicit parameter `ordering`, of type `Ordering[T]`, provides more information about type T—in this case, how to order Ts. Type T is mentioned in `List[T]`, the type of parameter `elements`, which appears in the earlier parameter list. Because `elements` must always be provided explicitly in any invocation of `maxListImpParm`, the compiler will know T at compile time and can therefore determine whether an implicit definition of type `Ordering[T]` is available. If so, it can pass in the second parameter list, `ordering`, implicitly.

This pattern is so common that the standard Scala library provides implicit “ordering” methods for many common types. You could therefore use this `maxListImpParm` method with a variety of types:

```
scala> maxListImpParm(List(1, 5, 10, 3))
res9: Int = 10

scala> maxListImpParm(List(1.5, 5.2, 10.7, 3.14159))
res10: Double = 10.7

scala> maxListImpParm(List("one", "two", "three"))
res11: String = two
```

In the first case, the compiler inserted an ordering for `Ints`; in the second case, for `Doubles`; in the third case, for `Strings`.

A style rule for implicit parameters

As a style rule, it is best to use a custom named type in the types of implicit parameters. For example, the types of `prompt` and `drink` in the previous example was not `String`, but `PreferredPrompt` and `PreferredDrink`, respectively. As a counterexample, consider that the `maxListImpParm` function could just as well have been written with the following type signature:

```
def maxListPoorStyle[T](elements: List[T])
    (implicit orderer: (T, T) => Boolean): T
```

To use this version of the function, though, the caller would have to supply an `orderer` parameter of type `(T, T) => Boolean`. This is a fairly generic type that includes any function from two `Ts` to a `Boolean`. It does not indicate anything at all about what the type is for; it could be an equality test, a less-than test, a greater-than test, or something else entirely.

The actual code for `maxListImpParm`, given in [Listing 21.3](#), shows better style. It uses an `ordering` parameter of type `Ordering[T]`. The word `Ordering` in this type indicates exactly what the implicit parameter is used for: it is for ordering elements of `T`. Because this ordering type is more explicit, it's no trouble to add implicit providers for this type in the standard library. To contrast, imagine the chaos that would ensue if you added an implicit of type `(T, T) => Boolean` in the standard library, and the compiler started sprinkling it around in people's code. You would end up with code that compiles and runs, but that does fairly arbitrary tests against pairs of items! Thus the style rule: Use at least one role-determining name within the type of an implicit parameter.

21.6 Context bounds

The previous example showed an opportunity to use an implicit but did not. Note that when you use `implicit` on a parameter, not only will the compiler try to *supply* that parameter with an implicit value, but the compiler will also *use* that parameter as an available implicit in the body of the method! Thus, the first use of `ordering` within the body of the method can be left out.

```
def maxList[T](elements: List[T])
  (implicit ordering: Ordering[T]): T =
  elements match {
    case List() =>
      throw new IllegalArgumentException("empty list!")
    case List(x) => x
    case x :: rest =>
      val maxRest = maxList(rest)      // (ordering) is implicit
      if (ordering.gt(x, maxRest)) x // this ordering is
      else maxRest                // still explicit
  }
```

Listing 21.4 · A function that uses an implicit parameter internally.

When the compiler examines the code in [Listing 21.4](#), it will see that the types do not match up. The expression `maxList(rest)` only supplies one parameter list, but `maxList` requires two. Since the second parameter list is implicit, the compiler does not give up type checking immediately. Instead, it looks for an implicit parameter of the appropriate type, in this case `Ordering[T]`. In this case, it finds one and rewrites the call to `maxList(rest)(ordering)`, after which the code type checks.

There is also a way to eliminate the second use of `ordering`. It involves the following method defined in the standard library:

```
def implicitly[T](implicit t: T) = t
```

The effect of calling `implicitly[Foo]` is that the compiler will look for an implicit definition of type *Foo*. It will then call the `implicitly` method with that object, which in turn returns the object right back. Thus you can write `implicitly[Foo]` whenever you want to find an implicit object of type *Foo* in the current scope. For example, [Listing 21.5](#) shows a use of `implicitly[Ordering[T]]` to retrieve the `ordering` parameter by its type.

Look closely at this last version of `maxList`. There is not a single mention of the `ordering` parameter in the text of the method. The second parameter could just as well be named “comparator”:

```
def maxList[T](elements: List[T])
  (implicit ordering: Ordering[T]): T =
  elements match {
    case List() =>
      throw new IllegalArgumentException("empty list!")
    case List(x) => x
    case x :: rest =>
      val maxRest = maxList(rest)
      if (implicitly[Ordering[T]].gt(x, maxRest)) x
      else maxRest
  }
```

Listing 21.5 · A function that uses `implicitly`.

```
def maxList[T](elements: List[T])
  (implicit comparator: Ordering[T]): T = // same body...
```

For that matter, this version works as well:

```
def maxList[T](elements: List[T])
  (implicit iceCream: Ordering[T]): T = // same body...
```

Because this pattern is common, Scala lets you leave out the name of this parameter and shorten the method header by using a *context bound*. Using a context bound, you would write the signature of `maxList` as shown in Listing 21.6. The syntax `[T : Ordering]` is a context bound, and it does two things. First, it introduces a type parameter `T` as normal. Second, it adds an implicit parameter of type `Ordering[T]`. In previous versions of `maxList`, that parameter was called `ordering`, but when using a context bound you don't know what the parameter will be called. As shown earlier, you often don't need to know what the parameter is called.

Intuitively, you can think of a context bound as saying something *about* a type parameter. When you write `[T <: Ordered[T]]` you are saying that a `T` is an `Ordered[T]`. To contrast, when you write `[T : Ordering]` you are not so much saying what `T` is; rather, you are saying that there is some form of ordering associated with `T`. Thus, a context bound is quite flexible. It allows you to use code that requires orderings—or any other property of a type—without having to change the definition of that type.

```
def maxList[T : Ordering](elements: List[T]): T =  
  elements match {  
    case List() =>  
      throw new IllegalArgumentException("empty list!")  
    case List(x) => x  
    case x :: rest =>  
      val maxRest = maxList(rest)  
      if (implicitly[Ordering[T]].gt(x, maxRest)) x  
      else maxRest  
  }
```

Listing 21.6 · A function with a context bound.

21.7 When multiple conversions apply

It can happen that multiple implicit conversions are in scope and each would work. For the most part, Scala refuses to insert a conversion in such a case. Implicits work well when the conversion left out is completely obvious and pure boilerplate. If multiple conversions apply, then the choice isn't so obvious after all.

Here's a simple example. There is a method that takes a sequence, a conversion that turns an integer into a range, and a conversion that turns an integer into a list of digits:

```
scala> def printLength(seq: Seq[Int]) = println(seq.length)  
printLength: (seq: Seq[Int])Unit  
  
scala> implicit def intToRange(i: Int) = 1 to i  
intToRange: (i:  
Int)scala.collection.immutable.Range.Inclusive  
  
scala> implicit def intToDigits(i: Int) =  
        i.toString.toList.map(_.toInt)  
intToDigits: (i: Int)List[Int]  
  
scala> printLength(12)  
<console>:26: error: type mismatch;  
       found   : Int(12)  
       required: Seq[Int]  
Note that implicit conversions are not applicable because
```

```
they are ambiguous:  
both method intToRange of type (i:  
Int)scala.collection.immutable.Range.Inclusive  
and method intToDigits of type (i: Int>List[Int]  
are possible conversion functions from Int(12) to Seq[Int]  
printLength(12)
```

The ambiguity here is real. Converting an integer to a sequence of digits is completely different from converting it to a range. In this case, the programmer should specify which one is intended and be explicit. Up through Scala 2.7, that was the end of the story. Whenever multiple implicit conversions applied, the compiler refused to choose between them. The situation was just as with method overloading. If you try to call `foo(null)` and there are two different `foo` overloads that accept `null`, the compiler will refuse. It will say that the method call's target is ambiguous.

Scala 2.8 loosened this rule. If one of the available conversions is strictly *more specific* than the others, then the compiler will choose the more specific one. The idea is that whenever there is a reason to believe a programmer would always choose one of the conversions over the others, don't require the programmer to write it explicitly. After all, method overloading has the same relaxation. Continuing the previous example, if one of the available `foo` methods takes a `String` while the other takes an `Any`, then choose the `String` version. It's clearly more specific.

To be more precise, one implicit conversion is *more specific* than another if one of the following applies:

- The argument type of the former is a subtype of the latter's.
- Both conversions are methods, and the enclosing class of the former extends the enclosing class of the latter.

The motivation to revisit this issue and revise the rule was to improve interoperation between Java collections, Scala collections, and strings.

Here's a simple example:

```
val cba = "abc".reverse
```

What is the type inferred for `cba`? Intuitively, the type should be `String`. Reversing a string should yield another string, right? However, in Scala 2.7,

what happened was that "abc" was converted to a Scala collection. Reversing a Scala collection yields a Scala collection, so the type of cba would be a collection. There's also an implicit conversion back to a string, but that didn't patch up every problem. For example, in versions prior to Scala 2.8, "abc" == "abc".reverse.reverse was false!

With Scala 2.8, the type of cba is `String`. The old implicit conversion to a Scala collection (now named `WrappedString`) is retained. However, there is a more specific conversion supplied from `String` to a new type called `StringOps`. `StringOps` has many methods such as `reverse`, but instead of returning a collection, they return a `String`. The conversion to `StringOps` is defined directly in `Predef`, whereas the conversion to a Scala collection is defined in a new class, `LowPriorityImplicits`, which is extended by `Predef`. Whenever a choice exists between these two conversions, the compiler chooses the conversion to `StringOps`, because it's defined in a subclass of the class where the other conversion is defined.

21.8 Debugging implicits

Implicits are a powerful feature in Scala, but one that's sometimes difficult to get right. This section contains a few tips for debugging implicits.

Sometimes you might wonder why the compiler did not find an implicit conversion that you think should apply. In that case it helps to write the conversion out explicitly. If that also gives an error message, you then know why the compiler could not apply your implicit.

For instance, assume that you mistakenly took `wrapString` to be a conversion from `Strings` to `Lists`, instead of `IndexedSeqs`. You would wonder why the following code does not work:

```
scala> val chars: List[Char] = "xyz"  
<console>:24: error: type mismatch;  
      found   : String("xyz")  
      required: List[Char]  
                           val chars: List[Char] = "xyz"  
                                         ^
```

Again, it helps to write the `wrapString` conversion explicitly to find out what went wrong:

```
scala> val chars: List[Char] = wrapString("xyz")
<console>:24: error: type mismatch;
           found   : scala.collection.immutable.WrappedString
           required: List[Char]
                  val chars: List[Char] = wrapString("xyz")^
```

With this, you have found the cause of the error: `wrapString` has the wrong return type. On the other hand, it's also possible that inserting the conversion explicitly will make the error go away. In that case you know that one of the other rules (such as the Scope Rule) was preventing the implicit conversion from being applied.

When you are debugging a program, it can sometimes help to see what implicit conversions the compiler is inserting. The `-Xprint:typer` option to the compiler is useful for this. If you run `scalac` with this option, the compiler will show you what your code looks like after all implicit conversions have been added by the type checker. An example is shown in [Listing 21.7](#) and [Listing 21.8](#). If you look at the last statement in each of these listings, you'll see that the second parameter list to `enjoy`, which was left off in the code in [Listing 21.7](#), “`enjoy("reader")`,” was inserted by the compiler, as shown in [Listing 21.8](#):

```
Mocha.this.enjoy("reader")(Mocha.this.pref)
```

If you are brave, try `scala -Xprint:typer` to get an interactive shell that prints out the post-typing source code it uses internally. If you do so, be prepared to see an enormous amount of boilerplate surrounding the meat of your code.

21.9 Conclusion

Implicits are a powerful, code-condensing feature of Scala. This chapter has shown you Scala's rules about implicits and several common programming situations where you can profit from using implicits.

As a word of warning, implicits can make code confusing if they are used too frequently. Thus, before adding a new implicit conversion, first ask whether you can achieve a similar effect through other means, such as inheritance, mixin composition, or method overloading. If all of these fail, however, and you feel like a lot of your code is still tedious and redundant, then implicits might just be able to help you out.

```
object Mocha extends App {
    class PreferredDrink(val preference: String)
    implicit val pref = new PreferredDrink("mocha")
    def enjoy(name: String)(implicit drink: PreferredDrink) = {
        print("Welcome, " + name)
        print(". Enjoy a ")
        print(drink.preference)
        println("!")
    }
    enjoy("reader")
}
```

Listing 21.7 · Sample code that uses an implicit parameter.

```
$ scalac -Xprint:typer mocha.scala
[[syntax trees at end of typer]]// Scala source: mocha.scala
package <empty> {
    final object Mocha extends java.lang.Object with Application
        with ScalaObject {
            // ...
            private[this] val pref: Mocha.PreferredDrink =
                new Mocha.this.PreferredDrink("mocha");
            implicit <stable> <accessor>
                def pref: Mocha.PreferredDrink = Mocha.this.pref;
            def enjoy(name: String)
                (implicit drink: Mocha.PreferredDrink): Unit = {
                    scala.this.Predef.print("Welcome, "+(name));
                    scala.this.Predef.print(". Enjoy a ");
                    scala.this.Predef.print(drink.preference);
                    scala.this.Predef.println("!");
                };
            Mocha.this.enjoy("reader")(Mocha.this.pref)
        }
}
```

Listing 21.8 · Sample code after type checking and insertion of implicits.

Chapter 22

Implementing Lists

Lists have been ubiquitous in this book. Class `List` is probably the most commonly used structured data type in Scala. [Chapter 16](#) showed you how to use lists. This chapter “opens up the covers” and explains a bit about how lists are implemented in Scala.

Knowing the internal workings of the `List` class is useful for several reasons. You gain a better idea of the relative efficiency of list operations, which will help you in writing fast and compact code using lists. You also gain a toolbox of techniques that you can apply in the design of your own libraries. Finally, the `List` class is a sophisticated application of Scala’s type system in general and its genericity concepts in particular. So studying class `List` will deepen your knowledge in these areas.

22.1 The `List` class in principle

Lists are not “built-in” as a language construct in Scala; they are defined by an abstract class `List` in the `scala` package, which comes with two subclasses for `::` and `Nil`. In this chapter we will present a quick tour through class `List`. This section presents a somewhat simplified account of the class, compared to its real implementation in the Scala standard library, which is covered in [Section 22.3](#).

```
package scala
abstract class List[+T] {
```

`List` is an abstract class, so you cannot define elements by calling the empty `List` constructor. For instance the expression “new `List`” would be ille-




Figure 22.1 · Class hierarchy for Scala lists.

gal. The class has a type parameter T. The + in front of this type parameter specifies that lists are covariant, as discussed in [Chapter 19](#).

Because of this property, you can assign a value of type List[Int] to a variable of type List[Any]:

```
scala> val xs = List(1, 2, 3)
xs: List[Int] = List(1, 2, 3)

scala> var ys: List[Any] = xs
ys: List[Any] = List(1, 2, 3)
```

All list operations can be defined in terms of three basic methods:

```
def isEmpty: Boolean
def head: T
def tail: List[T]
```

These three methods are all abstract in class List. They are defined in the subobject Nil and the subclass ::. The hierarchy for List is shown in [Figure 22.1](#).

The Nil object

The Nil object defines an empty list. Its definition is shown in [Listing 22.1](#). The Nil object inherits from type List[Nothing]. Because of covariance, this means that Nil is compatible with every instance of the List type.

```
case object Nil extends List[Nothing] {  
    override def isEmpty = true  
    def head: Nothing =  
        throw new NoSuchElementException("head of empty list")  
    def tail: List[Nothing] =  
        throw new NoSuchElementException("tail of empty list")  
}
```

Listing 22.1 · The definition of the Nil singleton object.

The three abstract methods of class List are implemented in the Nil object in a straightforward way: The isEmpty method returns true, and the head and tail methods both throw an exception. Note that throwing an exception is not only reasonable, but practically the only possible thing to do for head: Because Nil is a List of Nothing, the result type of head must be Nothing. Since there is no value of this type, this means that head cannot return a normal value. It has to return abnormally by throwing an exception.¹

The :: class

Class ::, pronounced “cons” for “construct,” represents non-empty lists. It’s named that way in order to support pattern matching with the infix :::. You have seen in Section 16.5 that every infix operation in a pattern is treated as a constructor application of the infix operator to its arguments. So the pattern x :: xs is treated as ::(x, xs) where :: is a case class.

Here is the definition of the :: class:

```
final case class ::[T](hd: T, tl: List[T]) extends List[T] {  
    def head = hd  
    def tail = tl  
    override def isEmpty: Boolean = false  
}
```

The implementation of the :: class is straightforward. It takes two parameters hd and tl, representing the head and the tail of the list to be constructed.

¹To be precise, the types would also permit for head to always go into an infinite loop instead of throwing an exception, but this is clearly not what’s wanted.

The definitions of the `head` and `tail` method simply return the corresponding parameter. In fact, this pattern can be abbreviated by letting the parameters directly implement the `head` and `tail` methods of the superclass `List`, as in the following equivalent but shorter definition of the `::` class:

```
final case class ::[T](head: T, tail: List[T])
  extends List[T] {
  override def isEmpty: Boolean = false
}
```

This works because every case class parameter is implicitly also a field of the class (it's like the parameter declaration was prefixed with `val`). Recall from [Section 20.3](#) that Scala allows you to implement an abstract parameterless method such as `head` or `tail` with a field. So the code above directly uses the parameters `head` and `tail` as implementations of the abstract methods `head` and `tail` that were inherited from class `List`.

Some more methods

All other `List` methods can be written using the basic three. For instance:

```
def length: Int =
  if (isEmpty) 0 else 1 + tail.length
```

or:

```
def drop(n: Int): List[T] =
  if (isEmpty) Nil
  else if (n <= 0) this
  else tail.drop(n - 1)
```

or:

```
def map[U](f: T => U): List[U] =
  if (isEmpty) Nil
  else f(head) :: tail.map(f)
```

List construction

The list construction methods `::` and `:::` are special. Because they end in a colon, they are bound to their right operand. That is, an operation such as `x :: xs` is treated as the method call `xs.::(x)`, not `x.::(xs)`. In fact, `x.::(xs)` would not make sense, as `x` is of the list element type, which can be arbitrary, so we cannot assume that this type would have a `::` method.

For this reason, the `::` method should take an element value and yield a new list. What is the required type of the element value? You might be tempted to say it should be the same as the list's element type, but in fact this is more restrictive than necessary.

To see why, consider this class hierarchy:

```
abstract class Fruit
class Apple extends Fruit
class Orange extends Fruit
```

[Listing 22.2](#) shows what happens when you construct lists of fruit:

```
scala> val apples = new Apple :: Nil
apples: List[Apple] = List(Apple@e885c6a)
scala> val fruits = new Orange :: apples
fruits: List[Fruit] = List(Orange@3f51b349, Apple@e885c6a)
```

[Listing 22.2](#) · Prepending a supertype element to a subtype list.

The `apples` value is treated as a `List` of `Apples`, as expected. However, the definition of `fruits` shows that it's still possible to add an element of a different type to that list. The element type of the resulting list is `Fruit`, which is the most precise common supertype of the original list element type (*i.e.*, `Apple`) and the type of the element to be added (*i.e.*, `Orange`). This flexibility is obtained by defining the `::` method (`cons`) as shown in [Listing 22.3](#):

```
def ::[U >: T](x: U): List[U] = new scala.::(x, this)
```

[Listing 22.3](#) · The definition of method `::` (`cons`) in class `List`.

Note that the method is itself polymorphic—it takes a type parameter named `U`. Furthermore, `U` is constrained in `[U >: T]` to be a supertype of the




Figure 22.2 · The structure of the Scala lists shown in Listing 22.2.

list element type T. The element to be added is required to be of type U and the result is a List[U].

With the formulation of :: shown in Listing 22.3, you can check how the definition of fruits shown in Listing 22.2 works out type-wise: In that definition, the type parameter U of :: is instantiated to Fruit. The lower-bound constraint of U is satisfied because the list apples has type List[Apple] and Fruit is a supertype of Apple. The argument to the :: is new Orange, which conforms to type Fruit. Therefore, the method application is type-correct with result type List[Fruit]. Figure 22.2 illustrates the structure of the lists that result from executing the code shown in Listing 22.2.

In fact, the polymorphic definition of :: with the lower bound T is not only convenient, it is also necessary to render the definition of class List type-correct. This is because Lists are defined to be covariant.

Assume for a moment that we had defined :: like this:

```
// A thought experiment (which wouldn't work)
def ::(x: T): List[T] = new scala.::(x, this)
```

You saw in Chapter 19 that method parameters count as contravariant positions, so the list element type T is in contravariant position in the definition above. But then List cannot be declared covariant in T. The lower bound [U >: T] thus kills two birds with one stone: It removes a typing problem and leads to a :: method that's more flexible to use. The list concatenation method :: is defined in a similar way to ::, as shown in Listing 22.4.

```
def :::[U >: T](prefix: List[U]): List[U] =  
  if (prefix.isEmpty) this  
  else prefix.head :: prefix.tail :: this
```

Listing 22.4 · The definition of method `:::` in class `List`.

Like `cons`, concatenation is polymorphic. The result type is “widened” as necessary to include the types of all list elements. Note again that the order of the arguments is swapped between an infix operation and an explicit method call. Because both `:::` and `::` end in a colon, they both bind to the right and are both right associative. For instance, the `else` part of the definition of `:::` shown in Listing 22.4 contains infix operations of both `::` and `::::`.

These infix operations can be expanded to equivalent method calls as follows:

```
prefix.head :: prefix.tail :: this  
  equals (because :: and :::: are right-associative)  
  
prefix.head :: (prefix.tail :::: this)  
  equals (because :: binds to the right)  
  
(prefix.tail :::: this):::(prefix.head)  
  equals (because :::: binds to the right)  
  
this:::(prefix.tail):::(prefix.head)
```

22.2 The `ListBuffer` class

The typical access pattern for a list is recursive. For instance, to increment every element of a list without using `map` you could write:

```
def incAll(xs: List[Int]): List[Int] = xs match {  
  case List() => List()  
  case x :: xs1 => x + 1 :: incAll(xs1)  
}
```

One shortcoming of this program pattern is that it is not tail recursive. Note that the recursive call to `incAll` above occurs inside a `::` operation. Therefore each recursive call requires a new stack frame.

On today's virtual machines this means that you cannot apply `incAll` to lists of much more than about 30,000 to 50,000 elements. This is a pity. How do you write a version of `incAll` that can work on lists of arbitrary size (as much as heap-capacity allows)?

One approach is to use a loop:

```
for (x <- xs) // ??
```

But what should go in the loop body? Note that where `incAll` constructs the list by prepending elements to the result of the recursive call, the loop needs to append new elements at the end of the result list. A very inefficient possibility is to use `:::`, the list append operator:

```
var result = List[Int]()    // a very inefficient approach
for (x <- xs) result = result :: List(x + 1)
result
```

This is terribly inefficient. Because `:::` takes time proportional to the length of its first operand, the whole operation takes time proportional to the square of the length of the list. This is clearly unacceptable.

A better alternative is to use a list buffer. List buffers let you accumulate the elements of a list. To do this, you use an operation such as “`buf += elem`”, which appends the element `elem` at the end of the list buffer `buf`. Once you are done appending elements, you can turn the buffer into a list using the `toList` operation.

`ListBuffer` is a class in package `scala.collection.mutable`. To use the simple name only, you can import `ListBuffer` from its package:

```
import scala.collection.mutable.ListBuffer
```

Using a list buffer, the body of `incAll` can now be written as follows:

```
val buf = new ListBuffer[Int]
for (x <- xs) buf += x + 1
buf.toList
```

This is a very efficient way to build lists. In fact, the list buffer implementation is organized so that both the append operation (`+=`) and the `toList` operation take (very short) constant time.

22.3 The List class in practice

The implementations of list methods given in [Section 22.1](#) are concise and clear, but suffer from the same stack overflow problem as the non-tail recursive implementation of `incAll`. Therefore, most methods in the real implementation of class `List` avoid recursion and use loops with list buffers instead. For example, [Listing 22.5](#) shows the real implementation of `map` in class `List`:

```
final override def map[U](f: T => U): List[U] = {
    val b = new ListBuffer[U]
    var these = this
    while (!these.isEmpty) {
        b += f(these.head)
        these = these.tail
    }
    b.toList
}
```

[Listing 22.5](#) · The definition of method `map` in class `List`.

This revised implementation traverses the list with a simple loop, which is highly efficient. A tail recursive implementation would be similarly efficient, but a general recursive implementation would be slower and less scalable. But what about the operation `b.toList` at the end? What is its complexity? In fact, the call to the `toList` method takes only a small number of cycles, which is independent of the length of the list.

To understand why, take a second look at class `::`, which constructs non-empty lists. In practice, this class does not quite correspond to its idealized definition given previously in [Section 22.1](#). The real definition is shown in [Listing 22.6](#). As you can see, there's one peculiarity: the `t1` argument is a `var!` This means that it is possible to modify the tail of a list after the list is constructed. However, because the variable `t1` has the modifier `private[scala]`, it can be accessed only from within package `scala`. Client code outside this package can neither read nor write `t1`.

Since the `ListBuffer` class is contained in a subpackage of package `scala`, `scala.collection.mutable`, `ListBuffer` can access the `t1` field of a `cons` cell. In fact the elements of a list buffer are represented as a list and

```
final case class ::[U](hd: U,
    private[scala] var tl: List[U]) extends List[U] {
    def head = hd
    def tail = tl
    override def isEmpty: Boolean = false
}
```

Listing 22.6 · The definition of the `::` subclass of `List`.

appending new elements involves a modification of the `tl` field of the last `::` cell in that list. Here's the start of class `ListBuffer`:

```
package scala.collection.immutable
final class ListBuffer[T] extends Buffer[T] {
    private var start: List[T] = Nil
    private var last0: ::[T] = _
    private var exported: Boolean = false
    ...
}
```

You see three private fields that characterize a `ListBuffer`:

- `start` points to the list of all elements stored in the buffer
- `last0` points to the last `::` cell in that list
- `exported` indicates whether the buffer has been turned into a list using a `toList` operation

The `toList` operation is very simple:

```
override def toList: List[T] = {
    exported = !start.isEmpty
    start
}
```

It returns the list of elements referred to by `start` and also sets `exported` to true if that list is nonempty. So `toList` is very efficient because it does not copy the list which is stored in a `ListBuffer`. But what happens if the list is further extended after the `toList` operation? Of course, once a list is returned from `toList`, it must be immutable. However, appending to the `last0` element will modify the list which is referred to by `start`.

To maintain the correctness of the list buffer operations, you need to work on a fresh list instead. This is achieved by the first line in the implementation of the `+=` operation:

```
override def += (x: T) = {
  if (exported) copy()
  if (start.isEmpty) {
    last0 = new scala.::(x, Nil)
    start = last0
  } else {
    val last1 = last0
    last0 = new scala.::(x, Nil)
    last1.tl = last0
  }
}
```

You see that `+=` copies the list pointed to by `start` if `exported` is true. So, in the end, there is no free lunch. If you want to go from lists which can be extended at the end to immutable lists, there needs to be some copying. However, the implementation of `ListBuffer` is such that copying is necessary only for list buffers that are further extended after they have been turned into lists. This case is quite rare in practice. Most use cases of list buffers add elements incrementally and then do one `toList` operation at the end. In such cases, no copying is necessary.

22.4 Functional on the outside

In the previous section, we showed key elements of the implementation of Scala’s `List` and `ListBuffer` classes. You saw that lists are purely functional on the “outside” but have an imperative implementation using list buffers on the “inside.” This is a typical strategy in Scala programming—trying to combine purity with efficiency by carefully delimiting the effects of impure operations.

But you might ask, Why insist on purity? Why not just open up the definition of lists, making the `tail` field, and maybe also the `head` field, mutable? The disadvantage of such an approach is that it would make programs much more fragile. Note that constructing lists with `::` re-uses the tail of the constructed list.

So when you write:

```
val ys = 1 :: xs
val zs = 2 :: xs
```

the tails of lists `ys` and `zs` are shared; they point to the same data structure. This is essential for efficiency; if the list `xs` was copied every time you added a new element onto it, this would be much slower. Because sharing is pervasive, changing list elements, if it were possible, would be quite dangerous. For instance, taking the code above, if you wanted to truncate list `ys` to its first two elements by writing:

```
ys.drop(2).tail = Nil // can't do this in Scala!
```

you would also truncate lists `zs` and `xs` as a side effect.

Clearly, it would be quite difficult to keep track of what gets changed. That's why Scala opts for pervasive sharing and no mutation for lists. The `ListBuffer` class still allows you to build up lists imperatively and incrementally, if you wish. But since list buffers are not lists, the types keep mutable buffers and immutable lists separate.

The design of Scala's `List` and `ListBuffer` is quite similar to what's done in Java's pair of classes `String` and `StringBuffer`. This is no coincidence. In both situations the designers wanted to maintain a pure immutable data structure but also provide an efficient way to construct this structure incrementally. For Java and Scala strings, `StringBuffers` (or, in Java 5, `StringBuilder`s) provide a way to construct a string incrementally. For Scala's lists, you have a choice: You can either construct lists incrementally by adding elements to the beginning of a list using `::`, or you use a list buffer for adding elements to the end. Which one is preferable depends on the situation. Usually, `::` lends itself well to recursive algorithms in the divide-and-conquer style. List buffers are often used in a more traditional loop-based style.

22.5 Conclusion

In this chapter, you saw how lists are implemented in Scala. `List` is one of the most heavily used data structures in Scala, and it has a refined implementation. `List`'s two subclasses, `Nil` and `::`, are both case classes. Instead of

recurring through this structure, however, many core list methods are implemented using a `ListBuffer`. `ListBuffer`, in turn, is carefully implemented so that it can efficiently build lists without allocating extraneous memory. It is functional on the outside, but uses mutation internally to speed up the common case where a buffer is discarded after `toList` has been called. After studying all of this, you now know the list classes inside and out, and you might have learned an implementation trick or two.

Chapter 23

For Expressions Revisited

Chapter 16 demonstrated that higher-order functions, such as `map`, `flatMap`, and `filter`, provide powerful constructions for dealing with lists. But sometimes the level of abstraction required by these functions makes a program a bit hard to understand.

Here's an example. Say you are given a list of persons, each defined as an instance of a class `Person`. Class `Person` has fields indicating the person's name, whether he or she is male, and his or her children.

Here's the class definition:

```
scala> case class Person(name: String,  
                         isMale: Boolean,  
                         children: Person*)
```

Here's a list of some sample persons:

```
val lara = Person("Lara", false)  
val bob = Person("Bob", true)  
val julie = Person("Julie", false, lara, bob)  
val persons = List(lara, bob, julie)
```

Now, say you want to find out the names of all pairs of mothers and their children in that list. Using `map`, `flatMap` and `filter`, you can formulate the following query:

```
scala> persons filter (p => !p.isMale) flatMap (p =>  
           (p.children map (c => (p.name, c.name))))  
res0: List[(String, String)] = List((Julie,Lara),  
                                    (Julie,Bob))
```

You could optimize this example a bit by using a `withFilter` call instead of `filter`. This would avoid the creation of an intermediate data structure for female persons:

```
scala> persons withFilter (p => !p.isMale) flatMap (p =>
  (p.children map (c => (p.name, c.name))))
res1: List[(String, String)] = List((Julie,Lara),
  (Julie,Bob))
```

These queries do their job, but they are not exactly trivial to write or understand. Is there a simpler way? In fact, there is. Remember the `for` expressions in [Section 7.3](#)? Using a `for` expression, the same example can be written as follows:

```
scala> for (p <- persons; if !p.isMale; c <- p.children)
  yield (p.name, c.name)
res2: List[(String, String)] = List((Julie,Lara),
  (Julie,Bob))
```

The result of this expression is exactly the same as the result of the previous expression. What's more, most readers of the code would likely find the `for` expression much clearer than the previous query, which used the higher-order functions, `map`, `flatMap`, and `withFilter`.

However, the last two queries are not as dissimilar as it might seem. In fact, it turns out that the Scala compiler will translate the second query into the first one. More generally, all `for` expressions that `yield` a result are translated by the compiler into combinations of invocations of the higher-order methods `map`, `flatMap`, and `withFilter`. All `for` loops without `yield` are translated into a smaller set of higher-order functions: just `withFilter` and `foreach`.

In this chapter, you'll find out first about the precise rules of writing `for` expressions. After that, you'll see how they can make combinatorial problems easier to solve. Finally, you'll learn how `for` expressions are translated, and how as a result, `for` expressions can help you “grow” the Scala language into new application domains.

23.1 For expressions

Generally, a `for` expression is of the form:

```
for ( seq ) yield expr
```

Here, *seq* is a sequence of *generators*, *definitions*, and *filters*, with semi-colons between successive elements. An example is the for expression:

```
for (p <- persons; n = p.name; if (n startsWith "To"))
    yield n
```

This for expression contains one generator, one definition, and one filter. As mentioned in [Section 7.3](#) on page 163, you can also enclose the sequence in braces instead of parentheses. Then the semicolons become optional:

```
for {
    p <- persons           // a generator
    n = p.name             // a definition
    if (n startsWith "To") // a filter
} yield n
```

A *generator* is of the form:

```
pat <- expr
```

The expression *expr* typically returns a list, even though you will see later that this can be generalized. The pattern *pat* gets matched one-by-one against all elements of that list. If the match succeeds, the variables in the pattern get bound to the corresponding parts of the element, just the way it is described in [Chapter 15](#). But if the match fails, no `MatchError` is thrown. Instead, the element is simply discarded from the iteration.

In the most common case, the pattern *pat* is just a variable *x*, as in `x <- expr`. In that case, the variable *x* simply iterates over all elements returned by *expr*.

A *definition* is of the form:

```
pat = expr
```

This definition binds the pattern *pat* to the value of *expr*, so it has the same effect as a `val` definition:

```
val x = expr
```

The most common case is again where the pattern is a simple variable *x* (e.g., `x = expr`). This defines *x* as a name for the value *expr*.

A *filter* is of the form:

```
if expr
```

Here, *expr* is an expression of type Boolean. The filter drops from the iteration all elements for which *expr* returns *false*.

Every *for* expression starts with a generator. If there are several generators in a *for* expression, later generators vary more rapidly than earlier ones. You can verify this easily with the following simple test:

```
scala> for (x <- List(1, 2); y <- List("one", "two"))
           yield (x, y)
res3: List[(Int, String)] =
List((1,one), (1,two), (2,one), (2,two))
```

23.2 The n-queens problem

A particularly suitable application area of *for* expressions are combinatorial puzzles. An example of such a puzzle is the 8-queens problem: Given a standard chess-board, place eight queens such that no queen is in check from any other (a queen can check another piece if they are on the same column, row, or diagonal). To find a solution to this problem, it's actually simpler to generalize it to chess-boards of arbitrary size. Hence, the problem is to place N queens on a chess-board of $N \times N$ squares, where the size N is arbitrary. We'll start numbering cells at one, so the upper-left cell of an $N \times N$ board has coordinate $(1, 1)$ and the lower-right cell has coordinate (N, N) .

To solve the N -queens problem, note that you need to place a queen in each row. So you could place queens in successive rows, each time checking that a newly placed queen is not in check from any other queens that have already been placed. In the course of this search, it might happen that a queen that needs to be placed in row k would be in check in all fields of that row from queens in row 1 to $k - 1$. In that case, you need to abort that part of the search in order to continue with a different configuration of queens in columns 1 to $k - 1$.

An imperative solution to this problem would place queens one by one, moving them around on the board. But it looks difficult to come up with a scheme that really tries all possibilities. A more functional approach represents a solution directly, as a value. A solution consists of a list of coordinates, one for each queen placed on the board. Note, however, that a full

solution can not be found in a single step. It needs to be built up gradually, by occupying successive rows with queens.

This suggests a recursive algorithm. Assume you have already generated all solutions of placing k queens on a board of size $N \times N$, where k is less than N . Each such solution can be presented by a list of length k of coordinates (row, column), where both row and column numbers range from 1 to N . It's convenient to treat these partial solution lists as stacks, where the coordinates of the queen in row k come first in the list, followed by the coordinates of the queen in row $k - 1$, and so on. The bottom of the stack is the coordinate of the queen placed in the first row of the board. All solutions together are represented as a list of lists, with one element for each solution.

Now, to place the next queen in row $k + 1$, generate all possible extensions of each previous solution by one more queen. This yields another list of solution lists, this time of length $k + 1$. Continue the process until you have obtained all solutions of the size of the chess-board N .

This algorithmic idea is embodied in function `placeQueens` below:

```
def queens(n: Int): List[List[(Int, Int)]] = {
    def placeQueens(k: Int): List[List[(Int, Int)]] =
        if (k == 0)
            List(List())
        else
            for {
                queens <- placeQueens(k - 1)
                column <- 1 to n
                queen = (k, column)
                if isSafe(queen, queens)
            } yield queen :: queens
    placeQueens(n)
}
```

The outer function `queens` in the program above simply calls `placeQueens` with the size of the board n as its argument. The task of the function application `placeQueens(k)` is to generate all partial solutions of length k in a list. Every element of the list is one solution, represented by a list of length k . So `placeQueens` returns a list of lists.

If the parameter k to `placeQueens` is 0, this means that it needs to generate all solutions of placing zero queens on zero rows. There is only one such

solution: place no queen at all. This solution is represented by the empty list. So if k is zero, `placeQueens` returns `List(List())`, a list consisting of a single element that is the empty list. Note that this is quite different from the empty list `List()`. If `placeQueens` returns `List()`, this means *no solutions*, instead of a single solution consisting of no placed queens.

In the other case, where k is not zero, all the work of `placeQueens` is done in a `for` expression. The first generator of that `for` expression iterates through all solutions of placing $k - 1$ queens on the board. The second generator iterates through all possible columns on which the k 'th queen might be placed. The third part of the `for` expression defines the newly considered queen position to be the pair consisting of row k and each produced column. The fourth part of the `for` expression is a filter which checks with `isSafe` whether the new queen is safe from check by all previous queens (the definition of `isSafe` will be discussed a bit later).

If the new queen is not in check from any other queens, it can form part of a partial solution, so `placeQueens` generates with `queen :: queens` a new solution. If the new queen is not safe from check, the filter returns `false`, so no solution is generated.

The only remaining bit is the `isSafe` method, which is used to check whether a given queen is in check from any other element in a list of queens. Here is its definition:

```
def isSafe(queen: (Int, Int), queens: List[(Int, Int)]) =  
    queens forall (q => !inCheck(queen, q))  
  
def inCheck(q1: (Int, Int), q2: (Int, Int)) =  
    q1._1 == q2._1 || // same row  
    q1._2 == q2._2 || // same column  
    (q1._1 - q2._1).abs == (q1._2 - q2._2).abs // on diagonal
```

The `isSafe` method expresses that a queen is safe with respect to some other queens if it is not in check from any other queen. The `inCheck` method expresses that queens q_1 and q_2 are mutually in check.

It returns `true` in one of three cases:

1. If the two queens have the same row coordinate,
2. If the two queens have the same column coordinate,
3. If the two queens are on the same diagonal (*i.e.*, the difference between their rows and the difference between their columns are the same).

The first case—that the two queens have the same row coordinate—cannot happen in the application because `placeQueens` already takes care to place each queen in a different row. So you could remove the test without changing the functionality of the program.

23.3 Querying with for expressions

The for notation is essentially equivalent to common operations of database query languages. For instance, say you are given a database named `books`, represented as a list of books, where `Book` is defined as follows:

```
case class Book(title: String, authors: String*)
```

Here is a small example database represented as an in-memory list:

```
val books: List[Book] =
  List(
    Book(
      "Structure and Interpretation of Computer Programs",
      "Abelson, Harold", "Sussman, Gerald J."
    ),
    Book(
      "Principles of Compiler Design",
      "Aho, Alfred", "Ullman, Jeffrey"
    ),
    Book(
      "Programming in Modula-2",
      "Wirth, Niklaus"
    ),
    Book(
      "Elements of ML Programming",
      "Ullman, Jeffrey"
    ),
    Book(
      "The Java Language Specification",
      "Gosling, James",
      "Joy, Bill", "Steele, Guy", "Bracha, Gilad"
    )
  )
```

To find the titles of all books whose author's last name is "Gosling":

```
scala> for (b <- books; a <- b.authors
           if a startsWith "Gosling")
           yield b.title
res4: List[String] = List(The Java Language Specification)
```

Or to find the titles of all books that have the string "Program" in their title:

```
scala> for (b <- books if (b.title indexOf "Program") >= 0)
           yield b.title
res5: List[String] = List(Structure and Interpretation of
Computer Programs, Programming in Modula-2, Elements of ML
Programming)
```

Or to find the names of all authors who have written at least two books in the database:

```
scala> for (b1 <- books; b2 <- books if b1 != b2;
           a1 <- b1.authors; a2 <- b2.authors if a1 == a2)
           yield a1
res6: List[String] = List(Ullman, Jeffrey, Ullman, Jeffrey)
```

The last solution is still not perfect because authors will appear several times in the list of results. You still need to remove duplicate authors from result lists. This can be achieved with the following function:

```
scala> def removeDuplicates[A](xs: List[A]): List[A] = {
           if (xs.isEmpty) xs
           else
             xs.head :: removeDuplicates(
               xs.tail filter (x => x != xs.head))
           }
removeDuplicates: [A](xs: List[A])List[A]
scala> removeDuplicates(res6)
res7: List[String] = List(Ullman, Jeffrey)
```

It's worth noting that the last expression in method `removeDuplicates` can be equivalently expressed using a `for` expression:

```
xs.head :: removeDuplicates(  
    for (x <- xs.tail if x != xs.head) yield x  
)
```

23.4 Translation of for expressions

Every `for` expression can be expressed in terms of the three higher-order functions `map`, `flatMap`, and `withFilter`. This section describes the translation scheme, which is also used by the Scala compiler.

Translating for expressions with one generator

First, assume you have a simple `for` expression:

```
for (x <- expr1) yield expr2
```

where x is a variable. Such an expression is translated to:

```
expr1.map(x => expr2)
```

Translating for expressions starting with a generator and a filter

Now, consider `for` expressions that combine a leading generator with some other elements. A `for` expression of the form:

```
for (x <- expr1 if expr2) yield expr3
```

is translated to:

```
for (x <- expr1 withFilter (x => expr2)) yield expr3
```

This translation gives another `for` expression that is shorter by one element than the original, because an `if` element is transformed into an application of `withFilter` on the first generator expression. The translation then continues with this second expression, so in the end you obtain:

```
expr1 withFilter (x => expr2) map (x => expr3)
```

The same translation scheme also applies if there are further elements following the filter. If seq is an arbitrary sequence of generators, definitions, and filters, then:

```
for (x <- expr1 if expr2; seq) yield expr3
```

is translated to:

```
for (x <- expr1 withFilter expr2; seq) yield expr3
```

Then translation continues with the second expression, which is again shorter by one element than the original one.

Translating for expressions starting with two generators

The next case handles for expressions that start with two generators, as in:

```
for (x <- expr1; y <- expr2; seq) yield expr3
```

Again, assume that *seq* is an arbitrary sequence of generators, definitions, and filters. In fact, *seq* might also be empty, and in that case there would not be a semicolon after *expr₂*. The translation scheme stays the same in each case. The for expression above is translated to an application of flatMap:

```
expr1.flatMap(x => for (y <- expr2; seq) yield expr3)
```

This time, there is another for expression in the function value passed to flatMap. That for expression (which is again simpler by one element than the original) is in turn translated with the same rules.

The three translation schemes given so far are sufficient to translate all for expressions that contain just generators and filters, and where generators bind only simple variables. Take, for instance, the query, “find all authors who have published at least two books,” from [Section 23.3](#):

```
for (b1 <- books; b2 <- books if b1 != b2;
     a1 <- b1.authors; a2 <- b2.authors if a1 == a2)
yield a1
```

This query translates to the following map/flatMap/filter combination:

```
books flatMap (b1 =>
  books withFilter (b2 => b1 != b2) flatMap (b2 =>
    b1.authors flatMap (a1 =>
      b2.authors withFilter (a2 => a1 == a2) map (a2 =>
        a1))))
```

The translation scheme presented so far does not yet handle generators that bind whole patterns instead of simple variables. It also does not yet cover definitions. These two aspects will be explained in the next two sub-sections.

Translating patterns in generators

The translation scheme becomes more complicated if the left hand side of generator is a pattern, *pat*, other than a simple variable. The case where the for expression binds a tuple of variables is still relatively easy to handle. In that case, almost the same scheme as for single variables applies.

A for expression of the form:

```
for ((x1, ..., xn) <- expr1) yield expr2
```

translates to:

```
expr1.map { case (x1, ..., xn) => expr2 }
```

Things become a bit more involved if the left hand side of the generator is an arbitrary pattern *pat* instead of a single variable or a tuple.

In this case:

```
for (pat <- expr1) yield expr2
```

translates to:

```
expr1 withFilter {  
    case pat => true  
    case _ => false  
} map {  
    case pat => expr2  
}
```

That is, the generated items are first filtered and only those that match *pat* are mapped. Therefore, it's guaranteed that a pattern-matching generator will never throw a `MatchError`.

The scheme here only treated the case where the for expression contains a single pattern-matching generator. Analogous rules apply if the for expression contains other generators, filters or definitions. Because these additional rules don't add much new insight, they are omitted from discussion here. If you are interested, you can look them up in the *Scala Language Specification* [Ode11].

Translating definitions

The last missing situation is where a `for` expression contains embedded definitions. Here's a typical case:

```
for (x <- expr1; y = expr2; seq) yield expr3
```

Assume again that `seq` is a (possibly empty) sequence of generators, definitions, and filters. This expression is translated to this one:

```
for ((x, y) <- for (x <- expr1) yield (x, expr2); seq)
    yield expr3
```

So you see that `expr2` is evaluated each time there is a new `x` value being generated. This re-evaluation is necessary because `expr2` might refer to `x` and so needs to be re-evaluated for changing values of `x`. For you as a programmer, the conclusion is that it's probably not a good idea to have definitions embedded in `for` expressions that do not refer to variables bound by some preceding generator, because re-evaluating such expressions would be wasteful. For instance, instead of:

```
for (x <- 1 to 1000; y = expensiveComputationNotInvolvingX)
    yield x * y
```

it's usually better to write:

```
val y = expensiveComputationNotInvolvingX
for (x <- 1 to 1000) yield x * y
```

Translating for loops

The previous subsections showed how `for` expressions that contain a `yield` are translated. What about `for` loops that simply perform a side effect without returning anything? Their translation is similar, but simpler than `for` expressions. In principle, wherever the previous translation scheme used a `map` or a `flatMap` in the translation, the translation scheme for `for` loops uses just a `foreach`.

For instance, the expression:

```
for (x <- expr1) body
```

translates to:

```
expr1 foreach (x => body)
```

A larger example is the expression:

```
for (x <- expr1; if expr2; y <- expr3) body
```

This expression translates to:

```
expr1 withFilter (x => expr2) foreach (x =>  
  expr3 foreach (y => body))
```

For example, the following expression sums up all elements of a matrix represented as a list of lists:

```
var sum = 0  
for (xs <- xss; x <- xs) sum += x
```

This loop is translated into two nested `foreach` applications:

```
var sum = 0  
xss foreach (xs =>  
  xs foreach (x =>  
    sum += x))
```

23.5 Going the other way

The previous section showed that `for` expressions can be translated into applications of the higher-order functions `map`, `flatMap`, and `withFilter`. In fact, you could equally go the other way: Every application of a `map`, `flatMap`, or `filter` can be represented as a `for` expression.

Here are implementations of the three methods in terms of `for` expressions. The methods are contained in an object `Demo` to distinguish them from the standard operations on `Lists`. To be concrete, the three functions all take a `List` as parameter, but the translation scheme would work just as well with other collection types:

```
object Demo {  
    def map[A, B](xs: List[A], f: A => B): List[B] =  
        for (x <- xs) yield f(x)  
  
    def flatMap[A, B](xs: List[A], f: A => List[B]): List[B] =  
        for (x <- xs; y <- f(x)) yield y  
  
    def filter[A](xs: List[A], p: A => Boolean): List[A] =  
        for (x <- xs if p(x)) yield x  
}
```

Not surprisingly, the translation of the for expression used in the body of `Demo.map` will produce a call to `map` in class `List`. Similarly, `Demo.flatMap` and `Demo.filter` translate to `flatMap` and `withFilter` in class `List`. So this little demonstration shows that for expressions really are equivalent in their expressiveness to applications of the three functions `map`, `flatMap`, and `withFilter`.

23.6 Generalizing for

Because the translation of for expressions only relies on the presence of methods `map`, `flatMap`, and `withFilter`, it is possible to apply the for notation to a large class of data types.

You have already seen for expressions over lists and arrays. These are supported because lists, as well as arrays, define operations `map`, `flatMap`, and `withFilter`. Because they define a `foreach` method as well, for loops over these data types are also possible.

Besides lists and arrays, there are many other types in the Scala standard library that support the same four methods and therefore allow for expressions. Examples are ranges, iterators, streams, and all implementations of sets. It's also perfectly possible for your own data types to support for expressions by defining the necessary methods. To support the full range of for expressions and for loops, you need to define `map`, `flatMap`, `withFilter`, and `foreach` as methods of your data type. But it's also possible to define a subset of these methods, and thereby support a subset of all possible for expressions or loops.

Here are the precise rules:

- If your type defines just `map`, it allows for expressions consisting of a single generator.

- If it defines `flatMap` as well as `map`, it allows for expressions consisting of several generators.
- If it defines `foreach`, it allows for loops (both with single and multiple generators).
- If it defines `withFilter`, it allows for filter expressions starting with an `if` in the `for` expression.

The translation of `for` expressions happens before type checking. This allows for maximum flexibility because the only requirement is that the result of expanding a `for` expression type checks. Scala defines no typing rules for the `for` expressions themselves, and does not require that methods `map`, `flatMap`, `withFilter`, or `foreach` have any particular type signatures.

Nevertheless, there is a typical setup that captures the most common intention of the higher order methods to which `for` expressions translate. Say you have a parameterized class, `C`, which typically would stand for some sort of collection. Then it's quite natural to pick the following type signatures for `map`, `flatMap`, `withFilter`, and `foreach`:

```
abstract class C[A] {  
    def map[B](f: A => B): C[B]  
    def flatMap[B](f: A => C[B]): C[B]  
    def withFilter(p: A => Boolean): C[A]  
    def foreach(b: A => Unit): Unit  
}
```

That is, the `map` function takes a function from the collection's element type `A` to some other type `B`. It produces a new collection of the same kind `C`, but with `B` as the element type. The `flatMap` method takes a function `f` from `A` to some `C`-collection of `B`s and produces a `C`-collection of `B`s. The `withFilter` method takes a predicate function from the collection's element type `A` to `Boolean`. It produces a collection of the same type as the one on which it is invoked. Finally, the `foreach` method takes a function from `A` to `Unit` and produces a `Unit` result:

In class `C` above, the `withFilter` method produces a new collection of the same class. That means that every invocation of `withFilter` creates a new `C` object, just the same as `filter` would work. Now, in the translation of `for` expressions, any calls to `withFilter` are always followed by calls to

one of the other three methods. Therefore, the object created by `withFilter` will be taken apart by one of the other methods immediately afterwards. If objects of class C are large (think long sequences), you might want to avoid the creation of such an intermediate object. A standard technique is to let `withFilter` return not a C object but just a wrapper object that “remembers” that elements need to be filtered before being processed further.

Concentrating on just the first three functions of class C, the following facts are noteworthy. In functional programming, there’s a general concept called a *monad*, which can explain a large number of types with computations, ranging from collections, to computations with state and I/O, backtracking computations, and transactions, to name a few. You can formulate functions `map`, `flatMap`, and `withFilter` on a monad, and, if you do, they end up having exactly the types given here.

Furthermore, you can characterize every monad by `map`, `flatMap`, and `withFilter`, plus a “unit” constructor that produces a monad from an element value. In an object-oriented language, this “unit” constructor is simply an instance constructor or a factory method. Therefore, `map`, `flatMap`, and `withFilter` can be seen as an object-oriented version of the functional concept of monad. Because for expressions are equivalent to applications of these three methods, they can be seen as syntax for monads.

All this suggests that the concept of for expression is more general than just iteration over a collection, and indeed it is. For instance, for expressions also play an important role in asynchronous I/O, or as an alternative notation for optional values. Watch out in the Scala libraries for occurrences of `map`, `flatMap`, and `withFilter`—when they are present, for expressions suggest themselves as a concise way of manipulating elements of the type.

23.7 Conclusion

In this chapter, you were given a peek under the hood of for expressions and for loops. You learned that they translate into applications of a standard set of higher-order methods. As a result, you saw that for expressions are really much more general than mere iterations over collections, and that you can design your own classes to support them.

Chapter 24

Collections in Depth

Scala includes an elegant and powerful collection library. Even though the collections API is subtle at first glance, the changes it can provoke in your programming style can be profound. Quite often it's as if you work on a higher level with the basic building blocks of a program being whole collections instead of their elements. This new style of programming requires some adaptation. Fortunately, the adaptation is helped by several nice properties of Scala collections. They are easy to use, concise, safe, fast, and universal.

Easy to use: A small vocabulary of twenty to fifty methods is enough to solve most collection problems in a couple of operations. No need to wrap your head around complicated looping structures or recursions. Persistent collections and side-effect-free operations mean that you need not worry about accidentally corrupting existing collections with new data. Interference between iterators and collection updates is eliminated.

Concise: You can achieve with a single word what used to take one or several loops. You can express functional operations with lightweight syntax and combine operations effortlessly, so that the result feels like a custom algebra.

Safe: This one has to be experienced to sink in. The statically typed and functional nature of Scala's collections means that the overwhelming majority of errors you might make are caught at compile-time. The reason is that (1) the collection operations themselves are heavily used and therefore well tested. (2) the usages of the collection operation

make inputs and output explicit as function parameters and results. (3) These explicit inputs and outputs are subject to static type checking. The bottom line is that the large majority of misuses will manifest themselves as type errors. It's not at all uncommon to have programs of several hundred lines run at first try.

Fast: Collection operations are tuned and optimized in the libraries. As a result, using collections is typically quite efficient. You might be able to do a little bit better with carefully hand-tuned data structures and operations, but you might also do a lot worse by making some suboptimal implementation decisions along the way. What's more, collections are have been adapted to parallel execution on multi-cores. Parallel collections support the same operations as sequential ones, so no new operations need to be learned and no code needs to be rewritten. You can turn a sequential collection into a parallel one simply by invoking the `par` method.

Universal: Collections provide the same operations on any type where it makes sense to do so. So you can achieve a lot with a fairly small vocabulary of operations. For instance, a string is conceptually a sequence of characters. Consequently, in Scala collections, strings support all sequence operations. The same holds for arrays.

This chapter describes in depth the APIs of the Scala collection classes from a user perspective. You've already seen a quick tour of the collections library, in [Chapter 17](#). This chapter takes you on a more detailed tour, showing all the collection classes and all the methods they define, so it includes everything you need to know to use Scala collections. Looking ahead, [Chapter 25](#) will concentrate on the architecture and extensibility aspects of the library, for people implementing new collection types.

24.1 Mutable and immutable collections

As is now familiar to you, Scala collections systematically distinguish between mutable and immutable collections. A mutable collection can be updated or extended in place. This means you can change, add, or remove elements of a collection as a side effect. Immutable collections, by contrast, never change. You still have operations that simulate additions, removals, or

updates, but those operations will in each case return a new collection and leave the old collection unchanged.

All collection classes are found in the package `scala.collection` or one of its subpackages: `mutable`, `immutable`, and `generic`. Most collection classes needed by client code exist in three variants, each of which has different characteristics with respect to mutability. The three variants are located in packages `scala.collection`, `scala.collection.immutable`, and `scala.collection.mutable`.

A collection in package `scala.collection.immutable` is guaranteed to be immutable for everyone. Such a collection will never change after it is created. Therefore, you can rely on the fact that accessing the same collection value repeatedly at different points in time will always yield a collection with the same elements.

A collection in package `scala.collection.mutable` is known to have some operations that change the collection in place. These operations let you write code to mutate the collection yourself. However, you must be careful to understand and defend against any updates performed by other parts of the code base.

A collection in package `scala.collection` can be either mutable or immutable. For instance, `scala.collection.IndexedSeq[T]` is a supertype of both `scala.collection.immutable.IndexedSeq[T]` and its mutable sibling `scala.collection.mutable.IndexedSeq[T]`. Generally, the root collections in package `scala.collection` define the same interface as the immutable collections. And typically, the mutable collections in package `scala.collection.mutable` add some side-effecting modification operations to this immutable interface.

The difference between root collections and immutable collections is that clients of an immutable collection have a guarantee that nobody can mutate the collection, whereas clients of a root collection only know that they can't change the collection themselves. Even though the static type of such a collection provides no operations for modifying the collection, it might still be possible that the run-time type is a mutable collection that can be changed by other clients.

By default, Scala always picks immutable collections. For instance, if you just write `Set` without any prefix or without having imported anything, you get an immutable set, and if you write `Iterable` you get an immutable iterable, because these are the default bindings imported from the `scala` package. To get the mutable default versions, you need to write explicitly

`collection.mutable.Set`, or `collection.mutable.Iterable`.

The last package in the collection hierarchy is `collection.generic`. This package contains building blocks for implementing collections. Typically, collection classes defer the implementations of some of their operations to classes in `generic`. Everyday users of the collection framework on the other hand should need to refer to classes in `generic` only in exceptional circumstances.

24.2 Collections consistency

The most important collection classes are shown in [Figure 24.1](#). There is quite a bit of commonality shared by all these classes. For instance, every kind of collection can be created by the same uniform syntax, writing the collection class name followed by its elements:

```
Traversable(1, 2, 3)
Iterable("x", "y", "z")
Map("x" -> 24, "y" -> 25, "z" -> 26)
Set(Color.Red, Color.Green, Color.Blue)
SortedSet("hello", "world")
Buffer(x, y, z)
IndexedSeq(1.0, 2.0)
LinearSeq(a, b, c)
```

The same principle also applies for specific collection implementations:

```
List(1, 2, 3)
HashMap("x" -> 24, "y" -> 25, "z" -> 26)
```

The `toString` methods for all collections produce output written as above, with a type name followed by the elements of the collection in parentheses. All collections support the API provided by `Traversable`, but their methods all return their own class rather than the root class `Traversable`. For instance, the `map` method on `List` has a return type of `List`, whereas the `map` method on `Set` has a return type of `Set`. Thus the static return type of these methods is fairly precise:

```
Traversable
  Iterable
    Seq
      IndexedSeq
        Vector
        ResizableArray
        GenericArray
      LinearSeq
        MutableList
        List
        Stream
      Buffer
        ListBuffer
        ArrayBuffer
    Set
      SortedSet
        TreeSet
      HashSet (mutable)
      LinkedHashSet
      HashSet (immutable)
      BitSet
      EmptySet, Set1, Set2, Set3, Set4
  Map
    SortedMap
      TreeMap
    HashMap (mutable)
    LinkedHashMap (mutable)
    HashMap (immutable)
    EmptyMap, Map1, Map2, Map3, Map4
```

Figure 24.1 · Collection hierarchy.

```
scala> List(1, 2, 3) map (_ + 1)
res0: List[Int] = List(2, 3, 4)

scala> Set(1, 2, 3) map (_ * 2)
res1: scala.collection.immutable.Set[Int] = Set(2, 4, 6)
```

Equality is also organized uniformly for all collection classes; more on this in [Section 24.13](#).

Most of the classes in [Figure 24.1](#) exist in three variants: root, mutable, and immutable. The only exception is the Buffer trait, which only exists as a mutable collection.

In the remainder of this chapter, we will review these classes one by one.

24.3 Trait Traversable

At the top of the collection hierarchy is trait `Traversable`. Its only abstract operation is `foreach`:

```
def foreach[U](f: Elem => U)
```

Collection classes implementing `Traversable` just need to define this method; all other methods can be inherited from `Traversable`.

The `foreach` method is meant to traverse all elements of the collection, and apply the given operation, `f`, to each element. The type of the operation is `Elem => U`, where `Elem` is the type of the collection's elements and `U` is an arbitrary result type. The invocation of `f` is done for its side effect only; in fact any function result of `f` is discarded by `foreach`.

`Traversable` also defines many concrete methods, which are all listed in [Table 24.1](#) on [page 535](#). These methods fall into the following categories:

Addition `++`, which appends two traversables together, or appends all elements of an iterator to a traversable.

Map operations `map`, `flatMap`, and `collect`, which produce a new collection by applying some function to collection elements.

Conversions `toIndexedSeq`, `toIterable`, `toStream`, `toArray`, `toList`, `toSeq`, `toSet`, and `toMap`, which turn a `Traversable` collection into a more specific collection. All these conversions return the receiver object if it already matches the demanded collection type. For instance, applying `toList` to a list will yield the list itself.

Copying operations `copyToBuffer` and `copyToArray`. As their names imply, these copy collection elements to a buffer or array, respectively.

Size operations `isEmpty`, `nonEmpty`, `size`, and `hasDefiniteSize`. Collections that are traversable can be finite or infinite. An example of an infinite traversable collection is the stream of natural numbers `Stream.from(0)`. The method `hasDefiniteSize` indicates whether a collection is possibly infinite. If `hasDefiniteSize` returns true, the collection is certainly finite. If it returns false, the collection might be infinite, in which case `size` will emit an error or not return.

Element retrieval operations `head`, `last`, `headOption`, `lastOption`, and `find`. These select the first or last element of a collection, or else the first element matching a condition. Note, however, that not all collections have a well-defined meaning of what “first” and “last” means. For instance, a hash set might store elements according to their hash keys, which might change from run to run. In that case, the “first” element of a hash set could also be different for different runs of a program. A collection is *ordered* if it always yields its elements in the same order. Most collections are ordered, but some (such as hash sets) are not—dropping the ordering provides a little bit of extra efficiency. Ordering is often essential to give reproducible tests and help in debugging. That’s why Scala collections provide ordered alternatives for all collection types. For instance, the ordered alternative for `HashSet` is `LinkedHashSet`.

Subcollection retrieval operations `takeWhile`, `tail`, `init`, `slice`, `take`, `drop`, `filter`, `dropWhile`, `filterNot`, and `withFilter`. These all return some subcollection identified by an index range or a predicate.

Subdivision operations `splitAt`, `span`, `partition`, and `groupBy`, which split the elements of this collection into several subcollections.

Element tests `exists`, `forall`, and `count`, which test collection elements with a given predicate.

Folds `foldLeft`, `foldRight`, `/:`, `:\, reduceLeft, reduceRight, which apply a binary operation to successive elements.`

Specific folds `sum`, `product`, `min`, and `max`, which work on collections of specific types (numeric or comparable).

String operations `mkString`, `addString`, and `stringPrefix`, which provide alternative ways of converting a collection to a string.

View operations consisting of two overloaded variants of the `view` method. A view is a collection that's evaluated lazily. You'll learn more about views in [Section 24.14](#).

Table 24.1 · Operations in trait Traversable

What it is	What it does
Abstract method:	
<code>xs foreach f</code>	Executes function <code>f</code> for every element of <code>xs</code> .
Addition:	
<code>xs ++ ys</code>	A collection consisting of the elements of both <code>xs</code> and <code>ys</code> . <code>ys</code> is a <code>TraversableOnce</code> collection, <i>i.e.</i> , either a <code>Traversable</code> or an <code>Iterator</code> .
Maps:	
<code>xs map f</code>	The collection obtained from applying the function <code>f</code> to every element in <code>xs</code> .
<code>xs flatMap f</code>	The collection obtained from applying the collection-valued function <code>f</code> to every element in <code>xs</code> and concatenating the results.
<code>xs collect f</code>	The collection obtained from applying the partial function <code>f</code> to every element in <code>xs</code> for which it is defined and collecting the results.
Conversions:	
<code>xs.toArray</code>	Converts the collection to an array.
<code>xs.toList</code>	Converts the collection to a list.
<code>xs.toIterable</code>	Converts the collection to an iterable.
<code>xs.toSeq</code>	Converts the collection to a sequence.
<code>xs.toIndexedSeq</code>	Converts the collection to an indexed sequence.
<code>xs.toStream</code>	Converts the collection to a stream (a lazily computed sequence).
<code>xs.toSet</code>	Converts the collection to a set.
<code>xs.toMap</code>	Converts a collection of key/value pairs to a map.

Table 24.1 · continued

Copying:

`xs.copyToBuffer buf` Copies all elements of the collection to buffer `buf`.

`xs.copyOfArray(arr, s, len)` Copies at most `len` elements of `arr`, starting at index `s`. The last two arguments are optional.

Size info:

`xs.isEmpty` Tests whether the collection is empty.

`xs.nonEmpty` Tests whether the collection contains elements.

`xs.size` The number of elements in the collection.

`xs.hasDefiniteSize` True if `xs` is known to have finite size.

Element retrieval:

`xs.head` The first element of the collection (or, some element, if no order is defined).

`xs.headOption` The first element of `xs` in an option value, or `None` if `xs` is empty.

`xs.last` The last element of the collection (or, some element, if no order is defined).

`xs.lastOption` The last element of `xs` in an option value, or `None` if `xs` is empty.

`xs.find p` An option containing the first element in `xs` that satisfies `p`, or `None` if no element qualifies.

Subcollections:

`xs.tail` The rest of the collection except `xs.head`.

`xs.init` The rest of the collection except `xs.last`.

`xs.slice (from, to)` A collection consisting of elements in some index range of `xs` (from `from`, up to and excluding `to`).

`xs.take n` A collection consisting of the first `n` elements of `xs` (or, some arbitrary `n` elements, if no order is defined).

`xs.drop n` The rest of the collection except `xs.take n`.

`xs.takeWhile p` The longest prefix of elements in the collection that all satisfy `p`.

`xs.dropWhile p` The collection without the longest prefix of elements that all satisfy `p`.

Table 24.1 · continued

<code>xs filter p</code>	The collection consisting of those elements of <code>xs</code> that satisfy the predicate <code>p</code> .
<code>xs withFilter p</code>	A non-strict filter of this collection. All operations on the resulting filter will only apply to those elements of <code>xs</code> for which the condition <code>p</code> is true.
<code>xs filterNot p</code>	The collection consisting of those elements of <code>xs</code> that do not satisfy the predicate <code>p</code> .
Subdivisions:	
<code>xs splitAt n</code>	Splits <code>xs</code> at a position, giving the pair of collections (<code>xs take n</code> , <code>xs drop n</code>).
<code>xs span p</code>	Splits <code>xs</code> according to a predicate, giving the pair of collections (<code>xs takeWhile p</code> , <code>xs.dropWhile p</code>).
<code>xs partition p</code>	Splits <code>xs</code> into a pair of collections; one with elements that satisfy the predicate <code>p</code> , the other with elements that do not, giving the pair of collections (<code>xs filter p</code> , <code>xs.filterNot p</code>).
<code>xs groupBy f</code>	Partitions <code>xs</code> into a map of collections according to a discriminator function <code>f</code> .
Element conditions:	
<code>xs forall p</code>	A boolean indicating whether the predicate <code>p</code> holds for all elements of <code>xs</code> .
<code>xs exists p</code>	A boolean indicating whether the predicate <code>p</code> holds for some element in <code>xs</code> .
<code>xs count p</code>	The number of elements in <code>xs</code> that satisfy the predicate <code>p</code> .
Folds:	
<code>(z /: xs)(op)</code>	Applies binary operation <code>op</code> between successive elements of <code>xs</code> , going left to right, starting with <code>z</code> .
<code>(xs :\: z)(op)</code>	Applies binary operation <code>op</code> between successive elements of <code>xs</code> , going right to left, starting with <code>z</code> .
<code>xs.foldLeft(z)(op)</code>	Same as <code>(z /: xs)(op)</code> .
<code>xs.foldRight(z)(op)</code>	Same as <code>(xs :\: z)(op)</code> .

Table 24.1 · continued

<code>xs reduceLeft op</code>	Applies binary operation op between successive elements of non-empty collection xs, going left to right.
<code>xs reduceRight op</code>	Applies binary operation op between successive elements of non-empty collection xs, going right to left.
Specific folds:	
<code>xs.sum</code>	The sum of the numeric element values of collection xs.
<code>xs.product</code>	The product of the numeric element values of collection xs.
<code>xs.min</code>	The minimum of the ordered element values of collection xs.
<code>xs.max</code>	The maximum of the ordered element values of collection xs.
Strings:	
<code>xs addString (b, start, sep, end)</code>	Adds a string to <code>StringBuilder b</code> that shows all elements of xs between separators <code>sep</code> enclosed in strings <code>start</code> and <code>end</code> . <code>start</code> , <code>sep</code> , and <code>end</code> are all optional.
<code>xs mkString (start, sep, end)</code>	Converts the collection to a string that shows all elements of xs between separators <code>sep</code> enclosed in strings <code>start</code> and <code>end</code> . <code>start</code> , <code>sep</code> , and <code>end</code> are all optional.
<code>xs.stringPrefix</code>	The collection name at the beginning of the string returned from <code>xs.toString</code> .
Views:	
<code>xs.view</code>	Produces a view over xs.
<code>xs view (from, to)</code>	Produces a view that represents the elements in some index range of xs.

24.4 Trait Iterable

The next trait from the top in Figure 24.1 is `Iterable`. All methods in this trait are defined in terms of an abstract method, `iterator`, which yields the collection's elements one by one. The abstract `foreach` method inherited

from trait Traversable is implemented in Iterable in terms of iterator. Here is the actual implementation:

```
def foreach[U](f: Elem => U): Unit = {
    val it = iterator
    while (it.hasNext) f(it.next())
}
```

Quite a few subclasses of Iterable override this standard implementation of foreach in Iterable, because they can provide a more efficient implementation. Remember that foreach is the basis of the implementation of all operations in Traversable, so its performance matters.

Two more methods exist in Iterable that return iterators: grouped and sliding. These iterators, however, do not return single elements but whole subsequences of elements of the original collection. The maximal size of these subsequences is given as an argument to these methods. The grouped method chunks its elements into increments, whereas sliding yields a sliding window over the elements. The difference between the two should become clear by looking at the following interpreter interaction:

```
scala> val xs = List(1, 2, 3, 4, 5)
xs: List[Int] = List(1, 2, 3, 4, 5)

scala> val git = xs grouped 3
git: Iterator[List[Int]] = non-empty iterator

scala> git.next()
res2: List[Int] = List(1, 2, 3)

scala> git.next()
res3: List[Int] = List(4, 5)

scala> val sit = xs sliding 3
sit: Iterator[List[Int]] = non-empty iterator

scala> sit.next()
res4: List[Int] = List(1, 2, 3)

scala> sit.next()
res5: List[Int] = List(2, 3, 4)

scala> sit.next()
res6: List[Int] = List(3, 4, 5)
```

Trait `Iterable` also adds some other methods to `Traversable` that can be implemented efficiently only if an iterator is available. They are summarized in [Table 24.2](#):

Table 24.2 · Operations in trait `Iterable`

What it is	What it does
Abstract method:	
<code>xs.iterator</code>	An iterator that yields every element in <code>xs</code> , in the same order as <code>foreach</code> traverses elements
Other iterators:	
<code>xs grouped size</code>	An iterator that yields fixed-sized “chunks” of this collection
<code>xs sliding size</code>	An iterator that yields a sliding fixed-sized window of elements in this collection
Subcollections:	
<code>xs takeRight n</code>	A collection consisting of the last <code>n</code> elements of <code>xs</code> (or, some arbitrary <code>n</code> elements, if no order is defined)
<code>xs dropRight n</code>	The rest of the collection except <code>xs takeRight n</code>
Zippers:	
<code>xs zip ys</code>	An iterable of pairs of corresponding elements from <code>xs</code> and <code>ys</code>
<code>xs zipAll (ys, x, y)</code>	An iterable of pairs of corresponding elements from <code>xs</code> and <code>ys</code> , where the shorter sequence is extended to match the longer one by appending elements <code>x</code> or <code>y</code>
<code>xs.zipWithIndex</code>	An iterable of pairs of elements from <code>xs</code> with their indicies
Comparison:	
<code>xs sameElements ys</code>	Tests whether <code>xs</code> and <code>ys</code> contain the same elements in the same order

Why have both `Traversable` and `Iterable`?

You might wonder why the extra trait `Traversable` is above `Iterable`. Can we not do everything with an iterator? So what's the point of having a more abstract trait that defines its methods in terms of `foreach` instead

of `iterator`? One reason for having `Traversable` is that sometimes it is easier or more efficient to provide an implementation of `foreach` than to provide an implementation of `iterator`. Here's a simple example. Let's say you want a class hierarchy for binary trees that have integer elements at the leaves. You might design this hierarchy like this:

```
sealed abstract class Tree
case class Branch(left: Tree, right: Tree) extends Tree
case class Node(elem: Int) extends Tree
```

Now assume you want to make trees traversable. To do this, have `Tree` inherit from `Traversable[Int]` and define a `foreach` method like this:

```
sealed abstract class Tree extends Traversable[Int] {
    def foreach[U](f: Int => U) = this match {
        case Node(elem) => f(elem)
        case Branch(l, r) => l.foreach(f); r.foreach(f)
    }
}
```

That's not too hard, and it is also very efficient—traversing a balanced tree takes time proportional to the number of elements in the tree. To see this, consider that for a balanced tree with N leaves you will have $N - 1$ interior nodes of class `Branch`. So the total number of steps to traverse the tree is $N + N - 1$.

Now, compare this with making trees iterable. To do this, have `Tree` inherit from `Iterable[Int]` and define an `iterator` method like this:

```
sealed abstract class Tree extends Iterable[Int] {
    def iterator: Iterator[Int] = this match {
        case Node(elem) => Iterator.single(elem)
        case Branch(l, r) => l.iterator ++ r.iterator
    }
}
```

At first glance, this looks no harder than the `foreach` solution. However, there's an efficiency problem that has to do with the implementation of the `iterator` concatenation method, `++`. Every time an element is produced by a concatenated iterator such as `l.iterator ++ r.iterator`, the computation needs to follow one indirection to get at the right iterator (either `l.iterator`,

or `r.iterator`). Overall, that makes $\log(N)$ indirections to get at a leaf of a balanced tree with N leaves. So the cost of visiting all elements of a tree went up from about $2N$ for the `foreach` traversal method to $N \log(N)$ for the traversal with `iterator`. If the tree has a million elements that means about two million steps for `foreach` and about twenty million steps for `iterator`. So the `foreach` solution has a clear advantage.

Subcategories of `Iterable`

In the inheritance hierarchy below `Iterable` you find three traits: `Seq`, `Set`, and `Map`. A common aspect of these three traits is that they all implement the `PartialFunction` trait¹ with its `apply` and `isDefinedAt` methods. However, the way each trait implements `PartialFunction` differs.

For sequences, `apply` is positional indexing, where elements are always numbered from 0. That is, `Seq(1, 2, 3)(1) == 2`. For sets, `apply` is a membership test. For instance, `Set('a', 'b', 'c')('b') == true` whereas `Set()('a') == false`. Finally for maps, `apply` is a selection. For instance, `Map('a' -> 1, 'b' -> 10, 'c' -> 100)('b') == 10`.

In the following three sections, we will explain each of the three kinds of collections in more detail.

24.5 The sequence traits `Seq`, `IndexedSeq`, and `LinearSeq`

The `Seq` trait represents sequences. A sequence is a kind of iterable that has a `length` and whose elements have fixed index positions, starting from 0.

The operations on sequences, summarized in [Figure 24.3](#), fall into the following categories:

Indexing and length operations `apply`, `isDefinedAt`, `length`, `indices`, and `lengthCompare`. For a `Seq`, the `apply` operation means indexing; hence a sequence of type `Seq[T]` is a partial function that takes an `Int` argument (an index) and yields a sequence element of type `T`. In other words `Seq[T]` extends `PartialFunction[Int, T]`. The elements of a sequence are indexed from zero up to the `length` of the sequence minus one. The `length` method on sequences is an alias of

¹Partial functions were described in [Section 15.7](#).

the `size` method of general collections. The `lengthCompare` method allows you to compare the lengths of two sequences even if one of the sequences has infinite length.

Index search operations `indexOf`, `lastIndexOf`, `indexOfSlice`, `lastIndexOfSlice`, `indexWhere`, `lastIndexWhere`, `segmentLength`, and `prefixLength`, which return the index of an element equal to a given value or matching some predicate.

Addition operations `:+`, `:+:`, and `padTo`, which return new sequences obtained by adding elements at the front or the end of a sequence.

Update operations `updated` and `patch`, which return a new sequence obtained by replacing some elements of the original sequence.

Sorting operations `sorted`, `sortWith`, and `sortBy`, which sort sequence elements according to various criteria.

Reversal operations `reverse`, `reverseIterator`, and `reverseMap`, which yield or process sequence elements in reverse order, from last to first.

Comparison operations `startsWith`, `endsWith`, `contains`, `corresponds`, and `containsSlice`, which relate two sequences or search an element in a sequence.

Multiset operations `intersect`, `diff`, `union`, and `distinct`, which perform set-like operations on the elements of two sequences or remove duplicates.

If a sequence is mutable, it offers in addition a side-effecting `update` method, which lets sequence elements be updated. Recall from [Chapter 3](#) that syntax like `seq(idx) = elem` is just a shorthand for `seq.update(idx, elem)`. Note the difference between `update` and `updated`. The `update` method changes a sequence element in place, and is only available for mutable sequences. The `updated` method is available for all sequences and always returns a new sequence instead of modifying the original.

Table 24.3 · Operations in trait Seq

What it is	What it does
Indexing and length:	
<code>xs(i)</code>	(or, written out, <code>xs apply i</code>) The element of <code>xs</code> at index <code>i</code> .
<code>xs.isDefinedAt i</code>	Tests whether <code>i</code> is contained in <code>xs.indices</code> .
<code>xs.length</code>	The length of the sequence (same as <code>size</code>).
<code>xs.lengthCompare ys</code>	Returns <code>-1</code> if <code>xs</code> is shorter than <code>ys</code> , <code>+1</code> if it is longer, and <code>0</code> if they have the same length. Works even if one of the sequences is infinite.
<code>xs.indices</code>	The index range of <code>xs</code> , extending from <code>0</code> to <code>xs.length - 1</code> .
Index search:	
<code>xs.indexOf x</code>	The index of the first element in <code>xs</code> equal to <code>x</code> (several variants exist).
<code>xs.lastIndexOf x</code>	The index of the last element in <code>xs</code> equal to <code>x</code> (several variants exist).
<code>xs.indexOfSlice ys</code>	The first index of <code>xs</code> such that successive elements starting from that index form the sequence <code>ys</code> .
<code>xs.lastIndexOfSlice ys</code>	The last index of <code>xs</code> such that successive elements starting from that index form the sequence <code>ys</code> .
<code>xs.indexWhere p</code>	The index of the first element in <code>xs</code> that satisfies <code>p</code> (several variants exist).
<code>xs.segmentLength (p, i)</code>	The length of the longest uninterrupted segment of elements in <code>xs</code> , starting with <code>xs(i)</code> , that all satisfy the predicate <code>p</code> .
<code>xs.prefixLength p</code>	The length of the longest prefix of elements in <code>xs</code> that all satisfy the predicate <code>p</code> .
Additions:	
<code>x +: xs</code>	A new sequence consisting of <code>x</code> prepended to <code>xs</code> .
<code>xs :+ x</code>	A new sequence that consists of <code>x</code> append to <code>xs</code> .
<code>xs.padTo (len, x)</code>	The sequence resulting from appending the value <code>x</code> to <code>xs</code> until length <code>len</code> is reached.
Updates:	

Table 24.3 · continued

<code>xs patch (i, ys, r)</code>	The sequence resulting from replacing r elements of xs starting with i by the patch ys.
<code>xs updated (i, x)</code>	A copy of xs with the element at index i replaced by x.
<code>xs(i) = x</code>	(or, written out, <code>xs.update(i, x)</code> , only available for <code>mutable.Seqs</code>) Changes the element of xs at index i to y.
Sorting:	
<code>xs.sorted</code>	A new sequence obtained by sorting the elements of xs using the standard ordering of the element type of xs.
<code>xs.sortWith lessThan</code>	A new sequence obtained by sorting the elements of xs, using <code>lessThan</code> as comparison operation.
<code>xs.sortBy f</code>	A new sequence obtained by sorting the elements of xs. Comparison between two elements proceeds by mapping the function f over both and comparing the results.
Reversals:	
<code>xs.reverse</code>	A sequence with the elements of xs in reverse order.
<code>xs.reverseIterator</code>	An iterator yielding all the elements of xs in reverse order.
<code>xs.reverseMap f</code>	A sequence obtained by mapping f over the elements of xs in reverse order.
Comparisons:	
<code>xs.startsWith ys</code>	Tests whether xs starts with sequence ys (several variants exist).
<code>xs.endsWith ys</code>	Tests whether xs ends with sequence ys (several variants exist).
<code>xs.contains x</code>	Tests whether xs has an element equal to x.
<code>xs.containsSlice ys</code>	Tests whether xs has a contiguous subsequence equal to ys.
<code>(xs corresponds ys)(p)</code>	Tests whether corresponding elements of xs and ys satisfy the binary predicate p.
Multiset operations:	

Table 24.3 · continued

<code>xs intersect ys</code>	The multi-set intersection of sequences xs and ys that preserves the order of elements in xs.
<code>xs diff ys</code>	The multi-set difference of sequences xs and ys that preserves the order of elements in xs.
<code>xs union ys</code>	Multiset union; same as <code>xs ++ ys</code> .
<code>xs.distinct</code>	A subsequence of xs that contains no duplicated element.

Each Seq trait has two subtraits, LinearSeq and IndexedSeq. These do not add any new operations, but each offers different performance characteristics. A linear sequence has efficient head and tail operations, whereas an indexed sequence has efficient apply, length, and (if mutable) update operations. List is a frequently used linear sequence, as is Stream. Two frequently used indexed sequences are Array and ArrayBuffer. The Vector class provides an interesting compromise between indexed and linear access. It has both effectively constant time indexing overhead and constant time linear access overhead. Because of this, vectors are a good foundation for mixed access patterns where both indexed and linear accesses are used. More on vectors in [Section 24.8](#).

Buffers

An important sub-category of mutable sequences is buffers. Buffers allow not only updates of existing elements but also element insertions, element removals, and efficient additions of new elements at the end of the buffer. The principal new methods supported by a buffer are `+=` and `++=`, for element addition at the end, `+=:` and `++=:` for addition at the front, `insert` and `insertAll` for element insertions, as well as `remove` and `-=` for element removal. These operations are summarized in [Table 24.4](#).

Two Buffer implementations that are commonly used are ListBuffer and ArrayBuffer. As the name implies, a ListBuffer is backed by a List and supports efficient conversion of its elements to a List, whereas an ArrayBuffer is backed by an array, and can be quickly converted into one. You saw a glimpse of the implementation of ListBuffer in [Section 22.2](#).

Table 24.4 · Operations in trait Buffer

What it is	What it does
Additions:	
<code>buf += x</code>	Appends element x to buffer buf, and returns buf itself as result
<code>buf += (x, y, z)</code>	Appends given elements to buffer
<code>buf ++= xs</code>	Appends all elements in xs to buffer
<code>x +=: buf</code>	Prepends element x to buffer
<code>xs ++=: buf</code>	Prepends all elements in xs to buffer
<code>buf insert (i, x)</code>	Inserts element x at index i in buffer
<code>buf insertAll (i, xs)</code>	Inserts all elements in xs at index i in buffer
Removals:	
<code>buf -= x</code>	Removes element x from buffer
<code>buf remove i</code>	Removes element at index i from buffer
<code>buf remove (i, n)</code>	Removes n elements starting at index i from buffer
<code>buf trimStart n</code>	Removes first n elements from buffer
<code>buf trimEnd n</code>	Removes last n elements from buffer
<code>buf.clear()</code>	Removes all elements from buffer
Cloning:	
<code>buf.clone</code>	A new buffer with the same elements as buf

24.6 Sets

Sets are Iterables that contain no duplicate elements. The operations on sets are summarized in [Table 24.5](#) for general sets and [Table 24.6](#) for mutable sets. They fall into the following categories:

Tests contains, apply, and subsetOf. The contains method indicates whether a set contains a given element. The apply method for a set is the same as contains, so `set(elem)` is the same as `set contains elem`. That means sets can also be used as test functions that return true for the elements they contain. For example:

```

scala> val fruit = Set("apple", "orange", "peach", "banana")
fruit: scala.collection.immutable.Set[String] =
Set(apple, orange, peach, banana)

scala> fruit("peach")
res7: Boolean = true

scala> fruit("potato")
res8: Boolean = false

```

Additions + and ++, which add one or more elements to a set, yielding a new set as a result.

Removals - and --, which remove one or more elements from a set, yielding a new set.

Set operations for union, intersection, and set difference. These set operations exist in two forms: alphabetic and symbolic. The alphabetic versions are intersect, union, and diff, whereas the symbolic versions are &, |, and &~. The ++ that Set inherits from Traversable can be seen as yet another alias of union or |, except that ++ takes a Traversable argument whereas union and | take sets.

Table 24.5 · Operations in trait Set

What it is	What it does
Tests:	
xs contains x	Tests whether x is an element of xs
xs(x)	Same as xs contains x
xs subsetOf ys	Tests whether xs is a subset of ys
Additions:	
xs + x	The set containing all elements of xs as well as x
xs + (x, y, z)	The set containing all elements of xs as well as the given additional elements
xs ++ ys	The set containing all elements of xs as well as all elements of ys

Removals:

Table 24.5 · continued

<code>xs - x</code>	The set containing all elements of <code>xs</code> except <code>x</code>
<code>xs - (x, y, z)</code>	The set containing all elements of <code>xs</code> except the given elements
<code>xs -- ys</code>	The set containing all elements of <code>xs</code> except the elements of <code>ys</code>
<code>xs.empty</code>	An empty set of the same class as <code>xs</code>
Binary operations:	
<code>xs & ys</code>	The set intersection of <code>xs</code> and <code>ys</code>
<code>xs intersect ys</code>	Same as <code>xs & ys</code>
<code>xs ys</code>	The set union of <code>xs</code> and <code>ys</code>
<code>xs union ys</code>	Same as <code>xs ys</code>
<code>xs &~ ys</code>	The set difference of <code>xs</code> and <code>ys</code>
<code>xs diff ys</code>	Same as <code>xs &~ ys</code>

Mutable sets have methods that add, remove, or update elements, which are summarized in [Table 24.6](#):

Table 24.6 · Operations in trait `mutable.Set`

What it is	What it does
Additions:	
<code>xs += x</code>	Adds element <code>x</code> to set <code>xs</code> as a side effect and returns <code>xs</code> itself
<code>xs += (x, y, z)</code>	Adds the given elements to set <code>xs</code> as a side effect and returns <code>xs</code> itself
<code>xs ++= ys</code>	Adds all elements in <code>ys</code> to set <code>xs</code> as a side effect and returns <code>xs</code> itself
<code>xs add x</code>	Adds element <code>x</code> to <code>xs</code> and returns <code>true</code> if <code>x</code> was not previously contained in the set, <code>false</code> if it was previously contained
Removals:	
<code>xs -= x</code>	Removes element <code>x</code> from set <code>xs</code> as a side effect and returns <code>xs</code> itself
<code>xs -= (x, y, z)</code>	Removes the given elements from set <code>xs</code> as a side effect and returns <code>xs</code> itself

Table 24.6 · continued

<code>xs --- ys</code>	Removes all elements in <code>ys</code> from set <code>xs</code> as a side effect and returns <code>xs</code> itself
<code>xs remove x</code>	Removes element <code>x</code> from <code>xs</code> and returns <code>true</code> if <code>x</code> was previously contained in the set, <code>false</code> if it was not previously contained
<code>xs retain p</code>	Keeps only those elements in <code>xs</code> that satisfy predicate <code>p</code>
<code>xs.clear()</code>	Removes all elements from <code>xs</code>
Update:	
<code>xs(x) = b</code>	(or, written out, <code>xs.update(x, b)</code>) If boolean argument <code>b</code> is <code>true</code> , adds <code>x</code> to <code>xs</code> , otherwise removes <code>x</code> from <code>xs</code>
Cloning:	
<code>xs.clone</code>	A new mutable set with the same elements as <code>xs</code>

Just like an immutable set, a mutable set offers the `+` and `++` operations for element additions and the `-` and `--` operations for element removals. But these are less often used for mutable sets since they involve copying the set. As a more efficient alternative, mutable sets offer the update methods `+=` and `-=`. The operation `s += elem` adds `elem` to the set `s` as a side effect, and returns the mutated set as a result. Likewise, `s -= elem` removes `elem` from the set, and returns the mutated set as a result. Besides `+=` and `-=` there are also the bulk operations `++=` and `--=`, which add or remove all elements of a traversable or an iterator.

The choice of the method names `+=` and `-=` means that very similar code can work with either mutable or immutable sets. Consider first the following interpreter dialogue that uses an immutable set `s`:

```
scala> var s = Set(1, 2, 3)
s: scala.collection.immutable.Set[Int] = Set(1, 2, 3)

scala> s += 4; s -= 2

scala> s
res10: scala.collection.immutable.Set[Int] = Set(1, 3, 4)
```

In this example, we used `+=` and `-=` on a `var` of type `immutable.Set`. As was explained in Step 10 in Chapter 3, a statement such as `s += 4` is an

abbreviation for `s = s + 4`. So this invokes the addition method `+` on the set `s` and then assigns the result back to the `s` variable. Consider now an analogous interaction with a mutable set:

```
scala> val s = collection.mutable.Set(1, 2, 3)
s: scala.collection.mutable.Set[Int] = Set(1, 2, 3)

scala> s += 4
res11: s.type = Set(1, 2, 3, 4)

scala> s -= 2
res12: s.type = Set(1, 3, 4)
```

The end effect is very similar to the previous interaction; we start with a `Set(1, 2, 3)` and end up with a `Set(1, 3, 4)`. However, even though the statements look the same as before, they do something different. The `s += 4` statement now invokes the `+=` method on the mutable set value `s`, changing the set in place. Likewise, the `s -= 2` statement now invokes the `=-` method on the same set.

Comparing the two interactions shows an important principle. You often can replace a mutable collection stored in a `val` by an immutable collection stored in a `var`, and *vice versa*. This works at least as long as there are no alias references to the collection through which you can observe whether it was updated in place or a new collection was created.

Mutable sets also provide `add` and `remove` as variants of `+=` and `=-`. The difference is that `add` and `remove` return a boolean result indicating whether the operation had an effect on the set.

The current default implementation of a mutable set uses a hash table to store the set's elements. The default implementation of an immutable set uses a representation that adapts to the number of elements of the set. An empty set is represented by just a singleton object. Sets of sizes up to four are represented by a single object that stores all elements as fields. Beyond that size, immutable sets are implemented as hash tries.²

A consequence of these representation choices is that for sets of small sizes, up to about four, immutable sets are more compact and more efficient than mutable sets. So if you expect the size of a set to be small, try to make it immutable.

²Hash tries are described in [Section 24.8](#).

24.7 Maps

Maps are Iterables of pairs of keys and values (also named *mappings* or *associations*). As explained in [Section 21.4](#), Scala’s Predef class offers an implicit conversion that lets you write key → value as an alternate syntax for the pair (key, value). Therefore, Map("x" → 24, "y" → 25, "z" → 26) means exactly the same as Map(("x", 24), ("y", 25), ("z", 26)), but reads better.

The fundamental operations on maps, summarized in [Table 24.7](#), are similar to those on sets. Mutable maps additionally support the operations shown in [Table 24.8](#). Map operations fall into the following categories:

Lookups apply, get, getOrElse, contains, and isDefinedAt. These operations turn maps into partial functions from keys to values. The fundamental lookup method for a map is:

```
def get(key): Option[Value]
```

The operation “m get key” tests whether the map contains an association for the given key. If so, it returns the associated value in a Some. If no key is defined in the map, get returns None. Maps also define an apply method that returns the value associated with a given key directly, without wrapping it in an Option. If the key is not defined in the map, an exception is raised.

Additions and updates +, ++, and updated, which let you add new bindings to a map or change existing bindings.

Removals – and --, which remove bindings from a map.

Subcollection producers keys, keySet, keysIterator, valuesIterator, and values, which return a map’s keys and values separately in various forms.

Transformations filterKeys and mapValues, which produce a new map by filtering and transforming bindings of an existing map.

Table 24.7 · Operations in trait Map

What it is	What it does
Lookups:	
<code>ms get k</code>	The value associated with key k in map <code>ms</code> as an option, or <code>None</code> if not found
<code>ms(k)</code>	(or, written out, <code>ms apply k</code>) The value associated with key k in map <code>ms</code> , or a thrown exception if not found
<code>ms getOrElse (k, d)</code>	The value associated with key k in map <code>ms</code> , or the default value <code>d</code> if not found
<code>ms contains k</code>	Tests whether <code>ms</code> contains a mapping for key k
<code>ms isDefinedAt k</code>	Same as <code>contains</code>
Additions and updates:	
<code>ms + (k -> v)</code>	The map containing all mappings of <code>ms</code> as well as the mapping <code>k -> v</code> from key k to value v
<code>ms + (k -> v, l -> w)</code>	The map containing all mappings of <code>ms</code> as well as the given key/value pairs
<code>ms ++ kvs</code>	The map containing all mappings of <code>ms</code> as well as all key/value pairs of <code>kvs</code>
<code>ms updated (k, v)</code>	Same as <code>ms + (k -> v)</code>
Removals:	
<code>ms - k</code>	The map containing all mappings of <code>ms</code> except for any mapping of key k
<code>ms - (k, l, m)</code>	The map containing all mappings of <code>ms</code> except for any mapping with the given keys
<code>ms -- ks</code>	The map containing all mappings of <code>ms</code> except for any mapping with a key in <code>ks</code>
Subcollections:	
<code>ms.keys</code>	An iterable containing each key in <code>ms</code>
<code>ms.keySet</code>	A set containing each key in <code>ms</code>
<code>ms.keysIterator</code>	An iterator yielding each key in <code>ms</code>
<code>ms.values</code>	An iterable containing each value associated with a key in <code>ms</code>
<code>ms.valuesIterator</code>	An iterator yielding each value associated with a key in <code>ms</code>

Table 24.7 · continued

Transformation:

<code>ms filterKeys p</code>	A map view containing only those mappings in <code>ms</code> where the key satisfies predicate <code>p</code>
<code>ms mapValues f</code>	A map view resulting from applying function <code>f</code> to each value associated with a key in <code>ms</code>

Table 24.8 · Operations in trait `mutable.Map`

What it is	What it does
Additions and updates:	
<code>ms(k) = v</code>	(or, written out, <code>ms.update(k, v)</code>) Adds mapping from key <code>k</code> to value <code>v</code> to map <code>ms</code> as a side effect, overwriting any previous mapping of <code>k</code>
<code>ms += (k -> v)</code>	Adds mapping from key <code>k</code> to value <code>v</code> to map <code>ms</code> as a side effect and returns <code>ms</code> itself
<code>ms += (k -> v, l -> w)</code>	Adds the given mappings to <code>ms</code> as a side effect and returns <code>ms</code> itself
<code>ms ++= kvs</code>	Adds all mappings in <code>kvs</code> to <code>ms</code> as a side effect and returns <code>ms</code> itself
<code>ms put (k, v)</code>	Adds mapping from key <code>k</code> to value <code>v</code> to <code>ms</code> and returns any value previously associated with <code>k</code> as an option
<code>msgetOrElseUpdate (k, d)</code>	If key <code>k</code> is defined in map <code>ms</code> , returns its associated value. Otherwise, updates <code>ms</code> with the mapping <code>k -> d</code> and returns <code>d</code>
Removals:	
<code>ms -= k</code>	Removes mapping with key <code>k</code> from <code>ms</code> as a side effect and returns <code>ms</code> itself
<code>ms -= (k, l, m)</code>	Removes mappings with the given keys from <code>ms</code> as a side effect and returns <code>ms</code> itself
<code>ms --- ks</code>	Removes all keys in <code>ks</code> from <code>ms</code> as a side effect and returns <code>ms</code> itself
<code>ms remove k</code>	Removes any mapping with key <code>k</code> from <code>ms</code> and returns any value previously associated with <code>k</code> as an option

Table 24.8 · continued

<code>ms retain p</code>	Keeps only those mappings in <code>ms</code> that have a key satisfying predicate <code>p</code> .
<code>ms.clear()</code>	Removes all mappings from <code>ms</code>
Transformation and cloning:	
<code>ms transform f</code>	Transforms all associated values in map <code>ms</code> with function <code>f</code>
<code>ms.clone</code>	Returns a new mutable map with the same mappings as <code>ms</code>

The addition and removal operations for maps mirror those for sets. As for sets, mutable maps also support the non-destructive addition operations `+`, `-`, and `updated`, but they are used less frequently because they involve a copying of the mutable map. Instead, a mutable map `m` is usually updated “in place,” using the two variants `m(key) = value` or `m += (key -> value)`. There is also the variant `m put (key, value)`, which returns an `Option` value that contains the value previously associated with `key`, or `None` if the `key` did not exist in the map before.

The `getOrElseUpdate` is useful for accessing maps that act as caches. Say you have an expensive computation triggered by invoking a function `f`:

```
scala> def f(x: String) = {
    |   println("taking my time.");
    |   Thread.sleep(100)
    |   x.reverse
  }
f: (x: String)String
```

Assume further that `f` has no side-effects, so invoking it again with the same argument will always yield the same result. In that case you could save time by storing previously computed bindings of argument and results of `f` in a map, and only computing the result of `f` if a result of an argument was not found there. You could say the map is a *cache* for the computations of the function `f`.

```
scala> val cache = collection.mutable.Map[String, String]()
cache: scala.collection.mutable.Map[String, String] = Map()
```

You can now create a more efficient caching version of the `f` function:

```
scala> def cachedF(s: String) = cache.getOrElseUpdate(s, f(s))
cachedF: (s: String)String

scala> cachedF("abc")
taking my time.
res16: String = cba

scala> cachedF("abc")
res17: String = cba
```

Note that the second argument to `getOrElseUpdate` is “by-name,” so the computation of `f("abc")` above is only performed if `getOrElseUpdate` requires the value of its second argument, which is precisely if its first argument is not found in the cache map. You could also have implemented `cachedF` directly, using just basic map operations, but it would have taken more code to do so:

```
def cachedF(arg: String) = cache get arg match {
  case Some(result) => result
  case None =>
    val result = f(arg)
    cache(arg) = result
    result
}
```

24.8 Concrete immutable collection classes

Scala provides many concrete immutable collection classes for you to choose from. They differ in the traits they implement (maps, sets, sequences), whether they can be infinite, and the speed of various operations. We’ll start by reviewing the most common immutable collection types.

Lists

Lists are finite immutable sequences. They provide constant-time access to their first element as well as the rest of the list, and they have a constant-time `cons` operation for adding a new element to the front of the list. Many other operations take linear time. See [Chapters 16](#) and [22](#) for extensive discussions about lists.

Streams

A stream is like a list except that its elements are computed lazily. Because of this, a stream can be infinitely long. Only those elements requested will be computed. Otherwise, streams have the same performance characteristics as lists.

Whereas lists are constructed with the `::` operator, streams are constructed with the similar-looking `#::`. Here is a simple example of a stream containing the integers 1, 2, and 3:

```
scala> val str = 1 #:: 2 #:: 3 #:: Stream.empty
str: scala.collection.immutable.Stream[Int] = Stream(1, ?)
```

The head of this stream is 1, and the tail of it has 2 and 3. The tail is not printed here, though, because it hasn't been computed yet! Streams are required to compute lazily, and the `toString` method of a stream is careful not to force any extra evaluation.

Below is a more complex example. It computes a stream that contains a Fibonacci sequence starting with the given two numbers. A Fibonacci sequence is one where each element is the sum of the previous two elements in the series:

```
scala> def fibFrom(a: Int, b: Int): Stream[Int] =
    a #:: fibFrom(b, a + b)
fibFrom: (a: Int, b: Int)Stream[Int]
```

This function is deceptively simple. The first element of the sequence is clearly `a`, and the rest of the sequence is the Fibonacci sequence starting with `b` followed by `a + b`. The tricky part is computing this sequence without causing an infinite recursion. If the function used `::` instead of `#::`, then every call to the function would result in another call, thus causing an infinite recursion. Since it uses `#::`, though, the right-hand side is not evaluated until it is requested.

Here are the first few elements of the Fibonacci sequence starting with two ones:

```
scala> val fibs = fibFrom(1, 1).take(7)
fibs: scala.collection.immutable.Stream[Int] = Stream(1, ?)

scala> fibs.toList
res23: List[Int] = List(1, 1, 2, 3, 5, 8, 13)
```

Vectors

Lists are very efficient when the algorithm processing them is careful to only process their heads. Accessing, adding, and removing the head of a list takes only constant time, whereas accessing or modifying elements later in the list takes time linear in the depth into the list.

Vectors are a collection type that give efficient access to elements beyond the head. Access to any elements of a vector take only “effectively constant time,” as defined below. It’s a larger constant than for access to the head of a list or for reading an element of an array, but it’s a constant nonetheless. As a result, algorithms using vectors do not have to be careful about accessing just the head of the sequence. They can access and modify elements at arbitrary locations, and thus they can be much more convenient to write.

Vectors are built and modified just like any other sequence:

```
scala> val vec = scala.collection.immutable.Vector.empty
vec: scala.collection.immutable.Vector[Nothing] = Vector()

scala> val vec2 = vec :+ 1 :+ 2
vec2: scala.collection.immutable.Vector[Int] = Vector(1, 2)

scala> val vec3 = 100 +: vec2
vec3: scala.collection.immutable.Vector[Int]
= Vector(100, 1, 2)

scala> vec3(0)
res24: Int = 100
```

Vectors are represented as broad, shallow trees. Every tree node contains up to 32 elements of the vector or contains up to 32 other tree nodes. Vectors with up to 32 elements can be represented in a single node. Vectors with up to $32 * 32 = 1024$ elements can be represented with a single indirection. Two hops from the root of the tree to the final element node are sufficient for vectors with up to 2^{15} elements, three hops for vectors with 2^{20} , four hops for vectors with 2^{25} elements and five hops for vectors with up to 2^{30} elements. So for all vectors of reasonable size, an element selection involves up to five primitive array selections. This is what we meant when we wrote that element access is “effectively constant time.”

Vectors are immutable, so you cannot change an element of a vector in place. However, with the updated method you can create a new vector that differs from a given vector only in a single element:

```
scala> val vec = Vector(1, 2, 3)
vec: scala.collection.immutable.Vector[Int] = Vector(1, 2, 3)
scala> vec updated (2, 4)
res25: scala.collection.immutable.Vector[Int] = Vector(1, 2, 4)
scala> vec
res26: scala.collection.immutable.Vector[Int] = Vector(1, 2, 3)
```

As the last line above shows, a call to `updated` has no effect on the original vector `vec`. Like selection, functional vector updates are also “effectively constant time.” Updating an element in the middle of a vector can be done by copying the node that contains the element, and every node that points to it, starting from the root of the tree. This means that a functional update creates between one and five nodes that each contain up to 32 elements or subtrees. This is certainly more expensive than an in-place update in a mutable array, but still a lot cheaper than copying the whole vector.

Because vectors strike a good balance between fast random selections and fast random functional updates, they are currently the default implementation of immutable indexed sequences:

```
scala> collection.immutable.IndexedSeq(1, 2, 3)
res27: scala.collection.immutable.IndexedSeq[Int]
= Vector(1, 2, 3)
```

Immutable stacks

If you need a last-in-first-out sequence, you can use a `Stack`. You push an element onto a stack with `push`, pop an element with `pop`, and peek at the top of the stack without removing it with `top`. All of these operations are constant time.

Here are some simple operations performed on a stack:

```
scala> val stack = scala.collection.immutable.Stack.empty
stack: scala.collection.immutable.Stack[Nothing] = Stack()
scala> val hasOne = stack.push(1)
hasOne: scala.collection.immutable.Stack[Int] = Stack(1)
scala> stack
res28: scala.collection.immutable.Stack[Nothing] = Stack()
```

```
scala> hasOne.top
res29: Int = 1

scala> hasOne.pop
res30: scala.collection.immutable.Stack[Int] = Stack()
```

Immutable stacks are used rarely in Scala programs because their functionality is subsumed by lists: A push on an immutable stack is the same as `a ::` on a list, and a pop on a stack is the same as `tail` on a list.

Immutable queues

A queue is just like a stack except that it is first-in-first-out rather than last-in-first-out. A simplified implementation of immutable queues was discussed in [Chapter 19](#). Here's how you can create an empty immutable queue:

```
scala> val empty = scala.collection.immutable.Queue[Int]()
empty: scala.collection.immutable.Queue[Int] = Queue()
```

You can append an element to an immutable queue with `enqueue`:

```
scala> val has1 = empty.enqueue(1)
has1: scala.collection.immutable.Queue[Int] = Queue(1)
```

To append multiple elements to a queue, call `enqueue` with a collection as its argument:

```
scala> val has123 = has1.enqueue(List(2, 3))
has123: scala.collection.immutable.Queue[Int] = Queue(1, 2,
3)
```

To remove an element from the head of the queue, use `dequeue`:

```
scala> val (element, has23) = has123.dequeue
element: Int = 1
has23: scala.collection.immutable.Queue[Int] = Queue(2, 3)
```

Note that `dequeue` returns a pair consisting of the element removed and the rest of the queue.

Ranges

A range is an ordered sequence of integers that are equally spaced apart. For example, “1, 2, 3” is a range, as is “5, 8, 11, 14.” To create a range in Scala, use the predefined methods `to` and `by`. Here are some examples:

```
scala> 1 to 3
res31: scala.collection.immutable.Range.Inclusive
      = Range(1, 2, 3)

scala> 5 to 14 by 3
res32: scala.collection.immutable.Range = Range(5, 8, 11, 14)
```

If you want to create a range that is exclusive of its upper limit, use the convenience method `until` instead of `to`:

```
scala> 1 until 3
res33: scala.collection.immutable.Range = Range(1, 2)
```

Ranges are represented in constant space, because they can be defined by just three numbers: their start, their end, and the stepping value. Because of this representation, most operations on ranges are extremely fast.

Hash tries

Hash tries³ are a standard way to implement immutable sets and maps efficiently. Their representation is similar to vectors in that they are also trees where every node has 32 elements or 32 subtrees, but selection is done based on a hash code. For instance, to find a given key in a map, you use the lowest five bits of the hash code of the key to select the first subtree, the next five bits the next subtree, and so on. Selection stops once all elements stored in a node have hash codes that differ from each other in the bits that are selected so far. Thus, not all the bits of the hash code are necessarily used.

Hash tries strike a nice balance between reasonably fast lookups and reasonably efficient functional insertions (+) and deletions (-). That's why they underlie Scala's default implementations of immutable maps and sets. In fact, Scala has a further optimization for immutable sets and maps that contain less than five elements. Sets and maps with one to four elements are stored as single objects that just contain the elements (or key/value pairs in

³“Trie” comes from the word “retrieval” and is pronounced *tree* or *try*.

the case of a map) as fields. The empty immutable set and empty immutable map is in each case a singleton object—there’s no need to duplicate storage for those because an empty immutable set or map will always stay empty.

Red-black trees

Red-black trees are a form of balanced binary trees where some nodes are designated “red” and others “black.” Like any balanced binary tree, operations on them reliably complete in time logarithmic to the size of the tree.

Scala provides implementations of sets and maps that use a red-black tree internally. You access them under the names `TreeSet` and `TreeMap`:

```
scala> val set = collection.immutable.TreeSet.empty[Int]
set: scala.collection.immutable.TreeSet[Int] = TreeSet()
scala> set + 1 + 3 + 3
res34: scala.collection.immutable.TreeSet[Int] = TreeSet(1, 3)
```

Red-black trees are also the standard implementation of `SortedSet` in Scala, because they provide an efficient iterator that returns all elements of the set in sorted order.

Immutable bit sets

A bit set represents a collection of small integers as the bits of a larger integer. For example, the bit set containing 3, 2, and 0 would be represented as the integer 1101 in binary, which is 13 in decimal.

Internally, bit sets use an array of 64-bit `Longs`. The first `Long` in the array is for integers 0 through 63, the second is for 64 through 127, and so on. Thus, bit sets are very compact so long as the largest integer in the set is less than a few hundred or so.

Operations on bit sets are very fast. Testing for inclusion takes constant time. Adding an item to the set takes time proportional to the number of `Longs` in the bit set’s array, which is typically a small number. Here are some simple examples of the use of a bit set:

```
scala> val bits = scala.collection.immutable.BitSet.empty
bits: scala.collection.immutable.BitSet = BitSet()
scala> val moreBits = bits + 3 + 4 + 4
moreBits: scala.collection.immutable.BitSet = BitSet(3, 4)
```

```
scala> moreBits(3)
res35: Boolean = true

scala> moreBits(0)
res36: Boolean = false
```

List maps

A list map represents a map as a linked list of key-value pairs. In general, operations on a list map might have to iterate through the entire list. Thus, operations on a list map take time linear in the size of the map. In fact there is little usage for list maps in Scala because standard immutable maps are almost always faster. The only possible difference is if the map is for some reason constructed in such a way that the first elements in the list are selected much more often than the other elements.

```
scala> val map = collection.immutable.ListMap(
    1 -> "one", 2 -> "two")
map: scala.collection.immutable.ListMap[Int, String] = Map(1
-> one, 2 -> two)

scala> map(2)
res37: String = "two"
```

24.9 Concrete mutable collection classes

Now that you've seen the most commonly used immutable collection classes that Scala provides in its standard library, take a look at the mutable collection classes.

Array buffers

You've already seen array buffers in [Section 17.1](#). An array buffer holds an array and a size. Most operations on an array buffer have the same speed as an array, because the operations simply access and modify the underlying array. Additionally, array buffers can have data efficiently added to the end. Appending an item to an array buffer takes amortized constant time. Thus, array buffers are useful for efficiently building up a large collection whenever the new items are always added to the end. Here are some examples:

```
scala> val buf = collection.mutable.ArrayBuffer.empty[Int]
buf: scala.collection.mutable.ArrayBuffer[Int]
= ArrayBuffer()

scala> buf += 1
res38: buf.type = ArrayBuffer(1)

scala> buf += 10
res39: buf.type = ArrayBuffer(1, 10)

scala> buf.toArray
res40: Array[Int] = Array(1, 10)
```

List buffers

You've also already seen list buffers in [Section 17.1](#). A list buffer is like an array buffer except that it uses a linked list internally instead of an array. If you plan to convert the buffer to a list once it is built up, use a list buffer instead of an array buffer. Here's an example:⁴

```
scala> val buf = collection.mutable.ListBuffer.empty[Int]
buf: scala.collection.mutable.ListBuffer[Int]
= ListBuffer()

scala> buf += 1
res41: buf.type = ListBuffer(1)

scala> buf += 10
res42: buf.type = ListBuffer(1, 10)

scala> buf.toList
res43: List[Int] = List(1, 10)
```

String builders

Just like an array buffer is useful for building arrays, and a list buffer is useful for building lists, a string builder is useful for building strings. String builders are so commonly used that they are already imported into the default namespace. Create them with a simple new `StringBuilder`, like this:

⁴The “`buf.type`” that appears in the interpreter responses in this and several other examples in this section is a *singleton type*. As will be explained in [Section 29.6](#), `buf.type` means the variable holds exactly the object referred to by `buf`.

```
scala> val buf = new StringBuilder
buf: StringBuilder =
scala> buf += 'a'
res44: buf.type = a
scala> buf +++ "bcdef"
res45: buf.type = abcdef
scala> buf.toString
res46: String = abcdef
```

Linked lists

Linked lists are mutable sequences that consist of nodes that are linked with next pointers. In most languages null would be picked as the empty linked list. That does not work for Scala collections, because even empty sequences must support all sequence methods. `LinkedList.empty.isEmpty`, in particular, should return `true` and not throw a `NullPointerException`. Empty linked lists are encoded instead in a special way: Their next field points back to the node itself.

Like their immutable cousins, linked lists are best operated on sequentially. In addition, linked lists make it easy to insert an element or linked list into another linked list.

Double linked lists

`DoubleLinkedLists` are like the single linked lists described in the previous subsection, except besides `next`, they have another mutable field, `prev`, that points to the element preceding the current node. The main benefit of that additional link is that it makes element removal very fast.

Mutable lists

A `MutableList` consists of a single linked list together with a pointer that refers to the terminal empty node of that list. This makes list append a constant time operation because it avoids having to traverse the list in search for its terminal node. `MutableList` is currently the standard implementation of `mutable.LinearSeq` in Scala.

Queues

Scala provides mutable queues in addition to immutable ones. You use a mutable queue similarly to the way you use an immutable one, but instead of enqueue, you use the `+=` and `++=` operators to append. Also, on a mutable queue, the `dequeue` method will just remove the head element from the queue and return it. Here's an example:

```
scala> val queue = new scala.collection.mutable.Queue[String]
queue: scala.collection.mutable.Queue[String] = Queue()
scala> queue += "a"
res47: queue.type = Queue(a)
scala> queue ++= List("b", "c")
res48: queue.type = Queue(a, b, c)
scala> queue
res49: scala.collection.mutable.Queue[String] = Queue(a, b, c)
scala> queue.dequeue
res50: String = a
scala> queue
res51: scala.collection.mutable.Queue[String] = Queue(b, c)
```

Array sequences

Array sequences are mutable sequences of fixed size that store their elements internally in an `Array[AnyRef]`. They are implemented in Scala by class `ArraySeq`.

You would typically use an `ArraySeq` if you want an array for its performance characteristics, but you also want to create generic instances of the sequence where you do not know the type of the elements and do not have a `ClassTag` to provide it at run-time. You will find out about these issues with arrays shortly, in [Section 24.10](#).

Stacks

You saw immutable stacks earlier. There is also a mutable version. It works exactly the same as the immutable version except that modifications happen in place. Here's an example:

```
scala> val stack = new scala.collection.mutable.Stack[Int]
stack: scala.collection.mutable.Stack[Int] = Stack()
scala> stack.push(1)
res52: stack.type = Stack(1)
scala> stack
res53: scala.collection.mutable.Stack[Int] = Stack(1)
scala> stack.push(2)
res54: stack.type = Stack(2, 1)
scala> stack
res55: scala.collection.mutable.Stack[Int] = Stack(2, 1)
scala> stack.top
res56: Int = 2
scala> stack
res57: scala.collection.mutable.Stack[Int] = Stack(2, 1)
scala> stack.pop
res58: Int = 2
scala> stack
res59: scala.collection.mutable.Stack[Int] = Stack(1)
```

Array stacks

ArrayList is an alternative implementation of a mutable stack, which is backed by an Array that gets resized as needed. It provides fast indexing and is generally slightly more efficient for most operations than a normal mutable stack.

Hash tables

A hash table stores its elements in an underlying array, placing each item at a position in the array determined by the hash code of that item. Adding an element to a hash table takes only constant time, so long as there isn't already another element in the array that has the same hash code. Hash tables are thus very fast so long as the objects placed in them have a good distribution of hash codes. As a result, the default mutable map and set types in Scala are based on hash tables.

Hash sets and maps are used just like any other set or map. Here are some simple examples:

```
scala> val map = collection.mutable.HashMap.empty[Int, String]
map: scala.collection.mutable.HashMap[Int, String] = Map()

scala> map += (1 -> "make a web site")
res60: map.type = Map(1 -> make a web site)

scala> map += (3 -> "profit!")
res61: map.type = Map(1 -> make a web site, 3 -> profit!)

scala> map(1)
res62: String = make a web site

scala> map contains 2
res63: Boolean = false
```

Iteration over a hash table is not guaranteed to occur in any particular order. Iteration simply proceeds through the underlying array in whichever order it happens to be. To get a guaranteed iteration order, use a *linked* hash map or set instead of a regular one. A linked hash map or set is just like a regular hash map or set except that it also includes a linked list of the elements in the order they were added. Iteration over such a collection is always in the same order that the elements were initially added.

Weak hash maps

A weak hash map is a special kind of hash map in which the garbage collector does not follow links from the map to the keys stored in it. This means that a key and its associated value will disappear from the map if there is no other reference to that key. Weak hash maps are useful for tasks such as caching, where you want to re-use an expensive function's result if the function is called again on the same key. If keys and function results are stored in a regular hash map, the map could grow without bounds, and no key would ever become garbage. Using a weak hash map avoids this problem. As soon as a key object becomes unreachable, its entry is removed from the weak hash map. Weak hash maps in Scala are implemented as a wrapper of an underlying Java implementation, `java.util.WeakHashMap`.

Concurrent Maps

A concurrent map can be accessed by several threads at once. In addition to the usual Map operations, it provides the following atomic operations:

Table 24.9 · Operations in trait ConcurrentMap

What it is	What it does
<code>m putIfAbsent(k, v)</code>	Adds key/value binding $k \rightarrow m$ unless k is already defined in m
<code>m remove (k, v)</code>	Removes entry for k if it is currently mapped to v
<code>m replace (k, old, new)</code>	Replaces value associated with key k to new , if it was previously bound to old
<code>m replace (k, v)</code>	Replaces value associated with key k to v , if it was previously bound to some value

ConcurrentMap is a trait in the Scala collections library. Currently, its only implementation is Java's `java.util.concurrent.ConcurrentMap`, which can be converted automatically into a Scala map using the standard Java/Scala collection conversions, which will be described in [Section 24.17](#).

Mutable bit sets

A mutable bit set is just like an immutable one, except that it can be modified in place. Mutable bit sets are slightly more efficient at updating than immutable ones, because they don't have to copy around Longs that haven't changed. Here is an example:

```
scala> val bits = scala.collection.mutable.BitSet.empty
bits: scala.collection.mutable.BitSet = BitSet()
scala> bits += 1
res64: bits.type = BitSet(1)
scala> bits += 3
res65: bits.type = BitSet(1, 3)
scala> bits
res66: scala.collection.mutable.BitSet = BitSet(1, 3)
```

24.10 Arrays

Arrays are a special kind of collection in Scala. One the one hand, Scala arrays correspond one-to-one to Java arrays. That is, a Scala array `Array[Int]` is represented as a Java `int[]`, an `Array[Double]` is represented as a Java `double[]` and an `Array[String]` is represented as a Java `String[]`. But at the same time, Scala arrays offer much more than their Java analogues. First, Scala arrays can be *generic*. That is, you can have an `Array[T]`, where T is a type parameter or abstract type. Second, Scala arrays are compatible with Scala sequences—you can pass an `Array[T]` where a `Seq[T]` is required. Finally, Scala arrays also support all sequence operations. Here's an example of this in action:

```
scala> val a1 = Array(1, 2, 3)
a1: Array[Int] = Array(1, 2, 3)

scala> val a2 = a1 map (_ * 3)
a2: Array[Int] = Array(3, 6, 9)

scala> val a3 = a2 filter (_ % 2 != 0)
a3: Array[Int] = Array(3, 9)

scala> a3.reverse
res1: Array[Int] = Array(9, 3)
```

Given that Scala arrays are represented just like Java arrays, how can these additional features be supported in Scala?

The answer lies in systematic use of implicit conversions. An array cannot pretend to be a sequence, because the data type representation of a native array is not a subtype of `Seq`. Instead, whenever an array would be used as a `Seq`, implicitly wrap it in a subclass of `Seq`. The name of that subclass is `scala.collection.mutable.WrappedArray`. Here you see it in action:

```
scala> val seq: Seq[Int] = a1
seq: Seq[Int] = WrappedArray(1, 2, 3)

scala> val a4: Array[Int] = seq.toArray
a4: Array[Int] = Array(1, 2, 3)

scala> a1 eq a4
res2: Boolean = true
```

This interaction demonstrates that arrays are compatible with sequences, because there's an implicit conversion from `Array` to `WrappedArray`. To go the other way, from a `WrappedArray` to an `Array`, you can use the `toArray` method defined in `Traversable`. The last interpreter line above shows that wrapping then unwrapping with `toArray` gives you back the same array you started with.

There is yet another implicit conversion that gets applied to arrays. This conversion simply “adds” all sequence methods to arrays but does not turn the array itself into a sequence. “Adding” means that the array is wrapped in another object of type `ArrayOps`, which supports all sequence methods. Typically, this `ArrayOps` object is short-lived; it will usually be inaccessible after the call to the sequence method and its storage can be recycled. Modern VMs often avoid creating this object entirely.

The difference between the two implicit conversions on arrays is demonstrated here:

```
scala> val seq: Seq[Int] = a1
seq: Seq[Int] = WrappedArray(1, 2, 3)

scala> seq.reverse
res2: Seq[Int] = WrappedArray(3, 2, 1)

scala> val ops: collection.mutable.ArrayOps[Int] = a1
ops: scala.collection.mutable.ArrayOps[Int] = [I(1, 2, 3)

scala> ops.reverse
res3: Array[Int] = Array(3, 2, 1)
```

You see that calling `reverse` on `seq`, which is a `WrappedArray`, will give again a `WrappedArray`. That's logical, because wrapped arrays are `Seqs`, and calling `reverse` on any `Seq` will give again a `Seq`. On the other hand, calling `reverse` on the `ops` value of class `ArrayOps` will result in an `Array`, not a `Seq`.

The `ArrayOps` example above was quite artificial, intended only to show the difference to `WrappedArray`. Normally, you'd never define a value of class `ArrayOps`. You'd just call a `Seq` method on an array:

```
scala> a1.reverse
res4: Array[Int] = Array(3, 2, 1)
```

The `ArrayOps` object gets inserted automatically by the implicit conversion. So the line above is equivalent to the following line, where `intArrayOps` was the conversion that was implicitly inserted previously:

```
scala> intArrayOps(a1).reverse
res5: Array[Int] = Array(3, 2, 1)
```

This raises the question how the compiler picked `intArrayOps` over the other implicit conversion to `WrappedArray` in the line above. After all, both conversions map an array to a type that supports a `reverse` method, which is what the input specified. The answer to that question is that the two implicit conversions are prioritized. The `ArrayOps` conversion has a higher priority than the `WrappedArray` conversion. The first is defined in the `Predef` object whereas the second is defined in a class `scala.LowPriorityImplicits`, which is a superclass of `Predef`. Implicits in subclasses and subobjects take precedence over implicits in base classes. So if both conversions are applicable, the one in `Predef` is chosen. A very similar scheme, which was described in [Section 21.7](#), works for strings.

So now you know how arrays can be compatible with sequences and how they can support all sequence operations. What about genericity? In Java you cannot write a `T[]` where `T` is a type parameter. How then is Scala's `Array[T]` represented? In fact a generic array like `Array[T]` could be at run time any of Java's eight primitive array types `byte[]`, `short[]`, `char[]`, `int[]`, `long[]`, `float[]`, `double[]`, `boolean[]`, or it could be an array of objects. The only common run-time type encompassing all of these types is `AnyRef` (or, equivalently `java.lang.Object`), so that's the type to which the Scala compiler maps `Array[T]`. At run-time, when an element of an array of type `Array[T]` is accessed or updated there is a sequence of type tests that determine the actual array type, followed by the correct array operation on the Java array. These type tests slow down array operations somewhat. You can expect accesses to generic arrays to be three to four times slower than accesses to primitive or object arrays. This means that if you need maximal performance, you should prefer concrete over generic arrays.

Representing the generic array type is not enough, however, there must also be a way to *create* generic arrays. This is an even harder problem, which requires a little bit of help from you. To illustrate the problem, consider the following attempt to write a generic method that creates an array:

```
// This is wrong!
def evenElems[T](xs: Vector[T]): Array[T] = {
    val arr = new Array[T]((xs.length + 1) / 2)
    for (i <- 0 until xs.length by 2) {
        arr(i / 2) = xs(i)
    }
}
```

The `evenElems` method returns a new array that consists of all elements of the argument vector `xs` that are at even positions in the vector. The first line of the body of `evenElems` creates the result array, which has the same element type as the argument. So depending on the actual type parameter for `T`, this could be an `Array[Int]`, or an `Array[Boolean]`, or an array of some of the other primitive types in Java, or an array of some reference type. But these types all have different runtime representations, so how is the Scala runtime going to pick the correct one? In fact, it can't do that based on the information it is given, because the actual type that corresponds to the type parameter `T` is erased at runtime. That's why you will get the following error message if you attempt to compile the code above:

```
error: cannot find class tag for element type T
val arr = new Array[T]((arr.length + 1) / 2)
^
```

What's required here is that you help the compiler by providing a runtime hint of what the actual type parameter of `evenElems` is. This runtime hint takes the form of a *class tag* of type `scala.reflect.ClassTag`. A class tag describes the *erased type* of a given type, which is all the information needed to construct an array of that type.

In many cases the compiler can generate a class tag on its own. Such is the case for a concrete type like `Int` or `String`. It's also the case for certain generic types, like `List[T]`, where enough information is known to predict the erased type; in this example the erased type would be `List`.

For fully generic cases, the usual idiom is to pass the class tag using a context bound, as discussed in [Section 21.6](#). Here is how the above definition could be fixed by using a context bound:

```
// This works
import scala.reflect.ClassTag
def evenElems[T: ClassTag](xs: Vector[T]): Array[T] = {
```

```

val arr = new Array[T]((xs.length + 1) / 2)
for (i <- 0 until xs.length by 2)
    arr(i / 2) = xs(i)
arr
}

```

In this new definition, when the `Array[T]` is created, the compiler looks for a class tag for the type parameter `T`, that is, it will look for an implicit value of type `ClassTag[T]`. If such a value is found, the class tag is used to construct the right kind of array. Otherwise, you'll see an error message like the one shown previously.

Here is an interpreter interaction that uses the `evenElems` method:

```

scala> evenElems(Vector(1, 2, 3, 4, 5))
res6: Array[Int] = Array(1, 3, 5)

scala> evenElems(Vector("this", "is", "a", "test", "run"))
res7: Array[java.lang.String] = Array(this, a, run)

```

In both cases, the Scala compiler automatically constructed a class tag for the element type (first `Int`, then `String`) and passed it to the implicit parameter of the `evenElems` method. The compiler can do that for all concrete types, but not if the argument is itself another type parameter without its class tag. For instance, the following fails:

```

scala> def wrap[U](xs: Vector[U]) = evenElems(xs)
<console>:9: error: No ClassTag available for U
      def wrap[U](xs: Vector[U]) = evenElems(xs)
                                         ^

```

What happened here is that the `evenElems` demands a class tag for the type parameter `U`, but none was found. The solution in this case is, of course, to demand another implicit class tag for `U`. So the following works:

```

scala> def wrap[U: ClassTag](xs: Vector[U]) = evenElems(xs)
wrap: [U](xs: Vector[U])(implicit evidence$1:
      scala.reflect.ClassTag[U])Array[U]

```

This example also shows that the context bound in the definition of `U` is just a shorthand for an implicit parameter named here `evidence$1` of type `ClassTag[U]`.

24.11 Strings

Like arrays, strings are not directly sequences, but they can be converted to them, and they also support all sequence operations. Here are some examples of operations you can invoke on strings:

```
scala> val str = "hello"
str: java.lang.String = hello
scala> str.reverse
res6: String = olleh
scala> str.map(_.toUpperCase)
res7: String = HELLO
scala> str drop 3
res8: String = lo
scala> str slice (1, 4)
res9: String = ell
scala> val s: Seq[Char] = str
s: Seq[Char] = WrappedString(h, e, l, l, o)
```

These operations are supported by two implicit conversions, which were explained in [Section 21.7](#). The first, low-priority conversion maps a `String` to a `WrappedString`, which is a subclass of `immutable.IndexedSeq`. This conversion was applied in the last line of the previous example in which a string was converted into a `Seq`. The other, high-priority conversion maps a string to a `StringOps` object, which adds all methods on immutable sequences to strings. This conversion was implicitly inserted in the method calls of `reverse`, `map`, `drop`, and `slice` in the previous example.

24.12 Performance characteristics

As the previous explanations have shown, different collection types have different performance characteristics. That's often the primary reason for picking one collection type over another. You can see the performance characteristics of some common operations on collections summarized in two tables, [Table 24.10](#) and [Table 24.11](#).

	head	tail	apply	update	prepend	append	insert
immutable							
List	C	C	L	L	C	L	-
Stream	C	C	L	L	C	L	-
Vector	eC	eC	eC	eC	eC	eC	-
Stack	C	C	L	L	C	L	-
Queue	aC	aC	L	L	L	C	-
Range	C	C	C	-	-	-	-
String	C	L	C	L	L	L	-
mutable							
ArrayBuffer	C	L	C	C	L	aC	L
ListBuffer	C	L	L	L	C	C	L
StringBuilder	C	L	C	C	L	aC	L
MutableList	C	L	L	L	C	C	L
Queue	C	L	L	L	C	C	L
ArraySeq	C	L	C	C	-	-	-
Stack	C	L	L	L	C	L	L
ArrayStack	C	L	C	C	aC	L	L
Array	C	L	C	C	-	-	-

Table 24.10 · Performance characteristics of sequence types

	lookup	add	remove	min
immutable				
HashSet/HashMap	eC	eC	eC	L
TreeSet/TreeMap	Log	Log	Log	Log
BitSet	C	L	L	eC ^a
ListMap	L	L	L	L
mutable				
HashSet/HashMap	eC	eC	eC	L
WeakHashMap	eC	eC	eC	L
BitSet	C	aC	C	eC ^a

Table 24.11 · Performance characteristics of set and map types

^aAssuming bits are densely packed.

The entries in these two tables are explained as follows:

- C The operation takes (fast) constant time.
- eC The operation takes effectively constant time, but this might depend on some assumptions such as the maximum length of a vector or the distribution of hash keys.
- aC The operation takes amortized constant time. Some invocations of the operation might take longer, but if many operations are performed on average only constant time per operation is taken.
- Log The operation takes time proportional to the logarithm of the collection size.
- L The operation is linear, that is it takes time proportional to the collection size.
- The operation is not supported.

Table 24.10 treats sequence types—both immutable and mutable—with the following operations:

- | | |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| head | Selecting the first element of the sequence. |
| tail | Producing a new sequence that consists of all elements except the first one. |
| apply | Indexing. |
| update | Functional update (with <code>updated</code>) for immutable sequences, side-effecting update (with <code>update</code>) for mutable sequences. |
| prepend | Adding an element to the front of the sequence.
For immutable sequences, this produces a new sequence. For mutable sequences it modifies the existing sequence. |
| append | Adding an element at the end of the sequence.
For immutable sequences, this produces a new sequence. For mutable sequences it modifies the existing sequence. |
| insert | Inserting an element at an arbitrary position in the sequence. This is only supported directly for mutable sequences. |

Table 24.11 treats mutable and immutable sets and maps with the following operations:

lookup	Testing whether an element is contained in set, or selecting a value associated with a key.
add	Adding a new element to a set or a new key/value pair to a map.
remove	Removing an element from a set or a key from a map.
min	The smallest element of the set, or the smallest key of a map.

24.13 Equality

The collection libraries have a uniform approach to equality and hashing. The idea is, first, to divide collections into sets, maps, and sequences. Collections in different categories are always unequal. For instance, `Set(1, 2, 3)` is unequal to `List(1, 2, 3)` even though they contain the same elements. On the other hand, within the same category, collections are equal if and only if they have the same elements (for sequences: the same elements in the same order). For example, `List(1, 2, 3) == Vector(1, 2, 3)`, and `HashSet(1, 2) == TreeSet(2, 1)`.

It does not matter for the equality check whether a collection is mutable or immutable. For a mutable collection, equality simply depends on the current elements at the time the equality test is performed. This means that a mutable collection might be equal to different collections at different times, depending what elements are added or removed. This is a potential trap when using a mutable collection as a key in a hash map. For example:

```
scala> import collection.mutable.{HashMap, ArrayBuffer}
import collection.mutable.{HashMap, ArrayBuffer}

scala> val buf = ArrayBuffer(1, 2, 3)
buf: scala.collection.mutable.ArrayBuffer[Int] =
ArrayBuffer(1, 2, 3)

scala> val map = HashMap(buf -> 3)
map: scala.collection.mutable.HashMap[scala.collection.
mutable.ArrayBuffer[Int],Int] = Map((ArrayBuffer(1, 2, 3),3))
```

```
scala> map(buf)
res13: Int = 3

scala> buf(0) += 1

scala> map(buf)
java.util.NoSuchElementException: key not found:
ArrayBuffer(2, 2, 3)
```

In this example, the selection in the last line will most likely fail because the hash code of the array `xs` has changed in the second-to-last line. Therefore, the hash-code-based lookup will look at a different place than the one in which `xs` was stored.

24.14 Views

Collections have quite a few methods that construct new collections. Some examples are `map`, `filter`, and `++`. We call such methods *transformers* because they take at least one collection as their receiver object and produce another collection in their result.

Transformers can be implemented in two principal ways: strict and non-strict (or lazy). A strict transformer constructs a new collection with all of its elements. A non-strict, or lazy, transformer constructs only a proxy for the result collection, and its elements are constructed on demand.

As an example of a non-strict transformer, consider the following implementation of a lazy `map` operation:

```
def lazyMap[T, U](coll: Iterable[T], f: T => U) =
  new Iterable[U] {
    def iterator = coll.iterator map f
  }
```

Note that `lazyMap` constructs a new `Iterable` without stepping through all elements of the given collection `coll`. The given function `f` is instead applied to the elements of the new collection's `iterator` as they are demanded.

Scala collections are by default strict in all their transformers, except for `Stream`, which implements all its transformer methods lazily. However, there is a systematic way to turn every collection into a lazy one and *vice*

versa, which is based on collection views. A *view* is a special kind of collection that represents some base collection, but implements all of its transformers lazily.

To go from a collection to its view, you can use the `view` method on the collection. If `xs` is some collection, then `xs.view` is the same collection, but with all transformers implemented lazily. To get back from a view to a strict collection, you can use the `force` method.

As an example, say you have a vector of `Int`s over which you want to map two functions in succession:

```
scala> val v = Vector(1 to 10: _*)
v: scala.collection.immutable.Vector[Int] =
Vector(1, 2, 3, 4, 5, 6, 7, 8, 9, 10)

scala> v map (_ + 1) map (_ * 2)
res5: scala.collection.immutable.Vector[Int] =
Vector(4, 6, 8, 10, 12, 14, 16, 18, 20, 22)
```

In the last statement, the expression `v map (_ + 1)` constructs a new vector that is then transformed into a third vector by the second call to `map (_ * 2)`. In many situations, constructing the intermediate result from the first call to `map` is a bit wasteful. In the pseudo example, it would be faster to do a single `map` with the composition of the two functions `(_ + 1)` and `(_ * 2)`. If you have the two functions available in the same place you can do this by hand. But quite often, successive transformations of a data structure are done in different program modules. Fusing those transformations would then undermine modularity. A more general way to avoid the intermediate results is by turning the vector first into a view, applying all transformations to the view, and finally forcing the view to a vector:

```
scala> (v.view map (_ + 1) map (_ * 2)).force
res12: Seq[Int] = Vector(4, 6, 8, 10, 12, 14, 16, 18, 20, 22)
```

We'll do this sequence of operations again, one by one:

```
scala> val vv = v.view
vv: scala.collection.SeqView[Int,Vector[Int]] =
SeqView(1, 2, 3, 4, 5, 6, 7, 8, 9, 10)
```

The application `v.view` gives you a `SeqView`, *i.e.*, a lazily evaluated `Seq`. The type `SeqView` has two type parameters. The first, `Int`, shows the type

of the view's elements. The second, `Vector[Int]`, shows you the type constructor you get back when forcing the view.

Applying the first `map` to the view gives you:

```
scala> vv map (_ + 1)
res13: scala.collection.SeqView[Int,Seq[_]] = SeqViewM(...)
```

The result of the `map` is a value that prints `SeqViewM(...)`. This is in essence a wrapper that records the fact that a `map` with function `(_ + 1)` needs to be applied on the vector `v`. It does not apply that map until the view is forced, however. The “M” after `SeqView` is an indication that the view encapsulates a `map` operation. Other letters indicate other delayed operations. For instance “S” indicates a delayed `slice` operation, and “R” indicates a `reverse`. We'll now apply the second `map` to the last result.

```
scala> res13 map (_ * 2)
res14: scala.collection.SeqView[Int,Seq[_]] = SeqViewMM(...)
```

You now get a `SeqView` that contains two `map` operations, so it prints with a double “M”: `SeqViewMM(...)`. Finally, forcing the last result gives:

```
scala> res14.force
res15: Seq[Int] = Vector(4, 6, 8, 10, 12, 14, 16, 18, 20, 22)
```

Both stored functions get applied as part of the execution of the `force` operation and a new vector is constructed. That way, no intermediate data structure is needed.

One detail to note is that the static type of the final result is a `Seq`, not a `Vector`. Tracing the types back we see that as soon as the first delayed `map` was applied, the result had static type `SeqViewM[Int, Seq[_]]`. That is, the “knowledge” that the view was applied to the specific sequence type `Vector` got lost. The implementation of a view for any particular class requires quite a bit of code, so the Scala collection libraries provide views mostly only for general collection types, not for specific implementations.⁵

There are two reasons why you might want to consider using views. The first is performance. You have seen that by switching a collection to a view the construction of intermediate results can be avoided. These savings can

⁵An exception to this is arrays: applying delayed operations on arrays will again give results with static type `Array`.

be quite important. As another example, consider the problem of finding the first palindrome in a list of words. A palindrome is a word that reads backwards the same as forwards. Here are the necessary definitions:

```
def isPalindrome(x: String) = x == x.reverse
def findPalindrome(s: Seq[String]) = s find isPalindrome
```

Now, assume you have a very long sequence words and you want to find a palindrome in the first million words of that sequence. Can you re-use the definition of `findPalindrome`? Of course, you could write:

```
findPalindrome(words take 1000000)
```

This nicely separates the two aspects of taking the first million words of a sequence and finding a palindrome in it. But the downside is that it always constructs an intermediary sequence consisting of one million words, even if the first word of that sequence is already a palindrome. So potentially, 999,999 words are copied into the intermediary result without being inspected at all afterwards. Many programmers would give up here and write their own specialized version of finding palindromes in some given prefix of an argument sequence. But with views, you don't have to. Simply write:

```
findPalindrome(words.view take 1000000)
```

This has the same nice separation of concerns, but instead of a sequence of a million elements it will only construct a single lightweight view object. This way, you do not need to choose between performance and modularity.

The second use case applies to views over mutable sequences. Many transformer functions on such views provide a window into the original sequence that can then be used to update selectively some elements of that sequence. To see this in an example, suppose you have an array `arr`:

```
scala> val arr = (0 to 9).toArray
arr: Array[Int] = Array(0, 1, 2, 3, 4, 5, 6, 7, 8, 9)
```

You can create a subwindow into that array by creating a slice of a view of the array:

```
scala> val subarr = arr.view.slice(3, 6)
subarr: scala.collection.mutable.IndexedSeqView[
    Int,Array[Int]] = IndexedSeqViewS(...)
```

This gives a view, `subarr`, which refers to the elements at positions 3 through 5 of the array `arr`. The view does not copy these elements, it just provides a reference to them. Now, assume you have a method that modifies some elements of a sequence. For instance, the following `negate` method would negate all elements of the sequence of integers it's given:

```
scala> def negate(xs: collection.mutable.Seq[Int]) =  
        for (i <- 0 until xs.length) xs(i) = -xs(i)  
negate: (xs: scala.collection.mutable.Seq[Int])Unit
```

Assume now you want to negate elements at positions three through five of the array `arr`. Can you use `negate` for this? Using a view, this is simple:

```
scala> negate(subarr)  
scala> arr  
res4: Array[Int] = Array(0, 1, 2, -3, -4, -5, 6, 7, 8, 9)
```

What happened here is that `negate` changed all elements of `subarr`, which were a slice of the elements of `arr`. Again, you see that views help in keeping things modular. The code above nicely separated the question of what index range to apply a method to from the question what method to apply.

After having seen all these nifty uses of views you might wonder why have strict collections at all? One reason is that performance comparisons do not always favor lazy over strict collections. For smaller collection sizes the added overhead of forming and applying closures in views is often greater than the gain from avoiding the intermediary data structures. A possibly more important reason is that evaluation in views can be very confusing if the delayed operations have side effects.

Here's an example that bit a few users of versions of Scala before 2.8. In these versions the `Range` type was lazy, so it behaved in effect like a view. People were trying to create a number of actors⁶ like this:

```
val actors = for (i <- 1 to 10) yield actor { ... }
```

They were surprised that none of the actors were executing afterwards, even though the `actor` method should create and start an actor from the code that's enclosed in the braces following it. To explain why nothing happened, remember that the `for` expression above is equivalent to an application of the `map` method:

⁶The Scala actors library has been deprecated, but this historical example is still relevant.

```
val actors = (1 to 10) map (i => actor { ... })
```

Since previously the range produced by `(1 to 10)` behaved like a view, the result of the `map` was again a view. That is, no element was computed, and, consequently, no actor was created! Actors would have been created by forcing the range of the whole expression, but it's far from obvious that this is what was required to make the actors do their work.

To avoid surprises like this, the Scala collections gained more regular rules in version 2.8. All collections except streams and views are strict. The only way to go from a strict to a lazy collection is via the `view` method. The only way to go back is via `force`. So the `actors` definition above would behave as expected in Scala 2.8 in that it would create and start ten actors. To get back the surprising previous behavior, you'd have to add an explicit `view` method call:

```
val actors = for (i <- (1 to 10).view) yield actor { ... }
```

In summary, views are a powerful tool to reconcile concerns of efficiency with concerns of modularity. But in order not to be entangled in aspects of delayed evaluation, you should restrict views to two scenarios. Either you apply views in purely functional code where collection transformations do not have side effects. Or you apply them over mutable collections where all modifications are done explicitly. What's best avoided is a mixture of views and operations that create new collections while also having side effects.

24.15 Iterators

An iterator is not a collection, but rather a way to access the elements of a collection one by one. The two basic operations on an iterator `it` are `next` and `hasNext`. A call to `it.next()` will return the next element of the iterator and advance the state of the iterator. Calling `next` again on the same iterator will then yield the element one beyond the one returned previously. If there are no more elements to return, a call to `next` will throw a `NoSuchElementException`. You can find out whether there are more elements to return using `Iterator`'s `hasNext` method.

The most straightforward way to “step through” all the elements returned by an iterator is to use a `while` loop:

```
while (it.hasNext)
    println(it.next())
```

Iterators in Scala also provide analogues of most of the methods that you find in the Traversable, Iterable, and Seq traits. For instance, they provide a `foreach` method that executes a given procedure on each element returned by an iterator. Using `foreach`, the loop above could be abbreviated to:

```
it foreach println
```

As always, `for` expressions can be used as an alternate syntax for expressions involving `foreach`, `map`, `filter`, and `flatMap`, so yet another way to print all elements returned by an iterator would be:

```
for (elem <- it) println(elem)
```

There's an important difference between the `foreach` method on iterators and the same method on traversable collections: When called on an iterator, `foreach` will leave the iterator at its end when it is done. So calling `next` again on the same iterator will fail with a `NoSuchElementException`. By contrast, when called on a collection, `foreach` leaves the number of elements in the collection unchanged (unless the passed function adds or removes elements, but this is discouraged, because it can easily lead to surprising results).

The other operations that `Iterator` has in common with `Traversable` have the same property of leaving the iterator at its end when done. For instance, iterators provide a `map` method, which returns a new iterator:

```
scala> val it = Iterator("a", "number", "of", "words")
it: Iterator[java.lang.String] = non-empty iterator

scala> it.map(_.length)
res1: Iterator[Int] = non-empty iterator

scala> res1 foreach println
1
6
2
5

scala> it.next()
java.util.NoSuchElementException: next on empty iterator
```

As you can see, after the call to `map`, the `it` iterator has advanced to its end.

Another example is the `dropWhile` method, which can be used to find the first element of an iterator that has a certain property. For instance, to find the first word in the iterator shown previously that has at least two characters, you could write:

```
scala> val it = Iterator("a", "number", "of", "words")
it: Iterator[java.lang.String] = non-empty iterator
scala> it dropWhile (_.length < 2)
res4: Iterator[java.lang.String] = non-empty iterator
scala> it.next()
res5: java.lang.String = number
```

Note again that `it` has changed by the call to `dropWhile`: `it` now points to the second word “number” in the list. In fact, `it` and the result `res4` returned by `dropWhile` will return exactly the same sequence of elements.

There is only one standard operation, `duplicate`, which allows you to re-use the same iterator:

```
val (it1, it2) = it.duplicate
```

The call to `duplicate` gives you *two* iterators, which each return exactly the same elements as the iterator `it`. The two iterators work independently; advancing one does not affect the other. By contrast the original iterator, `it`, is advanced to its end by `duplicate` and is thus rendered unusable.

In summary, iterators behave like collections *if you never access an iterator again after invoking a method on it*. The Scala collection libraries make this explicit with an abstraction called `TraversableOnce`, which is a common supertrait of `Traversable` and `Iterator`. As the name implies, `TraversableOnce` objects can be traversed using `foreach`, but the state of that object after the traversal is not specified. If the `TraversableOnce` object is in fact an `Iterator`, it will be at its end after the traversal, but if it is a `Traversable`, it will still exist as before. A common use case of `TraversableOnce` is as an argument type for methods that can take either an iterator or traversable as argument. An example is the appending method `++` in trait `Traversable`. It takes a `TraversableOnce` parameter, so you can append elements coming from either an iterator or a traversable collection.

All operations on iterators are summarized in [Table 24.12](#).

Table 24.12 · Operations in trait Iterator

What it is	What it does
Abstract methods:	
<code>it.next()</code>	Returns the next element in the iterator and advances past <code>it</code> .
<code>it.hasNext</code>	Returns <code>true</code> if <code>it</code> can return another element.
Variations:	
<code>it.buffered</code>	A buffered iterator returning all elements of <code>it</code> .
<code>it grouped size</code>	An iterator that yields the elements returned by <code>it</code> in fixed-sized sequence “chunks.”
<code>xs sliding size</code>	An iterator that yields the elements returned by <code>it</code> in sequences representing a sliding fixed-sized window.
Copying:	
<code>it copyToBuffer buf</code>	Copies all elements returned by <code>it</code> to buffer <code>buf</code> .
<code>it copyToArray(arr, s, l)</code>	Copies at most <code>l</code> elements returned by <code>it</code> to array <code>arr</code> starting at index <code>s</code> . The last two arguments are optional.
Duplication:	
<code>it.duplicate</code>	A pair of iterators that each independently return all elements of <code>it</code> .
Additions:	
<code>it ++ jt</code>	An iterator returning all elements returned by iterator <code>it</code> , followed by all elements returned by iterator <code>jt</code> .
<code>it padTo (len, x)</code>	The iterator that returns all elements of <code>it</code> followed by copies of <code>x</code> until length <code>len</code> elements are returned overall.
Maps:	
<code>it map f</code>	The iterator obtained from applying the function <code>f</code> to every element returned from <code>it</code> .
<code>it flatMap f</code>	The iterator obtained from applying the iterator-valued function <code>f</code> to every element in <code>it</code> and appending the results.

Table 24.12 · continued

<code>it.collect f</code>	The iterator obtained from applying the partial function <code>f</code> to every element in <code>it</code> for which it is defined and collecting the results.
Conversions:	
<code>it.toArray</code>	Collects the elements returned by <code>it</code> in an array.
<code>it.toList</code>	Collects the elements returned by <code>it</code> in a list.
<code>it.toIterable</code>	Collects the elements returned by <code>it</code> in an iterable.
<code>it.toSeq</code>	Collects the elements returned by <code>it</code> in a sequence.
<code>it.toIndexedSeq</code>	Collects the elements returned by <code>it</code> in an indexed sequence.
<code>it.toStream</code>	Collects the elements returned by <code>it</code> in a stream.
<code>it.toSet</code>	Collects the elements returned by <code>it</code> in a set.
<code>it.toMap</code>	Collects the key/value pairs returned by <code>it</code> in a map.
Size info:	
<code>it.isEmpty</code>	Tests whether the iterator is empty (opposite of <code>hasNext</code>).
<code>it.nonEmpty</code>	Tests whether the collection contains elements (alias of <code>hasNext</code>).
<code>it.size</code>	The number of elements returned by <code>it</code> . Note: <code>it</code> will be at its end after this operation!
<code>it.length</code>	Same as <code>it.size</code> .
<code>it.hasDefiniteSize</code>	Returns true if <code>it</code> is known to return finitely many elements (by default the same as <code>isEmpty</code>).
Element retrieval index search:	
<code>it.find p</code>	An option containing the first element returned by <code>it</code> that satisfies <code>p</code> , or <code>None</code> if no element qualifies. Note: The iterator advances to just after the element, or, if none is found, to the end.
<code>it.indexOf x</code>	The index of the first element returned by <code>it</code> that equals <code>x</code> . Note: The iterator advances past the position of this element.

Table 24.12 · continued

<code>it indexWhere p</code>	The index of the first element returned by <code>it</code> that satisfies <code>p</code> . Note: The iterator advances past the position of this element.
Subiterators:	
<code>it take n</code>	An iterator returning of the first <code>n</code> elements of <code>it</code> . Note: <code>it</code> will advance to the position after the <code>n</code> 'th element, or to its end, if it contains less than <code>n</code> elements.
<code>it drop n</code>	The iterator that starts with the $(n + 1)$ 'th element of <code>it</code> . Note: <code>it</code> will advance to the same position.
<code>it slice (m, n)</code>	The iterator that returns a slice of the elements returned from <code>it</code> , starting with the <code>m</code> 'th element and ending before the <code>n</code> 'th element.
<code>it takeWhile p</code>	An iterator returning elements from <code>it</code> as long as condition <code>p</code> is true.
<code>it dropWhile p</code>	An iterator skipping elements from <code>it</code> as long as condition <code>p</code> is true, and returning the remainder.
<code>it filter p</code>	An iterator returning all elements from <code>it</code> that satisfy the condition <code>p</code> .
<code>it withFilter p</code>	Same as <code>it filter p</code> . Needed so that iterators can be used in <code>for</code> expressions.
<code>it filterNot p</code>	An iterator returning all elements from <code>it</code> that do not satisfy the condition <code>p</code> .
Subdivisions:	
<code>it partition p</code>	Splits <code>it</code> into a pair of two iterators; one returning all elements from <code>it</code> that satisfy the predicate <code>p</code> , the other returning all elements from <code>it</code> that do not.
Element conditions:	
<code>it forall p</code>	A boolean indicating whether the predicate <code>p</code> holds for all elements returned by <code>it</code> .
<code>it exists p</code>	A boolean indicating whether the predicate <code>p</code> holds for some element in <code>it</code> .
<code>it count p</code>	The number of elements in <code>it</code> that satisfy the predicate <code>p</code> .
Folds:	

Table 24.12 · continued

<code>(z /: it)(op)</code>	Applies binary operation <code>op</code> between successive elements returned by <code>it</code> , going left to right, starting with <code>z</code> .
<code>(it :\ z)(op)</code>	Applies binary operation <code>op</code> between successive elements returned by <code>it</code> , going right to left, starting with <code>z</code> .
<code>it.foldLeft(z)(op)</code>	Same as <code>(z /: it)(op)</code> .
<code>it.foldRight(z)(op)</code>	Same as <code>(it :\ z)(op)</code> .
<code>it reduceLeft op</code>	Applies binary operation <code>op</code> between successive elements returned by non-empty iterator <code>it</code> , going left to right.
<code>it reduceRight op</code>	Applies binary operation <code>op</code> between successive elements returned by non-empty iterator <code>it</code> , going right to left.
Specific folds:	
<code>it.sum</code>	The sum of the numeric element values returned by iterator <code>it</code> .
<code>it.product</code>	The product of the numeric element values returned by iterator <code>it</code> .
<code>it.min</code>	The minimum of the ordered element values returned by iterator <code>it</code> .
<code>it.max</code>	The maximum of the ordered element values returned by iterator <code>it</code> .
Zippers:	
<code>it.zip jt</code>	An iterator of pairs of corresponding elements returned from iterators <code>it</code> and <code>jt</code> .
<code>it.zipAll (jt, x, y)</code>	An iterator of pairs of corresponding elements returned from iterators <code>it</code> and <code>jt</code> , where the shorter iterator is extended to match the longer one by appending elements <code>x</code> or <code>y</code> .
<code>it.zipWithIndex</code>	An iterator of pairs of elements returned from <code>it</code> with their indicies.
Update:	
<code>it.patch (i, jt, r)</code>	The iterator resulting from <code>it</code> by replacing <code>r</code> elements starting with <code>i</code> by the patch iterator <code>jt</code> .
Comparison:	

Table 24.12 · continued

<code>it sameElements jt</code>	A test whether iterators <code>it</code> and <code>jt</code> return the same elements in the same order. Note: At least one of <code>it</code> and <code>jt</code> will be at its end after this operation.
Strings:	
<code>it addString (b, start, sep, end)</code>	Adds a string to <code>StringBuilder b</code> that shows all elements returned by <code>it</code> between separators <code>sep</code> enclosed in strings <code>start</code> and <code>end</code> . <code>start,sep,</code> and <code>end</code> are all optional.
<code>it mkString (start, sep, end)</code>	Converts the iterator to a string that shows all elements returned by <code>it</code> between separators <code>sep</code> enclosed in strings <code>start</code> and <code>end</code> . <code>start,sep,</code> and <code>end</code> are all optional.

Buffered iterators

Sometimes you want an iterator that can “look ahead” so that you can inspect the next element to be returned without advancing past that element. Consider, for instance, the task to skip leading empty strings from an iterator that returns a sequence of strings. You might be tempted to write something like the following method:

```
// This won't work
def skipEmptyWordsNOT(it: Iterator[String]) = {
    while (it.next().isEmpty) {}
}
```

But looking at this code more closely, it’s clear that this is wrong: the code will indeed skip leading empty strings, but it will also advance `it` past the first non-empty string!

The solution to this problem is to use a buffered iterator, an instance of trait `BufferedIterator`. `BufferedIterator` is a subtrait of `Iterator`, which provides one extra method, `head`. Calling `head` on a buffered iterator will return its first element, but will not advance the iterator. Using a buffered iterator, skipping empty words can be written like this:

```
def skipEmptyWords(it: BufferedIterator[String]) =
    while (it.head.isEmpty) { it.next() }
```

Every iterator can be converted to a buffered iterator by calling its buffered method. Here's an example:

```
scala> val it = Iterator(1, 2, 3, 4)
it: Iterator[Int] = non-empty iterator

scala> val bit = it.buffered
bit: java.lang.Object with scala.collection.
    BufferedIterator[Int] = non-empty iterator

scala> bit.head
res10: Int = 1

scala> bit.next()
res11: Int = 1

scala> bit.next()
res11: Int = 2
```

Note that calling head on the buffered iterator, bit, did not advance it. Therefore, the subsequent call, bit.next(), returned again the same value as bit.head.

24.16 Creating collections from scratch

You have already seen syntax like `List(1, 2, 3)`, which creates a list of three integers, and `Map('A' -> 1, 'C' -> 2)`, which creates a map with two bindings. This is actually a universal feature of Scala collections. You can take any collection name and follow it by a list of elements in parentheses. The result will be a new collection with the given elements. Here are some more examples:

<code>Traversable()</code>	// An empty traversable object
<code>List()</code>	// The empty list
<code>List(1.0, 2.0)</code>	// A list with elements 1.0, 2.0
<code>Vector(1.0, 2.0)</code>	// A vector with elements 1.0, 2.0
<code>Iterator(1, 2, 3)</code>	// An iterator returning three integers.
<code>Set(dog, cat, bird)</code>	// A set of three animals
<code>HashSet(dog, cat, bird)</code>	// A hash set of the same animals
<code>Map('a' -> 7, 'b' -> 0)</code>	// A map from characters to integers

“Under the covers” each of the above lines is a call to the `apply` method of some object. For instance, the third line above expands to:

```
List.apply(1.0, 2.0)
```

So this is a call to the `apply` method of the companion object of the `List` class. That method takes an arbitrary number of arguments and constructs a list from them. Every collection class in the Scala library has a companion object with such an `apply` method. It does not matter whether the collection class represents a concrete implementation, like `List`, `Stream`, or `Vector`, or whether it is a trait such as `Seq`, `Set`, or `Traversable`. In the latter case, calling `apply` will produce some default implementation of the trait. Here are some examples:

```
scala> List(1, 2, 3)
res17: List[Int] = List(1, 2, 3)

scala> Traversable(1, 2, 3)
res18: Traversable[Int] = List(1, 2, 3)

scala> mutable.Traversable(1, 2, 3)
res19: scala.collection.mutable.Traversable[Int] =
    ArrayBuffer(1, 2, 3)
```

Besides `apply`, every collection companion object also defines a member `empty`, which returns an empty collection. So instead of `List()` you could write `List.empty`, instead of `Map()`, `Map.empty`, and so on.

Descendants of `Seq` traits also provide other factory operations in their companion objects. These are summarized in [Table 24.13](#). In short, there’s:

- `concat`, which concatenates an arbitrary number of traversables together,

- `fill` and `tabulate`, which generate single or multi-dimensional sequences of given dimensions initialized by some expression or tabulating function,

- `range`, which generates integer sequences with some constant step length, and

- `iterate`, which generates the sequence resulting from repeated application of a function to a start element.

Table 24.13 · Factory methods for sequences

What it is	What it does
<code>S.empty</code>	The empty sequence
<code>S(x, y, z)</code>	A sequence consisting of elements x, y, and z
<code>S.concat(xs, ys, zs)</code>	The sequence obtained by concatenating the elements of xs, ys, and zs
<code>S.fill(n)(e)</code>	A sequence of length n where each element is computed by expression e
<code>S.fill(m, n)(e)</code>	A sequence of sequences of dimension m × n where each element is computed by expression e (exists also in higher dimensions)
<code>S.tabulate(n)(f)</code>	A sequence of length n where the element at each index i is computed by f(i)
<code>S.tabulate(m, n)(f)</code>	A sequence of sequences of dimension m × n where the element at each index (i, j) is computed by f(i, j) (exists also in higher dimensions)
<code>S.range(start, end)</code>	The sequence of integers start ... end - 1
<code>S.range(start, end, step)</code>	The sequence of integers starting with start and progressing by step increments up to, and excluding, the end value
<code>S.iterate(x, n)(f)</code>	The sequence of length n with elements x, f(x), f(f(x)), ...

24.17 Conversions between Java and Scala collections

Like Scala, Java has a rich collections library. There are many similarities between the two. For instance, both libraries know iterators, iterables, sets, maps, and sequences. But there are also important differences. In particular, the Scala libraries put much more emphasis on immutable collections, and provide many more operations that transform a collection into a new one.

Sometimes you might need to convert from one collection framework to the other. For instance, you might want to access to an existing Java collection, as if it were a Scala collection. Or you might want to pass one of Scala's collections to a Java method that expects the Java counterpart. It is quite easy to do this, because Scala offers implicit conversions between all the major collection types in the `JavaConversions` object. In particular,

you will find bidirectional conversions between the following types:

Iterator	↔	java.util.Iterator
Iterator	↔	java.util.Enumeration
Iterable	↔	java.lang.Iterable
Iterable	↔	java.util.Collection
mutable.Buffer	↔	java.util.List
mutable.Set	↔	java.util.Set
mutable.Map	↔	java.util.Map

To enable these conversions, simply import like this:

```
scala> import collection.JavaConversions._  
import collection.JavaConversions._
```

You have now automatic conversions between Scala collections and their corresponding Java collections.

```
scala> import collection.mutable._  
import collection.mutable._  
  
scala> val jul: java.util.List[Int] = ArrayBuffer(1, 2, 3)  
jul: java.util.List[Int] = [1, 2, 3]  
  
scala> val buf: Seq[Int] = jul  
buf: scala.collection.mutable.Seq[Int] = ArrayBuffer(1, 2, 3)  
  
scala> val m: java.util.Map[String, Int] =  
        HashMap("abc" -> 1, "hello" -> 2)  
m: java.util.Map[String,Int] = {hello=2, abc=1}
```

Internally, these conversion work by setting up a “wrapper” object that forwards all operations to the underlying collection object. So collections are never copied when converting between Java and Scala. An interesting property is that if you do a round-trip conversion from, say, a Java type to its corresponding Scala type, and back to the same Java type, you end up with the identical collection object you started with.

Some other common Scala collections exist that can also be converted to Java types, but for which no corresponding conversion exists in the other direction. These are:

Seq	⇒	java.util.List
mutable.Seq	⇒	java.util.List
Set	⇒	java.util.Set
Map	⇒	java.util.Map

Because Java does not distinguish between mutable and immutable collections in their type, a conversion from, say, `collection.immutable.List` will yield a `java.util.List`, on which all attempted mutation operations will throw an `UnsupportedOperationException`. Here's an example:

```
scala> val jul: java.util.List[Int] = List(1, 2, 3)
jul: java.util.List[Int] = [1, 2, 3]
scala> jul.add(7)
java.lang.UnsupportedOperationException
        at java.util.AbstractList.add(AbstractList.java:131)
```

24.18 Conclusion

You've now seen how to use Scala's collection in great detail. Scala's collections take the approach of giving you powerful building blocks rather than a number of ad hoc utility methods. Putting together two or three such building blocks allows you to express an enormous number of useful computations. This style of library is especially effective due to Scala having a light syntax for function literals, and due to it providing many collection types that are persistent and immutable.

This chapter has shown collections from the point of view of a programmer using the collection library. The next chapter will show you how the collections are built and how you can add your own collection types.

Chapter 25

The Architecture of Scala Collections

This chapter describes the architecture of the Scala collections framework in detail. Continuing the theme of [Chapter 24](#), you will find out more about the internal workings of the framework. You will also learn how this architecture helps you define your own collections in a few lines of code, while reusing the overwhelming part of collection functionality from the framework.

[Chapter 24](#) enumerated a large number of collection operations, which exist uniformly on many different collection implementations. Implementing every collection operation anew for every collection type would lead to an enormous amount of code, most of which would be copied from somewhere else. Such code duplication could lead to inconsistencies over time, when an operation is added or modified in one part of the collection library but not in others. The principal design objective of the new collections framework was to avoid any duplication, defining every operation in as few places as possible.¹ The design approach was to implement most operations in collection “templates” that can be flexibly inherited from individual base classes and implementations. In this chapter, we will examine these templates, and other classes and traits that constitute the “building blocks” of the framework, as well as the construction principles they support.

25.1 Builders

Almost all collection operations are implemented in terms of *traversals* and *builders*. Traversals are handled by `Traversable`'s `foreach` method, and

¹Ideally, everything should be defined in one place only, but there are a few exceptions where things needed to be redefined.

building new collections is handled by instances of class `Builder`. Listing 25.1 presents a slightly abbreviated outline of this class.

```
package scala.collection.generic
class Builder[-Elem, +To] {
    def +=(elem: Elem): this.type
    def result(): To
    def clear()
    def mapResult[NewTo](f: To => NewTo): Builder[Elem, NewTo]
    = ...
}
```

Listing 25.1 · An outline of the `Builder` class.

You can add an element `x` to a builder `b` with `b += x`. There's also syntax to add more than one element at once: For instance, `b += (x, y)` and `b ++= xs` work as for buffers. (In fact, buffers are an enriched version of builders.) The `result()` method returns a collection from a builder. The state of the builder is undefined after taking its result, but it can be reset into a new empty state using `clear()`. Builders are generic in both the element type, `Elem`, and in the type, `To`, of collections they return.

Often, a builder can refer to some other builder for assembling the elements of a collection, but then would like to transform the result of the other builder—for example, to give it a different type. This task is simplified by method `mapResult` in class `Builder`. Suppose for instance you have an array buffer `buf`. Array buffers are builders for themselves, so taking the `result()` of an array buffer will return the same buffer. If you want to use this buffer to produce a builder that builds arrays, you can use `mapResult`:

```
scala> val buf = new ArrayBuffer[Int]
buf: scala.collection.mutable.ArrayBuffer[Int] = ArrayBuffer()
scala> val bldr = buf mapResult (_.toArray)
bldr: scala.collection.mutable.Builder[Int,Array[Int]]
= ArrayBuffer()
```

The result value, `bldr`, is a builder that uses the array buffer, `buf`, to collect elements. When a result is demanded from `bldr`, the result of `buf` is computed, which yields the array buffer `buf` itself. This array buffer is then

mapped with `_.toArray` to an array. So the end result is that `bldr` is a builder for arrays.

25.2 Factoring out common operations

The main design objectives of the collection library redesign were to have, at the same time, natural types and maximal sharing of implementation code. In particular, Scala’s collections follow the “same-result-type” principle: Whenever possible, a transformation method on a collection will yield a collection of the same type. For instance, the `filter` operation should yield, on every collection type, an instance of the same collection type. Applying `filter` on a `List` should give a `List`; applying it on a `Map` should give a `Map`; and so on. In the rest of this section, you will find out how this is achieved.

The fast track

The material in this section is a bit more dense than usual and might require some time to absorb. If you want to move ahead quickly, you could skip the remainder of this section and move on to [Section 25.3](#) on [page 604](#) where you will learn from concrete examples how to integrate your own collection classes in the framework.

The Scala collection library avoids code duplication and achieves the “same-result-type” principle by using generic builders and traversals over collections in so-called *implementation traits*. These traits are named with a `Like` suffix; for instance, `IndexedSeqLike` is the implementation trait for `IndexedSeq`, and similarly, `TraversableLike` is the implementation trait for `Traversable`. Collection classes such as `Traversable` or `IndexedSeq` inherit all their concrete method implementations from these traits. Implementation traits have two type parameters instead of one for normal collections. They parameterize not only over the collection’s element type, but also over the collection’s *representation type* (*i.e.*, the type of the underlying collection), such as `Seq[I]` or `List[T]`.

For instance, here is the header of trait `TraversableLike`:

```
trait TraversableLike[+Elem, +Repr] { ... }
```

The type parameter, `Elem`, stands for the element type of the traversable whereas the type parameter `Repr` stands for its representation. There are no constraints on `Repr`. In particular `Repr` might be instantiated to a type

```
package scala.collection

trait TraversableLike[+Elem, +Repr] {
    def newBuilder: Builder[Elem, Repr] // deferred
    def foreach[U](f: Elem => U) // deferred
    ...
    def filter(p: Elem => Boolean): Repr = {
        val b = newBuilder
        foreach { elem => if (p(elem)) b += elem }
        b.result
    }
}
```

Listing 25.2 · Implementation of `filter` in `TraversableLike`.

that is itself not a subtype of `Traversable`. That way, classes outside the collections hierarchy, such as `String` and `Array`, can still make use of all operations defined in a collection implementation trait.

Taking `filter` as an example, this operation is defined once for all collection classes in the trait `TraversableLike`. An outline of the relevant code is shown in Listing 25.2. The trait declares two abstract methods, `newBuilder` and `foreach`, which are implemented in concrete collection classes. The `filter` operation is implemented in the same way for all collections using these methods. It first constructs a new builder for the representation type `Repr`, using `newBuilder`. It then traverses all elements of the current collection, using `foreach`. If an element `x` satisfies the given predicate `p`—*i.e.*, `p(x)` is true—it is added with the builder. Finally, the elements collected in the builder are returned as an instance of the `Repr` collection type by calling the builder’s `result` method.

The `map` operation on collections is a bit more complicated. For instance, if `f` is a function from `String` to `Int`, and `xs` is a `List[String]`, then `xs map f` should give a `List[Int]`. Likewise, if `ys` is an `Array[String]`, then `ys map f` should give a `Array[Int]`. But how do you achieve that without duplicating the definition of the `map` method in lists and arrays?

The `newBuilder/foreach` framework shown in Listing 25.2 is not sufficient for this because it only allows creation of new instances of the same collection *type*, whereas `map` needs an instance of the same collection *type constructor* but possibly with a different element type. What’s more, even

the result type constructor of a function like `map` might depend, in non-trivial ways, on the other argument types. Here is an example:

```
scala> import collection.immutable.BitSet
import collection.immutable.BitSet
scala> val bits = BitSet(1, 2, 3)
bits: scala.collection.immutable.BitSet = BitSet(1, 2, 3)
scala> bits map (_ * 2)
res13: scala.collection.immutable.BitSet = BitSet(2, 4, 6)
scala> bits map (_.toFloat)
res14: scala.collection.immutable.Set[Float] =
Set(1.0, 2.0, 3.0)
```

If you `map` the doubling function `_ * 2` over a bit set you obtain another bit set. However, if you `map` the function `(_.toFloat)` over the same bit set, the result is a general `Set[Float]`. Of course, it can't be a bit set because bit sets contain `Ints`, not `Floats`.

Note that `map`'s result type depends on the type of function that's passed to it. If the result type of that function argument is again an `Int`, the result of `map` is a `BitSet`. But if the result type of the function argument is something else, the result of `map` is just a `Set`. You'll find out soon how this type-flexibility is achieved in Scala.

The problem with `BitSet` is not an isolated case. Here are two more interactions with the interpreter that both `map` a function over a `map`:

```
scala> Map("a" -> 1, "b" -> 2) map { case (x, y) => (y, x) }
res3: scala.collection.immutable.Map[Int,java.lang.String] =
Map(1 -> a, 2 -> b)
scala> Map("a" -> 1, "b" -> 2) map { case (x, y) => y }
res4: scala.collection.immutable.Iterable[Int] =
List(1, 2)
```

The first function swaps two arguments of a key/value pair. The result of mapping this function is again a map, but now going in the other direction. In fact, the first expression yields the inverse of the original map, provided it is invertible. The second function, however, maps the key/value pair to an integer, namely its value component. In that case, we cannot form a `Map` from the results, but we still can form an `Iterable`, a supertrait of `Map`.

You might ask, Why not restrict `map` so that it can always return the same kind of collection? For instance, on bit sets `map` could accept only Int-to-Int functions and on maps it could only accept pair-to-pair functions. Not only are such restrictions undesirable from an object-oriented modeling point of view, they are illegal because they would violate the Liskov Substitution Principle: A Map *is* an Iterable. So every operation that's legal on an Iterable must also be legal on a Map.

Scala solves this problem instead with overloading: Not the simple form of overloading inherited by Java (that would not be flexible enough), but the more systematic form of overloading that's provided by implicit parameters.

```
def map[B, That](f: Elem => B)
    (implicit bf: CanBuildFrom[Repr, B, That]): That = {
  val b = bf(this)
  for (x <- this) b += f(x)
  b.result
}
```

Listing 25.3 · Implementation of `map` in `TraversableLike`.

[Listing 25.3](#) shows trait `TraversableLike`'s implementation of `map`. It's quite similar to the implementation of `filter` shown in [Listing 25.2](#). The principal difference is that where `filter` used the `newBuilder` method, which is abstract in class `TraversableLike`, `map` uses a *builder factory* that's passed as an additional implicit parameter of type `CanBuildFrom`.

```
package scala.collection.generic
trait CanBuildFrom[-From, -Elem, +To] {
  // Creates a new builder
  def apply(from: From): Builder[Elem, To]
}
```

Listing 25.4 · The `CanBuildFrom` trait.

[Listing 25.4](#) shows the definition of the trait `CanBuildFrom`, which represents builder factories. It has three type parameters: `Elem` indicates the element type of the collection to be built, `To` indicates the type of collection to build, and `From` indicates the type for which this builder factory applies.

By defining the right implicit definitions of builder factories, you can tailor the right typing behavior as needed.

Take class `BitSet` as an example. Its companion object would contain a builder factory of type `CanBuildFrom[BitSet, Int, BitSet]`. This means that when operating on a `BitSet` you can construct another `BitSet`, provided the type of the collection to build is `Int`. If this is not the case, you can always fall back to a different implicit builder factory, this time implemented in `mutable.Set`'s companion object. The type of this more general builder factory, where `A` is a generic type parameter, is:

```
CanBuildFrom[Set[_], A, Set[A]]
```

This means that when operating on an arbitrary `Set`, expressed by the wildcard type `Set[_]`, you can build a `Set` again no matter what the element type `A` is. Given these two implicit instances of `CanBuildFrom`, you can then rely on Scala's rules for implicit resolution to pick the one that's appropriate and maximally specific.

So implicit resolution provides the correct static types for tricky collection operations, such as `map`. But what about the dynamic types? Specifically, say you have a list value that has `Iterable` as its static type, and you map some function over that value:

```
scala> val xs: Iterable[Int] = List(1, 2, 3)
xs: Iterable[Int] = List(1, 2, 3)

scala> val ys = xs map (x => x * x)
ys: Iterable[Int] = List(1, 4, 9)
```

The static type of `ys` above is `Iterable`, as expected. But its dynamic type is (and should be) still `List`! This behavior is achieved by one more indirection. The `apply` method in `CanBuildFrom` is passed the source collection as argument. Most builder factories for generic traversables (in fact all except builder factories for leaf classes) forward the call to a method `genericBuilder` of a collection. The `genericBuilder` method in turn calls the builder that belongs to the collection in which it is defined. So Scala uses static implicit resolution to resolve constraints on the types of `map`, and virtual dispatch to pick the best dynamic type that corresponds to these constraints.

25.3 Integrating new collections

What needs to be done if you want to integrate a new collection class, so that it can profit from all predefined operations at the right types? In this section we'll show you two examples that do this.

Integrating sequences

Say you want to create a new sequence type for RNA strands, which are sequences of bases A (adenine), T (thymine), G (guanine), and U (uracil). The definitions for bases are easily set up as shown in [Listing 25.5](#).

Every base is defined as a case object that inherits from a common abstract class `Base`. The `Base` class has a companion object that defines two functions that map between bases and the integers 0 to 3. You can see in the examples two different ways to use collections to implement these functions. The `toInt` function is implemented as a `Map` from `Base` values to integers. The reverse function, `fromInt`, is implemented as an array. This makes use of the fact that both maps and arrays *are* functions because they inherit from the `Function1` trait.

The next task is to define a class for strands of RNA. Conceptually, a strand of RNA is simply a `Seq[Base]`. However, RNA strands can get quite long, so it makes sense to invest some work in a compact representation. Because there are only four bases, a base can be identified with two bits, and you can therefore store sixteen bases as two-bit values in an integer. The idea, then, is to construct a specialized subclass of `Seq[Base]`, which uses this packed representation.

[Listing 25.6](#) presents the first version of this class; it will be refined later. The class `RNA1` has a constructor that takes an array of `Ints` as its first argument. This array contains the packed RNA data, with sixteen bases in each element, except for the last array element, which might be partially filled. The second argument, `length`, specifies the total number of bases on the array (and in the sequence). Class `RNA1` extends `IndexedSeq[Base]`. Trait `IndexedSeq`, which comes from package `scala.collection.immutable`, defines two abstract methods, `length` and `apply`.

These need to be implemented in concrete subclasses. Class `RNA1` implements `length` automatically by defining a parametric field (described in [Section 10.6](#)) of the same name. It implements the indexing method `apply` with the code given in [Listing 25.6](#). Essentially, `apply` first extracts an in-

```
abstract class Base
case object A extends Base
case object T extends Base
case object G extends Base
case object U extends Base

object Base {
    val fromInt: Int => Base = Array(A, T, G, U)
    val toInt: Base => Int = Map(A -> 0, T -> 1, G -> 2, U -> 3)
}
```

Listing 25.5 · RNA Bases.

teger value from the `groups` array, then extracts the correct two-bit number from that integer using right shift (`>>`) and mask (`&`). The private constants `S`, `N`, and `M` come from the `RNA1` companion object. `S` specifies the size of each packet (*i.e.*, two); `N` specifies the number of two-bit packets per integer; and `M` is a bit mask that isolates the lowest `S` bits in a word.

Note that the constructor of class `RNA1` is `private`. This means that clients cannot create `RNA1` sequences by calling `new`, which makes sense, because it hides the representation of `RNA1` sequences in terms of packed arrays from the user. If clients cannot see what the representation details of RNA sequences are, it becomes possible to change these representation details at any point in the future without affecting client code.

In other words, this design achieves a good decoupling of the interface of RNA sequences and its implementation. However, if constructing an RNA sequence with `new` is impossible, there must be some other way to create new RNA sequences, or else the whole class would be rather useless. There are two alternatives for RNA sequence creation, both provided by the `RNA1` companion object. The first way is method `fromSeq`, which converts a given sequence of bases (*i.e.*, a value of type `Seq[Base]`) into an instance of class `RNA1`. The `fromSeq` method does this by packing all the bases contained in its argument sequence into an array, then calling `RNA1`'s `private` constructor with that array and the length of the original sequence as arguments. This makes use of the fact that a `private` constructor of a class is visible in the class's companion object.

The second way to create an `RNA1` value is provided by the `apply` method in the `RNA1` object. It takes a variable number of `Base` arguments and simply

```
import collection.IndexedSeqLike
import collection.mutable.{Builder, ArrayBuffer}
import collection.generic.CanBuildFrom

final class RNA1 private (val groups: Array[Int],
    val length: Int) extends Indexable[Base] {

    import RNA1._

    def apply(idx: Int): Base = {
        if (idx < 0 || length <= idx)
            throw new IndexOutOfBoundsException
        Base.fromInt(groups(idx / N) >> (idx % N * S) & M)
    }
}

object RNA1 {

    // Number of bits necessary to represent group
    private val S = 2

    // Number of groups that fit in an Int
    private val N = 32 / S

    // Bitmask to isolate a group
    private val M = (1 << S) - 1

    def fromSeq(buf: Seq[Base]): RNA1 = {
        val groups = new ArrayBuffer[Int]((buf.length + N - 1) / N)
        for (i <- 0 until buf.length)
            groups(i / N) |= Base.toInt(buf(i)) << (i % N * S)
        new RNA1(groups, buf.length)
    }

    def apply(bases: Base*) = fromSeq(bases)
}
```

Listing 25.6 · RNA strands class, first version.

forwards them as a sequence to `fromSeq`.

Here are the two creation schemes in action:

```
scala> val xs = List(A, G, T, A)
xs: List[Product with Base] = List(A, G, T, A)

scala> RNA1.fromSeq(xs)
res1: RNA1 = RNA1(A, G, T, A)

scala> val rna1 = RNA1(A, U, G, G, T)
rna1: RNA1 = RNA1(A, U, G, G, T)
```

Adapting the result type of RNA methods

Here are some more interactions with the `RNA1` abstraction:

```
scala> rna1.length
res2: Int = 5

scala> rna1.last
res3: Base = T

scala> rna1.take(3)
res4: IndexedSeq[Base] = Vector(A, U, G)
```

The first two results are as expected, but the last result of taking the first three elements of `rna1` might not be. In fact, you see an `IndexedSeq[Base]` as static result type and a `Vector` as the dynamic type of the result value. You might have expected to see an `RNA1` value instead. But this is not possible because all that was done in [Listing 25.6](#) was make `RNA1` extend `IndexedSeq`. Class `IndexedSeq`, on the other hand, has a `take` method that returns an `IndexedSeq`, and that's implemented in terms of `IndexedSeq`'s default implementation, `Vector`.

Now that you understand why things are the way they are, the next question should be what needs to be done to change them? One way to do this would be to override the `take` method in class `RNA1`, maybe like this:

```
def take(count: Int): RNA1 = RNA1.fromSeq(super.take(count))
```

This would do the job for `take`. But what about `drop`, or `filter`, or `init`? In fact there are over fifty methods on sequences that return again a sequence.

For consistency, all of these would have to be overridden. This looks less and less like an attractive option.

Fortunately, there is a much easier way to achieve the same effect. The RNA class needs to inherit not only from `IndexedSeq`, but also from its implementation trait `IndexedSeqLike`. This is shown in [Listing 25.7](#). The new implementation differs from the previous one in only two aspects. First, class `RNA2` now also extends from `IndexedSeqLike[Base, RNA2]`. The `IndexedSeqLike` trait implements all concrete methods of `IndexedSeq` in an extensible way.

For instance, the return type of methods like `take`, `drop`, `filter` or `init` is the second type parameter passed to class `IndexedSeqLike` (*i.e.*, `RNA2` in [Listing 25.7](#)). To do this, `IndexedSeqLike` bases itself on the `newBuilder` abstraction, which creates a builder of the right kind. Subclasses of trait `IndexedSeqLike` have to override `newBuilder` to return collections of their own kind. In class `RNA2`, the `newBuilder` method returns a builder of type `Builder[Base, RNA2]`. To construct this builder, it first creates an `ArrayBuffer`, which itself is a `Builder[Base, ArrayBuffer]`. It then transforms the `ArrayBuffer` builder by calling its `mapResult` method to an `RNA2` builder. The `mapResult` method expects a transformation function from `ArrayBuffer` to `RNA2` as its parameter. The function given is simply `RNA2.fromSeq`, which converts an arbitrary base sequence to an `RNA2` value (recall that an array buffer is a kind of sequence, so `RNA2.fromSeq` can be applied to it).

```
final class RNA2 private (
    val groups: Array[Int],
    val length: Int
) extends IndexedSeq[Base] with IndexedSeqLike[Base, RNA2] {
    import RNA2._

    override def newBuilder: Builder[Base, RNA2] =
        new ArrayBuffer[Base] mapResult fromSeq

    def apply(idx: Int): Base = // as before
}
```

[Listing 25.7](#) · RNA strands class, second version.

If you had left out the `newBuilder` definition, you would have gotten an

error message like the following:

```
RNA2.scala:5: error: overriding method newBuilder in trait
TraversableLike of type => scala.collection.mutable.Builder[Base, RNA2];
method newBuilder in trait GenericTraversableTemplate of type
=> scala.collection.mutable.Builder[Base, IndexedSeq[Base]] has
incompatible type
class RNA2 private (val groups: Array[Int], val length: Int)
^
one error found
```

The error message is quite long and complicated, which reflects the intricate way the collection libraries are put together. It's best to ignore the information about where the methods come from, because in this case it detracts more than it helps. What remains is that a method `newBuilder` with result type `Builder[Base, RNA2]` needed to be defined, but a method `newBuilder` with result type `Builder[Base, IndexedSeq[Base]]` was found. The latter does not override the former.

The first method, whose result type is `Builder[Base, RNA2]`, is an abstract method that got instantiated at this type in [Listing 25.7](#) by passing the `RNA2` type parameter to `IndexedSeqLike`. The second method, of result type `Builder[Base, IndexedSeq[Base]]`, is what's provided by the inherited `IndexedSeq` class. In other words, the `RNA2` class is invalid without a definition of `newBuilder` with the first result type.

With the refined implementation of the `RNA` class in [Listing 25.7](#), methods like `take`, `drop`, or `filter` work now as expected:

```
scala> val rna2 = RNA2(A, U, G, G, T)
rna2: RNA2 = RNA2(A, U, G, G, T)

scala> rna2 take 3
res5: RNA2 = RNA2(A, U, G)

scala> rna2 filter (U !=)
res6: RNA2 = RNA2(A, G, G, T)
```

Dealing with map and friends

There is another class of methods in collections that we haven't dealt with yet. These methods do not always return the collection type exactly. They

might return the same kind of collection, but with a different element type. The classical example of this is the `map` method. If `s` is a `Seq[Int]`, and `f` is a function from `Int` to `String`, then `s.map(f)` would return a `Seq[String]`. So the element type changes between the receiver and the result, but the kind of collection stays the same.

There are a number of other methods that behave like `map`. For some of them you would expect this (*e.g.*, `flatMap`, `collect`), but for others you might not. For instance, the append method, `++`, also might return a result whose type differs from that of its arguments—appending a list of `String` to a list of `Int` would give a list of `Any`. How should these methods be adapted to RNA strands? Ideally we'd expect that mapping bases to bases over an RNA strand would yield again an RNA strand:

```
scala> val rna = RNA(A, U, G, G, T)
rna: RNA = RNA(A, U, G, G, T)

scala> rna map { case A => T case b => b }
res7: RNA = RNA(T, U, G, G, T)
```

Likewise, appending two RNA strands with `++` should yield again another RNA strand:

```
scala> rna ++ rna
res8: RNA = RNA(A, U, G, G, T, A, U, G, G, T)
```

On the other hand, mapping bases to some other type over an RNA strand cannot yield another RNA strand because the new elements have the wrong type. It has to yield a sequence instead. In the same vein appending elements that are not of type `Base` to an RNA strand can yield a general sequence, but it cannot yield another RNA strand.

```
scala> rna map Base.toInt
res2: IndexedSeq[Int] = Vector(0, 3, 2, 2, 1)

scala> rna ++ List("missing", "data")
res3: IndexedSeq[java.lang.Object] =
Vector(A, U, G, G, T, missing, data)
```

This is what you'd expect in the ideal case. But this is not what the `RNA2` class as given in [Listing 25.7](#) provides. In fact, if you ran the first two examples above with instances of this class you would obtain:

```
scala> val rna2 = RNA2(A, U, G, G, T)
rna2: RNA2 = RNA2(A, U, G, G, T)

scala> rna2 map { case A => T case b => b }
res0: IndexedSeq[Base] = Vector(T, U, G, G, T)

scala> rna2 ++ rna2
res1: IndexedSeq[Base] = Vector(A, U, G, G, T, A, U, G, G, T)
```

So the result of `map` and `++` is never an RNA strand, even if the element type of the generated collection is a `Base`. To see how to do better, it pays to have a close look at the signature of the `map` method (or of `++`, which has a similar signature). The `map` method is originally defined in class `scala.collection.TraversableLike` with the following signature:

```
def map[B, That](f: Elem => B)
  (implicit cbf: CanBuildFrom[Repr, B, That]): That
```

Here `Elem` is the type of elements of the collection, and `Repr` is the type of the collection itself; that is, the second type parameter that gets passed to implementation classes such as `TraversableLike` and `IndexedSeqLike`. The `map` method takes two more type parameters, `B` and `That`. The `B` parameter stands for the result type of the mapping function, which is also the element type of the new collection. The `That` appears as the result type of `map`, so it represents the type of the new collection that gets created.

How is the `That` type determined? It is linked to the other types by an implicit parameter `cbf`, of type `CanBuildFrom[Repr, B, That]`. These `CanBuildFrom` implicits are defined by the individual collection classes. In essence, an implicit value of type `CanBuildFrom[From, Elem, To]` says: “Here is a way, given a collection of type `From`, to build with elements of type `Elem` a collection of type `To`.”

Now the behavior of `map` and `++` on `RNA2` sequences becomes clearer. There is no `CanBuildFrom` instance that creates `RNA2` sequences, so the next best available `CanBuildFrom` was found in the companion object of the inherited trait `IndexedSeq`. That implicit creates `IndexedSeqs`, and that’s what you saw when applying `map` to `rna2`.

To address this shortcoming, you need to define an implicit instance of `CanBuildFrom` in the companion object of the `RNA` class. That instance should have type `CanBuildFrom[RNA, Base, RNA]`. Hence, this instance states that, given an `RNA` strand and a new element type `Base`, you can

```
final class RNA private (val groups: Array[Int], val length: Int)
  extends IndexedSeq[Base] with IndexedSeqLike[Base, RNA] {

  import RNA._

  // Mandatory re-implementation of 'newBuilder' in 'IndexedSeq'
  override protected[this] def newBuilder: Builder[Base, RNA] =
    RNA.newBuilder

  // Mandatory implementation of 'apply' in 'IndexedSeq'
  def apply(idx: Int): Base = {
    if (idx < 0 || length <= idx)
      throw new IndexOutOfBoundsException
    Base.fromInt(groups(idx / N) >> (idx % N * S) & M)
  }

  // Optional re-implementation of foreach,
  // to make it more efficient.
  override def foreach[U](f: Base => U): Unit = {
    var i = 0
    var b = 0
    while (i < length) {
      b = if (i % N == 0) groups(i / N) else b >>> S
      f(Base.fromInt(b & M))
      i += 1
    }
  }
}
```

Listing 25.8 · RNA strands class, final version.

build another collection which is again an RNA strand. Listing 25.8 and Listing 25.9 show the details.

```
object RNA {  
    private val S = 2           // number of bits in group  
    private val M = (1 << S) - 1 // bitmask to isolate a group  
    private val N = 32 / S      // number of groups in an Int  
  
    def fromSeq(buf: Seq[Base]): RNA = {  
        val groups = new Array[Int]((buf.length + N - 1) / N)  
        for (i <- 0 until buf.length)  
            groups(i / N) |= Base.toInt(buf(i)) << (i % N * S)  
        new RNA(groups, buf.length)  
    }  
  
    def apply(bases: Base*) = fromSeq(bases)  
  
    def newBuilder: Builder[Base, RNA] =  
        new ArrayBuffer mapResult fromSeq  
  
    implicit def canBuildFrom: CanBuildFrom[RNA, Base, RNA] =  
        new CanBuildFrom[RNA, Base, RNA] {  
            def apply(): Builder[Base, RNA] = newBuilder  
            def apply(from: RNA): Builder[Base, RNA] = newBuilder  
        }  
}
```

Listing 25.9 · RNA companion object—final version.

Compared to class RNA2 there are two important differences. First, the newBuilder implementation has moved from the RNA class to its companion object. The newBuilder method in class RNA simply forwards to this definition. Second, there is now an implicit CanBuildFrom value in object RNA. To create such an object you need to define two apply methods in the CanBuildFrom trait. Both create a new builder for an RNA collection, but they differ in their argument list. The apply() method simply creates a new builder of the right type. By contrast, the apply(from) method takes the original collection as argument. This can be useful to adapt the dynamic type of builder's return type to be the same as the dynamic type of the receiver. In the case of RNA this does not come into play because RNA is a final class, so

any receiver of static type RNA also has RNA as its dynamic type. That's why `apply(from)` also simply calls `newBuilder`, ignoring its argument.

That is it. The RNA class in [Listing 25.8](#) implements all collection methods at their natural types. Its implementation requires a little bit of protocol. In essence, you need to know where to put the `newBuilder` factories and the `canBuildFrom` implicits. On the plus side, with relatively little code you get a large number of methods automatically defined. Also, if you don't intend to do bulk operations like `take`, `drop`, `map`, or `++` on your collection, you can choose to not go the extra length and stop at the implementation shown in [Listing 25.6](#).

The discussion so far centered on the minimal amount of definitions needed to define new sequences with methods that obey certain types. But in practice you might also want to add new functionality to your sequences or override existing methods for better efficiency. An example of this is the overridden `foreach` method in class RNA. `foreach` is an important method in its own right because it implements loops over collections. Furthermore, many other collection methods are implemented in terms of `foreach`. So it makes sense to invest some effort optimizing the method's implementation.

The standard implementation of `foreach` in `IndexedSeq` will simply select every i 'th element of the collection using `apply`, where i ranges from 0 to the collection's length minus one. So this standard implementation selects an array element and unpacks a base from it once for every element in an RNA strand. The overriding `foreach` in class RNA is smarter than that. For every selected array element it immediately applies the given function to all bases contained in it. So the effort for array selection and bit unpacking is much reduced.

Integrating new sets and maps

As a second example you'll learn how to integrate a new kind of map into the collection framework. The idea is to implement a mutable map with `String` as the type of keys by a "Patricia trie".² The term *Patricia* is an abbreviation for "Practical Algorithm to Retrieve Information Coded in Alphanumeric." The idea is to store a set or a map as a tree where subsequent characters in a search key determines uniquely a descendant tree.

²Morrison, "PATRICIA—Practical Algorithm To Retrieve Information Coded in Alphanumeric" [Mor68]




Figure 25.1 · An example Patricia trie.

For instance, a Patricia trie storing the five strings, "abc", "abd", "al", "all", "xy", would look like the tree given in Figure 25.1. To find the node corresponding to the string "abc" in this trie, simply follow the subtree labeled "a", proceed from there to the subtree labeled "b" to finally reach its subtree labeled "c". If the Patricia trie is used as a map, the value that's associated with a key is stored in the nodes that can be reached by the key. If it is a set, you simply store a marker saying that the node is present in the set.

Patricia tries support very efficient lookups and updates. Another nice feature is that they support selecting a subcollection by giving a prefix. For instance, in the tree in Figure 25.1 you can obtain the sub-collection of all keys that start with an "a" simply by following the "a" link from the root of the tree.

Based on these ideas we will now walk you through the implementation of a map that's implemented as a Patricia trie. We call the map a `PrefixMap`, which means that it provides a method `withPrefix` that selects a submap of all keys starting with a given prefix.

We'll first define a prefix map with the keys shown in Figure 25.1:

```
scala> val m = PrefixMap("abc" -> 0, "abd" -> 1, "al" -> 2,
  "all" -> 3, "xy" -> 4)
m: PrefixMap[Int] = Map((abc,0), (abd,1), (al,2), (all,3),
(xy,4))
```

Then calling `withPrefix` on `m` will yield another prefix map:

```
scala> m withPrefix "a"
res14: PrefixMap[Int] = Map((bc,0), (bd,1), (l,2), (ll,3))
```

[Listing 25.10](#) shows the definition of `PrefixMap`. This class is parameterized with the type of associated values `T`, and extends `mutable.Map[String, T]`

```
import collection._

class PrefixMap[T]
extends mutable.Map[String, T]
  with mutable.MapLike[String, T, PrefixMap[T]] {

  var suffixes: immutable.Map[Char, PrefixMap[T]] = Map.empty
  var value: Option[T] = None

  def get(s: String): Option[T] =
    if (s.isEmpty) value
    else suffixes get (s(0)) flatMap (_.get(s substring 1))

  def withPrefix(s: String): PrefixMap[T] =
    if (s.isEmpty) this
    else {
      val leading = s(0)
      suffixes get leading match {
        case None =>
          suffixes = suffixes + (leading -> empty)
        case _ =>
      }
      suffixes(leading) withPrefix (s substring 1)
    }

  override def update(s: String, elem: T) =
    withPrefix(s).value = Some(elem)

  override def remove(s: String): Option[T] =
    if (s.isEmpty) { val prev = value; value = None; prev }
    else suffixes get (s(0)) flatMap (_.remove(s substring 1))

  def iterator: Iterator[(String, T)] =
    (for (v <- value.iterator) yield ("", v)) ++
    (for ((chr, m) <- suffixes.iterator;
          (s, v) <- m.iterator) yield (chr +: s, v))

  def += (kv: (String, T)): this.type = { update(kv._1, kv._2); this }

  def -= (s: String): this.type = { remove(s); this }

  override def empty = new PrefixMap[T]
}
```

Listing 25.10 · An implementation of prefix maps with Patricia tries.

and `mutable.MapLike[String, T, PrefixMap[T]]`. You have seen this pattern already for sequences in the RNA strand example. Then as now inheriting an implementation class such as `MapLike` serves to get the right result type for transformations such as `filter`.

A prefix map node has two mutable fields: `suffixes` and `value`. The `value` field contains an optional value that's associated with the node. It is initialized to `None`. The `suffixes` field contains a map from characters to `PrefixMap` values. It is initialized to the empty map. You might ask, Why did we pick an immutable map as the implementation type for `suffixes`? Would not a mutable map been more standard since `PrefixMap` as a whole is also mutable? The answer is that immutable maps that contain only a few elements are very efficient in both space and execution time.

For instance, maps that contain fewer than 5 elements are represented as a single object. By contrast, as described in [Section 17.2](#), the standard mutable map is a `HashMap`, which typically occupies around 80 bytes, even if it is empty. So if small collections are common, it's better to pick immutable over mutable. In the case of Patricia tries, we'd expect that most nodes, except the ones at the very top of the tree, would contain only a few successors. So storing these successors in an immutable map is likely to be more efficient.

Now have a look at the first method that needs to be implemented for a map: `get`. The algorithm is as follows: To get the value associated with the empty string in a prefix map, simply select the optional value stored in the root of the tree. Otherwise, if the key string is not empty, try to select the submap corresponding to the first character of the string. If that yields a map, follow up by looking up the remainder of the key string after its first character in that map. If the selection fails, the key is not stored in the map, so return with `None`. The combined selection over an option value is elegantly expressed using `flatMap`. When applied to an optional value, `ov`, and a closure, `f`, which in turn returns an optional value, `ov flatMap f` will succeed if both `ov` and `f` return a defined value. Otherwise `ov flatMap f` will return `None`.

The next two methods to implement for a mutable map are `+=` and `-=`. In the implementation of [Listing 25.10](#), these are defined in terms of two other methods: `update` and `remove`. The `remove` method is very similar to `get`, except that before returning any associated value, the field containing that value is set to `None`. The `update` method first calls `withPrefix` to navigate to the tree node that needs to be updated, then sets the `value` field of that

node to the given value. The `withPrefix` method navigates through the tree, creating sub-maps as necessary if some prefix of characters is not yet contained as a path in the tree.

The last abstract method to implement for a mutable map is `iterator`. This method needs to produce an iterator that yields all key/value pairs stored in the map. For any given prefix map this iterator is composed of the following parts: First, if the map contains a defined value, `Some(x)`, in the `value` field at its root, then `("\"", x)` is the first element returned from the iterator. Furthermore, the iterator needs to traverse the iterators of all submaps stored in the `suffixes` field, but it needs to add a character in front of every key string returned by those iterators. More precisely, if `m` is the submap reached from the root through a character `chr`, and `(s, v)` is an element returned from `m.iterator`, then the root's iterator will return `(chr +: s, v)` instead.

This logic is implemented quite concisely as a concatenation of two `for` expressions in the implementation of the `iterator` method in [Listing 25.10](#). The first `for` expression iterates over `value.iterator`. This makes use of the fact that `Option` values define an `iterator` method that returns either no element, if the option value is `None`, or exactly one element `x`, if the option value is `Some(x)`.

Note that there is no `newBuilder` method defined in `PrefixMap`. There is no need because maps and sets come with default builders, which are instances of class `MapBuilder`. For a mutable map the default builder starts with an empty map and then adds successive elements using the map's `+=` method. Mutable sets behave the same. The default builders for immutable maps and sets use the non-destructive element addition method `+`, instead of method `+=`. However, in all these cases, to build the right kind of set or map, you need to start with an empty set or map of this kind. This is provided by the `empty` method, which is the last method defined in `PrefixMap`. In [Listing 25.10](#), this method simply returns a fresh `PrefixMap`.

We'll now turn to the companion object `PrefixMap`, which is shown in [Listing 25.11](#). In fact it is not strictly necessary to define this companion object, as class `PrefixMap` can stand well on its own. The main purpose of object `PrefixMap` is to define some convenience factory methods. It also defines a `CanBuildFrom` implicit to make typing work out better.

The two convenience methods are `empty` and `apply`. The same methods are present for all other collections in Scala's collection framework so it makes sense to define them here too. With the two methods, you can write `PrefixMap` literals like you do for any other collection:

```
import scala.collection.mutable.{Builder, MapBuilder}
import scala.collection.generic.CanBuildFrom

object PrefixMap {
    def empty[T] = new PrefixMap[T]

    def apply[T](kvs: (String, T)*): PrefixMap[T] = {
        val m: PrefixMap[T] = empty
        for (kv <- kvs) m += kv
        m
    }

    def newBuilder[T]: Builder[(String, T), PrefixMap[T]] =
        new MapBuilder[String, T, PrefixMap[T]](empty)

    implicit def canBuildFrom[T]:
        CanBuildFrom[PrefixMap[_], (String, T), PrefixMap[T]] =
        new CanBuildFrom[PrefixMap[_], (String, T), PrefixMap[T]] {
            def apply(from: PrefixMap[_]) = newBuilder[T]
            def apply() = newBuilder[T]
        }
    }
}
```

Listing 25.11 · The companion object for prefix maps.

```
scala> PrefixMap("hello" -> 5, "hi" -> 2)
res0: PrefixMap[Int] = Map(hello,5), (hi,2))

scala> PrefixMap.empty[String]
res2: PrefixMap[String] = Map()
```

The other member in object `PrefixMap` is an implicit `CanBuildFrom` instance. It has the same purpose as the `CanBuildFrom` definition in the last section: to make methods like `map` return the best possible type. For instance, consider mapping a function over the key/value pairs of a `PrefixMap`. As long as that function produces pairs of strings and some second type, the result collection will again be a `PrefixMap`. Here's an example:

```
scala> res0 map { case (k, v) => (k + "!", "x" * v) }
res8: PrefixMap[String] = Map(hello!,xxxxxx), (hi!,xx))
```

The given function argument takes the key/value bindings of the prefix map `res0` and produces pairs of strings. The result of the `map` is a `PrefixMap`, this time with value type `String` instead of `Int`. Without the `canBuildFrom` implicit in `PrefixMap` the result would just have been a general mutable map, not a prefix map.

Summary

If you want to fully integrate a new collection class into the framework, you need to pay attention to the following points:

1. Decide whether the collection should be mutable or immutable.
2. Pick the right base traits for the collection.
3. Inherit from the right implementation trait to implement most collection operations.
4. If you want `map` and similar operations to return instances of your collection type, provide an implicit `CanBuildFrom` in your class's companion object.

25.4 Conclusion

You have now seen how Scala's collections are built and how you can build new kinds of collections. Because of Scala's rich support for abstraction, each new collection type can have a large number of methods without having to reimplement them all over again.

Chapter 26

Extractors

By now you have probably grown accustomed to the concise way data can be decomposed and analyzed using pattern matching. This chapter shows you how to generalize this concept further. Until now, constructor patterns were linked to case classes. For instance, `Some(x)` is a valid pattern because `Some` is a case class. Sometimes you might wish that you could write patterns like this without creating an associated case class. In fact, you might wish to be able to create your own kinds of patterns. Extractors give you a way to do so. This chapter explains what extractors are and how you can use them to define patterns that are decoupled from an object's representation.

26.1 An example: extracting email addresses

To illustrate the problem extractors solve, imagine that you need to analyze strings that represent email addresses. Given a string, you want to decide whether it is an email address or not, and, if it is, you want to access the user and domain parts of the address. The traditional way to do this uses three helper functions:

```
def isEmail(s: String): Boolean
def domain(s: String): String
def user(s: String): String
```

With these functions, you could parse a given string `s` as follows:

```
if (isEmail(s)) println(user(s) + " AT " + domain(s))
else println("not an email address")
```

This works, but is kind of clumsy. What's more, things would become more complicated if you combined several such tests. For instance you might want to find two successive strings in a list that are both email addresses with the same user. You can try this yourself with the access functions defined previously to see what would be involved.

You saw already in [Chapter 15](#) that pattern matching is ideal for attacking problems like this. Let's assume for the moment that you could match a string with a pattern:

```
EMail(user, domain)
```

The pattern would match if the string contained an embedded at sign (@). In that case it would bind variable user to the part of the string before the @ and variable domain to the part after it. Postulating a pattern like this, the previous expression could be written more clearly like this:

```
s match {
  case EMail(user, domain) => println(user + " AT " + domain)
  case _ => println("not an email address")
}
```

The more complicated problem of finding two successive email addresses with the same user part would translate to the following pattern:

```
ss match {
  case EMail(u1, d1) :: EMail(u2, d2) :: _ if (u1 == u2) => ...
  ...
}
```

This is much more legible than anything that could be written with access functions. However, the problem is that strings are not case classes; they do not have a representation that conforms to `EMail(user, domain)`. This is where Scala's extractors come in: they let you define new patterns for pre-existing types, where the pattern need not follow the internal representation of the type.

26.2 Extractors

An extractor in Scala is an object that has a method called `unapply` as one of its members. The purpose of that `unapply` method is to match a value and

take it apart. Often, the extractor object also defines a dual method `apply` for building values, but this is not required. As an example, Listing 26.1 shows an extractor object for email addresses:

```
object EMail {  
    // The injection method (optional)  
    def apply(user: String, domain: String) = user + "@" + domain  
    // The extraction method (mandatory)  
    def unapply(str: String): Option[(String, String)] = {  
        val parts = str split "@"  
        if (parts.length == 2) Some(parts(0), parts(1)) else None  
    }  
}
```

Listing 26.1 · The EMail string extractor object.

This object defines both `apply` and `unapply` methods. The `apply` method has the same meaning as always: it turns `EMail` into an object that can be applied to arguments in parentheses in the same way a method is applied. So you can write `EMail("John", "epfl.ch")` to construct the string `"John@epfl.ch"`. To make this more explicit, you could also let `EMail` inherit from Scala’s function type, like this:

```
object EMail extends ((String, String) => String) { ... }
```

Note

The `"(String, String) => String"` portion of the previous object declaration means the same as `Function2[String, String, String]`, which declares an abstract `apply` method that `EMail` implements. As a result of this declaration, you could, for example, pass `EMail` to a method expecting a `Function2[String, String, String]`.

The `unapply` method is what turns `EMail` into an extractor. In a sense, it reverses the construction process of `apply`. Where `apply` takes two strings and forms an email address string out of them, `unapply` takes an email address and returns potentially two strings: the user and the domain of the address. But `unapply` must also handle the case where the given string is not an email address. That’s why `unapply` returns an `Option`-type over pairs of strings. Its result is either `Some(user, domain)` if the string `str` is an email

address with the given user and domain parts,¹ or None, if str is not an email address. Here are some examples:

```
unapply("John@epfl.ch") equals Some("John", "epfl.ch")
unapply("John Doe") equals None
```

Now, whenever pattern matching encounters a pattern referring to an extractor object, it invokes the extractor's unapply method on the selector expression. For instance, executing the code:

```
selectorString match { case EMail(user, domain) => ... }
```

would lead to the call:

```
EMail.unapply(selectorString)
```

As you saw previously, this call to EMail.unapply will return either None or Some(u, d), for some values u for the user part of the address and d for the domain part. In the None case, the pattern does not match, and the system tries another pattern or fails with a MatchError exception. In the Some(u, d) case, the pattern matches and its variables are bound to the elements of the returned value. In the previous match, user would be bound to u and domain would be bound to d.

In the EMail pattern matching example, the type String of the selector expression, selectorString, conformed to unapply's argument type (which in the example was also String). This is quite common, but not necessary. It would also be possible to use the EMail extractor to match selector expressions for more general types. For instance, to find out whether an arbitrary value x was an email address string, you could write:

```
val x: Any = ...
x match { case EMail(user, domain) => ... }
```

Given this code, the pattern matcher will first check whether the given value x conforms to String, the parameter type of EMail's unapply method. If it does conform, the value is cast to String and pattern matching proceeds as before. If it does not conform, the pattern fails immediately.

¹As demonstrated here, where Some is applied to the tuple, (user, domain), you can leave off one pair of parentheses when passing a tuple to a function that takes a single argument. Thus, Some(user, domain) means the same as Some((user, domain)).

In object `EMail`, the `apply` method is called an *injection*, because it takes some arguments and yields an element of a given set (in our case: the set of strings that are email addresses). The `unapply` method is called an *extraction*, because it takes an element of the same set and extracts some of its parts (in our case: the user and domain substrings). Injections and extractions are often grouped together in one object, because then you can use the object's name for both a constructor and a pattern, which simulates the convention for pattern matching with case classes. However, it is also possible to define an extraction in an object without a corresponding injection. The object itself is called an *extractor*, regardless of whether or not it has an `apply` method.

If an injection method is included, it should be the dual to the extraction method. For instance, a call of:

```
EMail.unapply(EMail.apply(user, domain))
```

should return:

```
Some(user, domain)
```

i.e., the same sequence of arguments wrapped in a `Some`. Going in the other direction means running first the `unapply` and then the `apply`, as shown in the following code:

```
EMail.unapply(obj) match {
  case Some(u, d) => EMail.apply(u, d)
}
```

In that code, if the match on `obj` succeeds, you'd expect to get back that same object from the `apply`. These two conditions for the duality of `apply` and `unapply` are good design principles. They are not enforced by Scala, but it's recommended to keep to them when designing your extractors.

26.3 Patterns with zero or one variables

The `unapply` method of the previous example returned a pair of element values in the success case. This is easily generalized to patterns of more than two variables. To bind N variables, an `unapply` would return an N -element tuple, wrapped in a `Some`.

The case where a pattern binds just one variable is treated differently, however. There is no one-tuple in Scala. To return just one pattern element,

the unapply method simply wraps the element itself in a Some. For example, the extractor object shown in Listing 26.2 defines apply and unapply for strings that consist of the same substring appearing twice in a row:

```
object Twice {
    def apply(s: String): String = s + s
    def unapply(s: String): Option[String] = {
        val length = s.length / 2
        val half = s.substring(0, length)
        if (half == s.substring(length)) Some(half) else None
    }
}
```

Listing 26.2 · The Twice string extractor object.

It's also possible that an extractor pattern does not bind any variables. In that case the corresponding unapply method returns a boolean—true for success and false for failure. For instance, the extractor object shown in Listing 26.3 characterizes strings consisting of all uppercase characters:

```
object UpperCase {
    def unapply(s: String): Boolean = s.toUpperCase == s
}
```

Listing 26.3 · The UpperCase string extractor object.

This time, the extractor only defines an unapply, but not an apply. It would make no sense to define an apply, as there's nothing to construct.

The following userTwiceUpper function applies all previously defined extractors together in its pattern matching code:

```
def userTwiceUpper(s: String) = s match {
    case EMail(Twice(x @ UpperCase()), domain) =>
        "match: " + x + " in domain " + domain
    case _ =>
        "no match"
}
```

The first pattern of this function matches strings that are email addresses whose user part consists of two occurrences of the same string in uppercase letters. For instance:

```
scala> userTwiceUpper("DIDI@hotmail.com")
res0: String = match: DI in domain hotmail.com

scala> userTwiceUpper("DIDO@hotmail.com")
res1: String = no match

scala> userTwiceUpper("didi@hotmail.com")
res2: String = no match
```

Note that `UpperCase` in function `userTwiceUpper` takes an empty parameter list. This cannot be omitted as otherwise the match would test for equality with the object `UpperCase!` Note also that, even though `UpperCase()` itself does not bind any variables, it is still possible to associate a variable with the whole pattern matched by it. To do this, you use the standard scheme of variable binding explained in [Section 15.2](#): the form `x @ UpperCase()` associates the variable `x` with the pattern matched by `UpperCase()`. For instance, in the first `userTwiceUpper` invocation above, `x` was bound to "`DI`", because that was the value against which the `UpperCase()` pattern was matched.

26.4 Variable argument extractors

The previous extraction methods for email addresses all returned a fixed number of element values. Sometimes, this is not flexible enough. For example, you might want to match on a string representing a domain name, so that every part of the domain is kept in a different sub-pattern. This would let you express patterns such as the following:

```
dom match {
  case Domain("org", "acm") => println("acm.org")
  case Domain("com", "sun", "java") => println("java.sun.com")
  case Domain("net", _) => println("a .net domain")
}
```

In this example things were arranged so that domains are expanded in reverse order—from the top-level domain down to the sub-domains. This was

done so that you could better profit from sequence patterns. You saw in [Section 15.2](#) that a sequence wildcard pattern, `_*`, at the end of an argument list matches any remaining elements in a sequence. This feature is more useful if the top-level domain comes first, because then you can use sequence wildcards to match sub-domains of arbitrary depth.

The question remains how an extractor can support *vararg matching* as shown in the previous example, where patterns can have a varying number of sub-patterns. The `unapply` methods encountered so far are not sufficient, because they each return a fixed number of sub-elements in the success case. To handle this case, Scala lets you define a different extraction method specifically for vararg matching. This method is called `unapplySeq`. To see how it is written, have a look at the `Domain` extractor, shown in [Listing 26.4](#):

```
object Domain {  
    // The injection method (optional)  
    def apply(parts: String*): String =  
        parts.reverse.mkString(".")  
  
    // The extraction method (mandatory)  
    def unapplySeq(whole: String): Option[Seq[String]] =  
        Some(whole.split("\\.\\.").reverse)  
}
```

[Listing 26.4](#) · The `Domain` string extractor object.

The `Domain` object defines an `unapplySeq` method that first splits the string into parts separated by periods. This is done using Java's `split` method on strings, which takes a regular expression as its argument. The result of `split` is an array of substrings. The result of `unapplySeq` is then that array with all elements reversed and wrapped in a `Some`.

The result type of an `unapplySeq` must conform to `Option[Seq[T]]`, where the element type `T` is arbitrary. As you saw in [Section 17.1](#), `Seq` is an important class in Scala's collection hierarchy. It's a common superclass of several classes describing different kinds of sequences: `Lists`, `Arrays`, `WrappedString`, and several others.

For symmetry, `Domain` also has an `apply` method that builds a domain string from a variable argument parameter of domain parts starting with the top-level domain. As always, the `apply` method is optional.

You can use the Domain extractor to get more detailed information out of email strings. For instance, to search for an email address named "tom" in some ".com" domain, you could write the following function:

```
def isTomInDotCom(s: String): Boolean = s match {
  case EMail("tom", Domain("com", _*)) => true
  case _ => false
}
```

This gives the expected results:

```
scala> isTomInDotCom("tom@sun.com")
res3: Boolean = true

scala> isTomInDotCom("peter@sun.com")
res4: Boolean = false

scala> isTomInDotCom("tom@acm.org")
res5: Boolean = false
```

It's also possible to return some fixed elements from an unapplySeq together with the variable part. This is expressed by returning all elements in a tuple, where the variable part comes last, as usual. As an example, Listing 26.5 shows a new extractor for emails where the domain part is already expanded into a sequence:

```
object ExpandedEMail {
  def unapplySeq(email: String)
    : Option[(String, Seq[String])] = {
    val parts = email split "@"
    if (parts.length == 2)
      Some(parts(0), parts(1).split("\\.").reverse)
    else
      None
  }
}
```

Listing 26.5 · The ExpandedEMail extractor object.

The unapplySeq method in ExpandedEMail returns an optional value of a pair (a Tuple2). The first element of the pair is the user part. The second

element is a sequence of names representing the domain. You can match on this as usual:

```
scala> val s = "tom@support.epfl.ch"
s: String = tom@support.epfl.ch

scala> val ExpandedEMail(name, topdom, subdoms @ _) = s
name: String = tom
topdom: String = ch
subdoms: Seq[String] = WrappedArray(epfl, support)
```

26.5 Extractors and sequence patterns

You saw in [Section 15.2](#) that you can access the elements of a list or an array using sequence patterns such as:

```
List()
List(x, y, _*)
Array(x, 0, 0, _*)
```

In fact, these sequence patterns are all implemented using extractors in the standard Scala library. For instance, patterns of the form `List(...)` are possible because the `scala.List` companion object is an extractor that defines an `unapplySeq` method. [Listing 26.6](#) shows the relevant definitions:

```
package scala
object List {
  def apply[T](elems: T*) = elems.toList
  def unapplySeq[T](x: List[T]): Option[Seq[T]] = Some(x)
  ...
}
```

[Listing 26.6](#) · An extractor that defines an `unapplySeq` method.

The `List` object contains an `apply` method that takes a variable number of arguments. That's what lets you write expressions such as:

```
List()
List(1, 2, 3)
```

It also contains an `unapplySeq` method that returns all elements of the list as a sequence. That's what supports `List(...)` patterns. Very similar definitions exist in the object `scala.Array`. These support analogous injections and extractions for arrays.

26.6 Extractors versus case classes

Even though they are very useful, case classes have one shortcoming: they expose the concrete representation of data. This means that the name of the class in a constructor pattern corresponds to the concrete representation type of the selector object. If a match against:

```
case C(...)
```

succeeds, you know that the selector expression is an instance of class `C`.

Extractors break this link between data representations and patterns. You have seen in the examples in this section that they enable patterns that have nothing to do with the data type of the object that's selected on. This property is called *representation independence*. In open systems of large size, representation independence is very important because it allows you to change an implementation type used in a set of components without affecting clients of these components.

If your component had defined and exported a set of case classes, you'd be stuck with them because client code could already contain pattern matches against these case classes. Renaming some case classes or changing the class hierarchy would affect client code. Extractors do not share this problem, because they represent a layer of indirection between a data representation and the way it is viewed by clients. You could still change a concrete representation of a type, as long as you update all your extractors with it.

Representation independence is an important advantage of extractors over case classes. On the other hand, case classes also have some advantages of their own over extractors. First, they are much easier to set up and to define, and they require less code. Second, they usually lead to more efficient pattern matches than extractors, because the Scala compiler can optimize patterns over case classes much better than patterns over extractors. This is because the mechanisms of case classes are fixed, whereas an `unapply` or `unapplySeq` method in an extractor could do almost anything. Third, if your case classes inherit from a sealed base class, the Scala compiler will check

your pattern matches for exhaustiveness and will complain if some combination of possible values is not covered by a pattern. No such exhaustiveness checks are available for extractors.

So which of the two methods should you prefer for your pattern matches? It depends. If you write code for a closed application, case classes are usually preferable because of their advantages in conciseness, speed and static checking. If you decide to change your class hierarchy later, the application needs to be refactored, but this is usually not a problem. On the other hand, if you need to expose a type to unknown clients, extractors might be preferable because they maintain representation independence.

Fortunately, you need not decide right away. You could always start with case classes and then, if the need arises, change to extractors. Because patterns over extractors and patterns over case classes look exactly the same in Scala, pattern matches in your clients will continue to work.

Of course, there are also situations where it's clear from the start that the structure of your patterns does not match the representation type of your data. The email addresses discussed in this chapter were one such example. In that case, extractors are the only possible choice.

26.7 Regular expressions

One particularly useful application area of extractors are regular expressions. Like Java, Scala provides regular expressions through a library, but extractors make it much nicer to interact with them.

Forming regular expressions

Scala inherits its regular expression syntax from Java, which in turn inherits most of the features of Perl. We assume you know that syntax already; if not, there are many accessible tutorials, starting with the Javadoc documentation of class `java.util.regex.Pattern`. Here are just some examples that should be enough as refreshers:

`ab?` An ‘a’, possibly followed by a ‘b’.

`\d+` A number consisting of one or more digits represented by `\d`.

[a-dA-D]\w*	A word starting with a letter between a and d in lower or upper case, followed by a sequence of zero or more “word characters” denoted by \w. (A word character is a letter, digit, or underscore.)
(-)?(\d+)(\.\d*)?	A number consisting of an optional minus sign, followed by one or more digits, optionally followed by a period and zero or more digits. The number contains three <i>groups</i> , i.e., the minus sign, the part before the decimal point, and the fractional part including the decimal point. Groups are enclosed in parentheses.

Scala’s regular expression class resides in package `scala.util.matching`.

```
scala> import scala.util.matching.Regex
```

A new regular expression value is created by passing a string to the `Regex` constructor. For instance:

```
scala> val Decimal = new Regex("(-)?(\d+)(\.\d*)?")
Decimal: scala.util.matching.Regex = (-)?(\d+)(\.\d*)?
```

Note that, compared to the regular expression for decimal numbers given previously, every backslash appears twice in the string above. This is because in Java and Scala a single backslash is an escape character in a string literal, not a regular character that shows up in the string. So instead of ‘\’ you need to write ‘\\’ to get a single backslash in the string.

If a regular expression contains many backslashes this might be a bit painful to write and to read. Scala’s raw strings provide an alternative. As you saw in [Section 5.2](#), a raw string is a sequence of characters between triple quotes. The difference between a raw and a normal string is that all characters in a raw string appear exactly as they are typed. This includes backslashes, which are not treated as escape characters. So you could write equivalently and somewhat more legibly:

```
scala> val Decimal = new Regex("""(-)?(\d+)(\.\d*)?""")
Decimal: scala.util.matching.Regex = (-)?(\d+)(\.\d*)?
```

As you can see from the interpreter's output, the generated result value for `Decimal` is exactly the same as before.

Another, even shorter way to write a regular expression in Scala is this:

```
scala> val Decimal = """(-)?(\d+)(\.\d*)?""".r
Decimal: scala.util.matching.Regex = (-)?(\d+)(\.\d*)?
```

In other words, simply append a `.r` to a string to obtain a regular expression. This is possible because there is a method named `r` in class `StringOps`, which converts a string to a regular expression. The method is defined as shown in Listing 26.7:

```
package scala.runtime
import scala.util.matching.Regex
class StringOps(self: String) ... {
  ...
  def r = new Regex(self)
}
```

Listing 26.7 · How the `r` method is defined in `StringOps`.

Searching for regular expressions

You can search for occurrences of a regular expression in a string using several different operators:

`regex findFirstIn str`

Finds first occurrence of regular expression `regex` in string `str`, returning the result in an `Option` type.

`regex findAllIn str`

Finds all occurrences of regular expression `regex` in string `str`, returning the results in an `Iterator`.

`regex findPrefixOf str`

Finds an occurrence of regular expression `regex` at the start of string `str`, returning the result in an `Option` type.

For instance, you could define the input sequence below and then search decimal numbers in it:

```
scala> val Decimal = """(-)?(\d+)(\.\d*)?""".r
Decimal: scala.util.matching.Regex = (-)?(\d+)(\.\d*)?

scala> val input = "for -1.0 to 99 by 3"
input: String = for -1.0 to 99 by 3

scala> for (s <- Decimal findAllIn input)
    println(s)

-1.0
99
3

scala> Decimal findFirstIn input
res7: Option[String] = Some(-1.0)

scala> Decimal findPrefixOf input
res8: Option[String] = None
```

Extracting with regular expressions

What's more, every regular expression in Scala defines an extractor. The extractor is used to identify substrings that are matched by the groups of the regular expression. For instance, you could decompose a decimal number string as follows:

```
scala> val Decimal(sign, integerpart, decimalpart) = "-1.23"
sign: String = -
integerpart: String = 1
decimalpart: String = .23
```

In this example, the pattern, `Decimal(...)`, is used in a `val` definition, as described in [Section 15.7](#). What happens here is that the `Decimal` regular expression value defines an `unapplySeq` method. That method matches every string that corresponds to the regular expression syntax for decimal numbers. If the string matches, the parts that correspond to the three groups in the regular expression `(-)?(\d+)(\.\d*)?` are returned as elements of the pattern and are then matched by the three pattern variables `sign`, `integerpart`, and `decimalpart`. If a group is missing, the element value is set to null, as can be seen in the following example:

```
scala> val Decimal(sign, integerpart, decimalpart) = "1.0"
sign: String = null
integerpart: String = 1
decimalpart: String = .0
```

It's also possible to mix extractors with regular expression searches in a `for` expression. For instance, the following expression decomposes all decimal numbers it finds in the input string:

```
scala> for (Decimal(s, i, d) <- Decimal findAllIn input)
        println("sign: " + s + ", integer: " +
               i + ", decimal: " + d)
sign: -, integer: 1, decimal: .0
sign: null, integer: 99, decimal: null
sign: null, integer: 3, decimal: null
```

26.8 Conclusion

In this chapter you saw how to generalize pattern matching with extractors. Extractors let you define your own kinds of patterns, which need not correspond to the type of the expressions you select on. This gives you more flexibility in the kinds of patterns you can use for matching. In effect it's like having different possible views on the same data. It also gives you a layer between a type's representation and the way clients view it. This lets you do pattern matching while maintaining representation independence, a property which is very useful in large software systems.

Extractors are one more element in your tool box that let you define flexible library abstractions. They are used heavily in Scala's libraries, for instance, to enable convenient regular expression matching.

Chapter 27

Annotations

Annotations are structured information added to program source code. Like comments, they can be sprinkled throughout a program and attached to any variable, method, expression, or other program element. Unlike comments, they have structure, thus making them easier to machine process.

This chapter shows how to use annotations in Scala. It shows their general syntax and how to use several standard annotations.

This chapter does not show how to write new annotation processing tools, because it is beyond the scope of this book. [Chapter 31](#) shows one technique, but not the only one. Instead, this chapter focuses on how to use annotations, because it is more common to use annotations than to define new annotation processors.

27.1 Why have annotations?

There are many things you can do with a program other than compiling and running it. Some examples are:

1. Automatic generation of documentation as with Scaladoc.
2. Pretty printing code so that it matches your preferred style.
3. Checking code for common errors such as opening a file but, on some control paths, never closing it.
4. Experimental type checking, for example to manage side effects or ensure ownership properties.

Such tools are called *meta-programming* tools, because they are programs that take other programs as input. Annotations support these tools by letting the programmer sprinkle directives to the tool throughout their source code. Such directives let the tools be more effective than if they could have no user input. For example, annotations can improve the previously listed tools as follows:

1. A documentation generator could be instructed to document certain methods as deprecated.
2. A pretty printer could be instructed to skip over parts of the program that have been carefully hand formatted.
3. A checker for non-closed files could be instructed to ignore a particular file that has been manually verified to be closed.
4. A side-effects checker could be instructed to verify that a specified method has no side effects.

In all of these cases, it would in theory be possible for the programming language to provide ways to insert the extra information. In fact, most of these are directly supported in some language or another. However, there are too many such tools for one language to directly support them all. Further, all of this information is completely ignored by the compiler, which after all just wants to make the code run.

Scala's philosophy in cases like this is to include the minimum, orthogonal support in the core language such that a wide variety of meta-programming tools can be written. In this case, that minimum support is a system of annotations. The compiler understands just one feature, annotations, but it doesn't attach any meaning to individual annotations. Each meta-programming tool can then define and use its own specific annotations.

27.2 Syntax of annotations

A typical use of an annotation looks like this:

```
@deprecated def bigMistake() = //...
```

The annotation is the `@deprecated` part, and it applies to the entirety of the `bigMistake` method (not shown—it's too embarrassing). In this case,

the method is being marked as something the author of `bigMistake` wishes you not to use. Maybe `bigMistake` will be removed entirely from a future version of the code.

In the previous example, a method is annotated as `@deprecated`. Annotations are allowed in other places too. Annotations are allowed on any kind of declaration or definition, including `vals`, `vars`, `defs`, `classes`, `objects`, `traits`, and `types`. The annotation applies to the entirety of the declaration or definition that follows it:

```
@deprecated class QuickAndDirty {  
    //...  
}
```

Annotations can also be applied to an expression, as with the `@unchecked` annotation for pattern matching (see [Chapter 15](#)). To do so, place a colon (`:`) after the expression and then write the annotation. Syntactically, it looks like the annotation is being used as a type:

```
(e: @unchecked) match {  
    // non-exhaustive cases...  
}
```

Finally, annotations can be placed on types. Annotated types are described later in this chapter.

So far the annotations shown have been simply an at sign followed by an annotation class. Such simple annotations are common and useful, but annotations have a richer general form:

`@annot(exp1, exp2, ...)`

The `annot` specifies the class of annotation. All annotations must include that much. The `exp` parts are arguments to the annotation. For annotations like `@deprecated` that do not need any arguments, you would normally leave off the parentheses, but you can write `@deprecated()` if you like. For annotations that do have arguments, place the arguments in parentheses, for example, `@serial(1234)`.

The precise form of the arguments you may give to an annotation depends on the particular annotation class. Most annotation processors only let you supply immediate constants such as `123` or `"hello"`. The compiler itself supports arbitrary expressions, however, so long as they type check.

Some annotation classes can make use of this, for example, to let you refer to other variables that are in scope:

```
@cool val normal = "Hello"  
@coolerThan(normal) val fonzy = "Heeyyy"
```

Internally, Scala represents an annotation as just a constructor call of an annotation class—replace the ‘@’ by ‘new’ and you have a valid instance creation expression. This means that named and default annotation arguments are supported naturally, because Scala already has named and default arguments for method and constructor calls. One slightly tricky bit concerns annotations that conceptually take other annotations as arguments, which are required by some frameworks. You cannot write an annotation directly as an argument to an annotation, because annotations are not valid expressions. In such cases you must use ‘new’ instead of ‘@’, as illustrated here:

```
scala> import annotation._  
import annotation._  
  
scala> class strategy(arg: Annotation) extends Annotation  
defined class strategy  
  
scala> class delayed extends Annotation  
defined class delayed  
  
scala> @strategy(@delayed) def f() = {}  
<console>:1: error: illegal start of simple expression  
    @strategy(@delayed) def f() = {}  
                                ^  
  
scala> @strategy(new delayed) def f() = {}  
f: ()Unit
```

27.3 Standard annotations

Scala includes several standard annotations. They are for features that are used widely enough to merit putting in the language specification, but that are not fundamental enough to merit their own syntax. Over time, there should be a trickle of new annotations that are added to the standard in just the same way.

Deprecation

Sometimes you write a class or method that you later wish you had not. Once it is available, though, code written by other people might call the method. Thus, you cannot simply delete the method, because this would cause other people's code to stop compiling.

Deprecation lets you gracefully remove a method or class that turns out to be a mistake. You mark the method or class as deprecated, and then anyone who calls that method or class will get a deprecation warning. They had better heed this warning and update their code! The idea is that after a suitable amount of time has passed, you feel safe in assuming that all reasonable clients will have stopped accessing the deprecated class or method and thus that you can safely remove it.

You mark a method as deprecated simply by writing `@deprecated` before it. For example:

```
@deprecated def bigMistake() = //...
```

Such an annotation will cause the Scala compiler to emit deprecation warnings whenever Scala code accesses the method.

If you supply a string as an argument to `@deprecated`, that string will be emitted along with the error message. Use this message to explain to developers what they should use instead of the deprecated method.

```
@deprecated("use newShinyMethod() instead")
def bigMistake() = //...
```

Now any callers will get a message like this:

```
$ scalac -deprecation Deprecation2.scala
Deprecation2.scala:33: warning: method bigMistake in object
Deprecation2 is deprecated: use newShinyMethod() instead
          bigMistake()
          ^
one warning found
```

Volatile fields

Concurrent programming does not mix well with shared mutable state. For this reason, the focus of Scala's concurrency support is message passing and a minimum of shared mutable state. See Chapter ?? for the details.

Nonetheless, sometimes programmers want to use mutable state in their concurrent programs. The `@volatile` annotation helps in such cases. It informs the compiler that the variable in question will be used by multiple threads. Such variables are implemented so that reads and writes to the variable are slower, but accesses from multiple threads behave more predictably.

The `@volatile` keyword gives different guarantees on different platforms. On the Java platform, however, you get the same behavior as if you wrote the field in Java code and marked it with the Java `volatile` modifier.

Binary serialization

Many languages include a framework for binary *serialization*. A serialization framework helps you convert objects into a stream of bytes and *vice versa*. This is useful if you want to save objects to disk or send them over the network. XML can help with the same goals (see Chapter 28), but it has different trade offs regarding speed, space usage, flexibility, and portability.

Scala does not have its own serialization framework. Instead, you should use a framework from your underlying platform. What Scala does is provide three annotations that are useful for a variety of frameworks. Also, the Scala compiler for the Java platform interprets these annotations in the Java way (see Chapter 31).

The first annotation indicates whether a class is serializable at all. Most classes are serializable, but not all. A handle to a socket or GUI window, for example, cannot be serialized. By default, a class is not considered serializable. You should add a `@Serializable` annotation to any class you would like to be serializable.

The second annotation helps deal with serializable classes changing as time goes by. You can attach a serial number to the current version of a class by adding an annotation like `@SerialVersionUID(1234)`, where 1234 should be replaced by your serial number of choice. The framework should store this number in the generated byte stream. When you later reload that byte stream and try to convert it to an object, the framework can check that the current version of the class has the same version number as the version

in the byte stream. If you want to make a serialization-incompatible change to your class, then you can change the version number. The framework will then automatically refuse to load old instances of the class.

Finally, Scala provides a `@transient` annotation for fields that should not be serialized at all. If you mark a field as `@transient`, then the framework should not save the field even when the surrounding object is serialized. When the object is loaded, the field will be restored to the default value for the type of the field annotated as `@transient`.

Automatic get and set methods

Scala code normally does not need explicit get and set methods for fields, because Scala blends the syntax for field access and method invocation. Some platform-specific frameworks do expect get and set methods, however. For that purpose, Scala provides the `@scala.reflect.BeanProperty` annotation. If you add this annotation to a field, the compiler will automatically generate get and set methods for you. If you annotate a field named `crazy`, the get method will be named `getCrazy` and the set method will be named `setCrazy`.

The generated get and set methods are only available after a compilation pass completes. Thus, you cannot call these get and set methods from code you compile at the same time as the annotated fields. This should not be a problem in practice, because in Scala code you can access the fields directly. This feature is intended to support frameworks that expect regular get and set methods, and typically you do not compile the framework and the code that uses it at the same time.

Tailrec

You would typically add the `@tailrec` annotation to a method that needs to be tail recursive, for instance because you expect that it would recurse very deeply otherwise. To make sure that the Scala compiler does perform the tail-recursion optimization described in [Section 8.9](#) on this method, you can add `@tailrec` in front of the method definition. If the optimization cannot be performed, you will then get a warning together with an explanation of the reasons.

Unchecked

The `@unchecked` annotation is interpreted by the compiler during pattern matches. It tells the compiler not to worry if the `match` expression seems to leave out some cases. See [Section 15.5](#) for details.

Native methods

The `@native` annotation informs the compiler that a method's implementation is supplied by the runtime rather than in Scala code. The compiler will toggle the appropriate flags in the output, and it will be up to the developer to supply the implementation using a mechanism such as the Java Native Interface (JNI).

When using the `@native` annotation, a method body must be supplied, but it will not be emitted into the output. For example, here is how to declare that method `beginCountdown` will be supplied by the runtime:

```
@native
def beginCountdown() = {}
```

27.4 Conclusion

This chapter described the platform-independent aspects of annotations that you will most commonly need to know about. First of all it covered the syntax of annotations, because using annotations is far more common than defining new ones. Second it showed how to use several annotations that are supported by the standard Scala compiler, including `@deprecated`, `@volatile`, `@serializable`, `@BeanProperty`, `@tailrec`, and `@unchecked`.

[Chapter 31](#) gives additional, Java-specific information on annotations. It covers annotations only available when targeting Java, additional meanings of standard annotations when targeting Java, how to interoperate with Java-based annotations, and how to use Java-based mechanisms to define and process annotations in Scala.

Chapter 28

Working with XML

This chapter introduces Scala’s support for XML. After discussing semi-structured data in general, it shows the essential functionality in Scala for manipulating XML: how to make nodes with XML literals, how to save and load XML to files, and how to take apart XML nodes using query methods and pattern matching. This chapter is just a brief introduction to what is possible with XML, but it shows enough to get you started.

28.1 Semi-structured data

XML is a form of *semi-structured data*. It is more structured than plain strings, because it organizes the contents of the data into a tree. Plain XML is less structured than the objects of a programming language, though, as it admits free-form text between tags and it lacks a type system.¹

Semi-structured data is very helpful any time you need to serialize program data for saving in a file or shipping across a network. Instead of converting structured data all the way down to bytes, you convert it to and from semi-structured data. You then use pre-existing library routines to convert between semi-structured data and binary data, saving your time for more important problems.

There are many forms of semi-structured data, but XML is the most widely used on the Internet. There are XML tools on most operating systems, and most programming languages have XML libraries available. Its popularity is self-reinforcing. The more tools and libraries are developed

¹There are type systems for XML, such as XML Schemas, but they are beyond the scope of this book.

in response to XML's popularity, the more likely software engineers are to choose XML as part of their formats. If you write software that communicates over the Internet, then sooner or later you will need to interact with some service that speaks XML.

For all of these reasons, Scala includes special support for processing XML. This chapter shows you Scala's support for constructing XML, processing it with regular methods, and processing it with Scala's pattern matching. In addition to these nuts and bolts, the chapter shows along the way several common idioms for using XML in Scala.

28.2 XML overview

XML is built out of two basic elements, text and tags.² Text is, as usual, any sequence of characters. Tags, written like `<pod>`, consist of a less-than sign, an alphanumeric label, and a greater than sign. Tags can be *start* or *end* tags. An end tag looks just like a start tag except that it has a slash just before the tag's label, like this: `</pod>`.

Start and end tags must match each other, just like parentheses. Any start tag must eventually be followed by an end tag with the same label. Thus the following is illegal:

```
// Illegal XML
One <pod>, two <pod>, three <pod> zoo
```

Further, the contents of any two matching tags must itself be valid XML. You cannot have two pairs of matching tags overlap each other:

```
// Also illegal
<pod>Three <peas> in the </pod></peas>
```

You could, however, write it like this:

```
<pod>Three <peas></peas> in the </pod>
```

Since tags are required to match in this way, XML is structured as nested *elements*. Each pair of matching start and end tags forms an element, and elements may be nested within each other. In the above example, the entirety of `<pod>Three <peas></peas> in the </pod>` is an element, and `<peas></peas>` is an element nested within it.

²The full story is more complicated, but this is enough to be effective with XML.

Those are the basics. Two other things you should know are, first, there is a shorthand notation for a start tag followed immediately by its matching end tag. Simply write one tag with a slash put after the tag's label. Such a tag comprises an *empty element*. Using an empty element, the previous example could just as well be written as follows:

```
<pod>Three <peas/> in the </pod>
```

Second, start tags can have *attributes* attached to them. An attribute is a name-value pair written with an equals sign in the middle. The attribute name itself is plain, unstructured text, and the value is surrounded by either double quotes ("") or single quotes (''). Attributes look like this:

```
<pod peas="3" strings="true"/>
```

28.3 XML literals

Scala lets you type in XML as a **literal** anywhere that an expression is valid. Simply type a start tag and then continue writing XML content. The compiler will go into an XML-input mode and will read content as XML until it sees the end tag matching the start tag you began with:

```
scala> <a>
         This is some XML.
         Here is a tag: <atag/>
      </a>
res0: scala.xml.Elem =
<a>
  This is some XML.
  Here is a tag: <atag/>
</a>
```

The result of this expression is of type `Elem`, meaning it is an XML element with a label (“`a`”) and children (“This is some XML...,” *etc.*). Some other important XML classes are:

- Class `Node` is the abstract superclass of all XML node classes.
- Class `Text` is a node holding just text. For example, the “stuff” part of `<a>stuff` is of class `Text`.

- Class `NodeSeq` holds a sequence of nodes. Many methods in the XML library process `NodeSeqs` in places you might expect them to process individual `Nodes`. You can still use such methods with individual nodes, however, since `Node` extends from `NodeSeq`. This may sound weird, but it works out well for XML. You can think of an individual `Node` as a one-element `NodeSeq`.

You are not restricted to writing out the exact XML you want, character for character. You can evaluate Scala code in the middle of an XML literal by using curly braces `{}` as an escape. Here is a simple example:

```
scala> <a> {"hello" + ", world"} </a>
res1: scala.xml.Elem = <a> hello, world </a>
```

A braces escape can include arbitrary Scala content, including further XML literals. Thus, as the nesting level increases, your code can switch back and forth between XML and ordinary Scala code. Here's an example:

```
scala> val yearMade = 1955
yearMade: Int = 1955

scala> <a> { if (yearMade < 2000) <old>{yearMade}</old>
           else xml.NodeSeq.Empty }
         </a>
res2: scala.xml.Elem =
<a> <old>1955</old>
      </a>
```

If the code inside the curly braces evaluates to either an XML node or a sequence of XML nodes, those nodes are inserted directly as is. In the above example, if `yearMade` is less than 2000, it is wrapped in `<old>` tags and added to the `<a>` element. Otherwise, nothing is added. Note in the above example that "nothing" as an XML node is denoted with `xml.NodeSeq.Empty`.

An expression inside a brace escape does not have to evaluate to an XML node. It can evaluate to any Scala value. In such a case, the result is converted to a string and inserted as a text node:

```
scala> <a> {3 + 4} </a>
res3: scala.xml.Elem = <a> 7 </a>
```

Any `<`, `>`, and `&` characters in the text will be escaped if you print the node back out:

```
scala> <a> {"</a>potential security hole<a>"} </a>
res4: scala.xml.Elem = <a> &lt;/a&gt;potential security
hole&lt;a&gt; </a>
```

To contrast, if you create XML with low-level string operations, you will run into traps such as the following:

```
scala> "<a>" + "</a>potential security hole<a>" + "</a>"
res5: String = <a></a>potential security hole<a></a>
```

What happens here is that a user-supplied string has included XML tags of its own, in this case `` and `<a>`. This behavior can allow some nasty surprises for the original programmer, because it allows the user to affect the resulting XML tree outside of the space provided for the user inside the `<a>` element. You can prevent this entire class of problems by always constructing XML using XML literals, not string appends.

28.4 Serialization

You have now seen enough of Scala's XML support to write the first part of a serializer: conversion from internal data structures to XML. All you need for this are XML literals and their brace escapes.

As an example, suppose you are implementing a database to keep track of your extensive collection of vintage Coca-Cola thermometers. You might make the following internal class to hold entries in the catalog:

```
abstract class CCTherm {
    val description: String
    val yearMade: Int
    val dateObtained: String
    val bookPrice: Int      // in US cents
    val purchasePrice: Int  // in US cents
    val condition: Int      // 1 to 10
    override def toString = description
}
```

This is a straightforward, data-heavy class that holds various pieces of information such as when the thermometer was made, when you got it, and how much you paid for it.

To convert instances of this class to XML, simply add a `toXML` method that uses XML literals and brace escapes, like this:

```
abstract class CCTherm {  
    ...  
    def toXML =  
        <cctherm>  
            <description>{description}</description>  
            <yearMade>{yearMade}</yearMade>  
            <dateObtained>{dateObtained}</dateObtained>  
            <bookPrice>{bookPrice}</bookPrice>  
            <purchasePrice>{purchasePrice}</purchasePrice>  
            <condition>{condition}</condition>  
        </cctherm>  
}
```

Here is the method in action:

```
scala> val therm = new CCTherm {  
    val description = "hot dog #5"  
    val yearMade = 1952  
    val dateObtained = "March 14, 2006"  
    val bookPrice = 2199  
    val purchasePrice = 500  
    val condition = 9  
}  
therm: CCTherm = hot dog #5  
scala> therm.toXML  
res6: scala.xml.Elem =  
<cctherm>  
            <description>hot dog #5</description>  
            <yearMade>1952</yearMade>  
            <dateObtained>March 14, 2006</dateObtained>  
            <bookPrice>2199</bookPrice>  
            <purchasePrice>500</purchasePrice>  
            <condition>9</condition>  
        </cctherm>
```

Note

The “new CCTherm” expression in the previous example works even though CCTherm is an abstract class, because this syntax actually instantiates an anonymous subclass of CCTherm. Anonymous classes were described in [Section 20.5](#).

By the way, if you want to include a curly brace (‘{’ or ‘}’) as XML text, as opposed to using them to escape to Scala code, simply write two curly braces in a row:

```
scala> <a> {{{brace yourself!}}} </a>
res7: scala.xml.Elem = <a> {brace yourself!} </a>
```

28.5 Taking XML apart

Among the many methods available for the XML classes, there are three in particular that you should be aware of. They allow you to take apart XML without thinking too much about the precise way XML is represented in Scala. These methods are based on the XPath language for processing XML. As is common in Scala, you can write them directly in Scala code instead of needing to invoke an external tool.

Extracting text. By calling the `text` method on any XML node you retrieve all of the text within that node, minus any element tags:

```
scala> <a>Sounds <tag/> good</a>.text
res8: String = Sounds good
```

Any encoded characters are decoded automatically:

```
scala> <a> input ---&gt; output </a>.text
res9: String = " input ---> output "
```

Extracting sub-elements. If you want to find a sub-element by tag name, simply call `\` with the name of the tag:

```
scala> <a><b><c>hello</c></b></a> \ "b"
res10: scala.xml.NodeSeq = NodeSeq(<b><c>hello</c></b>)
```

You can do a “deep search” and look through sub-sub-elements, *etc.*, by using `\\" instead of the \ operator:`

```
scala> <a><b><c>hello</c></b></a> \\ "c"
res11: scala.xml.NodeSeq = NodeSeq()
scala> <a><b><c>hello</c></b></a> \\ "c"
res12: scala.xml.NodeSeq = NodeSeq(<c>hello</c>)
scala> <a><b><c>hello</c></b></a> \\ "a"
res13: scala.xml.NodeSeq = NodeSeq()
scala> <a><b><c>hello</c></b></a> \\ "a"
res14: scala.xml.NodeSeq =
NodeSeq(<a><b><c>hello</c></b></a>)
```

Note

Scala uses \ and \\ instead of XPath’s / and //. The reason is that // starts a comment in Scala! Thus, some other symbol has to be used, and using the other kind of slashes works well.

Extracting attributes. You can extract tag attributes using the same \ and \\ methods. Simply put an at sign (@) before the attribute name:

```
scala> val joe = <employee
           name="Joe"
           rank="code monkey"
           serial="123"/>
joe: scala.xml.Elem = <employee name="Joe" rank="code monkey"
                                serial="123"/>
scala> joe \\ "@name"
res15: scala.xml.NodeSeq = Joe
scala> joe \\ "@serial"
res16: scala.xml.NodeSeq = 123
```

28.6 Deserialization

Using the previous methods for taking XML apart, you can now write the dual of a serializer, a parser from XML back into your internal data struc-

tures. For example, you can parse back a CCTherm instance by using the following code:

```
def fromXML(node: scala.xml.Node): CCTherm =  
  new CCTherm {  
    val description  = (node \ "description").text  
    val yearMade     = (node \ "yearMade").text.toInt  
    val dateObtained = (node \ "dateObtained").text  
    val bookPrice     = (node \ "bookPrice").text.toInt  
    val purchasePrice = (node \ "purchasePrice").text.toInt  
    val condition     = (node \ "condition").text.toInt  
  }
```

This code searches through an input XML node, named node, to find each of the six pieces of data needed to specify a CCTherm. The data that is text is extracted with .text and left as is. Here is this method in action:

```
scala> val node = therm.toXML  
node: scala.xml.Elem =  
<cctherm>  
      <description>hot dog #5</description>  
      <yearMade>1952</yearMade>  
      <dateObtained>March 14, 2006</dateObtained>  
      <bookPrice>2199</bookPrice>  
      <purchasePrice>500</purchasePrice>  
      <condition>9</condition>  
</cctherm>  
  
scala> fromXML(node)  
res17: CCTherm = hot dog #5
```

28.7 Loading and saving

There is one last part needed to write a data serializer: conversion between XML and streams of bytes. This last part is the easiest, because there are library routines that will do it all for you. You simply have to call the right routine on the right data.

To convert XML to a string, all you need is `toString`. The presence of a workable `toString` is why you can experiment with XML in the Scala shell.

However, it is better to use a library routine and convert all the way to bytes. That way, the resulting XML can include a directive that specifies which character encoding was used. If you encode the string to bytes yourself, then the onus is on you to keep track of the character encoding.

To convert from XML to a file of bytes, you can use the `XML.save` command. You must specify a file name and a node to be saved:

```
scala.xml.XML.save("therm1.xml", node)
```

After running the above command, the resulting file `therm1.xml` looks like the following:

```
<?xml version='1.0' encoding='UTF-8'?>
<cctherm>
    <description>hot dog #5</description>
    <yearMade>1952</yearMade>
    <dateObtained>March 14, 2006</dateObtained>
    <bookPrice>2199</bookPrice>
    <purchasePrice>500</purchasePrice>
    <condition>9</condition>
</cctherm>
```

Loading is simpler than saving, because the file includes everything the loader needs to know. Simply call `XML.loadFile` on a file name:

```
scala> val loadnode = xml.XML.loadFile("therm1.xml")
loadnode: scala.xml.Elem =
<cctherm>
    <description>hot dog #5</description>
    <yearMade>1952</yearMade>
    <dateObtained>March 14, 2006</dateObtained>
    <bookPrice>2199</bookPrice>
    <purchasePrice>500</purchasePrice>
    <condition>9</condition>
</cctherm>

scala> fromXML(loadnode)
res14: CCTherm = hot dog #5
```

Those are the basic methods you need. There are many variations on these loading and saving methods, including methods for reading and writing to various kinds of readers, writers, input and output streams.

28.8 Pattern matching on XML

So far you have seen how to dissect XML using `text` and the XPath-like methods, `\` and `\\`. These are good when you know exactly what kind of XML structure you are taking apart. Sometimes, though, there are a few possible structures the XML could have. Maybe there are multiple kinds of records within the data, for example because you have extended your thermometer collection to include clocks and sandwich plates. Maybe you simply want to skip over any white space between tags. Whatever the reason, you can use the pattern matcher to sift through the possibilities.

An XML pattern looks just like an XML literal. The main difference is that if you insert a `{}` escape, then the code inside the `{}` is not an expression but a pattern. A pattern embedded in `{}` can use the full Scala pattern language, including binding new variables, performing type tests, and ignoring content using the `_` and `_*` patterns. Here is a simple example:

```
def proc(node: scala.xml.Node): String =  
  node match {  
    case <a>{contents}</a> => "It's an a: " + contents  
    case <b>{contents}</b> => "It's a b: " + contents  
    case _ => "It's something else."  
  }
```

This function has a pattern match with three cases. The first case looks for an `<a>` element whose contents consist of a single sub-node. It binds those contents to a variable named `contents` and then evaluates the code to the right of the associated right arrow (`=>`). The second case does the same thing but looks for a `` instead of an `<a>`, and the third case matches anything not matched by any other case. Here is the function in use:

```
scala> proc(<a>apple</a>)  
res18: String = It's an a: apple  
scala> proc(<b>banana</b>)  
res19: String = It's a b: banana
```

```
scala> proc(<c>cherry</c>)
res20: String = It's something else.
```

Most likely this function is not exactly what you want, because it looks precisely for contents consisting of a single sub-node within the `<a>` or ``. Thus it will fail to match in cases like the following:

```
scala> proc(<a>a <em>red</em> apple</a>)
res21: String = It's something else.
scala> proc(<a/>)
res22: String = It's something else.
```

If you want the function to match in cases like these, you can match against a sequence of nodes instead of a single one. The pattern for “any sequence” of XML nodes is written `'_*'`. Visually, this sequence looks like the wildcard pattern `(_)` followed by a regex-style Kleene star `(*)`. Here is the updated function that matches a sequence of sub-elements instead of a single sub-element:

```
def proc(node: scala.xml.Node): String =
  node match {
    case <a>{contents @ _*}</a> => "It's an a: " + contents
    case <b>{contents @ _*}</b> => "It's a b: " + contents
    case _ => "It's something else."
  }
```

Notice that the result of the `_*` is bound to the `contents` variable by using the `@` pattern described in [Section 15.2](#). Here is the new version in action:

```
scala> proc(<a>a <em>red</em> apple</a>)
res23: String = It's an a: ArrayBuffer(a , <em>red</em>,
apple)
scala> proc(<a/>)
res24: String = It's an a: WrappedArray()
```

As a final tip, be aware that XML patterns work very nicely with `for` expressions as a way to iterate through some parts of an XML tree while ignoring other parts. For example, suppose you wish to skip over the white space between records in the following XML structure:

```
val catalog =  
  <catalog>  
    <cctherm>  
      <description>hot dog #5</description>  
      <yearMade>1952</yearMade>  
      <dateObtained>March 14, 2006</dateObtained>  
      <bookPrice>2199</bookPrice>  
      <purchasePrice>500</purchasePrice>  
      <condition>9</condition>  
    </cctherm>  
    <cctherm>  
      <description>Sprite Boy</description>  
      <yearMade>1964</yearMade>  
      <dateObtained>April 28, 2003</dateObtained>  
      <bookPrice>1695</bookPrice>  
      <purchasePrice>595</purchasePrice>  
      <condition>5</condition>  
    </cctherm>  
  </catalog>
```

Visually, it looks like there are two nodes inside the `<catalog>` element. Actually, though, there are five. There is white space before, after, and between the two elements! If you do not consider this white space, you might incorrectly process the thermometer records as follows:

```
catalog match {  
  case <catalog>{therms @ _*}</catalog> =>  
    for (therm <- therms)  
      println("processing: " +  
        (therm \ "description").text)  
}
```

```
processing:  
processing: hot dog #5  
processing:  
processing: Sprite Boy  
processing:
```

Notice all of the lines that try to process white space as if it were a true thermometer record. What you would really like to do is ignore the white space and process only those sub-nodes that are inside a `<cctherm>` element. You can describe this subset using the pattern `<cctherm>{_*}</cctherm>`, and you can restrict the `for` expression to iterating over items that match that pattern:

```
catalog match {
  case <catalog>{therms @ _*}</catalog> =>
    for (therm @ <cctherm>{_*}</cctherm> <- therms)
      println("processing: " +
        (therm \ "description").text)
}

processing: hot dog #5
processing: Sprite Boy
```

28.9 Conclusion

This chapter has only scratched the surface of what you can do with XML. There are many other extensions, libraries, and tools you could learn about, some customized for Scala, some made for Java but usable in Scala, and some language-neutral. What you should walk away from this chapter with is how to use semi-structured data for interchange, and how to access semi-structured data via Scala's XML support.

Chapter 29

Modular Programming Using Objects

In [Chapter 1](#), we claimed that one way Scala is a scalable language is that you can use the same techniques to construct small as well as large programs. So far in this book we've focused primarily on *programming in the small*: designing and implementing the smaller program pieces out of which you can construct a larger program.¹ The other side of the story is *programming in the large*: organizing and assembling the smaller pieces into larger programs, applications, or systems. We touched on this subject when we discussed packages and access modifiers in [Chapter 13](#). In short, packages and access modifiers enable you to organize a large program using packages as *modules*, where a module is a “smaller program piece” with a well defined interface and a hidden implementation.

While the division of programs into packages is already quite helpful, it is limited because it provides no way to abstract. You cannot reconfigure a package two different ways within the same program, and you cannot inherit between packages. A package always includes one precise list of contents, and that list is fixed until you change the code.

In this chapter, we'll discuss how you can use Scala's object-oriented features to make a program more modular. We'll first show how a simple singleton object can be used as a module. Then we'll explain how you can use traits and classes as abstractions over modules. These abstractions can be reconfigured into multiple modules, even multiple times within the same program. Finally, we'll show a pragmatic technique for using traits to divide a module across multiple files.

¹This terminology was introduced in DeRemer, *et al.*, “Programming-in-the-large versus programming-in-the-small.” [\[DeR75\]](#)

29.1 The problem

As a program grows in size, it becomes increasingly important to organize it in a modular way. First, being able to compile different modules that make up the system separately helps different teams work independently. In addition, being able to unplug one implementation of a module and plug in another is useful, because it allows different configurations of a system to be used in different contexts, such as unit testing on a developer’s desktop, integration testing, staging, and deployment.

For example, you may have an application that uses a database and a message service. As you write code, you may want to run unit tests on your desktop that use mock versions of both the database and message service, which simulate these services sufficiently for testing without needing to talk across the network to a shared resource. During integration testing, you may want to use a mock message service but a live developer database. During staging and certainly during deployment, your organization will likely want to use live versions of both the database and message service.

Any technique that aims to facilitate this kind of modularity needs to provide a few essentials. First, there should be a module construct that provides a good separation of interface and implementation. Second, there should be a way to replace one module with another that has the same interface without changing or recompiling the modules that depend on the replaced one. Lastly, there should be a way to wire modules together. This wiring task can be thought of as *configuring* the system.

One approach to solving this problem is *dependency injection*, a technique supported on the Java platform by frameworks such as Spring and Guice, which are popular in the enterprise Java community.² Spring, for example, essentially allows you to represent the interface of a module as a Java interface and implementations of the module as Java classes. You can specify dependencies between modules and “wire” an application together via external XML configuration files. Although you can use Spring with Scala and thereby use Spring’s approach to achieving system-level modularity of your Scala programs, with Scala you have some alternatives enabled by the language itself. In the remainder of this chapter, we’ll show how to use objects as modules to achieve the desired “in the large” modularity without using an external framework.

²Fowler, “Inversion of control containers and the dependency injection pattern.” [Fow04]

29.2 A recipe application

Imagine you are building an enterprise web application that will allow users to manage recipes. You want to partition the software into layers, including a *domain layer* and an *application layer*. In the domain layer, you'll define *domain objects*, which will capture business concepts and rules, as well as encapsulate state that will be persisted to an external relational database. In the application layer, you'll provide an API organized in terms of the services the application offers to clients (including the user interface layer). The application layer will implement these services by coordinating tasks and delegating the work to the objects of the domain layer.³

You want to be able to plug in real or mock versions of certain objects in each of these layers, so that you can more easily write unit tests for your application. To achieve this goal, you can treat the objects you want to mock as modules. In Scala, there is no need for objects to be “small” things, no need to use some other kind of construct for “big” things like modules. One of the ways Scala is a scalable language is that the same constructs are used for structures both small and large.

For example, since one of the “things” you want to mock in the domain layer is the object that represents the relational database, you'll make that one of the modules. In the application layer, you'll treat a “database browser” object as a module. The database will hold all of the recipes that a person has collected. The browser will help search and browse that database, for example, to find every recipe that includes an ingredient you have on hand.

The first thing to do is to model foods and recipes. To keep things simple, a food will just have a name, as shown in Listing 29.1. A recipe will have a name, a list of ingredients, and some instructions, as shown in Listing 29.2.

```
package org.stairwaybook.recipe
abstract class Food(val name: String) {
    override def toString = name
}
```

Listing 29.1 · A simple Food entity class.

³The naming of these layers follows that of Evans, *Domain-Driven Design*. [Eva03]

```
package org.stairwaybook.recipe

class Recipe(
    val name: String,
    val ingredients: List[Food],
    val instructions: String
) {
    override def toString = name
}
```

Listing 29.2 · Simple Recipe entity class.

The Food and Recipe classes shown in [Listings 29.1](#) and [29.2](#) represent *entities* that will be persisted in the database.⁴ Listing 29.3 shows some singleton instances of these classes, which can be used when writing tests.

```
package org.stairwaybook.recipe

object Apple extends Food("Apple")
object Orange extends Food("Orange")
object Cream extends Food("Cream")
object Sugar extends Food("Sugar")

object FruitSalad extends Recipe(
    "fruit salad",
    List(Apple, Orange, Cream, Sugar),
    "Stir it all together."
)
```

Listing 29.3 · Food and Recipe examples for use in tests.

Scala uses objects for modules, so you can start modularizing your program by making two singleton objects to serve as mock implementations of the database and browser modules during testing. Because it is a mock,

⁴These entity classes are simplified to keep the example uncluttered with too much real-world detail. But transforming these classes into entities that could be persisted with Hibernate or the Java Persistence Architecture, , for example, would require only a few modifications, such as adding a private Long id field and a no-arg constructor, placing `scala.reflect.BeanProperty` annotations on the fields, specifying appropriate mappings via annotations or a separate XML file, and so on.

```
package org.stairwaybook.recipe

object SimpleDatabase {
    def allFoods = List(Apple, Orange, Cream, Sugar)

    def foodNamed(name: String): Option[Food] =
        allFoods.find(_.name == name)

    def allRecipes: List[Recipe] = List(FruitSalad)
}

object SimpleBrowser {
    def recipesUsing(food: Food) =
        SimpleDatabase.allRecipes.filter(recipe =>
            recipe.ingredients.contains(food))
}
```

Listing 29.4 · Mock database and browser modules.

the database module is backed by a simple in-memory list. Implementations of these objects are shown in [Listing 29.4](#). You can use this database and browser as follows:

```
scala> val apple = SimpleDatabase.foodNamed("Apple").get
apple: Food = Apple

scala> SimpleBrowser.recipesUsing(apple)
res0: List[Recipe] = List(fruit salad)
```

To make things a little more interesting, suppose the database sorts foods into categories. To implement this, you can add a `FoodCategory` class and a list of all categories in the database, as shown in [Listing 29.5](#). Notice in this example that the `private` keyword, so useful for implementing classes, is also useful for implementing modules. Items marked `private` are part of the implementation of a module, and thus are particularly easy to change without affecting other modules.

At this point, many more facilities could be added, but you get the idea. Programs can be divided into singleton objects, which you can think of as modules. This is not big news, but it becomes very useful when you consider abstraction (which we'll cover next).

```
package org.stairwaybook.recipe

object SimpleDatabase {
    def allFoods = List(Apple, Orange, Cream, Sugar)

    def foodNamed(name: String): Option[Food] =
        allFoods.find(_.name == name)

    def allRecipes: List[Recipe] = List(FruitSalad)

    case class FoodCategory(name: String, foods: List[Food])

    private var categories = List(
        FoodCategory("fruits", List(Apple, Orange)),
        FoodCategory("misc", List(Cream, Sugar)))

    def allCategories = categories
}

object SimpleBrowser {
    def recipesUsing(food: Food) =
        SimpleDatabase.allRecipes.filter(recipe =>
            recipe.ingredients.contains(food))

    def displayCategory(category: SimpleDatabase.FoodCategory) = {
        println(category)
    }
}
```

Listing 29.5 · Database and browser modules with categories added.

29.3 Abstraction

Although the examples shown so far did manage to partition your application into separate database and browser modules, the design is not yet very “modular.” The problem is that there is essentially a “hard link” from the browser module to the database modules:

```
SimpleDatabase.allRecipes.filter(recipe => ...
```

Because the `SimpleBrowser` module mentions the `SimpleDatabase` module by name, you won’t be able to plug in a different implementation of the database module without modifying and recompiling the browser module. In addition, although there’s no hard link from the `SimpleDatabase` module

```
abstract class Browser {  
    val database: Database  
  
    def recipesUsing(food: Food) =  
        database.allRecipes.filter(recipe =>  
            recipe.ingredients.contains(food))  
  
    def displayCategory(category: database.FoodCategory) = {  
        println(category)  
    }  
}
```

Listing 29.6 · A Browser class with an abstract database val.

to the `SimpleBrowser` module,⁵ there's no clear way to enable the user interface layer, for example, to be configured to use different implementations of the browser module.

When making these modules more pluggable, however, it is important to avoid duplicating code, because much code can likely be shared by different implementations of the same module. For example, suppose you want the same code base to support multiple recipe databases, and you want to be able to create a separate browser for each of these databases. You would like to reuse the browser code for each of the instances, because the only thing different about the browsers is which database they refer to. Except for the database implementation, the rest of the code can be reused character for character. How can the program be arranged to minimize repetitive code? How can the code be made reconfigurable, so that you can configure it using either database implementation?

The answer is a familiar one: If a module is an object, then a template for a module is a class. Just like a class describes the common parts of all its instances, a class can describe the parts of a module that are common to all of its possible configurations.

The browser definition therefore becomes a class, instead of an object, and the database to use is specified as an abstract member of the class, as shown in Listing 29.6. The database also becomes a class, including as much as possible that is common between all databases, and declaring the missing

⁵This is good, because each of these architectural layers should depend only on layers below them.

parts that a database must define. In this case, all database modules must define methods for `allFoods`, `allRecipes`, and `allCategories`, but since they can use an arbitrary definition, the methods must be left abstract in the `Database` class. The `foodNamed` method, by contrast, can be defined in the abstract `Database` class, as shown in Listing 29.7.

```
abstract class Database {  
    def allFoods: List[Food]  
    def allRecipes: List[Recipe]  
  
    def foodNamed(name: String) =  
        allFoods.find(f => f.name == name)  
  
    case class FoodCategory(name: String, foods: List[Food])  
    def allCategories: List[FoodCategory]  
}
```

Listing 29.7 · A `Database` class with abstract methods.

The `SimpleDatabase` object must be updated to inherit from the abstract `Database` class, as shown in Listing 29.8.

```
object SimpleDatabase extends Database {  
    def allFoods = List(Apple, Orange, Cream, Sugar)  
    def allRecipes: List[Recipe] = List(FruitSalad)  
  
    private var categories = List(  
        FoodCategory("fruits", List(Apple, Orange)),  
        FoodCategory("misc", List(Cream, Sugar)))  
  
    def allCategories = categories  
}
```

Listing 29.8 · The `SimpleDatabase` object as a `Database` subclass.

Then, a specific browser module is made by instantiating the `Browser` class and specifying which database to use, as shown in Listing 29.9.

You can use these more pluggable modules the same as before:

```
scala> val apple = SimpleDatabase.foodNamed("Apple").get  
apple: Food = Apple
```

```
object SimpleBrowser extends Browser {  
    val database = SimpleDatabase  
}
```

Listing 29.9 · The SimpleBrowser object as a Browser subclass.

```
scala> SimpleBrowser.recipesUsing(apple)  
res1: List[Recipe] = List(fruit salad)
```

Now, however, you can create a second mock database, and use the same browser class with it, as shown in Listing 29.10:

```
object StudentDatabase extends Database {  
    object FrozenFood extends Food("FrozenFood")  
  
    object HeatItUp extends Recipe(  
        "heat it up",  
        List(FrozenFood),  
        "Microwave the 'food' for 10 minutes.")  
  
    def allFoods = List(FrozenFood)  
    def allRecipes = List(HeatItUp)  
    def allCategories = List(  
        FoodCategory("edible", List(FrozenFood)))  
}  
  
object StudentBrowser extends Browser {  
    val database = StudentDatabase  
}
```

Listing 29.10 · A student database and browser.

29.4 Splitting modules into traits

Often a module is too large to fit comfortably into a single file. When that happens, you can use traits to split a module into separate files. For example, suppose you wanted to move categorization code out of the main Database file and into its own. You could create a trait for the code as shown in (Listing 29.11).

```
trait FoodCategories {  
    case class FoodCategory(name: String, foods: List[Food])  
    def allCategories: List[FoodCategory]  
}
```

Listing 29.11 · A trait for food categories.

Now class Database can mix in the FoodCategories trait instead of defining FoodCategory and allCategories itself, as shown in Listing 29.12:

```
abstract class Database extends FoodCategories {  
    def allFoods: List[Food]  
    def allRecipes: List[Recipe]  
    def foodNamed(name: String) =  
        allFoods.find(f => f.name == name)  
}
```

Listing 29.12 · A Database class that mixes in the FoodCategories trait.

You might try and divide SimpleDatabase into two traits, one for foods and one for recipes. This would allow you to define SimpleDatabase as shown in Listing 29.13:

```
object SimpleDatabase extends Database  
    with SimpleFoods with SimpleRecipes
```

Listing 29.13 · A SimpleDatabase object composed solely of mixins.

The SimpleFoods trait could look as shown in Listing 29.14:

```
trait SimpleFoods {  
    object Pear extends Food("Pear")  
    def allFoods = List(Apple, Pear)  
    def allCategories = Nil  
}
```

Listing 29.14 · A SimpleFoods trait.

So far so good, but unfortunately, a problem arises if you try to define a `SimpleRecipes` trait like this:

```
trait SimpleRecipes { // Does not compile
    object FruitSalad extends Recipe(
        "fruit salad",
        List(Apple, Pear), // Uh oh
        "Mix it all together."
    )
    def allRecipes = List(FruitSalad)
}
```

The problem is that `Pear` is located in a different trait from the one that uses it, so it is out of scope. The compiler has no idea that `SimpleRecipes` is only ever mixed together with `SimpleFoods`.

However, there is a way you can tell this to the compiler. Scala provides the *self type* for precisely this situation. Technically, a self type is an assumed type for this whenever this is mentioned within the class. Pragmatically, a self type specifies the requirements on any concrete class the trait is mixed into. If you have a trait that is only ever used when mixed in with another trait or traits, then you can specify that those other traits should be assumed. In the present case, it is enough to specify a self type of `SimpleFoods`, as shown in Listing 29.15:

```
trait SimpleRecipes {
    this: SimpleFoods =>
    object FruitSalad extends Recipe(
        "fruit salad",
        List(Apple, Pear), // Now Pear is in scope
        "Mix it all together."
    )
    def allRecipes = List(FruitSalad)
}
```

Listing 29.15 · A `SimpleRecipes` trait with a self type.

Given the new self type, `Pear` is now available. Implicitly, the reference to `Pear` is thought of as `this.Pear`. This is safe, because any *concrete*

class that mixes in `SimpleRecipes` must also be a subtype of `SimpleFoods`, which means that `Pear` will be a member. Abstract subclasses and traits do not have to follow this restriction, but since they cannot be instantiated with `new`, there is no risk that the `this.Pear` reference will fail.

29.5 Runtime linking

Scala modules can be linked together at runtime, and you can decide which modules will link to which depending on runtime computations. For example, Listing 29.16 shows a small program that chooses a database at runtime and then prints out all the apple recipes in it:

```
object GotApples {
  def main(args: Array[String]) = {
    val db: Database =
      if(args(0) == "student")
        StudentDatabase
      else
        SimpleDatabase

    object browser extends Browser {
      val database = db
    }

    val apple = SimpleDatabase.foodNamed("Apple").get
    for(recipe <- browser.recipesUsing(apple))
      println(recipe)
  }
}
```

Listing 29.16 · An app that dynamically selects a module implementation.

Now, if you use the simple database, you will find a recipe for fruit salad. If you use the student database, you will find no recipes at all using apples:

```
$ scala GotApples simple
fruit salad
$ scala GotApples student
$
```

Configuring with Scala code

You may wonder if you are not backsliding to the hard links problem of the original examples in this chapter, because the `GotApples` object shown in Listing 29.16 contains hard links to both `StudentDatabase` and `SimpleDatabase`. The difference here is that the hard links are localized in one file that can be replaced.

Every modular application needs some way to specify the actual module implementations to use in a particular situation. This act of “configuring” the application will by definition involve the naming of concrete module implementations. For example, in a Spring application, you configure by naming implementations in an external XML file. In Scala, you can configure via Scala code itself. One advantage to using Scala source over XML for configuration is that the process of running your configuration file through the Scala compiler should uncover any misspellings in it prior to its actual use.

29.6 Tracking module instances

Despite using the same code, the different browser and database modules created in the previous section really are separate modules. This means that each module has its own contents, including any nested classes. `FoodCategory` in `SimpleDatabase`, for example, is a different class from `FoodCategory` in `StudentDatabase`!

```
scala> val category = StudentDatabase.allCategories.head
category: StudentDatabase.FoodCategory =
FoodCategory(edible,List(FrozenFood))

scala> SimpleBrowser.displayCategory(category)
<console>:21: error: type mismatch;
 found   : StudentDatabase.FoodCategory
 required: SimpleBrowser.database.FoodCategory
                           SimpleBrowser.displayCategory(category)
                                         ^
```

If instead you prefer all `FoodCategory`s to be the same, you can accomplish this by moving the definition of `FoodCategory` outside of any class or trait.

The choice is yours, but as it is written, each `Database` gets its own, unique `FoodCategory` class.

Since the two `FoodCategory` classes shown in this example really are different, the compiler is correct to complain. Sometimes, though, you may encounter a case where two types are the same but the compiler can't verify it. You will see the compiler complaining that two types are not the same, even though you as the programmer know they are.

In such cases you can often fix the problem using *singleton types*. For example, in the `GotApples` program, the type checker does not know that `db` and `browser.database` are the same. This will cause type errors if you try to pass categories between the two objects:

```
object GotApples {
    // same definitions...

    for (category <- db.allCategories)
        browser.displayCategory(category)

    // ...
}

GotApples2.scala:14: error: type mismatch;
 found   : db.FoodCategory
 required: browser.database.FoodCategory
         browser.displayCategory(category)
                                ^
one error found
```

To avoid this error, you need to inform the type checker that they are the same object. You can do this by changing the definition of `browser.database` as shown in Listing 29.17:

```
object browser extends Browser {
    val database: db.type = db
}
```

Listing 29.17 · Using a singleton type.

This definition is the same as before except that `database` has the funny-looking type `db.type`. The “`.type`” on the end means that this is a *singleton type*. A singleton type is extremely specific and holds only one object; in this case, whichever object is referred to by `db`. Usually such types are too specific to be useful, which is why the compiler is reluctant to insert them automatically. In this case, though, the singleton type allows the compiler to know that `db` and `browser.database` are the same object—enough information to eliminate the type error.

29.7 Conclusion

This chapter has shown how to use Scala’s objects as modules. In addition to simple static modules, this approach gives you a variety of ways to create abstract, reconfigurable modules. There are actually even more abstraction techniques than shown, since anything that works on a class also works on a class used to implement a module. As always, how much of this power you use should be a matter of taste.

Modules are part of programming in the large, and thus are hard to experiment with. You need a large program before it really makes a difference. Nonetheless, after reading this chapter you know which Scala features to think about when you want to program in a modular style. Think about these techniques when you write your own large programs and recognize these coding patterns when you see them in other people’s code.

Chapter 30

Object Equality

Comparing two values for equality is ubiquitous in programming. It is also more tricky than it looks at first glance. This chapter looks at object equality in detail and gives some recommendations to consider when you design your own equality tests.

30.1 Equality in Scala

As mentioned in [Section 11.2](#), the definition of equality is different in Scala and Java. Java has two equality comparisons: the `==` operator, which is the natural equality for value types and object identity for reference types, and the `equals` method, which is (user-defined) canonical equality for reference types. This convention is problematic because the more natural symbol, `==`, does not always correspond to the natural notion of equality. When programming in Java, a common pitfall for beginners is to compare objects with `==` when they should be compared with `equals`. For instance, comparing two strings `x` and `y` using “`x == y`” might yield `false` in Java, even if `x` and `y` have exactly the same characters in the same order.

Scala also has an equality method signifying object identity, but it is not used much. That kind of equality, written “`x eq y`”, is true if `x` and `y` reference the same object. The `==` equality is reserved in Scala for the “natural” equality of each type. For value types, `==` is value comparison, just like in Java. For reference types, `==` is the same as `equals` in Scala. You can redefine the behavior of `==` for new types by overriding the `equals` method, which is always inherited from class `Any`. The inherited `equals`, which takes effect unless overridden, is object identity, as is the case in Java. So `equals`

(and with it, `==`) is by default the same as `eq`, but you can change its behavior by overriding the `equals` method in the classes you define. It is not possible to override `==` directly, as it is defined as a final method in class `Any`. That is, Scala treats `==` as if it were defined as follows in class `Any`:

```
final def == (that: Any): Boolean =  
  if (null eq this) {null eq that} else {this equals that}
```

30.2 Writing an equality method

How should the `equals` method be defined? It turns out that writing a correct equality method is surprisingly difficult in object-oriented languages. In fact, after studying a large body of Java code, the authors of a 2007 paper concluded that almost all implementations of `equals` methods are faulty.¹ This is problematic because equality is at the basis of many other things. For one, a faulty equality method for a type `C` might mean that you cannot reliably put an object of type `C` in a collection.

For example, you might have two elements, `elem1` and `elem2`, of type `C` which are equal (*i.e.*, “`elem1 equals elem2`” yields `true`). Nevertheless, with commonly occurring faulty implementations of the `equals` method, you could still see behavior like the following:

```
var hashSet: Set[C] = new collection.immutable.HashSet  
hashSet += elem1  
hashSet contains elem2    // returns false!
```

Here are four common pitfalls² that can cause inconsistent behavior when overriding `equals`:

1. Defining `equals` with the wrong signature.
2. Changing `equals` without also changing `hashCode`.
3. Defining `equals` in terms of mutable fields.
4. Failing to define `equals` as an equivalence relation.

These four pitfalls are discussed in the remainder of this section.

¹Vaziri, et al., “Declarative Object Identity Using Relation Types” [Vaz07]

²All but the third pitfall are described in the context of Java in the book, *Effective Java Second Edition*, by Joshua Bloch. [Blo08]

Pitfall #1: Defining equals with the wrong signature

Consider adding an equality method to the following class of simple points:

```
class Point(val x: Int, val y: Int) { ... }
```

A seemingly obvious but wrong way would be to define it like this:

```
// An utterly wrong definition of equals
def equals(other: Point): Boolean =
    this.x == other.x && this.y == other.y
```

What's wrong with this method? At first glance, it seems to work OK:

```
scala> val p1, p2 = new Point(1, 2)
p1: Point = Point@37d7d90f
p2: Point = Point@3beb846d

scala> val q = new Point(2, 3)
q: Point = Point@e0cf182

scala> p1 equals p2
res0: Boolean = true

scala> p1 equals q
res1: Boolean = false
```

However, trouble starts once you start putting points into a collection:

```
scala> import scala.collection.mutable
import scala.collection.mutable

scala> val coll = mutable.HashSet(p1)
coll: scala.collection.mutable.HashSet[Point] =
Set(Point@37d7d90f)

scala> coll contains p2
res2: Boolean = false
```

How to explain that `coll` does not contain `p2`, even though `p1` was added to it, and `p1` and `p2` are equal objects? The reason becomes clear in the following interaction, where the precise type of one of the compared points is masked. Define `p2a` as an alias of `p2`, but with type `Any` instead of `Point`:

```
scala> val p2a: Any = p2
p2a: Any = Point@3beb846d
```

Now, were you to repeat the first comparison, but with the alias p2a instead of p2, you would get:

```
scala> p1 equals p2a
res3: Boolean = false
```

What went wrong? The version of `equals` given previously does not override the standard method `equals` because its type is different. Here is the type of the `equals` method as it is defined in the root class `Any`:³

```
def equals(other: Any): Boolean
```

Because the `equals` method in `Point` takes a `Point` instead of an `Any` as an argument, it does not override `equals` in `Any`. Instead, it is just an overloaded alternative. Now, overloading in Scala and in Java is resolved by the static type of the argument, not the run-time type. So as long as the static type of the argument is `Point`, the `equals` method in `Point` is called. However, once the static argument is of type `Any`, the `equals` method in `Any` is called instead. This method has not been overridden, so it is still implemented by comparing object identity.

That's why the comparison “`p1 equals p2a`” yields `false` even though points `p1` and `p2a` have the same `x` and `y` values. That's also why the `contains` method in `HashSet` returned `false`. Since that method operates on generic sets, it calls the generic `equals` method in `Object` instead of the overloaded variant in `Point`. Here's a better `equals` method:

```
// A better definition, but still not perfect
override def equals(other: Any) = other match {
    case that: Point => this.x == that.x && this.y == that.y
    case _ => false
}
```

Now `equals` has the correct type. It takes a value of type `Any` as parameter and it yields a `Boolean` result. The implementation of this method uses a

³If you write a lot of Java, you might expect the argument to this method to be type `Object` instead of type `Any`. Don't worry about it; it is the same `equals` method. The compiler simply makes it appear to have type `Any`.

pattern match. It first tests whether the other object is also of type Point. If it is, it compares the coordinates of the two points and returns the result. Otherwise the result is false.

A related pitfall is to define == with a wrong signature. Normally, if you try to redefine == with the correct signature, which takes an argument of type Any, the compiler will give you an error because you try to override a final method of type Any.

Newcomers to Scala sometimes make two errors at once: They try to override == *and* they give it the wrong signature. For instance:

```
def ==(other: Point): Boolean = // Don't do this!
```

In this case, the user-defined == method is treated as an overloaded variant of the same-named method class Any and the program compiles. However, the behavior of the program would be just as dubious as if you had defined equals with the wrong signature.

Pitfall #2: Changing equals without also changing hashCode

We'll continue to use the example from pitfall #1. If you repeat the comparison of p1 and p2a with the latest definition of Point, you will get true, as expected. However, if you repeat the HashSet.contains test, you will probably still get false:

```
scala> val p1, p2 = new Point(1, 2)
p1: Point = Point@122c1533
p2: Point = Point@c23d097
scala> collection.mutable.HashSet(p1) contains p2
res4: Boolean = false
```

But this outcome is not 100% certain. You might also get true from the experiment. If you do, you can try with some other points with coordinates 1 and 2. Eventually, you'll get one that is not contained in the set. What goes wrong here is that Point redefined equals without also redefining hashCode.

Note that the collection in the example here is a HashSet. This means elements of the collection are put in “hash buckets” determined by their hash code. The contains test first determines a hash bucket to look in and then compares the given elements with all elements in that bucket. Now, the last

version of class `Point` did redefine `equals`, but it did not redefine `hashCode` at the same time. So `hashCode` is still what it was in its version in class `AnyRef`: some transformation of the address of the allocated object.

The hash codes of `p1` and `p2` are almost certainly different, even though the fields of both points are the same. Different hash codes mean, with high probability, different hash buckets in the set. The `contains` test will look for a matching element in the bucket which corresponds to `p2`'s hash code. In most cases, point `p1` will be in another bucket, so it will never be found. `p1` and `p2` might also end up by chance in the same hash bucket. In that case the test would return `true`. The problem is that the last implementation of `Point` violated the contract on `hashCode` as defined for class `Any`:⁴

If two objects are equal according to the `equals` method, then calling the `hashCode` method on each of the two objects must produce the same integer result.

In fact, it's well known in Java that `hashCode` and `equals` should always be redefined together. Furthermore, `hashCode` may only depend on fields that `equals` depends on. For the `Point` class, the following would be a suitable definition of `hashCode`:

```
class Point(val x: Int, val y: Int) {  
    override def hashCode = (x, y).##  
    override def equals(other: Any) = other match {  
        case that: Point => this.x == that.x && this.y == that.y  
        case _ => false  
    }  
}
```

This is just one of many possible implementations of `hashCode`. Recall that the `##` method is a shorthand for computing hash codes that works for primitive values, reference types, and `null`. When invoked on a collection or a tuple, it computes a mixed hash that is sensitive to the hash codes of all the elements in the collection. We'll provide more guidance on writing `hashCode` later in this chapter.

Adding `hashCode` fixes the problems of equality when defining classes like `Point`; however, there are other trouble spots to watch out for.

⁴The text of `Any`'s `hashCode` contract is inspired by the Javadoc documentation of class `java.lang.Object`.

Pitfall #3: Defining equals in terms of mutable fields

Consider the following slight variation of class Point:

```
class Point(var x: Int, var y: Int) { // Problematic
    override def hashCode = (x, y).##
    override def equals(other: Any) = other match {
        case that: Point => this.x == that.x && this.y == that.y
        case _ => false
    }
}
```

The only difference is that the fields x and y are now vars instead of vals. The equals and hashCode methods are now defined in terms of these mutable fields, so their results change when the fields change. This can have strange effects once you put points in collections:

```
scala> val p = new Point(1, 2)
p: Point@5428bd62
scala> val coll = collection.mutable.HashSet(p)
coll: scala.collection.mutable.HashSet[Point] =
Set(Point@5428bd62)
scala> coll contains p
res5: Boolean = true
```

Now, if you change a field in point p, does the collection still contain the point? We'll try it:

```
scala> p.x += 1
scala> coll contains p
res7: Boolean = false
```

This looks strange. Where did p go? More strangeness results if you check whether the iterator of the set contains p:

```
scala> coll.iterator contains p
res8: Boolean = true
```

So here's a set that does not contain p, yet p is among the elements of the set! What happened is that after the change to the x field, the point p ended

up in the wrong hash bucket of the set `coll`. That is, its original hash bucket no longer corresponded to the new value of its hash code. In a manner of speaking, point `p` “dropped out of sight” in the set `coll` even though it still belonged to its elements.

The lesson to be drawn from this example is that when `equals` and `hashCode` depend on mutable state, it causes problems for potential users. If you put such objects into collections, you have to be careful to never modify the depended-on state, and this is tricky. If you need a comparison that takes the current state of an object into account, you should usually name it something else, not `equals`.

Considering the last definition of `Point`, it would have been preferable to omit a redefinition of `hashCode` and name the comparison method `equalContents` or some other name different from `equals`. `Point` would then have inherited the default implementation of `equals` and `hashCode`; `p` would have stayed locatable in `coll` even after the modification to its `x` field.

Pitfall #4: Failing to define `equals` as an equivalence relation

The contract of the `equals` method in `scala.Any` specifies that `equals` must implement an equivalence relation on non-null objects:⁵

- *It is reflexive: For any non-null value `x`, the expression `x.equals(x)` should return true.*
- *It is symmetric: For any non-null values `x` and `y`, `x.equals(y)` should return true if and only if `y.equals(x)` returns true.*
- *It is transitive: For any non-null values `x`, `y`, and `z`, if `x.equals(y)` returns true and `y.equals(z)` returns true, then `x.equals(z)` should return true.*
- *It is consistent: For any non-null values `x` and `y`, multiple invocations of `x.equals(y)` should consistently return true or consistently return false, provided no information used in `equals` comparisons on the objects is modified.*
- *For any non-null value `x`, `x.equals(null)` should return false.*

⁵As with `hashCode`, `Any`'s `equals` method contract is based on `java.lang.Object`'s `equals` method contract.

The definition of equals developed for class Point up to now satisfies the contract for equals. However, things become more complicated once subclasses are considered. Say there is a subclass ColoredPoint of Point that adds a field color of type Color. Assume Color is defined as an enumeration, as presented in Section 20.9:

```
object Color extends Enumeration {
    val Red, Orange, Yellow, Green, Blue, Indigo, Violet = Value
}
```

ColoredPoint overrides equals to take the new color field into account:

```
class ColoredPoint(x: Int, y: Int, val color: Color.Value)
    extends Point(x, y) { // Problem: equals not symmetric

    override def equals(other: Any) = other match {
        case that: ColoredPoint =>
            this.color == that.color && super.equals(that)
        case _ => false
    }
}
```

This is what many programmers would likely write. Note that in this case, class ColoredPoint need not override hashCode. Because the new definition of equals on ColoredPoint is stricter than the overridden definition in Point (meaning it equates fewer pairs of objects), the contract for hashCode stays valid. If two colored points are equal, they must have the same coordinates, so their hash codes are guaranteed to be equal as well.

Taking the class ColoredPoint by itself, its definition of equals looks OK. However, the contract for equals is broken once points and colored points are mixed. Consider:

```
scala> val p = new Point(1, 2)
p: Point = Point@5428bd62

scala> val cp = new ColoredPoint(1, 2, Color.Red)
cp: ColoredPoint = ColoredPoint@5428bd62

scala> p equals cp
res9: Boolean = true

scala> cp equals p
res10: Boolean = false
```

The comparison “`p equals cp`” invokes `p`’s `equals` method, which is defined in class `Point`. This method only takes into account the coordinates of the two points. Consequently, the comparison yields `true`. On the other hand, the comparison “`cp equals p`” invokes `cp`’s `equals` method, which is defined in class `ColoredPoint`. This method returns `false` because `p` is not a `ColoredPoint`. So the relation defined by `equals` is not symmetric.

The loss in symmetry can have unexpected consequences for collections. Here’s an example:

```
scala> collection.mutable.HashSet[Point](p) contains cp
res11: Boolean = true

scala> collection.mutable.HashSet[Point](cp) contains p
res12: Boolean = false
```

Even though `p` and `cp` are equal, one `contains` test succeeds whereas the other one fails:

How can you change the definition of `equals` so that it becomes symmetric? Essentially there are two ways. You can either make the relation more general or more strict. Making it more general means that a pair of two objects, `x` and `y`, is taken to be equal if either comparing `x` with `y` or comparing `y` with `x` yields `true`. Here’s code that does this:

```
class ColoredPoint(x: Int, y: Int, val color: Color.Value)
    extends Point(x, y) { // Problem: equals not transitive

    override def equals(other: Any) = other match {
        case that: ColoredPoint =>
            (this.color == that.color) && super.equals(that)
        case that: Point =>
            that equals this
        case _ =>
            false
    }
}
```

The new definition of `equals` in `ColoredPoint` has one more case than the old one: If the other object is a `Point` but not a `ColoredPoint`, the method forwards to the `equals` method of `Point`. This has the desired effect of making `equals` symmetric. Now, both “`cp equals p`” and “`p equals cp`”

result in true. However, the contract for equals is still broken. The problem is that the new relation is no longer transitive!

Here's a sequence of statements that demonstrates this. Define a point and two colored points of different colors, all at the same position:

```
scala> val redp = new ColoredPoint(1, 2, Color.Red)
redp: ColoredPoint = ColoredPoint@5428bd62
scala> val bluep = new ColoredPoint(1, 2, Color.Blue)
bluep: ColoredPoint = ColoredPoint@5428bd62
```

Taken individually, redp is equal to p and p is equal to bluep:

```
scala> redp == p
res13: Boolean = true
scala> p == bluep
res14: Boolean = true
```

However, comparing redp and bluep yields false:

```
scala> redp == bluep
res15: Boolean = false
```

Hence, the transitivity clause of the equals's contract is violated.

Making the equals relation more general seems to lead to a dead end. We'll try to make it stricter instead. One way to make equals stricter is to always treat objects of different classes as different. This could be achieved by modifying the equals methods in classes Point and ColoredPoint. In class Point, you could add an extra comparison that checks whether the run-time class of the other Point is exactly the same as this Point's class:

```
// A technically valid, but unsatisfying, equals method
class Point(val x: Int, val y: Int) {
    override def hashCode = (x, y).##
    override def equals(other: Any) = other match {
        case that: Point =>
            this.x == that.x && this.y == that.y &&
            this.getClass == that.getClass
        case _ => false
    }
}
```

You can then revert class `ColoredPoint`'s implementation back to the version that previously had violated the symmetry requirement:⁶

```
class ColoredPoint(x: Int, y: Int, val color: Color.Value)
  extends Point(x, y) {

  override def equals(other: Any) = other match {
    case that: ColoredPoint =>
      (this.color == that.color) && super.equals(that)
    case _ => false
  }
}
```

Here, an instance of class `Point` is considered to be equal to some other instance of the same class, only if the objects have the same coordinates and they have the same run-time class, meaning `getClass` on either object returns the same value. The new definitions satisfy symmetry and transitivity because now every comparison between objects of different classes yields `false`. So a colored point can never be equal to a point. This convention looks reasonable, but one could argue that the new definition is too strict.

Consider the following slightly roundabout way to define a point at coordinates (1, 2):

```
scala> val pAnon = new Point(1, 1) { override val y = 2 }
pAnon: Point = $anon$1@5428bd62
```

Is `pAnon` equal to `p`? The answer is no because the `java.lang.Class` objects associated with `p` and `pAnon` are different. For `p` it is `Point`, whereas for `pAnon` it is an anonymous subclass of `Point`. But clearly, `pAnon` is just another point at coordinates (1, 2). It does not seem reasonable to treat it as being different from `p`.

So it seems we are stuck. Is there a sane way to redefine equality on several levels of the class hierarchy while keeping its contract? In fact, there is such a way, but it requires one more method to redefine together with `equals` and `hashCode`. The idea is that as soon as a class redefines `equals` (and `hashCode`), it should also explicitly state that objects of this class are never equal to objects of some superclass that implement a different equality

⁶Given the new implementation of `equals` in `Point`, this version of `ColoredPoint` no longer violates the symmetry requirement.

method. This is achieved by adding a method `canEqual` to every class that redefines `equals`. Here's the method's signature:

```
def canEqual(other: Any): Boolean
```

The method should return `true` if the other object is an instance of the class in which `canEqual` is (re)defined, `false` otherwise. It is called from `equals` to make sure that the objects are comparable both ways. Listing 30.1 shows a new (and final) implementation of class `Point` along these lines:

```
class Point(val x: Int, val y: Int) {  
    override def hashCode = (x, y).##  
    override def equals(other: Any) = other match {  
        case that: Point =>  
            (that canEqual this) &&  
            (this.x == that.x) && (this.y == that.y)  
        case _ =>  
            false  
    }  
    def canEqual(other: Any) = other.isInstanceOf[Point]  
}
```

Listing 30.1 · A superclass `equals` method that calls `canEqual`.

The `equals` method in this version of class `Point` contains the additional requirement that the other object *can equal* this one, as determined by the `canEqual` method. The implementation of `canEqual` in `Point` states that all instances of `Point` can be equal.

Listing 30.2 shows the corresponding implementation of `ColoredPoint`. It can be shown that the new definition of `Point` and `ColoredPoint` keeps the contract of `equals`. Equality is symmetric and transitive. Comparing a `Point` to a `ColoredPoint` always yields `false`. Indeed, for any point `p` and colored point `cp`, “`p equals cp`” will return `false` because “`cp canEqual p`” will return `false`. The reverse comparison, “`cp equals p`”, will also return `false` because `p` is not a `ColoredPoint`, so the first pattern match in the body of `equals` in `ColoredPoint` will fail.

On the other hand, instances of different subclasses of `Point` can be equal, as long as none of the classes redefines the equality method. For in-

```
class ColoredPoint(x: Int, y: Int, val color: Color.Value)
    extends Point(x, y) {

    override def hashCode = (super.hashCode, color).##
    override def equals(other: Any) = other match {
        case that: ColoredPoint =>
            (that canEqual this) &&
            super.equals(that) && this.color == that.color
        case _ =>
            false
    }
    override def canEqual(other: Any) =
        other.isInstanceOf[ColoredPoint]
}
```

Listing 30.2 · A subclass `equals` method that calls `canEqual`.

stance, with the new class definitions, the comparison of `p` and `pAnon` would yield true. Here are some examples:

```
scala> val p = new Point(1, 2)
p: Point = Point@5428bd62

scala> val cp = new ColoredPoint(1, 2, Color.Indigo)
cp: ColoredPoint = ColoredPoint@e6230d8f

scala> val pAnon = new Point(1, 1) { override val y = 2 }
pAnon: Point = $anon$1@5428bd62

scala> val coll = List(p)
coll: List[Point] = List(Point@5428bd62)

scala> coll contains p
res16: Boolean = true

scala> coll contains cp
res17: Boolean = false

scala> coll contains pAnon
res18: Boolean = true
```

These examples demonstrate that if a superclass `equals` implementation defines and calls `canEqual`, then programmers who implement subclasses can

decide whether or not their subclasses may be equal to instances of the superclass. Because `ColoredPoint` overrides `canEqual`, for example, a colored point may never be equal to a plain-old point. But because the anonymous subclass referenced from `pAnon` does not override `canEqual`, its instance can be equal to a `Point` instance.

One potential criticism of the `canEqual` approach is that it violates the Liskov Substitution Principle. For example, the technique of implementing `equals` by comparing run-time classes, which led to the inability to define a subclass whose instances can equal instances of the superclass, has been described as a violation of the LSP.⁷ The LSP states you should be able to use (substitute) a subclass instance where a superclass instance is required.

In the previous example, however, “`coll contains cp`” returned `false` even though `cp`’s `x` and `y` values matched those of the point in the collection. Thus, it may seem like a violation of the LSP because you can’t use a `ColoredPoint` here where a `Point` is expected. We believe this is the wrong interpretation, because the LSP doesn’t require that a subclass behaves identically to its superclass, just that it behaves in a way that fulfills the contract of its superclass.

The problem with writing an `equals` method that compares run-time classes is not that it violates the LSP, but that it doesn’t give you a way to create a subclass whose instances can equal superclass instances. For example, had we used the run-time class technique in the previous example, “`coll contains pAnon`” would have returned `false`, and that’s not what we wanted. By contrast, we really did want “`coll contains cp`” to return `false`, because by overriding `equals` in `ColoredPoint`, we were basically saying that an indigo-colored point at coordinates $(1, 2)$ is *not the same thing* as an uncolored point at $(1, 2)$. Thus, in the previous example we were able to pass two different `Point` subclass instances to the collection’s `contains` method, and we got back two different answers, both correct.

30.3 Defining equality for parameterized types

The `equals` methods in the previous examples all started with a pattern match that tested whether the type of the operand conformed to the type of the class containing the `equals` method. When classes are parameterized, this scheme needs to be adapted a little bit.

⁷Bloch, *Effective Java Second Edition*, p. 39 [Blo08]

As an example, consider binary trees. The class hierarchy shown in Listing 30.3 defines an abstract class `Tree` for a binary tree, with two alternative implementations: an `EmptyTree` object and a `Branch` class representing non-empty trees. A non-empty tree is made up of some element `elem`, and a `left` and `right` child tree. The type of its element is given by a type parameter `T`.

```
trait Tree[+T] {
    def elem: T
    def left: Tree[T]
    def right: Tree[T]
}

object EmptyTree extends Tree[Nothing] {
    def elem =
        throw new NoSuchElementException("EmptyTree.elem")
    def left =
        throw new NoSuchElementException("EmptyTree.left")
    def right =
        throw new NoSuchElementException("EmptyTree.right")
}

class Branch[+T](
    val elem: T,
    val left: Tree[T],
    val right: Tree[T]
) extends Tree[T]
```

Listing 30.3 · Hierarchy for binary trees.

We'll now add `equals` and `hashCode` methods to these classes. For class `Tree` itself there's nothing to do because we assume that these methods are implemented separately for each implementation of the abstract class. For object `EmptyTree`, there's still nothing to do because the default implementations of `equals` and `hashCode` that `EmptyTree` inherits from `AnyRef` work just fine. After all, an `EmptyTree` is only equal to itself, so equality should be reference equality, which is what's inherited from `AnyRef`.

But adding `equals` and `hashCode` to `Branch` requires some work. A `Branch` value should only be equal to other `Branch` values, and only if the two values have equal `elem`, `left` and `right` fields. It's natural to apply

the schema for `equals` that was developed in the previous sections of this chapter. This would give you:

```
class Branch[T](  
    val elem: T,  
    val left: Tree[T],  
    val right: Tree[T]  
) extends Tree[T] {  
  
    override def equals(other: Any) = other match {  
        case that: Branch[T] => this.elem == that.elem &&  
            this.left == that.left &&  
            this.right == that.right  
        case _ => false  
    }  
}
```

Compiling this example, however, gives an indication that “unchecked” warnings occurred. Compiling again with the `-unchecked` option reveals the following problem:

```
$ fsc -unchecked Tree.scala  
Tree.scala:14: warning: non variable type-argument T in type  
pattern is unchecked since it is eliminated by erasure  
    case that: Branch[T] => this.elem == that.elem &&  
                           ^
```

As the warning says, there is a pattern match against a `Branch[T]` type, yet the system can only check that the `other` reference is (some kind of) `Branch`; it cannot check that the element type of the tree is `T`. You encountered in [Chapter 19](#) the reason for this: Element types of parameterized types are eliminated by the compiler’s erasure phase; they are not available to be inspected at run-time.

So what can you do? Fortunately, it turns out that you need not necessarily check that two `Branches` have the same element types when comparing them. It’s quite possible that two `Branches` with different element types are equal, as long as their fields are the same. A simple example of this would be the `Branch` that consists of a single `Nil` element and two empty subtrees. It’s plausible to consider any two such `Branches` to be equal, no matter what static types they have:

```
scala> val b1 = new Branch[List[String]](Nil,
    EmptyTree, EmptyTree)
b1: Branch[List[String]] = Branch@9d5fa4f
scala> val b2 = new Branch[List[Int]](Nil,
    EmptyTree, EmptyTree)
b2: Branch[List[Int]] = Branch@56cdfc29
scala> b1 == b2
res19: Boolean = true
```

The positive result of the comparison above was obtained with the implementation of `equals` on `Branch` shown previously. This demonstrates that the element type of the `Branch` was not checked—if it had been checked, the result would have been `false`.

We can disagree on which of the two possible outcomes of the comparison would be more natural. In the end, this depends on the mental model of how classes are represented. In a model where type-parameters are present only at compile-time, it's natural to consider the two `Branch` values `b1` and `b2` to be equal. In an alternative model where a type parameter forms part of an object's value, it's equally natural to consider them different. Since Scala adopts the type erasure model, type parameters are not preserved at run time, so that `b1` and `b2` are naturally considered to be equal.

There's only a tiny change needed to formulate an `equals` method that does not produce an unchecked warning. Instead of an element type `T`, use a lower case letter, such as `t`:

```
case that: Branch[t] => this.elem == that.elem &&
    this.left == that.left &&
    this.right == that.right
```

Recall from [Section 15.2](#) that a type parameter in a pattern starting with a lower-case letter represents an unknown type. Now the pattern match:

```
case that: Branch[t] =>
```

will succeed for `Branch` values of any type. The type parameter `t` represents the unknown element type of the `Branch`. It can also be replaced by an underscore, as in the following case, which is equivalent to the previous one:

```
case that: Branch[_] =>
```

The only thing that remains is to define for class `Branch` the other two methods, `hashCode` and `canEqual`, which go with `equals`. Here's a possible implementation of `hashCode`:

```
override def hashCode: Int = (elem, left, right).##
```

This is only one of many possible implementations. As shown previously, the principle is to take `hashCode` values of all fields and combine them. Here's an implementation of method `canEqual` in class `Branch`:

```
def canEqual(other: Any) = other match {
    case that: Branch[_] => true
    case _ => false
}
```

The implementation of the `canEqual` method used a typed pattern match. It would also be possible to formulate it with `isInstanceOf`:

```
def canEqual(other: Any) = other.isInstanceOf[Branch[_]]
```

If you feel like nit-picking—and we encourage you to do so!—you might wonder what the occurrence of the underscore in the type above signifies. After all, `Branch[_]` is technically a type parameter of a method, not a type pattern. So how is it possible to leave some parts of it undefined?

The answer to this question is discussed in the next chapter. `Branch[_]` is shorthand for a so-called *wildcard type*, which is, roughly speaking, a type with some unknown parts in it. So even though technically the underscore stands for two different things in a pattern match and in a type parameter of a method call, in essence, the meaning is the same: It lets you label something that is unknown. The final version of `Branch` is shown in [Listing 30.4](#).

30.4 Recipes for `equals` and `hashCode`

In this section, we'll provide step-by-step recipes for creating `equals` and `hashCode` methods that should suffice for most situations. As an illustration, we'll use the methods of class `Rational`, shown in [Listing 30.5](#).

To create this class, we removed the mathematical operator methods from the version of class `Rational` shown in [Listing 6.5](#) on page 151. We also made a minor enhancement to `toString`, and modified the initializers

```
class Branch[T](  
    val elem: T,  
    val left: Tree[T],  
    val right: Tree[T]  
) extends Tree[T] {  
  
    override def equals(other: Any) = other match {  
        case that: Branch[_] => (that canEqual this) &&  
            this.elem == that.elem &&  
            this.left == that.left &&  
            this.right == that.right  
        case _ => false  
    }  
  
    def canEqual(other: Any) = other.isInstanceOf[Branch[_]]  
  
    override def hashCode: Int = (elem, left, right).##  
}
```

Listing 30.4 · A parameterized type with `equals` and `hashCode`.

of `numer` and `denom` to normalize all fractions to have a positive denominator (*i.e.*, to transform $\frac{1}{-2}$ to $-\frac{1}{2}$).

Recipe for `equals`

Here's the recipe for overriding `equals`:

1. To override `equals` in a non-final class, create a `canEqual` method. If the inherited definition of `equals` is from `AnyRef` (that is, `equals` was not redefined higher up in the class hierarchy), the definition of `canEqual` should be new; otherwise, it will override a previous definition of a method with the same name. The only exception to this requirement is for final classes that redefine the `equals` method inherited from `AnyRef`. For them the subclass anomalies described in [Section 30.2](#) cannot arise; consequently they need not define `canEqual`. The type of object passed to `canEqual` should be `Any`:

```
def canEqual(other: Any): Boolean =
```

2. The `canEqual` method should yield `true` if the argument object is an instance of the current class (*i.e.*, the class in which `canEqual` is defined), and `false` otherwise:

```
other.isInstanceOf[Rational]
```

3. In the `equals` method, make sure you declare the type of the object passed as an `Any`:

```
override def equals(other: Any): Boolean =
```

4. Write the body of the `equals` method as a single `match` expression. The selector of the `match` should be the object passed to `equals`:

```
other match {  
    // ...  
}
```

5. The `match` expression should have two cases. The first case should declare a typed pattern for the type of the class on which you're defining the `equals` method:

```
case that: Rational =>
```

6. In the body of this case, write an expression that logical-ands together the individual expressions that must be true for the objects to be equal. If the `equals` method you are overriding is not that of `AnyRef`, you will most likely want to include an invocation of the superclass's `equals` method:

```
super.equals(that) &&
```

If you are defining `equals` for a class that first introduced `canEqual`, you should invoke `canEqual` on the argument to the equality method, passing `this` as the argument:

```
(that canEqual this) &&
```

Overriding redefinitions of `equals` should also include the `canEqual` invocation, unless they contain a call to `super.equals`. In the latter case, the `canEqual` test will already be done by the superclass call. Lastly, for each field relevant to equality, verify that the field in this object is equal to the corresponding field in the passed object:

```
numer == that.numer &&
denom == that.denom
```

7. For the second case, use a wildcard pattern that yields false:

```
case _ => false
```

If you adhere to this recipe for `equals`, equality is guaranteed to be an equivalence relation, as is required by the `equals` contract.

Recipe for `hashCode`

For `hashCode`, you can usually achieve satisfactory results if you use the following recipe, which is similar to a recipe recommended for Java classes in *Effective Java*.⁸ Include in the calculation each field in your object that is used to determine equality in the `equals` method (the “relevant” fields). Make a tuple containing the values of all those fields. Then, invoke `##` on the resulting tuple.

For example, to implement the hash code for an object that has five relevant fields named `a`, `b`, `c`, `d`, and `e`, you would write:

```
override def hashCode: Int = (a, b, c, d, e).##
```

If the `equals` method invokes `super.equals(that)` as part of its calculation, you should start your `hashCode` calculation with an invocation of `super.hashCode`. For example, had `Rational`’s `equals` method invoked `super.equals(that)`, its `hashCode` would have been:

```
override def hashCode: Int = (super.hashCode, numer, denom).##
```

⁸Bloch, *Effective Java Second Edition*. [Blo08]

```
class Rational(n: Int, d: Int) {  
    require(d != 0)  
    private val g = gcd(n.abs, d.abs)  
    val numer = (if (d < 0) -n else n) / g  
    val denom = d.abs / g  
    private def gcd(a: Int, b: Int): Int =  
        if (b == 0) a else gcd(b, a % b)  
    override def equals(other: Any): Boolean =  
        other match {  
            case that: Rational =>  
                (that canEqual this) &&  
                numer == that.numer &&  
                denom == that.denom  
            case _ => false  
        }  
    def canEqual(other: Any): Boolean =  
        other.isInstanceOf[Rational]  
    override def hashCode: Int = (numer, denom).##  
    override def toString =  
        if (denom == 1) numer.toString else numer + "/" + denom  
}
```

Listing 30.5 · Class Rational with equals and hashCode.

One thing to keep in mind as you write hashCode methods using this approach is that your hash code will only be as good as the hash codes you build out of it, namely the hash codes you obtain by calling hashCode on the relevant fields of your object. Sometimes you may need to do something extra besides just calling hashCode on the field to get a useful hash code for that field. For example, if one of your fields is a collection, you probably want a hash code for that field that is based on all the elements contained in the collection. If the field is a Vector, List, Set, Map, or tuple, you can simply include it in the list of items you are hashing over, because equals and hashCode are overridden in those classes to take into account the con-

tained elements. However the same is not true for `Arrays`, which do not take elements into account when calculating a hash code. Thus for an array, you should treat each element of the array like an individual field of your object, calling `##` on each element explicitly or passing the array to one of the `hashCode` methods in singleton object `java.util.Arrays`.

Lastly, if you find that a particular hash code calculation is harming the performance of your program, consider caching the hash code. If the object is immutable, you can calculate the hash code when the object is created and store it in a field. You can do this by simply overriding `hashCode` with a `val` instead of a `def`, like this:

```
override val hashCode: Int = (numer, denom).##
```

This approach trades off memory for computation time, because each instance of the immutable class will have one more field to hold the cached hash code value.

30.5 Conclusion

In retrospect, defining a correct implementation of `equals` has been surprisingly subtle. You must be careful about the type signature; you must override `hashCode`; you should avoid dependencies on mutable state; and you should implement and use a `canEqual` method if your class is non-final.

Given how difficult it is to implement a correct equality method, you might prefer to define your classes of comparable objects as case classes. That way, the Scala compiler will add `equals` and `hashCode` methods with the right properties automatically.

Chapter 31

Combining Scala and Java

Scala code is often used in tandem with large Java programs and frameworks. Since Scala is highly compatible with Java, most of the time you can combine the languages without worrying very much. For example, standard frameworks, such as Swing, Servlets, and JUnit, are known to work just fine with Scala. Nonetheless, from time to time, you will run into some issue combining Java and Scala.

This chapter describes two aspects of combining Java and Scala. First, it discusses how Scala is translated to Java, which is especially important if you call Scala code from Java. Second, it discusses the use of Java annotations in Scala, an important feature if you want to use Scala with an existing Java framework.

31.1 Using Scala from Java

Most of the time you can think of Scala at the source code level. However, you will have a richer understanding of how the system works if you know something about its translation. Further, if you call Scala code from Java, you will need to know what Scala code looks like from a Java point of view.

General rules

Scala is implemented as a translation to standard Java bytecodes. As much as possible, Scala features map directly onto the equivalent Java features. For example, Scala classes, methods, strings, and exceptions are all compiled to the same in Java bytecode as their Java counterparts.

To make this happen required an occasional hard choice in the design of Scala. For example, it might have been nice to resolve overloaded methods at run time, using run-time types, rather than at compile time. Such a design would break with Java's, however, making it much trickier to mesh Java and Scala. In this case, Scala stays with Java's overloading resolution, and thus Scala methods and method calls can map directly to Java methods and method calls.

Scala has its own design for other features. For example, traits have no equivalent in Java. Similarly, while both Scala and Java have generic types, the details of the two systems clash. For language features like these, Scala code cannot be mapped directly to a Java construct, so it must be encoded using some combination of the structures Java does have.

For these features that are mapped indirectly, the encoding is not fixed. There is an ongoing effort to make the translations as simple as possible so, by the time you read this, some details may be different than at the time of writing. You can find out what translation your current Scala compiler uses by examining the “.class” files with tools like `javadoc`.

Those are the general rules. Consider now some special cases.

Value types

A value type like `Int` can be translated in two different ways to Java. Whenever possible, the compiler translates a Scala `Int` to a Java `int` to get better performance. Sometimes this is not possible, though, because the compiler is not sure whether it is translating an `Int` or some other data type. For example, a particular `List[Any]` might hold only `Ints`, but the compiler has no way to be sure.

In such cases, where the compiler is unsure whether an object is a value type or not, the compiler uses objects and relies on wrapper classes. For example, wrapper classes such as `java.lang.Integer` allow a value type to be wrapped inside a Java object and thereby manipulated by code that needs objects.¹

Singleton objects

Java has no exact equivalent to a singleton object, but it does have static methods. The Scala translation of singleton objects uses a combination of

¹The implementation of value types was discussed in detail in Section 11.2.

static and instance methods. For every Scala singleton object, the compiler will create a Java class for the object with a dollar sign added to the end. For a singleton object named App, the compiler produces a Java class named App\$. This class has all the methods and fields of the Scala singleton object. The Java class also has a single static field named MODULE\$ to hold the one instance of the class that is created at run time.

As a full example, suppose you compile the following singleton object:

```
object App {  
    def main(args: Array[String]) = {  
        println("Hello, world!")  
    }  
}
```

Scala will generate a Java App\$ class with the following fields and methods:

```
$ javap App$  
public final class App$ extends java.lang.Object  
implements scala.ScalaObject{  
    public static final App$ MODULE$;  
    public static {};  
    public App$();  
    public void main(java.lang.String[]);  
    public int $tag();  
}
```

That's the translation for the general case. An important special case is if you have a “standalone” singleton object, one which does not come with a class of the same name. For example, you might have a singleton object named App, and not have any class named App. In that case, the compiler will create a Java class named App that has a static forwarder method for each method of the Scala singleton object:

```
$ javap App  
Compiled from "App.scala"  
public final class App extends java.lang.Object{  
    public static final int $tag();  
    public static final void main(java.lang.String[]);  
}
```

To contrast, if you did have a class named `App`, Scala would create a corresponding Java `App` class to hold the members of the `App` class you defined. In that case it would not add any forwarding methods for the same-named singleton object, and Java code would have to access the singleton via the `MODULE$` field.

Traits as interfaces

Compiling any trait creates a Java interface of the same name. This interface is usable as a Java type, and it lets you call methods on Scala objects through variables of that type.

Implementing a trait in Java is another story. In the general case it is not practical; however, one special case is important. If you make a Scala trait that includes only abstract methods, then that trait will be translated directly to a Java interface with no other code to worry about. Essentially this means that you can write a Java interface in Scala syntax if you like.

31.2 Annotations

Scala's general annotations system is discussed in [Chapter 27](#). This section discusses Java-specific aspects of annotations.

Additional effects from standard annotations

Several annotations cause the compiler to emit extra information when targeting the Java platform. When the compiler sees such an annotation, it first processes it according to the general Scala rules, and then it does something extra for Java.

Deprecation For any method or class marked `@deprecated`, the compiler will add Java's own deprecation annotation to the emitted code. Because of this, Java compilers can issue deprecation warnings when Java code accesses deprecated Scala methods.

Volatile fields Likewise, any field marked `@volatile` in Scala is given the Java `volatile` modifier in the emitted code. Thus, volatile fields in Scala behave exactly according to Java's semantics, and accesses to volatile fields

are sequenced precisely according to the rules specified for volatile fields in the Java memory model.

Serialization Scala's three standard serialization annotations are all translated to Java equivalents. A `@serializable` class has Java's `Serializable` interface added to it. A `@SerialVersionUID(1234L)` annotation is converted to the following Java field definition:

```
// Java serial version marker  
private final static long serialVersionUID = 1234L
```

Any variable marked `@transient` is given the Java `transient` modifier.

Exceptions thrown

Scala does not check that thrown exceptions are caught. That is, Scala has no equivalent to Java's `throws` declarations on methods. All Scala methods are translated to Java methods that declare no thrown exceptions.²

The reason this feature is omitted from Scala is that the Java experience with it has not been purely positive. Because annotating methods with `throws` clauses is a heavy burden, too many developers write code that swallows and drops exceptions, just to get the code to compile without adding all those `throws` clauses. They may intend to improve the exception handling later, but experience shows that all too often time-pressed programmers will never come back and add proper exception handling. The twisted result is that this well-intentioned feature often ends up making code *less* reliable. A large amount of production Java code swallows and hides runtime exceptions, and the reason it does so is to satisfy the compiler.

Sometimes when interfacing to Java, however, you may need to write Scala code that has Java-friendly annotations describing which exceptions your methods may throw. For example, each method in an RMI remote interface is required to mention `java.io.RemoteException` in its `throws` clause. Thus, if you wish to write an RMI remote interface as a Scala trait with abstract methods, you would need to list `RemoteException` in the `throws` clauses for those methods. To accomplish this, all you have to do is mark your methods with `@throws` annotations. For example, the Scala class shown in Listing 31.1 has a method marked as throwing `IOException`.

²The reason it all works is that the Java bytecode verifier does not check the declarations anyway! The Java compiler checks, but not the verifier.

```
import java.io._  
class Reader(fname: String) {  
    private val in =  
        new BufferedReader(new FileReader(fname))  
    @throws(classOf[IOException])  
    def read() = in.read()  
}
```

Listing 31.1 · A Scala method that declares a Java throws clause.

Here is how it looks from Java:

```
$ javap Reader  
Compiled from "Reader.scala"  
public class Reader extends java.lang.Object implements  
scala.ScalaObject{  
    public Reader(java.lang.String);  
    public int read()          throws java.io.IOException;  
    public int $tag();  
}  
$
```

Note that the `read` method indicates with a Java throws clause that it may throw an `IOException`.

Java annotations

Existing annotations from Java frameworks can be used directly in Scala code. Any Java framework will see the annotations you write just as if you were writing in Java.

A wide variety of Java packages use annotations. As an example, consider JUnit 4. JUnit is a framework for writing and running automated tests. The latest version, JUnit 4, uses annotations to indicate which parts of your code are tests. The idea is that you write a lot of tests for your code, and then you run those tests whenever you change the source code. That way, if your changes add a new bug, one of the tests will fail and you will find out immediately.

Writing a test is easy. You simply write a method in a top-level class that exercises your code, and you use an annotation to mark the method as a test. It looks like this:

```
import org.junit.Test
import org.junit.Assert.assertEquals

class SetTest {

    @Test
    def testMultiAdd = {
        val set = Set() + 1 + 2 + 3 + 1 + 2 + 3
        assertEquals(3, set.size)
    }
}
```

The `testMultiAdd` method is a test. This test adds multiple items to a set and makes sure that each is added only once. The `assertEquals` method, which comes as part of the JUnit API, checks that its two arguments are equal. If they are different, then the test fails. In this case, the test verifies that repeatedly adding the same numbers does not increase the size of a set.

The test is marked using the annotation `org.junit.Test`. Note that this annotation has been imported, so it can be referred to as simply `@Test` instead of the more cumbersome `@org.junit.Test`.

That's all there is to it. The test can be run using any JUnit test runner. Here it is being run with the command-line test runner:

```
$ scala -cp junit-4.3.1.jar:. org.junit.runner.JUnitCore SetTest
JUnit version 4.3.1
.
Time: 0.023

OK (1 test)
```

Writing your own annotations

To make an annotation that is visible to Java reflection, you must use Java notation and compile it with `javac`. For this use case, writing the annotation in Scala does not seem helpful, so the standard compiler does not support it. The reasoning is that the Scala support would inevitably fall short of the

full possibilities of Java annotations, and further, Scala will probably one day have its own reflection, in which case you would want to access Scala annotations with Scala reflection.

Here is an example annotation:

```
import java.lang.annotation.*; // This is Java
@Retention(RetentionPolicy.RUNTIME)
@Target(ElementType.METHOD)
public @interface Ignore { }
```

After compiling the above with javac, you can use the annotation as follows:

```
object Tests {
    @Ignore
    def testData = List(0, 1, -1, 5, -5)

    def test1 = {
        assert(testData == (testData.head :: testData.tail))
    }

    def test2 = {
        assert(testData.contains(testData.head))
    }
}
```

In this example, `test1` and `test2` are supposed to be test methods, but `testData` should be ignored even though its name starts with “test”.

To see when these annotations are present, you can use the Java reflection APIs. Here is sample code to show how it works:

```
for {
    method <- Tests.getClass.getMethods
    if method.getName.startsWith("test")
    if method.getAnnotation(classOf[Ignore]) == null
} {
    println("found a test method: " + method)
}
```

Here, the reflective methods `getClass` and `getMethods` are used to inspect all the fields of the input object’s class. These are normal reflection methods. The annotation-specific part is the use of method `getAnnotation`. Many

reflection objects have a `getAnnotation` method for searching for annotations of a specific type. In this case, the code looks for an annotation of our new `Ignore` type. Since this is a Java API, success is indicated by whether the result is `null` or an actual annotation object.

Here is the code in action:

```
$ javac Ignore.java
$ scalac Tests.scala
$ scalac FindTests.scala
$ scala FindTests
found a test method: public void Tests$.test2()
found a test method: public void Tests$.test1()
```

As an aside, notice that the methods are in class `Tests$` instead of class `Tests` when viewed with Java reflection. As described at the beginning of the chapter, the implementation of a Scala singleton object is placed in a Java class with a dollar sign added to the end of its name. In this case, the implementation of `Tests` is in the Java class `Tests$`.

Be aware that when you use Java annotations you have to work within their limitations. For example, you can only use constants, not expressions, in the arguments to annotations. You can support `@serial(1234)` but not `@serial(x * 2)`, because `x * 2` is not a constant.

31.3 Wildcard types

All Java types have a Scala equivalent. This is necessary so that Scala code can access any legal Java class. Most of the time the translation is straightforward. `Pattern` in Java is `Pattern` in Scala, and `Iterator<Component>` in Java is `Iterator[Component]` in Scala. For some cases, though, the Scala types you have seen so far are not enough. What can be done with Java wildcard types such as `Iterator<?>` or `Iterator<? extends Component>`? What can be done about raw types like `Iterator`, where the type parameter is omitted? For Java wildcard types and raw types, Scala uses an extra kind of type also called a *wildcard type*.

Wildcard types are written using *placeholder syntax*, just like the short-hand function literals described in [Section 8.5](#). In the short hand for function literals, you can use an underscore (`_`) in place of an expression; for example, `(_ + 1)` is the same as `(x => x + 1)`. Wildcard types use the same idea,

only for types instead of expressions. If you write `Iterator[_]`, then the underscore is replacing a type. Such a type represents an Iterator where the element type is not known.

You can also insert upper and lower bounds when using this placeholder syntax. Simply add the bound after the underscore, using the same `<:` syntax used with type parameters ([Section 19.8](#) and [Section 19.5](#)). For example, the type `Iterator[_ <: Component]` is an iterator where the element type is not known, but whatever type it is, it must be a subtype of `Component`.

That's how you write a wildcard type, but how do you use it? In simple cases, you can ignore the wildcard and call methods on the base type. For example, suppose you had the following Java class:

```
// This is a Java class with wildcards
public class Wild {
    public Collection<?> contents() {
        Collection<String> stuff = new Vector<String>();
        stuff.add("a");
        stuff.add("b");
        stuff.add("see");
        return stuff;
    }
}
```

If you access this in Scala code you will see that it has a wildcard type:

```
scala> val contents = (new Wild).contents
contents: java.util.Collection[_] = [a, b, see]
```

If you want to find out how many elements are in this collection, you can simply ignore the wildcard part and call the `size` method as normal:

```
scala> contents.size()
res0: Int = 3
```

In more complicated cases, wildcard types can be more awkward. Since the wildcard type has no name, there is no way to use it in two separate places. For example, suppose you wanted to create a mutable Scala set and initialize it with the elements of `contents`:

```
import scala.collection.mutable
val iter = (new Wild).contents.iterator
val set = mutable.Set.empty[???]      // what type goes here?
while (iter.hasMore)
    set += iter.next()
```

A problem occurs on the third line. There is no way to name the type of elements in the Java collection, so you cannot write down a satisfactory type for `set`. To work around this kind of problem, here are two tricks you should consider:

1. When passing a wildcard type into a method, give a parameter to the method for the placeholder. You now have a name for the type that you can use as many times as you like.
2. Instead of returning wildcard type from a method, return an object that has abstract members for each of the placeholder types. (See [Chapter 20](#) for information on abstract members.)

Using these two tricks together, the previous code can be written as follows:

```
import scala.collection.mutable
import java.util.Collection

abstract class SetAndType {
    type Elem
    val set: mutable.Set[Elem]
}

def javaSet2ScalaSet[T](jset: Collection[T]): SetAndType = {
    val sset = mutable.Set.empty[T] // now T can be named!
    val iter = jset.iterator
    while (iter.hasNext)
        sset += iter.next()
    return new SetAndType {
        type Elem = T
        val set = sset
    }
}
```

You can see why Scala code normally does not use wildcard types. To do anything sophisticated with them, you tend to convert them to use abstract members. So you may as well use abstract members to begin with.

31.4 Compiling Scala and Java together

Usually when you compile Scala code that depends on Java code, you first build the Java code to class files. You then build the Scala code, putting the Java code's class files on the classpath. However, this approach doesn't work if the Java code has references back into the Scala code. In such a case, no matter which order you compile the code, one side or the other will have unsatisfied external references. These situations are not uncommon; all it takes is a mostly Java project where you replace one Java source file with a Scala source file.

To support such builds, Scala allows compiling against Java source code as well as Java class files. All you have to do is put the Java source files on the command line as if they were Scala files. The Scala compiler won't compile those Java files, but it will scan them to see what they contain. To use this facility, you first compile the Scala code using Java source files, and then compile the Java code using Scala class files.

Here is a typical sequence of commands:

```
$ scalac -d bin InventoryAnalysis.scala InventoryItem.java \
          Inventory.java
$ javac -cp bin -d bin Inventory.java InventoryItem.java \
          InventoryManagement.java
$ scala -cp bin InventoryManagement
Most expensive item = sprocket($4.99)
```

31.5 Java 8 integration in Scala 2.12

Java 8 added a few improvements to the Java language and bytecodes that Scala takes advantage of in its 2.12 release.³ By exploiting new features of Java 8, the Scala 2.12 compiler can generate smaller class and jar files and improve the binary compatibility of traits.

³Scala 2.12 requires Java 8 so that it can take advantage of Java 8 features.

Lambda expressions and “SAM” types

From the Scala programmer’s perspective, the most visible Java 8-related enhancement in Scala 2.12 is that Scala function literals can be used like Java 8 *lambda expressions* as a more concise form for anonymous class instance expressions. To pass behavior into a method prior to Java 8, Java programmers often defined anonymous inner class instances, like this:

```
JButton button = new JButton(); // This is Java
button.addActionListener(
    new ActionListener() {
        public void actionPerformed(ActionEvent event) {
            System.out.println("pressed!");
        }
    }
);
```

In this example, an anonymous instance of `ActionListener` is created and passed to the `addActionListener` of a Swing `JButton`. When a user clicks on the button, Swing will invoke the `actionPerformed` method on this instance, which will print "pressed!".

In Java 8, a lambda expression can be used anywhere an instance of a class or interface that contains just a single abstract method (SAM) is required. `ActionListener` is such an interface, because it contains a single abstract method, `actionPerformed`. Thus a lambda expression can be used to register an action listener on a Swing button. Here’s an example:

```
JButton button = new JButton(); // This is Java 8
button.addActionListener(
    event -> System.out.println("pressed!")
);
```

In Scala, you could also use an anonymous inner class instance in the same situation, but you might prefer to use a function literal, like this:

```
val button = new JButton
button.addActionListener(
    _ => println("pressed!")
)
```

As you have already seen in [Section 21.1](#), you could support such a coding style by defining an implicit conversion from the `ActionEvent => Unit` function type to `ActionListener`.

Scala 2.12 enables a function literal to be used in this case even in the absence of such an implicit conversion. As with Java 8, Scala 2.12 will allow a function type to be used where an instance of a class or trait declaring a single abstract method (SAM) is required. This will work with any SAM in Scala 2.12. For example, you might define a trait, `Increaser`, with a single abstract method, `increase`:

```
scala> trait Increaser {  
    def increase(i: Int): Int  
}  
defined trait Increaser
```

You could then define a method that takes an `Increaser`:

```
scala> def increaseOne(increaser: Increaser): Int =  
    increaser.increase(1)  
increaseOne: (increaser: Increaser)Int
```

To invoke your new method, you could pass in an anonymous instance of trait `Increaser`, like this:

```
scala> increaseOne(  
    new Increaser {  
        def increase(i: Int): Int = i + 7  
    }  
)  
res0: Int = 8
```

In Scala 2.12, however, you could alternatively just use a function literal, because `Increaser` is a SAM type:

```
scala> increaseOne(i => i + 7) // Scala 2.12  
res1: Int = 8
```

Using Java 8 Streams from Scala 2.12

Java's Stream is a functional data structure that offers a `map` method taking a `java.util.function.IntUnaryOperator`. From Scala you could invoke `Stream.map` to increment each element of an Array, like this:

```
scala> import java.util.function.IntUnaryOperator
import java.util.function.IntUnaryOperator

scala> import java.util.Arrays
import java.util.Arrays

scala> val stream = Arrays.stream(Array(1, 2, 3))
stream: java.util.stream.IntStream = ...

scala> stream.map(
    new IntUnaryOperator {
        def applyAsInt(i: Int): Int = i + 1
    }
).toArray
res3: Array[Int] = Array(2, 3, 4)
```

Because `IntUnaryOperator` is a SAM type, however, you could in Scala 2.12 invoke it more concisely with a function literal:

```
scala> val stream = Arrays.stream(Array(1, 2, 3))
stream: java.util.stream.IntStream = ...

scala> stream.map(i => i + 1).toArray // Scala 2.12
res4: Array[Int] = Array(2, 3, 4)
```

Note that only function *literals* will be adapted to SAM types, not arbitrary expressions that have a function type. For example, consider the following `val`, `f`, which has type `Int => Int`:

```
scala> val f = (i: Int) => i + 1
f: Int => Int = ...
```

Although `f` has the same type as the function literal passed to `stream.map` previously, you can't use `f` where an `IntUnaryOperator` is required:

```
scala> val stream = Arrays.stream(Array(1, 2, 3))
stream: java.util.stream.IntStream = ...
```

```
scala> stream.map(f).toArray
<console>:16: error: type mismatch;
         found   : Int => Int
         required: java.util.function.IntUnaryOperator
                  stream.map(f).toArray
                           ^
```

To use f, you can explicitly call it using a function literal, like this:

```
scala> stream.map(i => f(i)).toArray
res5: Array[Int] = Array(2, 3, 4)
```

Or, you could annotate f with IntUnaryOperator, the type expected by Stream.map, when you define f:

```
scala> val f: IntUnaryOperator = i => i + 1
f: java.util.function.IntUnaryOperator = ...
scala> val stream = Arrays.stream(Array(1, 2, 3))
stream: java.util.stream.IntStream = ...
scala> stream.map(f).toArray
res6: Array[Int] = Array(2, 3, 4)
```

With Scala 2.12 and Java 8, you can also invoke methods compiled with Scala from Java, passing Scala function types using Java lambda expressions. Although Scala function types are defined as traits that include concrete methods, Scala 2.12 compiles traits to Java interfaces with *default methods*, a new feature of Java 8. As a result, Scala function types appear to Java as SAMs.

31.6 Conclusion

Most of the time, you can ignore how Scala is implemented, and simply write and run your code. But sometimes it is nice to “look under the hood,” so this chapter has gone into three aspects of Scala’s implementation on the Java platform: What the translation looks like, how Scala and Java annotations work together, and how Scala’s wildcard types let you access Java wildcard types. It also covered using Java’s concurrency primitives from Scala and compiling combined Scala and Java projects. These topics are important whenever you use Scala and Java together.

Chapter 32

Futures and Concurrency

One consequence of the proliferation of multicore processors has been an increased interest in concurrency. Java provides concurrency support built around shared memory and locking. Although this support is sufficient, this approach turns out to be quite difficult to get right in practice. Scala's standard library offers an alternative that avoids these difficulties by focusing on asynchronous transformations of immutable state: the Future.

Although Java also offers a Future, it is very different from Scala's. Both represent the result of an asynchronous computation, but Java's Future requires that you access the result via a blocking `get` method. Although you can call `isDone` to find out if a Java Future has completed before calling `get`, thereby avoiding any blocking, you must wait until the Java Future has completed before proceeding with any computation that uses the result.

By contrast, you can specify transformations on a Scala Future whether it has completed or not. Each transformation results in a new Future representing the asynchronous result of the original Future transformed by the function. The thread that performs the computation is determined by an implicitly provided *execution context*. This allows you to describe asynchronous computations as a series of transformations of immutable values, with no need to reason about shared memory and locks.

32.1 Trouble in paradise

On the Java platform, each object is associated with a logical *monitor*, which can be used to control multi-threaded access to data. To use this model, you decide what data will be shared by multiple threads and mark as “syn-

“chronized” sections of the code that access, or control access to, the shared data. The Java runtime employs a locking mechanism to ensure that only one thread at a time enters synchronized sections guarded by the same lock, thereby enabling you to orchestrate multi-threaded access to the shared data.

For compatibility’s sake, Scala provides access to Java’s concurrency primitives. The `wait`, `notify`, and `notifyAll` methods can be called in Scala, and they have the same meaning as in Java. Scala doesn’t technically have a `synchronized` keyword, but it includes a predefined `synchronized` method that can be called as follows:

```
var counter = 0
synchronized {
    // One thread in here at a time
    counter = counter + 1
}
```

Unfortunately, programmers have found it very difficult to reliably build robust multi-threaded applications using the shared data and locks model, especially as applications grow in size and complexity. The problem is that at each point in the program, you must reason about what data you are modifying or accessing that might be modified or accessed by other threads, and what locks are being held. At each method call, you must reason about what locks it will try to hold and convince yourself that it will not deadlock while trying to obtain them. Compounding the problem, the locks you reason about are not fixed at compile time, because the program is free to create new locks at run time as it progresses.

Making things worse, testing is not reliable with multi-threaded code. Since threads are non-deterministic, you might successfully test a program one thousand times—and the program could still go wrong the first time it runs on a customer’s machine. With shared data and locks, you must get the program correct through reason alone.

Moreover, you can’t solve the problem by over-synchronizing either. It can be just as problematic to synchronize everything as it is to synchronize nothing. Although new lock operations may remove possibilities for race conditions, they simultaneously add possibilities for deadlocks. A correct lock-using program must have neither race conditions nor deadlocks, so you cannot play it safe by overdoing it in either direction.

The `java.util.concurrent` library provides higher level abstractions for concurrent programming. Using the concurrency utilities makes multi-

threaded programming far less error prone than rolling your own abstractions with Java’s low-level synchronization primitives. Nevertheless, the concurrent utilities are also based on the shared data and locks model, and as a result, do not solve the fundamental difficulties of using that model.

32.2 Asynchronous execution and Trys

Although not a silver bullet, Scala’s Future offers one way to deal with concurrency that can reduce, and often eliminate, the need to reason about shared data and locks. When you invoke a Scala method, it performs a computation “while you wait” and returns a result. If that result is a Future, the Future represents another computation to be performed asynchronously, often by a completely different thread. As a result, many operations on Future require an implicit *execution context* that provides a strategy for executing functions asynchronously. For example, if you try to create a future via the Future.apply factory method without providing an implicit execution context, an instance of scala.concurrent.ExecutionContext, you’ll get a compiler error:

```
scala> import scala.concurrent.Future
import scala.concurrent.Future
scala> val fut = Future { Thread.sleep(10000); 21 + 21 }
<console>:11: error: Cannot find an implicit ExecutionContext.
          You might pass an (implicit ec: ExecutionContext)
                           parameter to your method or import
                           scala.concurrent.ExecutionContext.Implicits.global.
                           val fut = Future { Thread.sleep(10000); 21 + 21 }
```

The error message gives you one way to solve the problem: importing a global execution context provided by Scala itself. On the JVM, the global execution context uses a thread pool.¹ Once you bring an implicit execution context into scope, you can create a future:

```
scala> import scala.concurrent.ExecutionContext.Implicits.global
import scala.concurrent.ExecutionContext.Implicits.global
```

¹On Scala.js, the global execution context places tasks on the JavaScript event queue.

```
scala> val fut = Future { Thread.sleep(10000); 21 + 21 }
fut: scala.concurrent.Future[Int] = ...
```

The future created in the previous example asynchronously executes the block of code, using the global execution context, then completes with the value 42. Once it starts execution, that thread will sleep for ten seconds. Thus this future will take at least ten seconds to complete.

Two methods on Future allow you to poll: `isCompleted` and `value`. When invoked on a future that has not yet completed, `isCompleted` will return `false` and `value` will return `None`.

```
scala> fut.isCompleted
res0: Boolean = false

scala> fut.value
res1: Option[scala.util.Try[Int]] = None
```

Once the future completes (in this case, after at least ten seconds has gone by), `isCompleted` will return `true` and `value` will return a `Some`:

```
scala> fut.isCompleted
res2: Boolean = true

scala> fut.value
res3: Option[scala.util.Try[Int]] = Some(Success(42))
```

The option returned by `value` contains a `Try`. As shown in [Figure 32.1](#), a `Try` is either a `Success`, which contains a value of type `T`, or a `Failure`, which contains an exception (an instance of `java.lang.Throwable`). The purpose of `Try` is to provide for asynchronous computations what the `try` expression provides for synchronous computations: It allows you to deal with the possibility that the computation will complete abruptly with an exception rather than return a result.²

For synchronous computations you can use `try/catch` to ensure that a thread that invokes a method catches and handles exceptions thrown by the method. For asynchronous computations, however, the thread that initiates the computation often moves on to other tasks. Later if that asynchronous

²Note that the Java Future also has a way to deal with the potential of an exception being thrown by the asynchronous computation: its `get` method will throw that exception wrapped in an `ExecutionException`.




Figure 32.1 · Class hierarchy for Try.

computation fails with an exception, the original thread is no longer able to handle the exception in a catch clause. Thus when working with a Future representing an asynchronous activity, you use Try to deal with the possibility that the activity fails to yield a value and instead completes abruptly an exception. Here's an example that shows what happens when an asynchronous activity fails:

```

scala> val fut = Future { Thread.sleep(10000); 21 / 0 }
fut: scala.concurrent.Future[Int] = ...
scala> fut.value
res4: Option[scala.util.Try[Int]] = None
  
```

Then, after ten seconds:

```

scala> fut.value
res5: Option[scala.util.Try[Int]] =
  Some(Failure(java.lang.ArithmetricException: / by zero))
  
```

32.3 Working with Futures

Scala's Future allows you to specify transformations on Future results and obtain a *new future* that represents the composition of the two asynchronous computations: the original and the transformation.

Transforming Futures with `map`

The most fundamental such operation is `map`. Instead of blocking then continuing with another computation, you can just `map` the next computation onto the future. The result will be a new future that represents the original asynchronously computed result transformed asynchronously by the function passed to `map`.

For example, the following future will complete after ten seconds:

```
scala> val fut = Future { Thread.sleep(10000); 21 + 21 }
fut: scala.concurrent.Future[Int] = ...
```

Mapping this future with a function that increments by one will yield another future. This new future will represent a computation consisting of the original addition followed by the subsequent increment:

```
scala> val result = fut.map(x => x + 1)
result: scala.concurrent.Future[Int] = ...
scala> result.value
res5: Option[scala.util.Try[Int]] = None
```

Once the original future completes and the function has been applied to its result, the future returned by `map` will complete:

```
scala> result.value
res6: Option[scala.util.Try[Int]] = Some(Success(43))
```

Note that the operations performed in this example—the future creation, the $21 + 21$ sum calculation, and the $42 + 1$ increment—may be performed by three different threads.

Transforming Futures with `for` expressions

Because Scala's future also declares a `flatMap` method, you can transform futures using a `for` expression. For example, consider the following two futures that will, after ten seconds, produce 42 and 46:

```
scala> val fut1 = Future { Thread.sleep(10000); 21 + 21 }
fut1: scala.concurrent.Future[Int] = ...
```

```
scala> val fut2 = Future { Thread.sleep(10000); 23 + 23 }
fut2: scala.concurrent.Future[Int] = ...
```

Given these two futures, you can obtain a new future representing the asynchronous sum of their results like this:

```
scala> for {
    x <- fut1
    y <- fut2
  } yield x + y
res7: scala.concurrent.Future[Int] = ...
```

Once the original futures have completed, and the subsequent sum completes, you'll be able to see the result:

```
scala> res7.value
res8: Option[scala.util.Try[Int]] = Some(Success(88))
```

Because for expressions serialize their transformations,³ if you don't create the futures before the for expression, they won't run in parallel. For example, although the previous for expression requires around ten seconds to complete, the following for expression requires at least twenty seconds:

```
scala> for {
    x <- Future { Thread.sleep(10000); 21 + 21 }
    y <- Future { Thread.sleep(10000); 23 + 23 }
  } yield x + y
res9: scala.concurrent.Future[Int] = ...

scala> res9.value
res27: Option[scala.util.Try[Int]] = None
scala> // Will need at least 20 seconds to complete
scala> res9.value
res28: Option[scala.util.Try[Int]] = Some(Success(88))
```

³The for expression shown in this example will be rewritten as a call to `fut1.flatMap` passing in a function that calls `fut2.map`: `fut1.flatMap(x => fut2.map(y => x + y))`.

Creating the Future: Future.failed, Future.successful, Future.fromTry, and Promises

Besides the apply method, used in earlier examples to create futures, the Future companion object also includes three factory methods for creating already-completed futures: successful, failed, and fromTry. These factory methods do not require an ExecutionContext.

The successful factory method creates a future that has already succeeded:

```
scala> Future.successful { 21 + 21 }
res2: scala.concurrent.Future[Int] = ...
```

The failed method creates a future that has already failed:

```
scala> Future.failed(new Exception("bummer!"))
res3: scala.concurrent.Future[Nothing] = ...
```

The fromTry method creates an already completed future from a Try:

```
scala> import scala.util.{Success,Failure}
import scala.util.{Success, Failure}

scala> Future.fromTry(Success { 21 + 21 })
res4: scala.concurrent.Future[Int] = ...

scala> Future.fromTry(Failure(new Exception("bummer!")))
res5: scala.concurrent.Future[Nothing] = ...
```

The most general way to create a future is to use a Promise. Given a promise you can obtain a future that is controlled by the promise. The future will complete when you complete the promise. Here's an example:

```
scala> val pro = Promise[Int]
pro: scala.concurrent.Promise[Int] = ...

scala> val fut = pro.future
fut: scala.concurrent.Future[Int] = ...

scala> fut.value
res8: Option[scala.util.Try[Int]] = None
```

You can complete the promise with methods named `success`, `failure`, and `complete`. These methods on `Promise` are similar to those described previously for constructing already completed futures. For example, the `success` method will complete the future successfully:

```
scala> pro.success(42)
res9: pro.type = ...
scala> fut.value
res10: Option[scala.util.Try[Int]] = Some(Success(42))
```

The `failure` method takes an exception that will cause the future to fail with that exception. The `complete` method takes a `Try`. A `completeWith` method, which takes a future, also exists; the promise's future will thereafter mirror the completion status of the future you passed to `completeWith`.

Filtering: `filter` and `collect`

Scala's future offers two methods, `filter` and `collect`, that allow you to ensure a property holds true about a future value. The `filter` method validates the future result, leaving it the same if it is valid. Here's an example that ensures an `Int` is positive:

```
scala> val fut = Future { 42 }
fut: scala.concurrent.Future[Int] = ...
scala> val valid = fut.filter(res => res > 0)
valid: scala.concurrent.Future[Int] = ...
scala> valid.value
res0: Option[scala.util.Try[Int]] = Some(Success(42))
```

If the future value is not valid, the future returned by `filter` will fail with a `NoSuchElementException`:

```
scala> val invalid = fut.filter(res => res < 0)
invalid: scala.concurrent.Future[Int] = ...
scala> invalid.value
res1: Option[scala.util.Try[Int]] =
Some(Failure(java.util.NoSuchElementException:
Future.filter predicate is not satisfied))
```

Because Future also offers a `withFilter` method, you can perform the same operation with `for` expression filters:

```
scala> val valid = for (res <- fut if res > 0) yield res
valid: scala.concurrent.Future[Int] = ...
scala> valid.value
res2: Option[scala.util.Try[Int]] = Some(Success(42))
scala> val invalid = for (res <- fut if res < 0) yield res
invalid: scala.concurrent.Future[Int] = ...
scala> invalid.value
res3: Option[scala.util.Try[Int]] =
  Some(Failure(java.util.NoSuchElementException:
    Future.filter predicate is not satisfied))
```

Future's `collect` method allows you to validate the future value and transform it in one operation. If the partial function passed to `collect` is defined at the future result, the future returned by `collect` will succeed with that value transformed by the function:

```
scala> val valid =
        fut collect { case res if res > 0 => res + 46 }
valid: scala.concurrent.Future[Int] = ...
scala> valid.value
res17: Option[scala.util.Try[Int]] = Some(Success(88))
```

Otherwise, the future will fail with `NoSuchElementException`:

```
scala> val invalid =
        fut collect { case res if res < 0 => res + 46 }
invalid: scala.concurrent.Future[Int] = ...
scala> invalid.value
res18: Option[scala.util.Try[Int]] =
  Some(Failure(java.util.NoSuchElementException:
    Future.collect partial function is not defined at: 42))
```

Dealing with failure: failed, fallBackTo, recover, and recoverWith

Scala's future provides ways to work with futures that fail, including failed, fallBackTo, recover, and recoverWith. The failed method will transform a failed future of any type into a successful Future[Throwable] that holds onto the exception that caused the failure. Here's an example:

```
scala> val failure = Future { 42 / 0 }
failure: scala.concurrent.Future[Int] = ...
scala> failure.value
res23: Option[scala.util.Try[Int]] =
  Some(Failure(java.lang.ArithmetricException: / by zero))
scala> val expectedFailure = failure.failed
expectedFailure: scala.concurrent.Future[Throwable] = ...
scala> expectedFailure.value
res25: Option[scala.util.Try[Throwable]] =
  Some(Success(java.lang.ArithmetricException: / by zero))
```

If the future on which the failed method is called ultimately succeeds, the future returned by failed will itself fail with a NoSuchElementException. The failed method is appropriate, therefore, only when you expect that the future will fail. Here's an example:

```
scala> val success = Future { 42 / 1 }
success: scala.concurrent.Future[Int] = ...
scala> success.value
res21: Option[scala.util.Try[Int]] = Some(Success(42))
scala> val unexpectedSuccess = success.failed
unexpectedSuccess: scala.concurrent.Future[Throwable] = ...
scala> unexpectedSuccess.value
res26: Option[scala.util.Try[Throwable]] =
  Some(Failure(java.util.NoSuchElementException:
    Future.failed not completed with a throwable.))
```

The fallBackTo method allows you to provide an alternate future to use in case the future on which you invoke fallBackTo fails. Here's an example in which a failed future falls back to a successful future:

```
scala> val fallback = failure.failureTo(success)
fallback: scala.concurrent.Future[Int] = ...
scala> fallback.value
res27: Option[scala.util.Try[Int]] = Some(Success(42))
```

If the original future on which `failureTo` is invoked fails, a failure of the future passed to `failureTo` is essentially ignored. The future returned by `failureTo` will fail with the initial exception. Here's an example:

```
scala> val failedFallback = failure.failureTo(
  Future { val res = 42; require(res < 0); res }
)
failedFallback: scala.concurrent.Future[Int] = ...
scala> failedFallback.value
res28: Option[scala.util.Try[Int]] =
Some(Failure(java.lang.ArithmaticException: / by zero))
```

The `recover` method allows you to transform a failed future into a successful one, allowing a successful future's result to pass through unchanged. For example, on a future that fails with `ArithmaticException`, you can use the `recover` method to transform the failure into a success, like this:

```
scala> val recovered = failedFallback recover {
  case ex: ArithmaticException => -1
}
recovered: scala.concurrent.Future[Int] = ...
scala> recovered.value
res32: Option[scala.util.Try[Int]] = Some(Success(-1))
```

If the original future doesn't fail, the future returned by `recover` will complete with the same value:

```
scala> val unrecovered = fallback recover {
  case ex: ArithmaticException => -1
}
unrecovered: scala.concurrent.Future[Int] = ...
scala> unrecovered.value
res33: Option[scala.util.Try[Int]] = Some(Success(42))
```

Similarly, if the partial function passed to recover isn't defined at the exception with which the original future ultimately fails, that original failure will pass through:

```
scala> val alsoUnrecovered = failedFallback recover {
    case ex: IllegalArgumentException => -2
}
alsoUnrecovered: scala.concurrent.Future[Int] = ...
scala> alsoUnrecovered.value
res34: Option[scala.util.Try[Int]] =
  Some(Failure(java.lang.ArithmaticException: / by zero))
```

The recoverWith method is similar to recover, except instead of recovering to a value like recover, the recoverWith method allows you to recover to a future value. Here's an example:

```
scala> val alsoRecovered = failedFallback recoverWith {
    case ex: ArithmeticException => Future { 42 + 46 }
}
alsoRecovered: scala.concurrent.Future[Int] = ...
scala> alsoRecovered.value
res35: Option[scala.util.Try[Int]] = Some(Success(88))
```

As with recover, if either the original future doesn't fail, or the partial function passed to recoverWith isn't defined at the exception the original future ultimately fails with, the original success (or failure) will pass through to the future returned by recoverWith.

Mapping both possibilities: transform

Future's transform method accepts two functions with which to transform a future: one to use in case of success and the other in case of failure:

```
scala> val first = success.transform(
    res => res * -1,
    ex => new Exception("see cause", ex)
)
first: scala.concurrent.Future[Int] = ...
```

If the future succeeds, the first function is used:

```
scala> first.value
res42: Option[scala.util.Try[Int]] = Some(Success(-42))
```

If the future fails, the second function is used:

```
scala> val second = failure.transform(
    res => res * -1,
    ex => new Exception("see cause", ex)
)
second: scala.concurrent.Future[Int] = ...
scala> second.value
res43: Option[scala.util.Try[Int]] =
  Some(Failure(java.lang.Exception: see cause))
```

Note that with the `transform` method shown in the previous examples, you can't change a successful future into a failed one, nor can you change a failed future into a successful one. To make this kind of transformation easier, Scala 2.12 introduced an alternate overloaded form of `transform` that takes a function from `Try` to `Try`. Here are some examples:

```
scala> val firstCase = success.transform { // Scala 2.12
    case Success(res) => Success(res * -1)
    case Failure(ex) =>
        Failure(new Exception("see cause", ex))
}
first: scala.concurrent.Future[Int] = ...
scala> firstCase.value
res6: Option[scala.util.Try[Int]] = Some(Success(-42))

scala> val secondCase = failure.transform {
    case Success(res) => Success(res * -1)
    case Failure(ex) =>
        Failure(new Exception("see cause", ex))
}
secondCase: scala.concurrent.Future[Int] = ...
scala> secondCase.value
res8: Option[scala.util.Try[Int]] =
  Some(Failure(java.lang.Exception: see cause))
```

Here's an example of using the new `transform` method to transform a failure into a success:

```
scala> val nonNegative = failure.transform { // Scala 2.12
           case Success(res) => Success(res.abs + 1)
           case Failure(_) => Success(0)
       }
nonNegative: scala.concurrent.Future[Int] = ...
scala> nonNegative.value
res11: Option[scala.util.Try[Int]] = Some(Success(0))
```

Combining futures: `zip`, `Future.fold`, `Future.reduce`, `Future.sequence`, and `Future.traverse`

Future and its companion object offer methods that allow you to combine multiple futures. The `zip` method will transform two successful futures into a future tuple of both values. Here's an example:

```
scala> val zippedSuccess = success zip recovered
zippedSuccess: scala.concurrent.Future[(Int, Int)] = ...
scala> zippedSuccess.value
res46: Option[scala.util.Try[(Int, Int)]] =
  Some(Success((42,-1)))
```

If either of the futures fail, however, the future returned by `zip` will also fail with the same exception:

```
scala> val zippedFailure = success zip failure
zippedFailure: scala.concurrent.Future[(Int, Int)] = ...
scala> zippedFailure.value
res48: Option[scala.util.Try[(Int, Int)]] =
  Some(Failure(java.lang.ArithmetricException: / by zero))
```

If both futures fail, the failed future that results will contain the exception stored in the initial future, the one on which `zip` was invoked.

Future's companion object offers a `fold` method that allows you to accumulate a result across a `TraversableOnce` collection of futures, yielding a

future result. If all futures in the collection succeed, the resulting future will succeed with the accumulated result. If any future in the collection fails, the resulting future will fail. If multiple futures fail, the result will fail with the same exception with which the first future (earliest in the `TraversableOnce` collection) fails. Here's an example:

```
scala> val fortyTwo = Future { 21 + 21 }
fortyTwo: scala.concurrent.Future[Int] = ...
scala> val fortySix = Future { 23 + 23 }
fortySix: scala.concurrent.Future[Int] = ...
scala> val futureNums = List(fortyTwo, fortySix)
futureNums: List[scala.concurrent.Future[Int]] = ...
scala> val folded =
    Future.fold(futureNums)(0) { (acc, num) =>
    acc + num
}
folded: scala.concurrent.Future[Int] = ...
scala> folded.value
res53: Option[scala.util.Try[Int]] = Some(Success(88))
```

The `Future.reduce` method performs a fold without a zero, using the initial future result as the start value. Here's an example:

```
scala> val reduced =
    Future.reduce(futureNums) { (acc, num) =>
    acc + num
}
reduced: scala.concurrent.Future[Int] = ...
scala> reduced.value
res54: Option[scala.util.Try[Int]] = Some(Success(88))
```

If you pass an empty collection to `reduce`, the resulting future will fail with a `NoSuchElementException`.

The `Future.sequence` method transforms a `TraversableOnce` collection of futures into a future `TraversableOnce` of values. For instance, in the following example, `sequence` is used to transform a `List[Future[Int]]` to a `Future[List[Int]]`:

```
scala> val futureList = Future.sequence(futureNums)
futureList: scala.concurrent.Future[List[Int]] = ...
scala> futureList.value
res55: Option[scala.util.Try[List[Int]]] =
Some(Success(List(42, 46)))
```

The `Future.traverse` method will change a `TraversableOnce` of any element type into a `TraversableOnce` of futures and “sequence” that into a future `TraversableOnce` of values. For example, here a `List[Int]` is transformed into a `Future[List[Int]]` by `Future.traverse`:

```
scala> val traversed =
  Future.traverse(List(1, 2, 3)) { i => Future(i) }
traversed: scala.concurrent.Future[List[Int]] = ...
scala> traversed.value
res58: Option[scala.util.Try[List[Int]]] =
Some(Success(List(1, 2, 3)))
```

Performing side-effects: `foreach`, `onComplete`, and `andThen`

Sometimes you may need to perform a side effect after a future completes. `Future` provides several methods for this purpose. The most basic method is `foreach`, which will perform a side effect if a future completes successfully. For instance, in the following example a `println` is not executed in the case of a failed future, just a successful future:

```
scala> failure.foreach(ex => println(ex))
scala> success.foreach(res => println(res))
42
```

Since `for` without `yield` will rewrite to an invocation of `foreach`, you can also accomplish the same effect using `for` expressions:

```
scala> for (res <- failure) println(res)
scala> for (res <- success) println(res)
42
```

Future also offers two methods for registering “callback” functions. The `onComplete` method will be executed whether the future ultimately succeeds or fails. The function will be passed a Try—a Success holding the result if the future succeeded, else a Failure holding the exception that caused the future to fail. Here’s an example:

```
scala> import scala.util.{Success, Failure}
import scala.util.{Success, Failure}

scala> success onComplete {
    case Success(res) => println(res)
    case Failure(ex) => println(ex)
}

42

scala> failure onComplete {
    case Success(res) => println(res)
    case Failure(ex) => println(ex)
}

java.lang.ArithmetricException: / by zero
```

Future does not guarantee any order of execution for callback functions registered with `onComplete`. If you want to enforce an order for callback functions, you must use `andThen` instead. The `andThen` method returns a new future that mirrors (succeeds or fails in the same way as) the original future on which you invoke `andThen`, but it does not complete until the callback function has been fully executed:

```
scala> val newFuture = success andThen {
    case Success(res) => println(res)
    case Failure(ex) => println(ex)
}

42

newFuture: scala.concurrent.Future[Int] = ...

scala> newFuture.value
res76: Option[scala.util.Try[Int]] = Some(Success(42))
```

Note that if a callback function passed to `andThen` throws an exception when executed, that exception will not be propagated to subsequent callbacks or reported via the resulting future.

Other methods added in 2.12: `flatten`, `zipWith`, and `transformWith`

The `flatten` method, added in 2.12, transforms a Future nested inside another Future into a Future of the nested type. For example, `flatten` can transform a `Future[Future[Int]]` into a `Future[Int]`:

```
scala> val nestedFuture = Future { Future { 42 } }
nestedFuture: Future[Future[Int]] = ...
scala> val flattened = nestedFuture.flatten // Scala 2.12
flattened: scala.concurrent.Future[Int] = Future(Success(42))
```

The `zipWith` method, added in 2.12, essentially zips two Futures together, then performs a `map` on the resulting tuple. Here's an example of the two-step process, a `zip` followed by a `map`:

```
scala> val futNum = Future { 21 + 21 }
futNum: scala.concurrent.Future[Int] = ...
scala> val futStr = Future { "ans" + "wer" }
futStr: scala.concurrent.Future[String] = ...
scala> val zipped = futNum zip futStr
zipped: scala.concurrent.Future[(Int, String)] = ...
scala> val mapped = zipped map {
    case (num, str) => s"$num is the $str"
  }
mapped: scala.concurrent.Future[String] = ...
scala> mapped.value
res2: Option[scala.util.Try[String]] =
  Some(Success(42 is the answer))
```

The `zipWith` method allows you to perform the same operation in one step:

```
scala> val fut = futNum.zipWith(futStr) { // Scala 2.12
    case (num, str) => s"$num is the $str"
  }
zipWithed: scala.concurrent.Future[String] = ...
scala> fut.value
res3: Option[scala.util.Try[String]] =
  Some(Success(42 is the answer))
```

Future also gained a `transformWith` method in Scala 2.12, which allows you to transform a future using a function from Try to Future. Here's an example:

```
scala> val flipped = success.transformWith { // Scala 2.12
    case Success(res) =>
        Future { throw new Exception(res.toString) }
    case Failure(ex) => Future { 21 + 21 }
}
flipped: scala.concurrent.Future[Int] = ...
scala> flipped.value
res5: Option[scala.util.Try[Int]] =
Some(Failure(java.lang.Exception: 42))
```

The `transformWith` method is similar to the new, overloaded `transform` method added in Scala 2.12, except instead of yielding a Try in your passed function as in `transform`, `transformWith` allows you to yield a future.

32.4 Testing with Futures

One advantage of Scala's futures is that they help you avoid blocking. On most JVM implementations, after creating just a few thousand threads, the cost of context switching between threads will degrade performance to an unacceptable level. By avoiding blocking, you can keep the finite number of threads you decide to work with busy. Nevertheless, Scala does allow you to block on a future result when you need to. Scala's `Await` object facilitates blocking to wait for future results. Here's an example:

```
scala> import scala.concurrent.Await
import scala.concurrent.Await
scala> import scala.concurrent.duration._
import scala.concurrent.duration._
scala> val fut = Future { Thread.sleep(10000); 21 + 21 }
fut: scala.concurrent.Future[Int] = ...
scala> val x = Await.result(fut, 15.seconds) // blocks
x: Int = 42
```

`Await.result` takes a Future and a Duration. The Duration indicates how long `Await.result` should wait for a Future to complete before timing out. In this example, fifteen seconds was specified for the Duration. Thus the `Await.result` method should not time out before the future completes with its eventual value, 42.

One place where blocking has been generally accepted is in tests of asynchronous code. Now that the `Await.result` has returned, you can perform a computation using that result, such as an assertion in a test:

```
scala> import org.scalatest.Matchers._  
import org.scalatest.Matchers._  
  
scala> x should be (42)  
res0: org.scalatest.Assertion = Succeeded
```

Alternatively, you can use blocking constructs provided by ScalaTest's trait `ScalaFutures`. For example, the `futureValue` method, implicitly added to Future by `ScalaFutures`, will block until the future completes. If the future fails, `futureValue` will throw a `TestFailedException` describing the problem. If the future succeeds, `futureValue` will return the successful result of the future so you can perform assertions on that value:

```
scala> import org.scalatest.concurrent.ScalaFutures._  
import org.scalatest.concurrent.ScalaFutures._  
  
scala> val fut = Future { Thread.sleep(10000); 21 + 21 }  
fut: scala.concurrent.Future[Int] = ...  
  
scala> fut.futureValue should be (42) // futureValue blocks  
res1: org.scalatest.Assertion = Succeeded
```

While blocking in tests is often fine, ScalaTest 3.0 adds “async” testing styles that allow you to test futures without blocking. Given a future, instead of blocking and performing assertions on the result, you can map assertions directly onto that future and return the resulting `Future[Assertion]` to ScalaTest. An example is shown in Listing 32.1. When the future assertion completes, ScalaTest will fire events (test succeeded, test failed, etc.) to the test reporter asynchronously.

The async testing use case illustrates a general principle for working with futures: Once in “future space,” try to stay in future space. Don’t block on a

```
import org.scalatest.AsyncFunSpec
import scala.concurrent.Future

class AddSpec extends AsyncFunSpec {

    def addSoon(addends: Int*): Future[Int] =
        Future { addends.sum }

    describe("addSoon") {
        it("will eventually compute a sum of passed Ints") {
            val futureSum: Future[Int] = addSoon(1, 2)
            // You can map assertions onto a Future, then return
            // the resulting Future[Assertion] to ScalaTest:
            futureSum map { sum => assert(sum == 3) }
        }
    }
}
```

Listing 32.1 · Returning a future assertion to ScalaTest.

future then continue the computation with the result. Stay asynchronous by performing a series of transformations, each of which returns a new future to transform. To get results out of future space, register side effects to be performed asynchronously once futures complete. This approach will help you make maximum use of your threads.

32.5 Conclusion

Concurrent programming gives you great power. It lets you simplify your code and take advantage of multiple processors. It's unfortunate that the most widely used concurrency primitives, threads, locks, and monitors, are such a minefield of deadlocks and race conditions. Futures provide a way out of that minefield, letting you write concurrent programs without as great a risk of deadlocks and race conditions. This chapter has introduced several fundamental constructs for working with futures in Scala, including how to create futures, how to transform them, and how to test them, among other nuts and bolts. It then showed you how to use these constructs as part of a general futures style.

Chapter 33

Combinator Parsing

Occasionally, you may need to process a small, special-purpose language. For example, you may need to read configuration files for your software, and you want to make them easier to modify by hand than XML. Alternatively, maybe you want to support an input language in your program, such as search terms with boolean operators (computer, find me a movie “with ‘space ships’ and without ‘love stories’”). Whatever the reason, you are going to need a *parser*. You need a way to convert the input language into some data structure your software can process.

Essentially, you have only a few choices. One choice is to roll your own parser (and lexical analyzer). If you are not an expert, this is hard. If you are an expert, it is still time consuming.

An alternative choice is to use a parser generator. There exist quite a few of these generators. Some of the better known are Yacc and Bison for parsers written in C and ANTLR for parsers written in Java. You’ll probably also need a scanner generator such as Lex, Flex, or JFlex to go with it. This might be the best solution, except for a couple of inconveniences. You need to learn new tools, including their—sometimes obscure—error messages. You also need to figure out how to connect the output of these tools to your program. This might limit the choice of your programming language, and complicate your tool chain.

This chapter presents a third alternative. Instead of using the standalone domain specific language of a parser generator, you will use an *internal domain specific language*, or internal DSL for short. The internal DSL will consist of a library of *parser combinators*—functions and operators defined in Scala that will serve as building blocks for parsers. These building blocks

will map one to one to the constructions of a context-free grammar, to make them easy to understand.

This chapter introduces only one language feature that was not explained before: `this` aliasing, in [Section 33.6](#). The chapter does, however, heavily use several other features that were explained in previous chapters. Among others, parameterized types, abstract types, functions as objects, operator overloading, by-name parameters, and implicit conversions all play important roles. The chapter shows how these language elements can be combined in the design of a very high-level library.

The concepts explained in this chapter tend to be a bit more advanced than previous chapters. If you have a good grounding in compiler construction, you'll profit from it reading this chapter, because it will help you put things better in perspective. However, the only prerequisite for understanding this chapter is that you know about regular and context-free grammars. If you don't, the material in this chapter can also safely be skipped.

33.1 Example: Arithmetic expressions

We'll start with an example. Say you want to construct a parser for arithmetic expressions consisting of floating-point numbers, parentheses, and the binary operators `+`, `-`, `*`, and `/`. The first step is always to write down a grammar for the language to be parsed. Here's the grammar for arithmetic expressions:

```
expr  ::=  term {"+" term | "-"} term}.
term  ::=  factor {"*" factor | "/" factor}.
factor ::=  floatingPointNumber | "(" expr ")".
```

Here, `|` denotes alternative productions, and `{ ... }` denotes repetition (zero or more times). And although there's no use of it in this example, `[...]` denotes an optional occurrence.

This context-free grammar defines formally a language of arithmetic expressions. Every expression (represented by `expr`) is a *term*, which can be followed by a sequence of `+` or `-` operators and further *terms*. A *term* is a *factor*, possibly followed by a sequence of `*` or `/` operators and further *factors*. A *factor* is either a numeric literal or an expression in parentheses. Note that the grammar already encodes the relative precedence of operators. For instance, `*` binds more tightly than `+`, because a `*` operation gives a *term*,

whereas a `+` operation gives an *expr*, and *exprs* can contain *terms* but a *term* can contain an *expr* only when the latter is enclosed in parentheses.

Now that you have defined the grammar, what's next? If you use Scala's combinator parsers, you are basically done! You only need to perform some systematic text replacements and wrap the parser in a class, as shown in Listing 33.1:

```
import scala.util.parsing.combinator._

class Arith extends JavaTokenParsers {
    def expr: Parser[Any] = term~rep("+~term | "-~term)
    def term: Parser[Any] = factor~rep("*~factor | "/"~factor)
    def factor: Parser[Any] = floatingPointNumber | "("~expr~")"
}
```

Listing 33.1 · An arithmetic expression parser.

The parsers for arithmetic expressions are contained in a class that inherits from the trait `JavaTokenParsers`. This trait provides the basic machinery for writing a parser and also provides some primitive parsers that recognize some word classes: identifiers, string literals and numbers. In the example in Listing 33.1 you need only the primitive `floatingPointNumber` parser, which is inherited from this trait.

The three definitions in class `Arith` represent the productions for arithmetic expressions. As you can see, they follow very closely the productions of the context-free grammar. In fact, you could generate this part automatically from the context-free grammar, by performing a number of simple text replacements:

1. Every production becomes a method, so you need to prefix it with `def`.
2. The result type of each method is `Parser[Any]`, so you need to change the `::=` symbol to “`: Parser[Any] =`”. You’ll find out later in this chapter what the type `Parser[Any]` signifies, and also how to make it more precise.
3. In the grammar, sequential composition was implicit, but in the program it is expressed by an explicit operator: `~`. So you need to insert a `~` between every two consecutive symbols of a production. In the example in Listing 33.1 we chose not to write any spaces around the `~`

operator. That way, the parser code keeps closely to the visual appearance of the grammar—it just replaces spaces by ~ characters.

4. Repetition is expressed `rep(...)` instead of `{ ... }`. Analogously (though not shown in the example), option is expressed `opt(...)` instead of `[...]`.
5. The period `(.)` at the end of each production is omitted—you can, however, write a semicolon `(;)` if you prefer.

That's all there is to it. The resulting class `Arith` defines three parsers, `expr`, `term` and `factor`, which can be used to parse arithmetic expressions and their parts.

33.2 Running your parser

You can exercise your parser with the following small program:

```
object ParseExpr extends Arith {  
    def main(args: Array[String]) = {  
        println("input : " + args(0))  
        println(parseAll(expr, args(0)))  
    }  
}
```

The `ParseExpr` object defines a `main` method that parses the first command-line argument passed to it. It prints the original input argument, and then prints its parsed version. Parsing is done by the expression:

```
parseAll(expr, input)
```

This expression applies the parser, `expr`, to the given `input`. It expects that all of the input matches, *i.e.*, that there are no characters trailing a parsed expression. There's also a method `parse`, which allows you to parse an input prefix, leaving some remainder unread.

You can run the arithmetic parser with the following command:

```
$ scala ParseExpr "2 * (3 + 7)"  
input: 2 * (3 + 7)  
[1.12] parsed: ((2~List((*~(((~((3~List())~List((+  
~(7~List()))))))~))))~List())
```

The output tells you that the parser successfully analyzed the input string up to position [1.12]. That means the first line and the twelfth column—in other words, the whole input string—was parsed. Disregard for the moment the result after “parsed:”. It is not very useful, and you will find out later how to get more specific parser results.

You can also try to introduce some input string that is not a legal expression. For instance, you could write one closing parenthesis too many:

```
$ scala ParseExpr "2 * (3 + 7))"  
input: 2 * (3 + 7))  
[1.12] failure: `-' expected but `)' found  
  
2 * (3 + 7))  
^
```

Here, the expr parser parsed everything until the final closing parenthesis, which does not form part of the arithmetic expression. The parseAll method then issued an error message, which said that it expected a – operator at the point of the closing parenthesis. You’ll find out later in this chapter why it produced this particular error message, and how you can improve it.

33.3 Basic regular expression parsers

The parser for arithmetic expressions made use of another parser, named floatingPointNumber. This parser, which was inherited from Arith’s supertype, JavaTokenParsers, recognizes a floating point number in the format of Java. But what do you do if you need to parse numbers in a format that’s a bit different from Java’s? In this situation, you can use a *regular expression parser*.

The idea is that you can use any regular expression as a parser. The regular expression parses all strings that it can match. Its result is the parsed string. For instance, the regular expression parser shown in Listing 33.2 describes Java’s identifiers:

```
object MyParsers extends RegexParsers {  
    val ident: Parser[String] = """[a-zA-Z_]\w*""".r  
}
```

Listing 33.2 · A regular expression parser for Java identifiers.

The `MyParsers` object of [Listing 33.2](#) inherits from trait `RegexParsers`, whereas `Arith` inherited from `JavaTokenParsers`. Scala's parsing combinators are arranged in a hierarchy of traits, which are all contained in package `scala.util.parsing.combinator`. The top-level trait is `Parsers`, which defines a very general parsing framework for all sorts of input. One level below is trait `RegexParsers`, which requires that the input is a sequence of characters and provides for regular expression parsing. Even more specialized is trait `JavaTokenParsers`, which implements parsers for basic classes of words (or *tokens*) as they are defined in Java.

33.4 Another example: JSON

JSON, the JavaScript Object Notation, is a popular data interchange format. In this section, we'll show you how to write a parser for it. Here's a grammar that describes the syntax of JSON:

```
value   ::=  obj | arr | stringLiteral |  
           floatingPointNumber |  
           "null" | "true" | "false".  
obj    ::=  "{" [members] "}".  
arr    ::=  "[" [values] "]".  
members ::=  member {"," member}.  
member  ::=  stringLiteral ":" value.  
values   ::=  value {"," value}.
```

A JSON value is an object, array, string, number, or one of the three reserved words `null`, `true`, or `false`. A JSON object is a (possibly empty) sequence of members separated by commas and enclosed in braces. Each member is a string/value pair where the string and the value are separated by a colon. Finally, a JSON array is a sequence of values separated by commas and enclosed in square brackets. As an example, [Listing 33.3](#) contains an address-book formatted as a JSON object.

Parsing such data is straightforward when using Scala's parser combinators. The complete parser is shown in [Listing 33.4](#). This parser follows the same structure as the arithmetic expression parser. It is again a straightforward mapping of the productions of the JSON grammar. The productions

```
{  
    "address book": {  
        "name": "John Smith",  
        "address": {  
            "street": "10 Market Street",  
            "city": "San Francisco, CA",  
            "zip": 94111  
        },  
        "phone numbers": [  
            "408 338-4238",  
            "408 111-6892"  
        ]  
    }  
}
```

Listing 33.3 · Data in JSON format.

use one shortcut that simplifies the grammar: The `repsep` combinator parses a (possibly empty) sequence of terms that are separated by a given separator string. For instance, in the example in Listing 33.4, `repsep(member, ",")` parses a comma-separated sequence of `member` terms. Otherwise, the productions in the parser correspond exactly to the productions in the grammar, as was the case for the arithmetic expression parsers.

To try out the JSON parsers, we'll change the framework a bit, so that the parser operates on a file instead of on the command line:

```
import java.io.FileReader  
  
object ParseJSON extends JSON {  
    def main(args: Array[String]) = {  
        val reader = new FileReader(args(0))  
        println(parseAll(value, reader))  
    }  
}
```

The `main` method in this program first creates a `FileReader` object. It then parses the characters returned by that reader according to the `value` production of the JSON grammar. Note that `parseAll` and `parse` exist in

overloaded variants: both can take a character sequence or alternatively an input reader as second argument.

If you store the “address book” object shown in Listing 33.3 into a file named address-book.json and run the ParseJSON program on it, you should get:

```
$ scala ParseJSON address-book.json
[13.4] parsed: (({~List(((\"address book\"~:)~(({{~List(((\"name\"~:)~"John Smith"), ((\"address\"~:)~(({{~List(((\"street\"~:)~"10 Market Street"), ((\"city\"~:)~"San Francisco ,CA"), ((\"zip\"~:)~94111)))~}}), ((\"phone numbers\"~:)~(([~List("408 338-4238", "408 111-6892"))~]))~}))))~})
```

33.5 Parser output

The ParseJSON program successfully parsed the JSON address book. However, the parser output looks strange. It seems to be a sequence composed of bits and pieces of the input glued together with lists and ~ combinations. This output is not very useful. It is less readable for humans than the input, but it is also too disorganized to be easily analyzable by a computer. It’s time to do something about this.

```
import scala.util.parsing.combinator._
class JSON extends JavaTokenParsers {
    def value : Parser[Any] = obj | arr |
                           stringLiteral |
                           floatingPointNumber |
                           "null" | "true" | "false"
    def obj   : Parser[Any] = "{"~repsep(member, ",")~"}"
    def arr   : Parser[Any] = "["~repsep(value, ",")~"]"
    def member: Parser[Any] = stringLiteral~":"~value
}
```

Listing 33.4 · A simple JSON parser.

To figure out what to do, you need to know first what the individual parsers in the combinator frameworks return as a result (provided they succeed in parsing the input). Here are the rules:

1. Each parser written as a string (such as: "{" or ":" or "null") returns the parsed string itself.
2. Regular expression parsers such as """[a-zA-Z_]\w*""".r also return the parsed string itself. The same holds for regular expression parsers such as `stringLiteral` or `floatingPointNumber`, which are inherited from trait `JavaTokenParsers`.
3. A sequential composition `P~Q` returns the results of both `P` and of `Q`. These results are returned in an instance of a case class that is also written `~`. So if `P` returns "true" and `Q` returns "?", then the sequential composition `P~Q` returns `~("true", "?")`, which prints as `(true~?)`.
4. An alternative composition `P | Q` returns the result of either `P` or `Q`, whichever one succeeds.
5. A repetition `rep(P)` or `repsep(P, separator)` returns a list of the results of all runs of `P`.
6. An option `opt(P)` returns an instance of Scala's `Option` type. It returns `Some(R)` if `P` succeeds with result `R` and `None` if `P` fails.

With these rules you can now deduce *why* the parser output appeared as it did in the previous examples. However, the output is still not very convenient. It would be much better to map a JSON object into an internal Scala representation that represents the meaning of the JSON value. A more natural representation would be as follows:

- A JSON object is represented as a Scala map of type `Map[String, Any]`. Every member is represented as a key/value binding in the map.
- A JSON array is represented as a Scala list of type `List[Any]`.
- A JSON string is represented as a Scala `String`.
- A JSON numeric literal is represented as a Scala `Double`.

- The values `true`, `false`, and `null` are represented as the Scala values with the same names.

To produce this representation, you need to make use of one more combination form for parsers: `^^`.

The `^^` operator *transforms* the result of a parser. Expressions using this operator have the form `P ^^ f` where `P` is a parser and `f` is a function. `P ^^ f` parses the same sentences as just `P`. Whenever `P` returns with some result `R`, the result of `P ^^ f` is `f(R)`.

As an example, here is a parser that parses a floating point number and converts it to a Scala value of type `Double`:

```
floatingPointNumber ^^ (_.toDouble)
```

And here is a parser that parses the string "true" and returns Scala's boolean `true` value:

```
"true" ^^ (x => true)
```

Now for more advanced transformations. Here's a new version of a parser for JSON objects that returns a Scala Map:

```
def obj: Parser[Map[String, Any]] = // Can be improved
  "{" ~ repsep(member, ",") ~ "}" ^^
    { case "{" ~ ms ~ "}" => Map() ++ ms }
```

Remember that the `~` operator produces as its result an instance of a case class with the same name: `~`. Here's a definition of that class—it's an inner class of trait `Parsers`:

```
case class ~(+A, +B)(x: A, y: B) {
  override def toString = "(" + x + "~" + y + ")"
}
```

The name of the class is intentionally the same as the name of the sequence combinator method, `~`. That way, you can match parser results with patterns that follow the same structure as the parsers themselves. For instance, the pattern `"{" ~ ms ~ "}"` matches a result string `"{"` followed by a result variable `ms`, which is followed in turn by a result string `"}"`. This pattern corresponds exactly to what is returned by the parser on the left of the `^^`.

In its desugared versions where the `~` operator comes first, the same pattern reads `~(~("{}", ms), "{}")`, but this is much less legible.

The purpose of the `"{}~ms~{}"` pattern is to strip off the braces so that you can get at the list of members resulting from the `repsep(member, ",")` parser. In cases like these there is also an alternative that avoids producing unnecessary parser results that are immediately discarded by the pattern match. The alternative makes use of the `~>` and `<~` parser combinators. Both express sequential composition like `~`, but `~>` keeps only the result of its right operand, whereas `<~` keeps only the result of its left operand. Using these combinators, the JSON object parser can be expressed more succinctly:

```
def obj: Parser[Map[String, Any]] =  
  "{}~> repsep(member, ",") <~"}" ^^ (Map() ++ _)
```

[Listing 33.5](#) shows a full JSON parser that returns meaningful results. If you run this parser on the `address-book.json` file, you will get the following result (after adding some newlines and indentation):

```
$ scala JSON1Test address-book.json  
[14.1] parsed: Map(  
  address book -> Map(  
    name -> John Smith,  
    address -> Map(  
      street -> 10 Market Street,  
      city -> San Francisco, CA,  
      zip -> 94111),  
    phone numbers -> List(408 338-4238, 408 111-6892)  
  )  
)
```

This is all you need to know in order to get started writing your own parsers. As an aide to memory, [Table 33.1](#) lists the parser combinators that were discussed so far.

Symbolic versus alphanumeric names

Many of the parser combinators in [Table 33.1](#) use symbolic names. This has both advantages and disadvantages. On the minus side, symbolic names take time to learn. Users who are unfamiliar with Scala's combinator parsing

```

import scala.util.parsing.combinator._

class JSON1 extends JavaTokenParsers {

  def obj: Parser[Map[String, Any]] =
    "{" ~> repsep(member, ",") <~ "}" ^^ (Map() ++ _)

  def arr: Parser[List[Any]] =
    "[" ~> repsep(value, ",") <~ "]"

  def member: Parser[(String, Any)] =
    stringLiteral~":"value ^^
      { case name~":"value => (name, value) }

  def value: Parser[Any] = (
    obj
    | arr
    | stringLiteral
    | floatingPointNumber ^^ (_.toDouble)
    | "null" ^> (x => null)
    | "true" ^> (x => true)
    | "false" ^> (x => false)
  )
}

```

Listing 33.5 · A full JSON parser that returns meaningful results.

Table 33.1 · Summary of parser combinators

"..."	literal
"...".r	regular expression
P~Q	sequential composition
P <~ Q, P ~> Q	sequential composition; keep left/right only
P Q	alternative
opt(P)	option
rep(P)	repetition
repsep(P, Q)	interleaved repetition
P ^^ f	result conversion

Turning off semicolon inference

Note that the body of the value parser in [Listing 33.5](#) is enclosed in parentheses. This is a little trick to disable semicolon inference in parser expressions. You saw in [Section 4.2](#) that Scala assumes there's a semicolon between any two lines that can be separate statements syntactically, unless the first line ends in an infix operator, or the two lines are enclosed in parentheses or square brackets. Now, you could have written the `|` operator at the end of each alternative instead of at the beginning of the following one, like this:

```
def value: Parser[Any] =  
    obj |  
    arr |  
    stringLiteral |  
    ...
```

In that case, no parentheses around the body of the value parser would have been required. However, some people prefer to see the `|` operator at the beginning of the second alternative rather than at the end of the first. Normally, this would lead to an unwanted semicolon between the two lines, like this:

```
obj; // semicolon implicitly inserted  
| arr
```

The semicolon changes the structure of the code, causing it to fail compilation. Putting the whole expression in parentheses avoids the semicolon and makes the code compile correctly.

libraries are probably mystified what `~`, `~>`, or `^` mean. On the plus side, symbolic names are short, and can be chosen to have the “right” precedences and associativities. For instance, the parser combinators `~`, `^`, and `|` are chosen intentionally in decreasing order of precedence. A typical grammar production is composed of alternatives that have a parsing part and a transformation part. The parsing part usually contains several sequential items separated by `~` operators. With the chosen precedences of `~`, `^`, and `|` you can write such a grammar production without needing any parentheses.

Furthermore, symbolic operators take less visual real estate than alphabetic ones. That's important for a parser because it lets you concentrate on the grammar at hand, instead of the combinators themselves. To see the difference, imagine for a moment that sequential composition (\sim) was called `andThen` and alternative (`|`) was called `orElse`. The arithmetic expression parsers in Listing 33.1 on page 738 would look as follows:

```
class ArithHypothetical extends JavaTokenParsers {  
    def expr: Parser[Any] =  
        term andThen rep(("+" andThen term) orElse  
                         ("-" andThen term))  
    def term: Parser[Any] =  
        factor andThen rep(("*" andThen factor) orElse  
                           ("/" andThen factor))  
    def factor: Parser[Any] =  
        floatingPointNumber orElse  
        ("(" andThen expr andThen "))")  
}
```

You notice that the code becomes much longer, and that it's hard to "see" the grammar among all those operators and parentheses. On the other hand, somebody new to combinator parsing could probably figure out better what the code is supposed to do.

33.6 Implementing combinator parsers

The previous sections have shown that Scala's combinator parsers provide a convenient means for constructing your own parsers. Since they are nothing more than a Scala library, they fit seamlessly into your Scala programs. So it's very easy to combine a parser with some code that processes the results it delivers, or to rig a parser so that it takes its input from some specific source (say, a file, a string, or a character array).

How is this achieved? In the rest of this chapter you'll take a look "under the hood" of the combinator parser library. You'll see what a parser is, and how the primitive parsers and parser combinators encountered in previous sections are implemented. You can safely skip these parts if all you want to do is write some simple combinator parsers. On the other hand, reading the rest of this chapter should give you a deeper understanding of combinator

Choosing between symbolic and alphabetic names

As guidelines for choosing between symbolic and alphabetic names we recommend the following:

- Use symbolic names in cases where they already have a universally established meaning. For instance, nobody would recommend writing add instead of + for numeric addition.
- Otherwise, give preference to alphabetic names if you want your code to be understandable to casual readers.
- You can still choose symbolic names for domain-specific libraries, if this gives clear advantages in legibility and you do not expect anyway that a casual reader without a firm grounding in the domain would be able to understand the code immediately.

In the case of parser combinators we are looking at a highly domain-specific language, which casual readers may have trouble understanding even with alphabetic names. Furthermore, symbolic names give clear advantages in legibility for the expert. So we believe their use is warranted in this application.

parsers in particular, and of the design principles of a combinator domain-specific language in general.

The core of Scala's combinator parsing framework is contained in the trait `scala.util.parsing.combinator.Parsers`. This trait defines the `Parser` type as well as all fundamental combinators. Except where stated explicitly otherwise, the definitions explained in the following two subsections all reside in this trait. That is, they are assumed to be contained in a trait definition that starts as follows:

```
package scala.util.parsing.combinator
trait Parsers {
    ... // code goes here unless otherwise stated
}
```

A `Parser` is in essence just a function from some input type to a parse result. As a first approximation, the type could be written as follows:

```
type Parser[T] = Input => ParseResult[T]
```

Parser input

Sometimes, a parser reads a stream of tokens instead of a raw sequence of characters. A separate lexical analyzer is then used to convert a stream of raw characters into a stream of tokens. The type of parser inputs is defined as follows:

```
type Input = Reader[Elem]
```

The class `Reader` comes from the package `scala.util.parsing.input`. It is similar to a `Stream`, but also keeps track of the positions of all the elements it reads. The type `Elem` represents individual input elements. It is an abstract type member of the `Parsers` trait:

```
type Elem
```

This means that subclasses and subtraits of `Parsers` need to instantiate class `Elem` to the type of input elements that are being parsed. For instance, `RegexParsers` and `JavaTokenParsers` fix `Elem` to be equal to `Char`. But it would also be possible to set `Elem` to some other type, such as the type of tokens returned from a separate lexer.

Parser results

A parser might either succeed or fail on some given input. Consequently class `ParseResult` has two subclasses for representing success and failure:

```
sealed abstract class ParseResult[+T]
case class Success[T](result: T, in: Input)
  extends ParseResult[T]
case class Failure(msg: String, in: Input)
  extends ParseResult[Nothing]
```

The `Success` case carries the result returned from the parser in its `result` parameter. The type of parser results is arbitrary; that's why `ParseResult`, `Success`, and `Parser` are all parameterized with a type parameter `T`. The type parameter represents the kinds of results returned by a given parser. `Success` also takes a second parameter, `in`, which refers to the input immediately following the part that the parser consumed. This field is needed for chaining parsers, so that one parser can operate after another. Note that this is a purely functional approach to parsing. `Input` is not read as a side effect,

but it is kept in a stream. A parser analyzes some part of the input stream, and then returns the remaining part in its result.

The other subclass of `ParseResult` is `Failure`. This class takes as a parameter a message that describes why the parser failed. Like `Success`, `Failure` also takes the remaining input stream as a second parameter. This is needed not for chaining (the parser won't continue after a failure), but to position the error message at the correct place in the input stream.

Note that parse results are defined to be covariant in the type parameter `T`. That is, a parser returning `Strings` as result, say, is compatible with a parser returning `AnyRefs`.

The Parser class

The previous characterization of parsers as functions from inputs to parse results was a bit oversimplified. The previous examples showed that parsers also implement *methods* such as `~` for sequential composition of two parsers and `|` for their alternative composition. So `Parser` is in reality a class that inherits from the function type `Input => ParseResult[T]` and additionally defines these methods:

```
abstract class Parser[+T] extends (Input => ParseResult[T])
{ p =>
    // An unspecified method that defines
    // the behavior of this parser.
    def apply(in: Input): ParseResult[T]
    def ~ ...
    def | ...
    ...
}
```

Since parsers are (*i.e.*, inherit from) functions, they need to define an `apply` method. You see an abstract `apply` method in class `Parser`, but this is just for documentation, as the same method is in any case inherited from the parent type `Input => ParseResult[T]` (recall that this type is an abbreviation for `scala.Function1[Input, ParseResult[T]]`). The `apply` method still needs to be implemented in the individual parsers that inherit from the abstract `Parser` class. These parsers will be discussed after the following section on this aliasing.

Aliasing `this`

The body of the `Parser` class starts with a curious expression:

```
abstract class Parser[+T] extends ... { p =>
```

A clause such as “`id =>`” immediately after the opening brace of a class template defines the identifier `id` as an alias for `this` in the class. It’s as if you had written:

```
val id = this
```

in the class body, except that the Scala compiler knows that `id` is an alias for `this`. For instance, you could access an object-private member `m` of the class using either `id.m` or `this.m`; the two are completely equivalent. The first expression would not compile if `id` were just defined as a `val` with `this` as its right hand side, because in that case the Scala compiler would treat `id` as a normal identifier.

You saw syntax like this in [Section 29.4](#), where it was used to give a `self type` to a trait. Aliasing can also be a good abbreviation when you need to access the `this` of an outer class. Here’s an example:

```
class Outer { outer =>
    class Inner {
        println(Outer.this eq outer) // prints: true
    }
}
```

The example defines two nested classes, `Outer` and `Inner`. Inside `Inner` the `this` value of the `Outer` class is referred to twice, using different expressions. The first expression shows the Java way of doing things: You can prefix the reserved word `this` with the name of an outer class and a period; such an expression then refers to the `this` of the outer class. The second expression shows the alternative that Scala gives you. By introducing an alias named `outer` for `this` in class `Outer`, you can refer to this alias directly also in inner classes. The Scala way is more concise, and can also improve clarity, if you choose the name of the alias well. You’ll see examples of this in [pages 754](#) and [755](#).

Single-token parsers

Trait Parsers defines a generic parser `elem` that can be used to parse any single token:

```
def elem(kind: String, p: Elem => Boolean) =  
  new Parser[Elem] {  
    def apply(in: Input) =  
      if (p(in.first)) Success(in.first, in.rest)  
      else Failure(kind + " expected", in)  
  }
```

This parser takes two parameters: a kind string describing what kind of token should be parsed and a predicate `p` on `Elements`, which indicates whether an element fits the class of tokens to be parsed.

When applying the parser `elem(kind, p)` to some input `in`, the first element of the input stream is tested with predicate `p`. If `p` returns `true`, the parser succeeds. Its result is the element itself, and its remaining input is the input stream starting just after the element that was parsed. On the other hand, if `p` returns `false`, the parser fails with an error message that indicates what kind of token was expected.

Sequential composition

The `elem` parser only consumes a single element. To parse more interesting phrases, you can string parsers together with the sequential composition operator `~`. As you have seen before, `P~Q` is a parser that applies first the `P` parser to a given input string. Then, if `P` succeeds, the `Q` parser is applied to the input that's left after `P` has done its job.

The `~` combinator is implemented as a method in class `Parser`. Its definition is shown in [Listing 33.6](#). The method is a member of the `Parser` class. Inside this class, `p` is specified by the “`p =>`” part as an alias of `this`, so `p` designates the left operand (or: receiver) of `~`. Its right operand is represented by parameter `q`. Now, if `p~q` is run on some input `in`, first `p` is run on `in` and the result is analyzed in a pattern match. If `p` succeeds, `q` is run on the remaining input `in1`. If `q` also succeeds, the parser as a whole succeeds. Its result is a `~` object containing both the result of `p` (*i.e.*, `x`) and the result of `q` (*i.e.*, `y`). On the other hand, if either `p` or `q` fails the result of `p~q` is the `Failure` object returned by `p` or `q`.

```

abstract class Parser[+T] ... { p =>
  ...
  def ~ [U](q: => Parser[U]) = new Parser[T~U] {
    def apply(in: Input) = p(in) match {
      case Success(x, in1) =>
        q(in1) match {
          case Success(y, in2) => Success(new ~(x, y), in2)
          case failure => failure
        }
      case failure => failure
    }
  }
}

```

Listing 33.6 · The \sim combinator method.

The result type of \sim is a parser that returns an instance of the case class \sim with elements of types T and U. The type expression $T\sim U$ is just a more legible shorthand for the parameterized type $\sim[T, U]$. Generally, Scala always interprets a binary type operation such as $A \text{ op } B$, as the parameterized type $\text{op}[A, B]$. This is analogous to the situation for patterns, where a binary pattern $P \text{ op } Q$ is also interpreted as an application, *i.e.*, $\text{op}(P, Q)$.

The other two sequential composition operators, $\text{<}~$ and $\text{~}>$, could be defined just like \sim , only with some small adjustment in how the result is computed. A more elegant technique, though, is to define them in terms of \sim as follows:

```

def <~ [U](q: => Parser[U]): Parser[T] =
  (p~q) ^^ { case x~y => x }
def ~> [U](q: => Parser[U]): Parser[U] =
  (p~q) ^^ { case x~y => y }

```

Alternative composition

An alternative composition $P \mid Q$ applies either P or Q to a given input. It first tries P. If P succeeds, the whole parser succeeds with the result of P. Otherwise, if P fails, then Q is tried *on the same input* as P. The result of Q is then the result of the whole parser.

Here is a definition of `|` as a method of class `Parser`:

```
def | (q: => Parser[T]) = new Parser[T] {
  def apply(in: Input) = p(in) match {
    case s1 @ Success(_, _) => s1
    case failure => q(in)
  }
}
```

Note that if `P` and `Q` both fail, then the failure message is determined by `Q`. This subtle choice is discussed later, in [Section 33.9](#).

Dealing with recursion

Note that the `q` parameter in methods `~` and `|` is *by-name*—its type is preceded by `=>`. This means that the actual parser argument will be evaluated only when `q` is needed, which should only be the case after `p` has run. This makes it possible to write recursive parsers like the following one which parses a number enclosed by arbitrarily many parentheses:

```
def parens = floatingPointNumber | "(~parens~)"
```

If `|` and `~` took *by-value parameters*, this definition would immediately cause a stack overflow without reading anything, because the value of `parens` occurs in the middle of its right-hand side.

Result conversion

The last method of class `Parser` converts a parser’s result. The parser `P ^^ f` succeeds exactly when `P` succeeds. In that case it returns `P`’s result converted using the function `f`. Here is the implementation of this method:

```
def ^^ [U](f: T => U): Parser[U] = new Parser[U] {
  def apply(in: Input) = p(in) match {
    case Success(x, in1) => Success(f(x), in1)
    case failure => failure
  }
}
```

`} // end Parser`

Parsers that don't read any input

There are also two parsers that do not consume any input: `success(result)` always succeeds with the given result. The parser `failure(msg)` always fails with error message `msg`. Both are implemented as methods in trait `Parsers`, the outer trait that also contains class `Parser`:

```
def success[T](v: T) = new Parser[T] {
    def apply(in: Input) = Success(v, in)
}
def failure(msg: String) = new Parser[Nothing] {
    def apply(in: Input) = Failure(msg, in)
}
```

Option and repetition

Also defined in trait `Parsers` are the option and repetition combinators `opt`, `rep`, and `repsep`. They are all implemented in terms of sequential composition, alternative, and result conversion:

```
def opt[T](p: => Parser[T]): Parser[Option[T]] = (
    p ^^ Some(_)
    | success(None)
)

def rep[T](p: => Parser[T]): Parser[List[T]] = (
    p~rep(p) ^^ { case x~xs => x :: xs }
    | success(List())
)

def repsep[T](p: => Parser[T],
    q: => Parser[Any]): Parser[List[T]] = (
    p~rep(q~> p) ^^ { case r~rs => r :: rs }
    | success(List())
)

} // end Parsers
```

33.7 String literals and regular expressions

The parsers you saw so far made use of string literals and regular expressions to parse single words. The support for these comes from `RegexParsers`, a subtrait of `Parsers`:

```
trait RegexParsers extends Parsers {
```

This trait is more specialized than trait `Parsers` in that it only works for inputs that are sequences of characters:

```
type Elem = Char
```

It defines two methods, `literal` and `regex`, with the following signatures:

```
implicit def literal(s: String): Parser[String] = ...
implicit def regex(r: Regex): Parser[String] = ...
```

Note that both methods have an `implicit` modifier, so they are automatically applied whenever a `String` or `Regex` is given but a `Parser` is expected. That's why you can write string literals and regular expressions directly in a grammar, without having to wrap them with one of these methods. For instance, the parser `"(~expr~)"` will be automatically expanded to `literal("(")~expr~literal(")")`.

The `RegexParsers` trait also takes care of handling white space between symbols. To do this, it calls a method named `handleWhiteSpace` before running a `literal` or `regex` parser. The `handleWhiteSpace` method skips the longest input sequence that conforms to the `whiteSpace` regular expression, which is defined by default as follows:

```
protected val whiteSpace = """\s+""".r
} // end RegexParsers
```

If you prefer a different treatment of white space, you can override the `whiteSpace` val. For instance, if you want white space not to be skipped at all, you can override `whiteSpace` with the empty regular expression:

```
object MyParsers extends RegexParsers {
  override val whiteSpace = "".r
  ...
}
```

33.8 Lexing and parsing

The task of syntax analysis is often split into two phases. The *lexer* phase recognizes individual words in the input and classifies them into some *token* classes. This phase is also called *lexical analysis*. This is followed by a *syntactical analysis* phase that analyzes sequences of tokens. Syntactical analysis is also sometimes just called parsing, even though this is slightly imprecise, as lexical analysis can also be regarded as a parsing problem.

The `Parsers` trait as described in the previous section can be used for either phase, because its input elements are of the abstract type `Elem`. For lexical analysis, `Elem` would be instantiated to `Char`, meaning the individual characters that make up a word are being parsed. The syntactical analyzer would in turn instantiate `Elem` to the type of token returned by the lexer.

Scala's parsing combinators provide several utility classes for lexical and syntactic analysis. These are contained in two sub-packages, one for each kind of analysis:

```
scala.util.parsing.combinator.lexical  
scala.util.parsing.combinator.syntactical
```

If you want to split your parser into a separate lexer and syntactical analyzer, you should consult the Scaladoc documentation for these packages. But for simple parsers, the regular expression based approach shown previously in this chapter is usually sufficient.

33.9 Error reporting

There's one final topic that was not covered yet: how does the parser issue an error message? Error reporting for parsers is somewhat of a black art. One problem is that when a parser rejects some input, it generally has encountered many different failures. Each alternative parse must have failed, and recursively so at each choice point. Which of the usually numerous failures should be emitted as error message to the user?

Scala's parsing library implements a simple heuristic: among all failures, the one that occurred at the latest position in the input is chosen. In other words, the parser picks the longest prefix that is still valid and issues an error message that describes why parsing the prefix could not be continued

further. If there are several failure points at that latest position, the one that was visited last is chosen.

For instance, consider running the JSON parser on a faulty address book which starts with the line:

```
{ "name": John,
```

The longest legal prefix of this phrase is “{ “name”: ”. So the JSON parser will flag the word John as an error. The JSON parser expects a value at this point, but John is an identifier, which does not count as a value (presumably, the author of the document had forgotten to enclose the name in quotation marks). The error message issued by the parser for this document is:

```
[1.13] failure: "false" expected but identifier John found  
{ "name": John,  
^
```

The part that “false” was expected comes from the fact that “false” is the last alternative of the production for value in the JSON grammar. So this was the last failure at this point. Users who know the JSON grammar in detail can reconstruct the error message, but for non-experts this error message is probably surprising and can also be quite misleading.

A better error message can be engineered by adding a “catch-all” failure point as last alternative of a value production:

```
def value: Parser[Any] =  
  obj | arr | stringLit | floatingPointNumber | "null" |  
  "true" | "false" | failure("illegal start of value")
```

This addition does not change the set of inputs that are accepted as valid documents. What it does is improve the error messages, because now it will be the explicitly added failure that comes as last alternative and therefore gets reported:

```
[1.13] failure: illegal start of value  
{ "name": John,  
^
```

The implementation of the “latest possible” scheme of error reporting uses a field named `lastFailure` in trait `Parsers` to mark the failure that occurred at the latest position in the input:

```
var lastFailure: Option[Failure] = None
```

The field is initialized to `None`. It is updated in the constructor of the `Failure` class:

```
case class Failure(msg: String, in: Input)
  extends ParseResult[Nothing] {

  if (lastFailure.isDefined &&
      lastFailure.get.in.pos <= in.pos)
    lastFailure = Some(this)
}
```

The field is read by the `phrase` method, which emits the final error message if the parser failed. Here is the implementation of `phrase` in trait `Parsers`:

```
def phrase[T](p: Parser[T]) = new Parser[T] {
  lastFailure = None
  def apply(in: Input) = p(in) match {
    case s @ Success(out, in1) =>
      if (in1.atEnd) s
      else Failure("end of input expected", in1)
    case f : Failure =>
      lastFailure
  }
}
```

The `phrase` method runs its argument parser `p`. If `p` succeeds with a completely consumed input, the success result of `p` is returned. If `p` succeeds but the input is not read completely, a failure with message “end of input expected” is returned. If `p` fails, the failure or error stored in `lastFailure` is returned. Note that the treatment of `lastFailure` is non-functional; it is updated as a side effect by the constructor of `Failure` and by the `phrase` method itself. A functional version of the same scheme would be possible, but it would require threading the `lastFailure` value through every parser result, no matter whether this result is a `Success` or a `Failure`.

33.10 Backtracking versus LL(1)

The parser combinators employ *backtracking* to choose between different parsers in an alternative. In an expression `P | Q`, if `P` fails, then `Q` is run on

the same input as P. This happens even if P has parsed some tokens before failing. In this case the same tokens will be parsed again by Q.

Backtracking imposes only a few restrictions on how to formulate a grammar so that it can be parsed. Essentially, you just need to avoid left-recursive productions. A production such as:

$$\text{expr} ::= \text{expr} \text{ "+" term} \mid \text{term}.$$

will always fail because `expr` immediately calls itself and thus never progresses any further.¹ On the other hand, backtracking is potentially costly because the same input can be parsed several times. Consider for instance the production:

$$\text{expr} ::= \text{term} \text{ "+" expr} \mid \text{term}.$$

What happens if the `expr` parser is applied to an input such as $(1 + 2) * 3$ which constitutes a legal term? The first alternative would be tried, and would fail when matching the `+` sign. Then the second alternative would be tried on the same term and this would succeed. In the end the term ended up being parsed twice.

It is often possible to modify the grammar so that backtracking can be avoided. For instance, in the case of arithmetic expressions, either one of the following productions would work:

$$\text{expr} ::= \text{term} \text{ ["+" expr].}$$

$$\text{expr} ::= \text{term} \text{ {"+" term}.}$$

Many languages admit so-called “LL(1)” grammars.² When a combinator parser is formed from such a grammar, it will never backtrack, *i.e.*, the input position will never be reset to an earlier value. For instance, the grammars for arithmetic expressions and JSON terms earlier in this chapter are both LL(1), so the backtracking capabilities of the parser combinator framework are never exercised for inputs from these languages.

The combinator parsing framework allows you to express the expectation that a grammar is LL(1) explicitly, using a new operator `~!`. This operator is

¹There are ways to avoid stack overflows even in the presence of left-recursion, but this requires a more refined parsing combinator framework, which to date has not been implemented.

²Aho, et al., *Compilers: Principles, Techniques, and Tools*. [Aho86]

like sequential composition \sim but it will never backtrack to “un-read” input elements that have already been parsed. Using this operator, the productions in the arithmetic expression parser could alternatively be written as follows:

```
def expr : Parser[Any] =
  term ~! rep("+ " ~! term | "- " ~! term)
def term : Parser[Any] =
  factor ~! rep("* " ~! factor | "/" ~! factor)
def factor: Parser[Any] =
  "(" ~! expr ~! ")" | floatingPointNumber
```

One advantage of an LL(1) parser is that it can use a simpler input technique. Input can be read sequentially, and input elements can be discarded once they are read. That’s another reason why LL(1) parsers are usually more efficient than backtracking parsers.

33.11 Conclusion

You have now seen all the essential elements of Scala’s combinator parsing framework. It’s surprisingly little code for something that’s genuinely useful. With the framework you can construct parsers for a large class of context-free grammars. The framework lets you get started quickly, but it is also customizable to new kinds of grammars and input methods. Being a Scala library, it integrates seamlessly with the rest of the language. So it’s easy to integrate a combinator parser in a larger Scala program.

One downside of combinator parsers is that they are not very efficient, at least not when compared with parsers generated from special purpose tools such as Yacc or Bison. There are two reasons for this. First, the backtracking method used by combinator parsing is itself not very efficient. Depending on the grammar and the parse input, it might yield an exponential slow-down due to repeated backtracking. This can be fixed by making the grammar LL(1) and by using the committed sequential composition operator, $\sim!$.

The second problem affecting the performance of combinator parsers is that they mix parser construction and input analysis in the same set of operations. In effect, a parser is generated anew for each input that’s parsed.

This problem can be overcome, but it requires a different implementation of the parser combinator framework. In an optimizing framework, a parser would no longer be represented as a function from inputs to parse results.

Instead, it would be represented as a tree, where every construction step was represented as a case class. For instance, sequential composition could be represented by a case class `Seq`, alternative by `Alt`, and so on. The “outermost” parser method, `phrase`, could then take this symbolic representation of a parser and convert it to highly efficient parsing tables, using standard parser generator algorithms.

What’s nice about all this is that from a user perspective nothing changes compared to plain combinator parsers. Users still write parsers in terms of `ident`, `floatingPointNumber`, `~`, `|`, and so on. They need not be aware that these methods generate a symbolic representation of a parser instead of a parser function. Since the `phrase` combinator converts these representations into real parsers, everything works as before.

The advantage of this scheme with respect to performance is two-fold. First, you can now factor out parser construction from input analysis. If you were to write:

```
val jsonParser = phrase(value)
```

and then apply `jsonParser` to several different inputs, the `jsonParser` would be constructed only once, not every time an input is read.

Second, the parser generation can use efficient parsing algorithms such as LALR(1).³ These algorithms usually lead to much faster parsers than parsers that operate with backtracking.

At present, such an optimizing parser generator has not yet been written for Scala. But it would be perfectly possible to do so. If someone contributes such a generator, it will be easy to integrate into the standard Scala library. Even postulating that such a generator will exist at some point in the future, however, there are reasons for keeping the current parser combinator framework around. It is much easier to understand and to adapt than a parser generator, and the difference in speed would often not matter in practice, unless you want to parse very large inputs.

³Aho, et al., *Compilers: Principles, Techniques, and Tools*. [Aho86]

Chapter 34

GUI Programming

In this chapter you'll learn how to develop in Scala applications that use a graphical user interface (GUI). The applications we'll develop are based on a Scala library that provides access to Java's Swing framework of GUI classes. Conceptually, the Scala library resembles the underlying Swing classes, but hides much of their complexity. You'll find out that developing GUI applications using the framework is actually quite easy.

Even with Scala's simplifications, a framework like Swing is quite rich, with many different classes and many methods in each class. To find your way in such a rich library, it helps to use an IDE such as Scala's Eclipse plugin. The advantage is that the IDE can show you interactively with its command completion which classes are available in a package and which methods are available for objects you reference. This speeds up your learning considerably when you first explore an unknown library space.

34.1 A first Swing application

As a first Swing application, we'll start with a window containing a single button. To program with Swing, you need to import various classes from Scala's Swing API package:

```
import scala.swing._
```

[Listing 34.1](#) shows the code of your first Swing application in Scala. If you compile and run that file, you should see a window as shown on the left of [Figure 34.1](#). The window can be resized to a larger size as shown on the right of [Figure 34.1](#).




Figure 34.1 · A simple Swing application: initial (left) and resized (right).

```
import scala.swing._

object FirstSwingApp extends SimpleSwingApplication {
    def top = new MainFrame {
        title = "First Swing App"
        contents = new Button {
            text = "Click me"
        }
    }
}
```

Listing 34.1 · A simple Swing application in Scala.

If you analyze the code in Listing 34.1 line by line, you'll notice the following elements:

```
object FirstSwingApp extends SimpleSwingApplication {
```

In the first line after the import, the `FirstSwingApp` object inherits from `scala.swing.SimpleSwingApplication`. This application differs from traditional command-line applications, which may inherit from `scala.App`. The `SimpleSwingApplication` class already defines a `main` method that contains some setup code for Java's Swing framework. The `main` method then proceeds to call the `top` method, which you supply:

```
def top = new MainFrame {
```

The next line implements the `top` method. This method contains the code that defines your top-level GUI component. This is usually some kind

of `Frame`—*i.e.*, a window that can contain arbitrary data. In Listing 34.1, we chose a `MainFrame` as the top-level component. A `MainFrame` is like a normal Swing `Frame` except that closing it will also close the whole GUI application.

```
title = "First Swing App"
```

Frames have a number of attributes. Two of the most important are the frame’s `title`, which will be written in the title bar, and its `contents`, which will be displayed in the window itself. In Scala’s Swing API, such attributes are modeled as properties. You know from Section 18.2 that properties are encoded in Scala as pairs of getter and setter methods. For instance, the `title` property of a `Frame` object is modeled as a getter method:

```
def title: String
```

and a setter method:

```
def title_=(s: String)
```

It is this setter method that gets invoked by the above assignment to `title`. The effect of the assignment is that the chosen title is shown in the header of the window. If you leave it out, the window will have an empty title.

```
contents = new Button {
```

The top frame is the root component of the Swing application. It is a `Container`, which means that further components can be defined in it. Every Swing container has a `contents` property, which allows you to get and set the components it contains. The getter `contents` of this property has type `Seq[Component]`, indicating that a component can in general have several objects as its contents. Frames, however, always have just a single component as their `contents`. This component is set and potentially changed using the setter `contents_=`. For example, in Listing 34.1 a single `Button` constitutes the `contents` of the top frame.

```
text = "Click me"
```

The button also gets a title, in this case “Click me.”




Figure 34.2 · A reactive Swing application: initial (left) after clicks (right).

```
import scala.swing._

object SecondSwingApp extends SimpleSwingApplication {
    def top = new MainFrame {
        title = "Second Swing App"
        val button = new Button {
            text = "Click me"
        }
        val label = new Label {
            text = "No button clicks registered"
        }
        contents = new BoxPanel(Orientation.Vertical) {
            contents += button
            contents += label
            border = Swing.EmptyBorder(30, 30, 10, 30)
        }
    }
}
```

Listing 34.2 · Component assembly on a panel.

34.2 Panels and layouts

As next step, we'll add some text as a second content element to the top frame of the application. The left part of [Figure 34.2](#) shows what the application should look like.

You saw in the last section that a frame contains exactly one child com-

ponent. Hence, to make a frame with both a button and a label, you need to create a different container component that holds both. That's what *panels* are used for. A Panel is a container that displays all the components it contains according to some fixed layout rules. There are a number of different possible layouts that are implemented by various subclasses of class Panel, ranging from simple to quite intricate. In fact, one of the hardest parts of a complex GUI application can be getting the layouts right—it's not easy to come up with something that displays reasonably well on all sorts of devices and for all window sizes.

[Listing 34.2](#) shows a complete implementation. In this class, the two sub-components of the top frame are named button and label. The button is defined as before. The label is a displayed text field that can't be edited:

```
val label = new Label {  
    text = "No button clicks registered"  
}
```

The code in [Listing 34.2](#) picks a simple vertical layout where components are stacked on top of each other in a BoxPanel:

```
contents = new BoxPanel(Orientation.Vertical) {
```

The contents property of the BoxPanel is an (initially empty) buffer, to which the button and label elements are added with the += operator:

```
contents += button  
contents += label
```

We also add a border around the two objects by assigning to the border property of the panel:

```
border = Swing.EmptyBorder(30, 30, 10, 30)
```

As is the case with other GUI components, borders are represented as objects. EmptyBorder is a factory method in object Swing that takes four parameters indicating the width of the borders on the top, right, bottom, and left sides of the objects to be drawn.

Simple as it is, the example has already shown the basic way to structure a GUI application. It is built from components, which are instances of `scala.swing` classes such as `Frame`, `Panel`, `Label` or `Button`. Components

have properties, which can be customized by the application. Panel components can contain several other components in their `contents` property, so that in the end a GUI application consists of a tree of components.

34.3 Handling events

On the other hand, the application still misses an essential property. If you run the code in [Listing 34.2](#) and click on the displayed button, nothing happens. In fact, the application is completely static; it does not react in any way to user events except for the close button of the top frame, which terminates the application. So as a next step, we'll refine the application so that it displays together with the button a label that indicates how often the button was clicked. The right part of [Figure 34.2](#) contains a snapshot of what the application should look like after a few button clicks.

To achieve this behavior, you need to connect a user-input event (the button was clicked) with an action (the displayed label is updated). Java and Scala have fundamentally the same "publish/subscribe" approach to event handling: Components may be publishers and/or subscribers. A publisher publishes events. A subscriber subscribes with a publisher to be notified of any published events. Publishers are also called "event sources," and subscribers are also called "event listeners". For instance a `Button` is an event source, which publishes an event, `ButtonClicked`, indicating that the button was clicked.

In Scala, subscribing to an event source `source` is done by the call `listenTo(source)`. There's also a way to unsubscribe from an event source using `deafTo(source)`. In the current example application, the first thing to do is to get the top frame to listen to its button, so that it gets notified of any events that the button issues. To do that you need to add the following call to the body of the top frame:

```
listenTo(button)
```

Being notified of events is only half the story; the other half is handling them. It is here that the Scala Swing framework is most different from (and radically simpler than) the Java Swing API's. In Java, signaling an event means calling a "notify" method in an object that has to implement some `Listener` interfaces. Usually, this involves a fair amount of indirection and boilerplate code, which makes event-handling applications hard to write and read.

By contrast, in Scala, an event is a real object that gets sent to subscribing components much like messages are sent to actors. For instance, pressing a button will create an event which is an instance of the following case class:

```
case class ButtonClicked(source: Button)
```

The parameter of the case class refers to the button that was clicked. As with all other Scala Swing events, this event class is contained in a package named `scala.swing.event`.

To have your component react to incoming events you need to add a handler to a property called `reactions`. Here's the code that does this:

```
var nClicks = 0
reactions += {
    case ButtonClicked(b) =>
        nClicks += 1
        label.text = "Number of button clicks: " + nClicks
}
```

The first line above defines a variable, `nClicks`, which holds the number of times a button was clicked. The remaining lines add the code between braces as a *handler* to the `reactions` property of the top frame. Handlers are functions defined by pattern matching on events, much like Akka actor receive methods are defined by pattern matching on messages. The handler above matches events of the form `ButtonClicked(b)`, *i.e.*, any event which is an instance of class `ButtonClicked`. The pattern variable `b` refers to the actual button that was clicked. The action that corresponds to this event in the code above increments `nClicks` and updates the text of the label.

Generally, a handler is a `PartialFunction` that matches on events and performs some actions. It is also possible to match on more than one kind of event in a single handler by using multiple cases.

The `reactions` property implements a collection, just like the `contents` property does. Some components come with predefined reactions. For instance, a `Frame` has a predefined reaction that it will close if the user presses the close button on the upper right. If you install your own reactions by adding them with `+=` to the `reactions` property, the reactions you define will be considered in addition to the standard ones. Conceptually, the handlers installed in `reactions` form a stack. In the current example, if the top frame receives an event, the first handler tried will be the one that matches

```
import scala.swing._  
import scala.swing.event._  
  
object ReactiveSwingApp extends SimpleSwingApplication {  
    def top = new MainFrame {  
        title = "Reactive Swing App"  
        val button = new Button {  
            text = "Click me"  
        }  
        val label = new Label {  
            text = "No button clicks registered"  
        }  
        contents = new BoxPanel(Orientation.Vertical) {  
            contents += button  
            contents += label  
            border = Swing.EmptyBorder(30, 30, 10, 30)  
        }  
        listenTo(button)  
        var nClicks = 0  
        reactions += {  
            case ButtonClicked(b) =>  
                nClicks += 1  
                label.text = "Number of button clicks: " + nClicks  
        }  
    }  
}
```

Listing 34.3 · Implementing a reactive Swing application.

on `ButtonClicked`, because it was the last handler installed for the frame. If the received event is of type `ButtonClicked`, the code associated with the pattern will be invoked. After that code has completed, the system will search for further handlers in the event stack that might also be applicable. If the received event is not of type `ButtonClicked`, the event is immediately propagated to the rest of the installed handler stack. It's also possible to remove handlers from the `reactions` property, using the `-=` operator.

[Listing 34.3](#) shows the completed application, including `reactions`. The code illustrates the essential elements of a GUI application in Scala's Swing




Figure 34.3 · A converter between degrees Celsius and Fahrenheit.

framework: The application consists of a tree of components, starting with the top frame. The components shown in the code are Frame, BoxPanel, Button, and Label, but there are many other kinds of components defined in the Swing libraries. Each component is customized by setting attributes. Two important attributes are contents, which fixes the children of a component in the tree, and reactions, which determines how the component reacts to events.

34.4 Example: Celsius/Fahrenheit converter

As another example, we'll write a GUI program that converts between temperature degrees in Celsius and Fahrenheit. The user interface of the program is shown in [Figure 34.3](#). It consists of two text fields (shown in white) with a label following each. One text field shows temperatures in degrees Celsius, the other in degrees Fahrenheit. Each of the two fields can be edited by the user of the application. Once the user has changed the temperature in either field, the temperature in the other field should automatically update.

[Listing 34.4](#) shows the complete code that implements this application. The imports at the top of the code use a short-hand:

```
import swing._  
import event._
```

This is in fact equivalent to the imports used before:

```
import scala.swing._  
import scala.swing.event._
```

```
import swing._  
import event._  
  
object TempConverter extends SimpleSwingApplication {  
    def top = new MainFrame {  
        title = "Celsius/Fahrenheit Converter"  
        object celsius extends TextField { columns = 5 }  
        object fahrenheit extends TextField { columns = 5 }  
        contents = new FlowPanel {  
            contents += celsius  
            contents += new Label(" Celsius = ")  
            contents += fahrenheit  
            contents += new Label(" Fahrenheit")  
            border = Swing.EmptyBorder(15, 10, 10, 10)  
        }  
        listenTo(celsius, fahrenheit)  
        reactions += {  
            case EditDone(`fahrenheit`) =>  
                val f = fahrenheit.text.toInt  
                val c = (f - 32) * 5 / 9  
                celsius.text = c.toString  
            case EditDone(`celsius`) =>  
                val c = celsius.text.toInt  
                val f = c * 9 / 5 + 32  
                fahrenheit.text = f.toString  
        }  
    }  
}
```

Listing 34.4 · An implementation of the temperature converter.

The reason you can use the shorthand is that packages nest in Scala. Because package `scala.swing` is contained in package `scala`, and everything in that package imported automatically, you can write just `swing` to refer to the package. Likewise, package `scala.swing.event`, is contained as subpackage `event` in package `scala.swing`. Because you have imported everything in `scala.swing` in the first import, you can refer to the `event` package with just `event` thereafter.

The two components `celsius` and `fahrenheit` in `TempConverter` are objects of class `TextField`. A `TextField` in Swing is a component that lets you edit a single line of text. It has a default width, which is given in the `columns` property measured in characters (set to 5 for both fields).

The contents of `TempConverter` are assembled into a panel, which includes the two text fields and two labels that explain what the fields are. The panel is of class `FlowPanel`, which means it displays all its elements one after another, in one or more rows, depending on the width of the frame.

The reactions of `TempConverter` are defined by a handler that contains two cases. Each case matches an `EditDone` event for one of the two text fields. Such an event gets issued when a text field has been edited by the user. Note the form of the patterns, which include back ticks around the element names:

```
case EditDone(`celsius`)
```

As was explained in [Section 15.2](#), the back ticks around `celsius` ensure that the pattern matches only if the source of the event was the `celsius` object. If you had omitted the back ticks and just written `case EditDone(celsius)`, the pattern would have matched every event of class `EditDone`. The changed field would then be stored in the pattern variable `celsius`. Obviously, this is not what you want. Alternatively, you could have defined the two `TextField` objects starting with upper case characters, *i.e.*, `Celsius` and `Fahrenheit`. In that case you could have matched them directly without back ticks, as in `case EditDone(Celsius)`.

The two actions of the `EditDone` events convert one quantity to another. Each starts by reading out the contents of the modified field and converting it to an `Int`. It then applies the formula for converting one temperature degree to the other, and stores the result back as a string in the other text field.

34.5 Conclusion

This chapter has given you a first taste of GUI programming, using Scala's wrappers for the Swing framework. It has shown how to assemble GUI components, how to customize their properties, and how to handle events. For space reasons, we could discuss only a small number of simple components. There are many more kinds of components. You can find out about them by

consulting the Scala documentation of the package `scala.swing`. The next section will develop an example of a more complicated Swing application.

There are also many tutorials on the original Java Swing framework, on which the Scala wrapper is based.¹ The Scala wrappers resemble the underlying Swing classes, but try to simplify concepts where possible and make them more uniform. The simplification makes extensive use of the properties of the Scala language. For instance, Scala's emulation of properties and its operator overloading allow convenient property definitions using assignments and `+=` operations. Its “everything is an object” philosophy makes it possible to inherit the main method of a GUI application. The method can thus be hidden from user applications, including the boilerplate code for setting things up that comes with it. Finally, and most importantly, Scala's first-class functions and pattern matching make it possible to formulate event handling as the `reactions` component property, which greatly simplifies life for the application developer.

¹See, for instance, *The Java Tutorials*. [Jay]

Chapter 35

The SCells Spreadsheet

In the previous chapters you saw many different constructs of the Scala programming language. In this chapter you'll see how these constructs play together in the implementation of a sizable application. The task is to write a spreadsheet application, which will be named SCells.

There are several reasons why this task is interesting. First, everybody knows spreadsheets, so it is easy to understand what the application should do. Second, spreadsheets are programs that exercise a large range of different computing tasks. There's the visual aspect, where a spreadsheet is seen as a rich GUI application. There's the symbolic aspect, having to do with formulas and how to parse and interpret them. There's the calculational aspect, dealing with how to update possibly large tables incrementally. There's the reactive aspect, where spreadsheets are seen as programs that react in intricate ways to events. Finally, there's the component aspect where the application is constructed as a set of reusable components. All these aspects will be treated in depth in this chapter.

35.1 The visual framework

We'll start by writing the basic visual framework of the application. [Figure 35.1](#) shows the first iteration of the user interface. You can see that a spreadsheet is a scrollable table. It has rows going from 0 to 99 and columns going from A to Z. You express this in Swing by defining a spreadsheet as a `ScrollPane` containing a `Table`. [Listing 35.1](#) shows the code.

The spreadsheet component shown in [Listing 35.1](#) is defined in package `org.stairwaybook.scells`, which will contain all classes, traits, and




Figure 35.1 · A simple spreadsheet table.

objects needed for the application. It imports from package `scala.swing` essential elements of Scala's Swing wrapper. `Spreadsheet` itself is a class that takes `height` and `width` (in numbers of cells) as parameters. The class extends `ScrollPane`, which gives it the scroll-bars at the bottom and right in [Figure 35.1](#). It contains two sub-components named `table` and `rowHeader`.

The `table` component is an instance of an anonymous subclass of class `scala.swing.Table`. The four lines in its body set some of its attributes: `rowHeight` for the height of a table row in points, `autoResizeMode` to turn auto-sizing the table off, `showGrid` to show a grid of lines between cells, and `gridColor` to set the color of the grid to a dark gray.

The `rowHeader` component, which contains the row-number headers at the left of the spreadsheet in [Figure 35.1](#), is a `ListView` that displays in its

```
package org.stairwaybook.scells
import swing._

class Spreadsheet(val height: Int, val width: Int)
    extends ScrollPane {

    val table = new Table(height, width) {
        rowHeight = 25
        autoResizeMode = Table.AutoResizeMode.Off
        showGrid = true
        gridColor = new java.awt.Color(150, 150, 150)
    }

    val rowHeader =
        new ListView((0 until height) map (_.toString)) {
            fixedCellWidth = 30
            fixedCellHeight = table.rowHeight
        }

    viewportView = table
    rowHeaderView = rowHeader
}
```

Listing 35.1 · Code for spreadsheet in [Figure 35.1](#).

elements the strings 0 through 99. The two lines in its body fix the width of a cell to be 30 points and the height to be the same as the `table`'s `rowHeight`.

The whole spreadsheet is assembled by setting two fields in `ScrollPane`. The field `viewportView` is set to the `table`, and the field `rowHeaderView` is set to the `rowHeader` list. The difference between the two views is that a view port of a scroll pane is the area that scrolls with the two bars, whereas the row header on the left stays fixed when you move the horizontal scroll bar. By some quirk, Swing already supplies by default a column header at the top of the table, so there's no need to define one explicitly.

To try out the rudimentary spreadsheet shown in [Listing 35.1](#), you just need to define a main program that creates the `Spreadsheet` component. Such a program is shown in [Listing 35.2](#).

Program `Main` inherits from `SimpleSwingApplication`, which takes care of all the low-level details that need to be set up before a Swing application can be run. You only need to define the top-level window of the applica-

```
package org.stairwaybook.scells
import swing._

object Main extends SimpleSwingApplication {
    def top = new MainFrame {
        title = "ScalaSheet"
        contents = new Spreadsheet(100, 26)
    }
}
```

Listing 35.2 · The main program for the spreadsheet application.

cation in the `top` method. In our example, `top` is a `MainFrame` that has two elements defined: its `title`, set to “ScalaSheet,” and its `contents`, set to an instance of class `Spreadsheet` with 100 rows and 26 columns. That’s all. If you launch this application with `scala org.stairwaybook.scells.Main`, you should see the spreadsheet in [Figure 35.1](#).

35.2 Disconnecting data entry and display

If you play a bit with the spreadsheet written so far, you’ll quickly notice that the output that’s displayed in a cell is always exactly what you entered in the cell. A real spreadsheet does not behave like that. In a real spreadsheet, you would enter a formula and you’d see its value. So what is entered into a cell is different from what is displayed.

As a first step to a real spreadsheet application, you should concentrate on disentangling data entry and display. The basic mechanism for display is contained in the `rendererComponent` method of class `Table`. By default, `rendererComponent` always displays what’s entered. If you want to change that, you need to override `rendererComponent` to do something different. [Listing 35.3](#) shows a new version of `Spreadsheet` with a `rendererComponent` method.

The `rendererComponent` method overrides a default method in class `Table`. It takes four parameters. The `isSelected` and `hasFocus` parameters are Booleans that indicate whether the cell has been selected and whether it has focus, meaning that keyboard events will go into the cell. The remaining two parameters, `row` and `column`, give the cell’s coordinates.

```
package org.stairwaybook.scells
import swing._

class Spreadsheet(val height: Int, val width: Int)
    extends ScrollPane {

    val cellModel = new Model(height, width)
    import cellModel._

    val table = new Table(height, width) {
        // settings as before...

        override def rendererComponent(isSelected: Boolean,
            hasFocus: Boolean, row: Int, column: Int): Component =
            if (hasFocus) new TextField(userData(row, column))
            else
                new Label(cells(row)(column).toString) {
                    xAlignment = Alignment.Right
                }

        def userData(row: Int, column: Int): String = {
            val v = this(row, column)
            if (v == null) "" else v.toString
        }
    }
    // rest as before...
}
```

Listing 35.3 · A spreadsheet with a `rendererComponent` method.

The new `rendererComponent` method checks whether the cell has input focus. If `hasFocus` is true, the cell is used for editing. In this case you want to display an editable `TextField` that contains the data the user has entered so far. This data is returned by the helper method `userData`, which displays the contents of the table at a given `row` and `column`. The contents are retrieved by the call `this(row, column)`.¹ The `userData` method also takes care to display a `null` element as the empty string instead of “null.”

¹Although “`this(row, column)`” may look similar to a constructor invocation, it is in this case an invocation of the `apply` method on the current `Table` instance.

```
package org.stairwaybook.scells
class Model(val height: Int, val width: Int) {
    case class Cell(row: Int, column: Int)
    val cells = Array.ofDim[Cell](height, width)
    for (i <- 0 until height; j <- 0 until width)
        cells(i)(j) = new Cell(i, j)
}
```

Listing 35.4 · First version of the Model class.

So far so good. But what should be displayed if the cell does not have focus? In a real spreadsheet this would be the value of a cell. Thus, there are really two tables at work. The first table, named table contains what the user entered. A second “shadow” table contains the internal representation of cells and what should be displayed. In the spreadsheet example, this table is a two-dimensional array called cells. If a cell at a given row and column does not have editing focus, the rendererComponent method will display the element cells(row)(column). The element cannot be edited, so it should be displayed in a Label instead of in an editable TextField.

It remains to define the internal array of cells. You could do this directly in the Spreadsheet class, but it’s generally preferable to separate the view of a GUI component from its internal model. That’s why in the example above the cells array is defined in a separate class named Model. The model is integrated into the Spreadsheet by defining a value cellModel of type Model. The import clause that follows this val definition makes the members of cellModel available inside Spreadsheet without having to prefix them. Listing 35.4 shows a first simplified version of a Model class. The class defines an inner class, Cell, and a two-dimensional array, cells, of Cell elements. Each element is initialized to be a fresh Cell.

That’s it. If you compile the modified Spreadsheet class with the Model class and run the Main application you should see a window as in Figure 35.2.

The objective of this section was to arrive at a design where the displayed value of a cell is different from the string that was entered into it. This objective has clearly been met, albeit in a very crude way. In the new spreadsheet you can enter anything you want into a cell, but it will always display just its coordinates once it loses focus. Clearly, we are not done yet.

	A	B	C	D	E	F
0	Cell(0,0)	Cell(0,1)	Cell(0,2)	Cell(0,3)	Cell(0,4)	Cell(0,5)
1	Cell(1,0)	Cell(1,1)	Cell(1,2)	Cell(1,3)	Cell(1,4)	Cell(1,5)
2	Cell(2,0)	Cell(2,1)	Cell(2,2)	Cell(2,3)	Cell(2,4)	Cell(2,5)
3	Cell(3,0)	Cell(3,1)	Cell(3,2)	Cell(3,3)	Cell(3,4)	Cell(3,5)
4	Cell(4,0)	Cell(4,1)	Cell(4,2)	Cell(4,3)	Cell(4,4)	Cell(4,5)
5	Cell(5,0)	Cell(5,1)	Cell(5,2)	Cell(5,3)	Cell(5,4)	Cell(5,5)
6	Cell(6,0)	Cell(6,1)	Cell(6,2)	Cell(6,3)	Cell(6,4)	Cell(6,5)
7	Cell(7,0)	Cell(7,1)	Cell(7,2)	Cell(7,3)	Cell(7,4)	Cell(7,5)
8	Cell(8,0)	Cell(8,1)	Cell(8,2)	Cell(8,3)	Cell(8,4)	Cell(8,5)
9	Cell(9,0)	Cell(9,1)	Cell(9,2)	Cell(9,3)	Cell(9,4)	Cell(9,5)
10	Cell(10,0)	Cell(10,1)		Cell(10,3)	Cell(10,4)	Cell(10,5)
11	Cell(11,0)	Cell(11,1)	Cell(11,2)	Cell(11,3)	Cell(11,4)	Cell(11,5)
12	Cell(12,0)	Cell(12,1)	Cell(12,2)	Cell(12,3)	Cell(12,4)	Cell(12,5)
13	Cell(13,0)	Cell(13,1)	Cell(13,2)	Cell(13,3)	Cell(13,4)	Cell(13,5)
14	Cell(14,0)	Cell(14,1)	Cell(14,2)	Cell(14,3)	Cell(14,4)	Cell(14,5)
15	Cell(15,0)	Cell(15,1)	Cell(15,2)	Cell(15,3)	Cell(15,4)	Cell(15,5)

Figure 35.2 · Cells displaying themselves.

35.3 Formulas

In reality, a spreadsheet cell holds two things: An actual *value* and a *formula* to compute this value. There are three types of formulas in a spreadsheet:

1. Numeric values such as 1.22, -3, or 0.
2. Textual labels such as Annual sales, Deprecation, or total.
3. Formulas that compute a new value from the contents of cells, such as “=add(A1,B2)”, or “=sum(mul(2, A2), C1:D16)”

A formula that computes a value always starts with an equals sign and is followed by an arithmetic expression. The SCells spreadsheet has a par-

ticularly simple and uniform convention for arithmetic expressions: every expression is an application of some function to a list of arguments. The function name is an identifier such as `add` for binary addition, or `sum` for summation of an arbitrary number of operands. A function argument can be a number, a reference to a cell, a reference to a range of cells such as `C1:D16`, or another function application. You'll see later that SCells has an open architecture that makes it easy to install your own functions via mixin composition.

The first step to handling formulas is writing down the types that represent them. As you might expect, the different kinds of formulas are represented by case classes. Listing 35.5 shows the contents of a file named `Formulas.scala`, where these case classes are defined:

```
package org.stairwaybook.scells

trait Formula

case class Coord(row: Int, column: Int) extends Formula {
    override def toString = ('A' + column).toChar.toString + row
}

case class Range(c1: Coord, c2: Coord) extends Formula {
    override def toString = c1.toString + ":" + c2.toString
}

case class Number(value: Double) extends Formula {
    override def toString = value.toString
}

case class Textual(value: String) extends Formula {
    override def toString = value
}

case class Application(function: String,
    arguments: List[Formula]) extends Formula {

    override def toString =
        function + arguments.mkString("(", ", ", ", ", ")")
}

object Empty extends Textual("")
```

Listing 35.5 · Classes representing formulas.

Trait `Formula`, shown in Listing 35.5, has five case classes as children:

Coord	for cell coordinates such as A3,
Range	for cell ranges such as A3:B17,
Number	for floating-point numbers such as 3.1415,
Textual	for textual labels such as Deprecation,
Application	for function applications such as sum(A1,A2).

Each case class overrides the `toString` method so that it displays its kind of formula in the standard way shown above. For convenience there's also an `Empty` object that represents the contents of an empty cell. The `Empty` object is an instance of the `Textual` class with an empty string argument.

35.4 Parsing formulas

In the previous section you saw the different kinds of formulas and how they display as strings. In this section you'll see how to reverse the process: to transform a user input string into a `Formula` tree. The rest of this section explains one by one the different elements of a class `FormulaParsers`, which contains the parsers that do the transformation. The class builds on the combinator framework given in [Chapter 33](#). Specifically, formula parsers are an instance of the `RegexParsers` class explained in that chapter:

```
package org.stairwaybook.scells
import scala.util.parsing.combinator._
object FormulaParsers extends RegexParsers {
```

The first two elements of object `FormulaParsers` are auxiliary parsers for identifiers and decimal numbers:

```
def ident: Parser[String] = """[a-zA-Z_]\w*""".r
def decimal: Parser[String] = """-?\d+(\.\d*)?""".r
```

As you can see from the first regular expression above, an identifier starts with a letter or underscore. This is followed by an arbitrary number of “word” characters represented by the regular expression code `\w`, which recognizes letters, digits or underscores. The second regular expression describes decimal numbers, which consist of an optional minus sign, one or more digits that are represented by regular expression code `\d`, and an optional decimal part consisting of a period followed by zero or more digits.

The next element of object `FormulaParsers` is the cell parser, which recognizes the coordinates of a cell, such as C11 or B2. It first calls a regular expression parser that determines the form of a coordinate: a single letter followed by one or more digits. The string returned from that parser is then converted to a cell coordinate by separating the letter from the numerical part and converting the two parts to indices for the cell's column and row:

```
def cell: Parser[Coord] =  
  """[A-Za-z]\d+""".r ^^ { s =>  
    val column = s.charAt(0).toUpperCase - 'A'  
    val row = s.substring(1).toInt  
    Coord(row, column)  
  }
```

Note that the `cell` parser is a bit restrictive in that it allows only column coordinates consisting of a single letter. Hence the number of spreadsheet columns is in effect restricted to be at most 26, because further columns cannot be parsed. It's a good idea to generalize the parser so that it accepts cells with several leading letters. This is left as an exercise to you.

The range parser recognizes a range of cells. Such a range is composed of two cell coordinates with a colon between them:

```
def range: Parser[Range] =  
  cell~":"~cell ^^ {  
    case c1~":"~c2 => Range(c1, c2)  
  }
```

The number parser recognizes a decimal number, which is converted to a `Double` and wrapped in an instance of the `Number` class:

```
def number: Parser[Number] =  
  decimal ^^ (d => Number(d.toDouble))
```

The application parser recognizes a function application. Such an application is composed of an identifier followed by a list of argument expressions in parentheses:

```
def application: Parser[Application] =  
  ident~":"(~repsep(expr, ",")~")" ^^ {  
    case f~":"(~ps~")" => Application(f, ps)  
  }
```

The `expr` parser recognizes a formula expression—either a top-level formula following an ‘=’, or an argument to a function. Such a formula expression is defined to be a cell, a range of cells, a number, or an application:

```
def expr: Parser[Formula] =  
    range | cell | number | application
```

This definition of the `expr` parser contains a slight oversimplification because ranges of cells should only appear as function arguments; they should not be allowed as top-level formulas. You could change the formula grammar so that the two uses of expressions are separated, and ranges are excluded syntactically from top-level formulas. In the spreadsheet presented here such an error is instead detected once an expression is evaluated.

The `textual` parser recognizes an arbitrary input string, as long as it does not start with an equals sign (recall that strings that start with ‘=’ are considered to be formulas):

```
def textual: Parser[Textual] =  
    """[^=].*""".r ^^ Textual
```

The `formula` parser recognizes all kinds of legal inputs into a cell. A formula is either a number, or a `textual` entry, or a formula starting with an equals sign:

```
def formula: Parser[Formula] =  
    number | textual | "=" ~> expr
```

This concludes the grammar for spreadsheet cells. The final method `parse` uses this grammar in a method that converts an input string into a `Formula` tree:

```
def parse(input: String): Formula =  
    parseAll(formula, input) match {  
        case Success(e, _) => e  
        case f: NoSuccess => Textual("[" + f.msg + "]")  
    }  
} //end FormulaParsers
```

The `parse` method parses all of the input with the `formula` parser. If that succeeds, the resulting formula is returned. If it fails, a `Textual` object with an error message is returned instead.

```
package org.stairwaybook.scells
import swing._
import event._

class Spreadsheet(val height: Int, val width: Int) ... {
    val table = new Table(height, width) {
        ...
        reactions += {
            case TableUpdated(table, rows, column) =>
                for (row <- rows)
                    cells(row)(column).formula =
                        FormulaParsers.parse(userData(row, column))
        }
    }
}
```

Listing 35.6 · A spreadsheet that parses formulas.

That's everything there is to parsing formulas. The only thing that remains is to integrate the parser into the spreadsheet. To do this, you can enrich the Cell class in class Model by a formula field:

```
case class Cell(row: Int, column: Int) {
    var formula: Formula = Empty
    override def toString = formula.toString
}
```

In the new version of the Cell class, the `toString` method is defined to display the cell's formula. That way you can check whether formulas have been correctly parsed.

The last step in this section is to integrate the parser into the spreadsheet. Parsing a formula happens as a reaction to the user's input into a cell. A completed cell input is modeled in the Swing library by a `TableUpdated` event. The `TableUpdated` class is contained in package `scala.swing.event`. The event is of the form:

```
TableUpdated(table, rows, column)
```

It contains the `table` that was changed, as well as a set of coordinates of affected cells given by `rows` and `column`. The `rows` parameter is a range




Figure 35.3 · Cells displaying their formulas.

value of type `Range[Int]`.² The `column` parameter is an integer. So in general a `TableUpdated` event can refer to several affected cells, but they would be on a consecutive range of rows and share the same column.

Once a table is changed, the affected cells need to be re-parsed. To react to a `TableUpdated` event, you add a case to the `reactions` value of the `table` component, as is shown in [Listing 35.6](#). Now, whenever the table is edited the formulas of all affected cells will be updated by parsing the corresponding user data. When compiling the classes discussed so far and launching the `sheets.Main` application you should see a spreadsheet application like the one shown in [Figure 35.3](#). You can edit cells by typing into

²`Range[Int]` is also the type of a Scala expression such as “1 to N”.

them. After editing is done, a cell displays the formula it contains. You can also try to type some illegal input such as the one reading `=add(1, X)` in the field that has the editing focus in [Figure 35.3](#). Illegal input will show up as an error message. For instance, once you'd leave the edited field in [Figure 35.3](#) you should see the error message `[`(' expected]` in the cell (to see all of the error message you might need to widen the column by dragging the separation between the column headers to the right).

35.5 Evaluation

Of course, in the end a spreadsheet should evaluate formulas, not just display them. In this section, we'll add the necessary components to achieve this.

What's needed is a method, `evaluate`, which takes a formula and returns the value of that formula in the current spreadsheet, represented as a `Double`. We'll place this method in a new trait, `Evaluator`. The method needs to access the `cells` field in class `Model` to find out about the current values of cells that are referenced in a formula. On the other hand, the `Model` class needs to call `evaluate`. Hence, there's a mutual dependency between the `Model` and the `Evaluator`. A good way to express such mutual dependencies between classes was shown in [Chapter 29](#): you use inheritance in one direction and self types in the other.

In the spreadsheet example, class `Model` inherits from `Evaluator` and thus gains access to its `evaluation` method. To go the other way, class `Evaluator` defines its self type to be `Model`, like this:

```
package org.stairwaybook.scells
trait Evaluator { this: Model => ...
```

That way, the `this` value inside class `Evaluator` is assumed to be `Model` and the `cells` array is accessible by writing either `cells` or `this.cells`.

Now that the wiring is done, we'll concentrate on defining the contents of class `Evaluator`. [Listing 35.7](#) shows the implementation of the `evaluate` method. As you might expect, the method contains a pattern match over the different types of formulas. For a coordinate `Coord(row, column)`, it returns the value of the `cells` array at that coordinate. For a number `Number(v)`, it returns the value `v`. For a textual label `Textual(s)`, it returns zero. Finally, for an application `Application(function, arguments)`, it

```
def evaluate(e: Formula): Double = try {
    e match {
        case Coord(row, column) =>
            cells(row)(column).value
        case Number(v) =>
            v
        case Textual(_) =>
            0
        case Application(function, arguments) =>
            val argvals = arguments flatMap evalList
            operations(function)(argvals)
    }
} catch {
    case ex: Exception => Double.NaN
}
```

Listing 35.7 · The evaluate method of trait Evaluator.

computes the values of all arguments, retrieves a function object corresponding to the function name from an operations table and applies that function to all argument values.

The operations table maps function names to function objects. It is defined as follows:

```
type Op = List[Double] => Double
val operations = new collection.mutable.HashMap[String, Op]
```

As you can see from this definition, operations are modeled as functions from lists of values to values. The Op type introduces a convenient alias for the type of an operation.

The computation in evaluate is wrapped in a try-catch to guard against input errors. There are actually quite a few things that can go wrong when evaluating a cell formula: coordinates might be out of range; function names might be undefined; functions might have the wrong number of arguments; arithmetic operations might be illegal or overflow. The reaction to any of these errors is the same: a “not-a-number” value is returned. The returned value, Double.NaN, is the IEEE representation for a computation that does not have a representable floating-point value. This might happen because

of an overflow or a division by zero, for example. The evaluate method of Listing 35.7 chooses to return the same value also for all other kinds of errors. The advantage of this scheme is that it's simple to understand and doesn't require much code to implement. Its disadvantage is that all kinds of errors are lumped together, so a spreadsheet user does not get any detailed feedback on what went wrong. If you wish you can experiment with more refined ways of representing errors in the SCells application.

The evaluation of arguments is different from the evaluation of top-level formulas. Arguments may be lists whereas top-level functions may not. For instance, the argument expression A1:A3 in `sum(A1:A3)` returns the values of cells A1, A2, A3 in a list. This list is then passed to the `sum` operation. It's also possible to mix lists and single values in argument expressions, for instance the operation `sum(A1:A3, 1.0, C7)`, which would sum up five values. To handle arguments that might evaluate to lists, there's another evaluation function, called `evalList`, which takes a formula and returns a list of values:

```
private def evalList(e: Formula): List[Double] = e match {
    case Range(_, _) => references(e) map (_.value)
    case _ => List(evaluate(e))
}
```

If the formula argument passed to `evalList` is a `Range`, the returned value is a list consisting of the values of all cells referenced by the range. For every other formula the result is a list consisting of the single result value of that formula. The cells referenced by a formula are computed by a third function, `references`. Here is its definition:

```
def references(e: Formula): List[Cell] = e match {
    case Coord(row, column) =>
        List(cells(row)(column))
    case Range(Coord(r1, c1), Coord(r2, c2)) =>
        for (row <- (r1 to r2).toList; column <- c1 to c2)
            yield cells(row)(column)
    case Application(function, arguments) =>
        arguments flatMap references
    case _ =>
        List()
}
```

}

```
} // end Evaluator
```

The references method is actually more general than needed right now in that it computes the list of cells referenced by any sort of formula, not just a Range formula. It will turn out later that the added functionality is needed to compute the sets of cells that need updating. The body of the method is a straightforward pattern match on kinds of formulas. For a coordinate Coord(row, column), it returns a single-element list containing the cell at that coordinate. For a range expression Range(coord1, coord2), it returns all cells between the two coordinates, computed by a for expression. For a function application Application(function, arguments), it returns the cells referenced by each argument expression, concatenated via flatMap into a single list. For the other two types of formulas, Textual and Number, it returns an empty list.

35.6 Operation libraries

The class Evaluator itself defines no operations that can be performed on cells: its operations table is initially empty. The idea is to define such operations in other traits, which are then mixed into the Model class. Listing 35.8 shows an example trait that implements common arithmetic operations:

```
package org.stairwaybook.scells
trait Arithmetic { this: Evaluator =>
  operations += (
    "add"  -> { case List(x, y) => x + y },
    "sub"  -> { case List(x, y) => x - y },
    "div"  -> { case List(x, y) => x / y },
    "mul"  -> { case List(x, y) => x * y },
    "mod"  -> { case List(x, y) => x % y },
    "sum"  -> { xs => (0.0 /: xs)(_ + _) },
    "prod" -> { xs => (1.0 /: xs)(_ * _) }
  )
}
```

Listing 35.8 · A library for arithmetic operations.

Interestingly, this trait has no exported members. The only thing it does is populate the operations table during its initialization. It gets access to

that table by using a self type Evaluator, *i.e.*, by the same technique the `Arithmetic` class uses to get access to the model.

Of the seven operations that are defined by the `Arithmetic` trait, five are binary operations and two take an arbitrary number of arguments. The binary operations all follow the same schema. For instance, the addition operation `add` is defined by the expression:

```
{ case List(x, y) => x + y }
```

That is, it expects an argument list consisting of two elements `x` and `y` and returns the sum of `x` and `y`. If the argument list contains a number of elements different from two, a `MatchError` is thrown. This corresponds to the general “let it crash” philosophy of SCell’s evaluation model, where incorrect input is expected to lead to a runtime exception that then gets caught by the try-catch inside the evaluation method.

The last two operations, `sum` and `prod`, take a list of arguments of arbitrary length and insert a binary operation between successive elements. So they are instances of the “fold left” schema that’s expressed in class `List` by the `/:` operation. For instance, to sum a list of numbers `List(x, y, z)`, the operation computes $0 + x + y + z$. The first operand, `0`, is the result if the list is empty.

You can integrate this operation library into the spreadsheet application by mixing the `Arithmetic` trait into the `Model` class, like this:

```
package org.stairwaybook.scells

class Model(val height: Int, val width: Int)
    extends Evaluator with Arithmetic {

    case class Cell(row: Int, column: Int) {
        var formula: Formula = Empty
        def value = evaluate(formula)

        override def toString = formula match {
            case Textual(s) => s
            case _ => value.toString
        }
    }

    ... // rest as before
}
```




Figure 35.4 · Cells that evaluate.

Another change in the `Model` class concerns the way cells display themselves. In the new version, the displayed value of a cell depends on its formula. If the formula is a `Textual` field, the contents of the field are displayed literally. In all other cases, the formula is evaluated and the result value of that evaluation is displayed.

If you compile the changed traits and classes and relaunch the Main program you get something that starts to resemble a real spreadsheet. [Figure 35.4](#) shows an example. You can enter formulas into cells and get them to evaluate themselves. For instance, once you close the editing focus on cell C5 in [Figure 35.4](#), you should see 86.0, the result of evaluating the formula `sum(C1:C4)`.

However, there's a crucial element still missing. If you change the value

of cell C1 in [Figure 35.4](#) from 20 to 100, the sum in cell C5 will not be automatically updated to 166. You'll have to click on C5 manually to see a change in its value. What's still missing is a way to have cells recompute their values automatically after a change.

35.7 Change propagation

If a cell's value has changed, all cells that depend on that value should have their results recomputed and redisplayed. The simplest way to achieve this would be to recompute the value of every cell in the spreadsheet after each change. However such an approach does not scale well as the spreadsheet grows in size.

A better approach is to recompute the values of only those cells that refer to a changed cell in their formula. The idea is to use an event-based publish/subscribe framework for change propagation: once a cell gets assigned a formula, it will subscribe to be notified of all value changes in cells to which the formula refers. A value change in one of these cells will trigger a re-evaluation of the subscriber cell. If such a re-evaluation causes a change in the value of the cell, it will in turn notify all cells that depend on it. The process continues until all cell values have stabilized, *i.e.*, there are no more changes in the values of any cell.³

The publish/subscribe framework is implemented in class `Model` using the standard event mechanism of Scala's Swing framework. Here's a new (and final) version of this class:

```
package org.stairwaybook.scells
import swing._

class Model(val height: Int, val width: Int)
  extends Evaluator with Arithmetic {
```

Compared to the previous version of `Model`, this version adds a new import of `swing._`, which makes Swing's event abstractions directly available.

The main modifications of class `Model` concern the nested class `Cell`. Class `Cell` now inherits from `Publisher`, so that it can publish events. The event-handling logic is completely contained in the setters of two properties: `value` and `formula`. Here is `Cell`'s new version:

³This assumes that there are no cyclic dependencies between cells. We discuss dropping this assumption at the end of this chapter.

```
case class Cell(row: Int, column: Int) extends Publisher {
  override def toString = formula match {
    case Textual(s) => s
    case _ => value.toString
  }
}
```

To the outside, it looks like `value` and `formula` are two variables in class `Cell`. Their actual implementation is in terms of two private fields that are equipped with public getters, `value` and `formula`, and setters, `value_=` and `formula_=`. Here are the definitions implementing the `value` property:

```
private var v: Double = 0
def value: Double = v
def value_=(w: Double) = {
  if (!(v == w || v.isNaN && w.isNaN)) {
    v = w
    publish(ValueChanged(this))
  }
}
```

The `value_=` setter assigns a new value `w` to the private field `v`. If the new value is different from the old one, it also publishes a `ValueChanged` event with the cell itself as argument. Note that the test whether the value has changed is a bit tricky because it involves the value `NaN`. The Java spec says that `NaN` is different from every other value, including itself! Therefore, a test whether two values are the same has to treat `NaN` specially: two values `v`, `w` are the same if they are equal with respect to `==`, or they are both the value `NaN`, *i.e.*, `v.isNaN` and `w.isNaN` both yield `true`.

Whereas the `value_=` setter does the publishing in the publish/subscribe framework, the `formula_=` setter does the subscribing:

```
private var f: Formula = Empty
def formula: Formula = f
def formula_=(f: Formula) = {
  for (c <- references(formula)) deafTo(c)
  this.f = f
  for (c <- references(formula)) listenTo(c)
  value = evaluate(f)
}
```

If a cell is assigned a new formula, it first unsubscribes with `deafTo` from all cells referenced by the previous formula value. It then stores the new formula in the private variable `f` and subscribes with `listenTo` to all cells referenced by it. Finally, it recomputes its value using the new formula.

The last piece of code in the revised class `Cell` specifies how to react to a `ValueChanged` event:

```
reactions += {  
    case ValueChanged(_) => value = evaluate(formula)  
}  
} // end class Cell
```

The `ValueChanged` class is also contained in class `Model`:

```
case class ValueChanged(cell: Cell) extends event.Event
```

The rest of class `Model` is as before:

```
val cells = Array.ofDim[Cell](height, width)  
for (i <- 0 until height; j <- 0 until width)  
    cells(i)(j) = new Cell(i, j)  
} // end class Model
```

The spreadsheet code is now almost complete. The final piece missing is the re-display of modified cells. So far, all value propagation concerned the internal `Cell` values only; the visible table was not affected. One way to change this would be to add a `redraw` command to the `value_=` setter. However, this would undermine the strict separation between model and view that you have seen so far. A more modular solution is to notify the table of all `ValueChanged` events and let it do the redrawing itself. [Listing 35.9](#) shows the final spreadsheet component, which implements this scheme.

Class `Spreadsheet` of [Listing 35.9](#) has only two new revisions. First, the `table` component now subscribes with `listenTo` to all cells in the model. Second, there's a new case in the table's `reactions`: if it is notified of a `ValueChanged(cell)` event, it demands a redraw of the corresponding cell with a call of `updateCell(cell.row, cell.column)`.

```
package org.stairwaybook.scells
import swing._, event._

class Spreadsheet(val height: Int, val width: Int)
    extends ScrollPane {

    val cellModel = new Model(height, width)
    import cellModel._

    val table = new Table(height, width) {
        ... // settings as in Listing 35.1

        override def rendererComponent(
            isSelected: Boolean, hasFocus: Boolean,
            row: Int, column: Int) =
            ... // as in Listing 35.3

        def userData(row: Int, column: Int): String =
            ... // as in Listing 35.3

        reactions += {
            case TableUpdated(table, rows, column) =>
                for (row <- rows)
                    cells(row)(column).formula =
                        FormulaParsers.parse(userData(row, column))
            case ValueChanged(cell) =>
                updateCell(cell.row, cell.column)
        }
        for (row <- cells; cell <- row) listenTo(cell)
    }

    val rowHeader = new ListView(0 until height) {
        fixedCellWidth = 30
        fixedCellHeight = table.rowHeight
    }

    viewportView = table
    rowHeaderView = rowHeader
}
```

Listing 35.9 · The finished spreadsheet component.

35.8 Conclusion

The spreadsheet developed in this chapter is fully functional, even though at some points it adopts the simplest solution to implement rather than the most convenient one for the user. That way, it could be written in just under 200 lines of code. Nevertheless, the architecture of the spreadsheet makes modifications and extensions easy. In case you would like to experiment with the code a bit further, here are some suggestions of what you could change or add:

1. You could make the spreadsheet resizable, so that the number of rows and columns can be changed interactively.
2. You could add new kinds of formulas, for instance binary operations, or other functions.
3. You might think about what to do when cells refer recursively to themselves. For instance, if cell A1 holds the formula `add(B1, 1)` and cell B1 holds the formula `mul(A1, 2)`, a re-evaluation of either cell will trigger a stack-overflow. Clearly, that's not a very good solution. As alternatives, you could either disallow such a situation, or just compute one iteration each time one of the cells is touched.
4. You could enhance error handling, giving more detailed messages describing what went wrong.
5. You could add a formula entry field at the top of the spreadsheet, so that long formulas could be entered more conveniently.

At the beginning of this book we stressed the scalability aspect of Scala. We claimed that the combination of Scala's object-oriented and functional constructs makes it suitable for programs ranging from small scripts to very large systems. The spreadsheet presented here is clearly still a small system, even though it would probably take up much more than 200 lines in most other languages. Nevertheless, you can see many of the details that make Scala scalable at play in this application.

The spreadsheet uses Scala's classes and traits with their mixin composition to combine its components in flexible ways. Recursive dependencies between components are expressed using self types. The need for static state is completely eliminated—the only top-level components that are not classes

are formula trees and formula parsers, and both of these are purely functional. The application also uses higher-order functions and pattern matching extensively, both for accessing formulas and for event handling. So it is a good showcase of how functional and object-oriented programming can be combined smoothly.

One important reason why the spreadsheet application is so concise is that it can base itself on powerful libraries. The parser combinator library provides in effect an internal domain-specific language for writing parsers. Without it, parsing formulas would have been much more difficult. The event handling in Scala's Swing libraries is a good example of the power of control abstractions. If you know Java's Swing libraries, you probably appreciate the conciseness of Scala's reactions concept, particularly when compared to the tedium of writing notify methods and implementing listener interfaces in the classical publish/subscribe design pattern. So the spreadsheet demonstrates the benefits of extensibility, where high-level libraries can be made to look just like language extensions.

Appendix A

Scala Scripts on Unix and Windows

If you’re on some flavor of Unix, you can run a Scala script as a shell script by prepending a “pound bang” directive at the top of the file. For example, type the following into a file named helloarg:

```
#!/bin/sh
exec scala "$0" "$@"
!#
// Say hello to the first argument
println("Hello, " + args(0) + "!")
```

The initial `#!/bin/sh` must be the very first line in the file. Once you set its execute permission:

```
$ chmod +x helloarg
```

You can run the Scala script as a shell script by simply saying:

```
$ ./helloarg globe
```

If you’re on Windows, you can achieve the same effect by naming the file `helloarg.bat` and placing this at the top of your script:

```
::#!@echo offcall scala %0 %*goto :eof::!#
```

Glossary

algebraic data type A type defined by providing several alternatives, each of which comes with its own constructor. It usually comes with a way to decompose the type through pattern matching. The concept is found in specification languages and functional programming languages. Algebraic data types can be emulated in Scala with case classes.

alternative A branch of a match expression. It has the form “*case pattern => expression*.” Another name for alternative is *case*.

annotation An *annotation* appears in source code and is attached to some part of the syntax. Annotations are computer processable, so you can use them to effectively add an extension to Scala.

anonymous class An anonymous class is a synthetic subclass generated by the Scala compiler from a new expression in which the class or trait name is followed by curly braces. The curly braces contains the body of the anonymous subclass, which may be empty. However, if the name following new refers to a trait or class that contains abstract members, these must be made concrete inside the curly braces that define the body of the anonymous subclass.

anonymous function Another name for function literal.

apply You can *apply* a method, function, or closure *to* arguments, which means you invoke it on those arguments.

argument When a function is invoked, an *argument* is passed for each parameter of that function. The parameter is the variable that refers to the argument. The argument is the object passed at invocation time. In addition, applications can take (command line) arguments that show up in the `Array[String]` passed to `main` methods of singleton objects.

assign You can *assign* an object *to* a variable. Afterwards, the variable will refer to the object.

auxiliary constructor Extra constructors defined inside the curly braces of the class definition, which look like method definitions named `this`, but with no result type.

block One or more expressions and declarations surrounded by curly braces.

When the block evaluates, all of its expressions and declarations are processed in order, and then the block returns the value of the last expression as its own value. Blocks are commonly used as the bodies of functions, for expressions, while loops, and any other place where you want to group a number of statements together. More formally, a block is an encapsulation construct for which you can only see side effects and a result value. The curly braces in which you define a class or object do not, therefore, form a block, because fields and methods (which are defined inside those curly braces) are visible from the outside. Such curly braces form a *template*.

bound variable A *bound variable* of an expression is a variable that's both used and defined inside the expression. For instance, in the function literal expression `(x: Int) => (x, y)`, both variables `x` and `y` are used, but only `x` is bound, because it is defined in the expression as an `Int` and the sole argument to the function described by the expression.

by-name parameter A parameter that is marked with a `=>` in front of the parameter type, *e.g.*, `(x: => Int)`. The argument corresponding to a by-name parameter is evaluated not before the method is invoked, but each time the parameter is referenced *by name* inside the method. If a parameter is not by-name, it is *by-value*.

by-value parameter A parameter that is *not* marked with a `=>` in front of the parameter type, *e.g.*, `(x: Int)`. The argument corresponding to a by-value parameter is evaluated before the method is invoked. By-value parameters contrast with *by-name* parameters.

class Defined with the `class` keyword, a *class* may either be abstract or concrete, and may be parameterized with types and values when instantiated. In “`new Array[String](2)`”, the class being instantiated

is `Array` and the type of the value that results is `Array[String]`. A class that takes type parameters is called a *type constructor*. A type can be said to have a class as well, as in: the class of type `Array[String]` is `Array`.

closure A function object that captures free variables, and is said to be “closed” over the variables visible at the time it is created.

companion class A class that shares the same name with a singleton object defined in the same source file. The class is the singleton object’s companion class.

companion object A singleton object that shares the same name with a class defined in the same source file. Companion objects and classes have access to each other’s private members. In addition, any implicit conversions defined in the companion object will be in scope anywhere the class is used.

contravariant A *contravariant* annotation can be applied to a type parameter of a class or trait by putting a minus sign (-) before the type parameter. The class or trait then subtypes contravariantly with—in the opposite direction as—the type annotated parameter. For example, `Function1` is contravariant in its first type parameter, and so `Function1[Any, Any]` is a subtype of `Function1[String, Any]`.

covariant A *covariant* annotation can be applied to a type parameter of a class or trait by putting a plus sign (+) before the type parameter. The class or trait then subtypes covariantly with—in the same direction as—the type annotated parameter. For example, `List` is covariant in its type parameter, so `List[String]` is a subtype of `List[Any]`.

currying A way to write functions with multiple parameter lists. For instance `def f(x: Int)(y: Int)` is a curried function with two parameter lists. A curried function is applied by passing several arguments lists, as in: `f(3)(4)`. However, it is also possible to write a *partial application* of a curried function, such as `f(3)`.

declare You can *declare* an abstract field, method, or type, which gives an entity a name but not an implementation. The key difference between

declarations and definitions is that definitions establish an implementation for the named entity, declarations do not.

define To *define* something in a Scala program is to give it a name and an implementation. You can define classes, traits, singleton objects, fields, methods, local functions, local variables, *etc.* Because definitions always involve some kind of implementation, abstract members are *declared* not defined.

direct subclass A class is a *direct subclass* of its direct superclass.

direct superclass The class from which a class or trait is immediately derived, the nearest class above it in its inheritance hierarchy. If a class Parent is mentioned in a class Child's optional extends clause, then Parent is the direct superclass of Child. If a trait is mentioned in Child's extends clause, the trait's direct superclass is the Child's direct superclass. If Child has no extends clause, then AnyRef is the direct superclass of Child. If a class's direct superclass takes type parameters, for example `class Child extends Parent[String]`, the direct superclass of Child is still Parent, not Parent[String]. On the other hand, Parent[String] would be the direct *supertype* of Child. See *supertype* for more discussion of the distinction between class and type.

equality When used without qualification, *equality* is the relation between values expressed by ‘`==`’. See also *reference equality*.

expression Any bit of Scala code that yields a result. You can also say that an expression *evaluates to* a result or *results in* a value.

filter An if followed by a boolean expression in a for expression. In `for(i <- 1 to 10; if i % 2 == 0)`, the filter is “if `i % 2 == 0`”. The value to the right of the if is the *filter expression*.

filter expression A *filter expression* is the boolean expression following an if in a for expression. In `for(i <- 1 to 10; if i % 2 == 0)`, the filter expression is “`i % 2 == 0`”.

first-class function Scala supports *first-class functions*, which means you can express functions in *function literal* syntax, *i.e.*, `(x: Int) => x + 1`,

and that functions can be represented by objects, which are called *function values*.

for comprehension Another name for *for expression*.

free variable A *free variable* of an expression is a variable that's used inside the expression but not defined inside the expression. For instance, in the function literal expression `(x: Int) => (x, y)`, both variables `x` and `y` are used, but only `y` is a free variable, because it is not defined inside the expression.

function A *function* can be *invoked* with a list of arguments to produce a result. A function has a parameter list, a body, and a result type. Functions that are members of a class, trait, or singleton object are called *methods*. Functions defined inside other functions are called *local functions*. Functions with the result type of `Unit` are called *procedures*. Anonymous functions in source code are called *function literals*. At run time, function literals are instantiated into objects called *function values*.

function literal A function with no name in Scala source code, specified with function literal syntax. For example, `(x: Int, y: Int) => x + y`.

function value A function object that can be invoked just like any other function. A function value's class extends one of the `FunctionN` traits (*e.g.*, `Function0`, `Function1`) from package `scala`, and is usually expressed in source code via *function literal* syntax. A function value is “invoked” when its `apply` method is called. A function value that captures free variables is a *closure*.

functional style The *functional style* of programming emphasizes functions and evaluation results and deemphasizes the order in which operations occur. The style is characterized by passing function values into looping methods, immutable data, methods with no side effects. It is the dominant paradigm of languages such as Haskell and Erlang, and contrasts with the *imperative style*.

generator A *generator* defines a named `val` and assigns to it a series of values in a *for* expression. For example, in `for(i <- 1 to 10)`, the

generator is “`i <- 1 to 10`”. The value to the right of the `<-` is the *generator expression*.

generator expression A *generator expression* generates a series of values in a for expression. For example, in `for(i <- 1 to 10)`, the generator expression is “`1 to 10`”.

generic class A class that takes type parameters. For example, because `scala.List` takes a type parameter, `scala.List` is a generic class.

generic trait A trait that takes type parameters. For example, because trait `scala.collection.Set` takes a type parameter, it is a generic trait.

helper function A function whose purpose is to provide a service to one or more other functions nearby. Helper functions are often implemented as local functions.

helper method A helper function that’s a member of a class. Helper methods are often private.

immutable An object is *immutable* if its value cannot be changed after it is created in any way visible to clients. Objects may or may not be immutable.

imperative style The *imperative style* of programming emphasizes careful sequencing of operations so that their effects happen in the right order. The style is characterized by iteration with loops, mutating data in place, and methods with side effects. It is the dominant paradigm of languages such as C, C++, C# and Java, and contrasts with the *functional style*.

initialize When a variable is defined in Scala source code, you must *initialize* it with an object.

instance An *instance*, or class instance, is an object, a concept that exists only at run time.

instantiate To *instantiate* a class is to make a new object from the class, an action that happens only at run time.

invariant *Invariant* is used in two ways. It can mean a property that always holds true when a data structure is well-formed. For example, it is an invariant of a sorted binary tree that each node is ordered before its right subnode, if it has a right subnode. *Invariant* is also sometimes used as a synonym for nonvariant: “class `Array` is invariant in its type parameter.”

invoke You can *invoke* a method, function, or closure *on* arguments, meaning its body will be executed with the specified arguments.

JVM The *JVM* is the Java Virtual Machine, or *runtime*, that hosts a running Scala program.

literal `1`, `"One"`, and `(x: Int) => x + 1` are examples of *literals*. A literal is a shorthand way to describe an object, where the shorthand exactly mirrors the structure of the created object.

local function A *local function* is a `def` defined inside a block. To contrast, a `def` defined as a member of a class, trait, or singleton object is called a *method*.

local variable A *local variable* is a `val` or `var` defined inside a block. Although similar to local variables, parameters to functions are not referred to as local variables, but simply as parameters or “variables” without the “local.”

member A *member* is any named element of the template of a class, trait, or singleton object. A member may be accessed with the name of its owner, a dot, and its simple name. For example, top-level fields and methods defined in a class are members of that class. A trait defined inside a class is a member of its enclosing class. A type defined with the `type` keyword in a class is a member of that class. A class is a member of the package in which it is defined. By contrast, a local variable or local function is not a member of its surrounding block.

message Actors communicate with each other by sending each other *messages*. Sending a message does not interrupt what the receiver is doing. The receiver can wait until it has finished its current activity and its invariants have been reestablished.

meta-programming Meta-programming software is software whose input is itself software. Compilers are meta-programs, as are tools like scaladoc. Meta-programming software is required in order to do anything with an *annotation*.

method A *method* is a function that is a member of some class, trait, or singleton object.

mixin *Mixin* is what a trait is called when it is being used in a mixin composition. In other words, in “trait Hat,” Hat is just a trait, but in “new Cat extends AnyRef with Hat,” Hat can be called a mixin. When used as a verb, “mix in” is two words. For example, you can *mix traits into* classes or other traits.

Mixin composition The process of mixing traits into classes or other traits. *Mixin composition* differs from traditional multiple inheritance in that the type of the super reference is not known at the point the trait is defined, but rather is determined anew each time the trait is mixed into a class or other trait.

modifier A keyword that qualifies a class, trait, field, or method definition in some way. For example, the `private` modifier indicates that a class, trait, field, or method being defined is private.

multiple definitions The same expression can be assigned in *multiple definitions* if you use the syntax `val v1, v2, v3 = exp`.

nonvariant A type parameter of a class or trait is by default *nonvariant*. The class or trait then does not subtype when that parameter changes. For example, because class `Array` is nonvariant in its type parameter, `Array[String]` is neither a subtype nor a supertype of `Array[Any]`.

operation In Scala, every *operation* is a method call. Methods may be invoked in *operator notation*, such as `b + 2`, and when in that notation, `+` is an *operator*.

parameter Functions may take zero to many *parameters*. Each parameter has a name and a type. The distinction between parameters and arguments is that arguments refer to the actual objects passed when a

function is invoked. Parameters are the variables that refer to those passed arguments.

parameterless function A function that takes no parameters, which is defined without any empty parentheses. Invocations of parameterless functions may not supply parentheses. This supports the *uniform access principle*, which enables the `def` to be changed into a `val` without requiring a change to client code.

parameterless method A *parameterless method* is a parameterless function that is a member of a class, trait, or singleton object.

parametric field A field defined as a class parameter.

partially applied function A function that's used in an expression and that misses some of its arguments. For instance, if function `f` has type `Int => Int => Int`, then `f` and `f(1)` are *partially applied functions*.

path-dependent type A type like `swiss.cow.Food`. The `swiss.cow` part is a *path* that forms a reference to an object. The meaning of the type is sensitive to the path you use to access it. The types `swiss.cow.Food` and `fish.Food`, for example, are different types.

pattern In a `match` expression alternative, a *pattern* follows each `case` keyword and precedes either a *pattern guard* or the `=>` symbol.

pattern guard In a `match` expression alternative, a *pattern guard* can follow a *pattern*. For example, in “`case x if x % 2 == 0 => x + 1`”, the pattern guard is “`if x % 2 == 0`”. A case with a pattern guard will only be selected if the pattern matches and the pattern guard yields true.

predicate A *predicate* is a function with a Boolean result type.

primary constructor The main constructor of a class, which invokes a superclass constructor, if necessary, initializes fields to passed values, and executes any top-level code defined between the curly braces of the class. Fields are initialized only for value parameters not passed to the superclass constructor, except for any that are not used in the body of the class and can therefore be optimized away.

procedure A *procedure* is a function with result type of `Unit`, which is therefore executed solely for its side effects.

reassignable A variable may or may not be *reassignable*. A var is reassignable while a val is not.

recursive A function is *recursive* if it calls itself. If the only place the function calls itself is the last expression of the function, then the function is *tail recursive*.

reference A *reference* is the Java abstraction of a pointer, which uniquely identifies an object that resides on the JVM's heap. Reference type variables hold references to objects, because reference types (instances of AnyRef) are implemented as Java objects that reside on the JVM's heap. Value type variables, by contrast, may sometimes hold a reference (to a boxed wrapper type) and sometimes not (when the object is being represented as a primitive value). Speaking generally, a Scala variable *refers* to an object. The term "refers" is more abstract than "holds a reference." If a variable of type scala.Int is currently represented as a primitive Java int value, then that variable still refers to the Int object, but no reference is involved.

reference equality *Reference equality* means that two references identify the very same Java object. Reference equality can be determined, for reference types only, by calling eq in AnyRef. (In Java programs, reference equality can be determined using == on Java reference types.)

reference type A *reference type* is a subclass of AnyRef. Instances of reference types always reside on the JVM's heap at run time.

referential transparency A property of functions that are independent of temporal context and have no side effects. For a particular input, an invocation of a referentially transparent function can be replaced by its result without changing the program semantics.

refers A variable in a running Scala program always *refers* to some object. Even if that variable is assigned to null, it conceptually refers to the Null object. At runtime, an object may be implemented by a Java object or a value of a primitive type, but Scala allows programmers to think at a higher level of abstraction about their code as they imagine it running. See also *reference*.

refinement type A type formed by supplying a base type a number of members inside curly braces. The members in the curly braces refine the

types that are present in the base type. For example, the type of “animal that eats grass” is `Animal { type SuitableFood = Grass }`.

result An expression in a Scala program yields a *result*. The result of every expression in Scala is an object.

result type A method’s *result type* is the type of the value that results from calling the method. (In Java, this concept is called the return type.)

return A function in a Scala program *returns* a value. You can call this value the *result* of the function. You can also say the function *results in* the value. The result of every function in Scala is an object.

runtime The Java Virtual Machine, or JVM, that hosts a running Scala program. *Runtime* encompasses both the virtual machine, as defined by the Java Virtual Machine Specification, and the runtime libraries of the Java API and the standard Scala API. The phrase *at run time* (with a space between *run* and *time*) means when the program is running, and contrasts with compile time.

runtime type The type of an object at run time. To contrast, a *static type* is the type of an expression at compile time. Most runtime types are simply bare classes with no type parameters. For example, the runtime type of "Hi" is `String`, and the runtime type of `(x: Int) => x + 1` is `Function1`. Runtime types can be tested with `isInstanceOf`.

script A file containing top level definitions and statements, which can be run directly with `scala` without explicitly compiling. A script must end in an expression, not a definition.

selector The value being matched on in a `match` expression. For example, in “`s match { case _ => }`”, the selector is `s`.

self type A *self type* of a trait is the assumed type of `this`, the receiver, to be used within the trait. Any concrete class that mixes in the trait must ensure that its type conforms to the trait’s self type. The most common use of self types is for dividing a large class into several traits as described in [Chapter 29](#).

semi-structured data XML data is semi-structured. It is more structured than a flat binary file or text file, but it does not have the full structure of a programming language’s data structures.

serialization You can *serialize* an object into a byte stream which can then be saved to files or transmitted over the network. You can later *deserialize* the byte stream, even on different computer, and obtain an object that is the same as the original serialized object.

shadow A new declaration of a local variable *shadows* one of the same name in an enclosing scope.

signature *Signature* is short for *type signature*.

singleton object An object defined with the `object` keyword. Each singleton object has one and only one instance. A singleton object that shares its name with a class, and is defined in the same source file as that class, is that class’s *companion object*. The class is its *companion class*. A singleton object that doesn’t have a companion class is a *standalone object*.

standalone object A singleton object that has no companion class.

statement An expression, definition, or import, *i.e.*, things that can go into a template or a block in Scala source code.

static type See *type*.

subclass A class is a *subclass* of all of its superclasses and supertraits.

subtrait A trait is a *subtrait* of all of its supertraits.

subtype The Scala compiler will allow any of a type’s *subtypes* to be used as a substitute wherever that type is required. For classes and traits that take no type parameters, the subtype relationship mirrors the subclass relationship. For example, if class `Cat` is a subclass of abstract class `Animal`, and neither takes type parameters, type `Cat` is a subtype of type `Animal`. Likewise, if trait `Apple` is a subtrait of trait `Fruit`, and neither takes type parameters, type `Apple` is a subtype of type `Fruit`. For classes and traits that take type parameters, however, variance comes into play. For example, because abstract class `List`

is declared to be covariant in its lone type parameter (*i.e.*, `List` is declared `List[+A]`), `List[Cat]` is a subtype of `List[Animal]`, and `List[Apple]` a subtype of `List[Fruit]`. These subtype relationships exist even though the class of each of these types is `List`. By contrast, because `Set` is not declared to be covariant in its type parameter (*i.e.*, `Set` is declared `Set[A]` with no plus sign), `Set[Cat]` is *not* a subtype of `Set[Animal]`. A subtype should correctly implement the contracts of its supertypes, so that the Liskov Substitution Principle applies, but the compiler only verifies this property at the level of type checking.

superclass A class's *superclasses* include its direct superclass, its direct superclass's direct superclass, and so on, all the way up to `Any`.

supertrait A class's or trait's *supertraits*, if any, include all traits directly mixed into the class or trait or any of its superclasses, plus any supertraits of those traits.

supertype A type is a *supertype* of all of its subtypes.

synthetic class A *synthetic class* is generated automatically by the compiler rather than being written by hand by the programmer.

tail recursive A function is *tail recursive* if the only place the function calls itself is the last operation of the function.

target typing *Target typing* is a form of type inference that takes into account the type that's expected. In `nums.filter((x) => x > 0)`, for example, the Scala compiler infers type of `x` to be the element type of `nums`, because the `filter` method invokes the function on each element of `nums`.

template A *template* is the body of a class, trait, or singleton object definition. It defines the type signature, behavior, and initial state of the class, trait, or object.

trait A *trait*, which is defined with the `trait` keyword, is like an abstract class that cannot take any value parameters and can be "mixed into" classes or other traits via the process known as *mixin composition*. When a trait is being mixed into a class or trait, it is called a *mixin*. A

trait may be parameterized with one or more types. When parameterized with types, the trait constructs a type. For example, Set is a trait that takes a single type parameter, whereas Set[Int] is a type. Also, Set is said to be “the trait of” type Set[Int].

type Every variable and expression in a Scala program has a *type* that is known at compile time. A type restricts the possible values to which a variable can refer, or an expression can produce, at run time. A variable or expression’s type can also be referred to as a *static type* if necessary to differentiate it from an object’s *runtime type*. In other words, “type” by itself means static type. Type is distinct from class because a class that takes type parameters can construct many types. For example, List is a class, but not a type. List[T] is a type with a free type parameter. List[Int] and List[String] are also types (called *ground types* because they have no free type parameters). A type can have a “class” or “trait.” For example, the class of type List[Int] is List. The trait of type Set[String] is Set.

type constraint Some annotations are *type constraints*, meaning that they add additional limits, or constraints, on what values the type includes. For example, @positive could be a type constraint on the type Int, limiting the type of 32-bit integers down to those that are positive. Type constraints are not checked by the standard Scala compiler, but must instead be checked by an extra tool or by a compiler plugin.

type constructor A class or trait that takes type parameters.

type parameter A parameter to a generic class or generic method that must be filled in by a type. For example, class List is defined as “class List[T] { … }”, and method identity, a member of object Predef, is defined as “def identity[T](x:T) = x”. The T in both cases is a type parameter.

type signature A method’s *type signature* comprises its name, the number, order, and types of its parameters, if any, and its result type. The type signature of a class, trait, or singleton object comprises its name, the type signatures of all of its members and constructors, and its declared inheritance and mixin relations.

uniform access principle The *uniform access principle* states that variables and parameterless functions should be accessed using the same syntax. Scala supports this principle by not allowing parentheses to be placed at call sites of parameterless functions. As a result, a parameterless function definition can be changed to a `val`, or *vice versa*, without affecting client code.

unreachable At the Scala level, objects can become *unreachable*, at which point the memory they occupy may be reclaimed by the runtime. Unreachable does not necessarily mean unreferenced. Reference types (instances of `AnyRef`) are implemented as objects that reside on the JVM's heap. When an instance of a reference type becomes unreachable, it indeed becomes unreferenced, and is available for garbage collection. Value types (instances of `AnyVal`) are implemented as both primitive type values and as instances of Java wrapper types (such as `java.lang.Integer`), which reside on the heap. Value type instances can be boxed (converted from a primitive value to a wrapper object) and unboxed (converted from a wrapper object to a primitive value) throughout the lifetime of the variables that refer to them. If a value type instance currently represented as a wrapper object on the JVM's heap becomes unreachable, it indeed becomes unreferenced, and is available for garbage collection. But if a value type currently represented as a primitive value becomes unreachable, then it does not become unreferenced, because it does not exist as an object on the JVM's heap at that point in time. The runtime may reclaim memory occupied by unreachable objects, but if an `Int`, for example, is implemented at run time by a primitive Java `int` that occupies some memory in the stack frame of an executing method, then the memory for that object is “reclaimed” when the stack frame is popped as the method completes. Memory for reference types, such as `Strings`, may be reclaimed by the JVM's garbage collector after they become unreachable.

unreferenced See *unreachable*.

value The result of any computation or expression in Scala is a *value*, and in Scala, every value is an object. The term *value* essentially means the image of an object in memory (on the JVM's heap or stack).

value type A *value type* is any subclass of AnyVal, such as Int, Double, or Unit. This term has meaning at the level of Scala source code. At runtime, instances of value types that correspond to Java primitive types may be implemented in terms of primitive type values or instances of wrapper types, such as java.lang.Integer. Over the lifetime of a value type instance, the runtime may transform it back and forth between primitive and wrapper types (*i.e.*, to box and unbox it).

variable A named entity that refers to an object. A variable is either a val or a var. Both vals and vars must be initialized when defined, but only vars can be later reassigned to refer to a different object.

variance A type parameter of a class or trait can be marked with a *variance* annotation, either covariant (+) or contravariant (-). Such variance annotations indicate how subtyping works for a generic class or trait. For example, the generic class List is covariant in its type parameter, and thus List[String] is a subtype of List[Any]. By default, *i.e.*, absent a + or - annotation, type parameters are nonvariant.

wildcard type A wildcard type includes references to type variables that are unknown. For example, Array[_] is a wildcard type. It is an array where the element type is completely unknown.

yield An expression can *yield* a result. The yield keyword designates the result of a for expression.

Bibliography

- [Abe96] Abelson, Harold and Gerald Jay Sussman. *Structure and Interpretation of Computer Programs*. The MIT Press, second edition, 1996.
- [Aho86] Aho, Alfred V., Ravi Sethi, and Jeffrey D. Ullman. *Compilers: Principles, Techniques, and Tools*. Addison-Wesley Longman Publishing Co., Inc., Boston, MA, USA, 1986. ISBN 0-201-10088-6.
- [Bay72] Bayer, Rudolf. “Symmetric binary B-Trees: Data structure and maintenance algorithms.” *Acta Informatica*, 1(4):290–306, 1972.
- [Blo08] Bloch, Joshua. *Effective Java Second Edition*. Addison-Wesley, 2008.
- [DeR75] DeRemer, Frank and Hans Kron. “Programming-in-the large versus programming-in-the-small.” In *Proceedings of the international conference on Reliable software*, pages 114–121. ACM, New York, NY, USA, 1975. doi:<http://doi.acm.org/10.1145/800027.808431>.
- [Dij70] Dijkstra, Edsger W. “Notes on Structured Programming.”, April 1970. Circulated privately. Available at <http://www.cs.utexas.edu/users/EWD/ewd02xx/EWD249.PDF> as EWD249 (accessed June 6, 2008).
- [Eck98] Eckel, Bruce. *Thinking in Java*. Prentice Hall, 1998.
- [Emi07] Emir, Burak, Martin Odersky, and John Williams. “Matching Objects With Patterns.” In *Proc. ECOOP*, Springer LNCS, pages 273–295. July 2007.
- [Eva03] Evans, Eric. *Domain-Driven Design: Tackling Complexity in the Heart of Software*. Addison-Wesley Professional, 2003.

- [Fow04] Fowler, Martin. “Inversion of Control Containers and the Dependency Injection pattern.” January 2004. Available on the web at <http://martinfowler.com/articles/injection.html> (accesssed August 6, 2008).
- [Gam95] Gamma, Erich, Richard Helm, Ralph Johnson, and John Vlissides. *Design Patterns : Elements of Reusable Object-Oriented Software.* Addison-Wesley, 1995.
- [Goe06] Goetz, Brian, Tim Peierls, Joshua Bloch, Joseph Bowbeer, David Homes, and Doug Lea. *Java Concurrency in Practice.* Addison Wesley, 2006.
- [Jav] *The Java Tutorials: Creating a GUI with JFC/Swing.* Available on the web at <http://java.sun.com/docs/books/tutorial/uiswing>.
- [Kay96] Kay, Alan C. “The Early History of Smalltalk.” In *History of programming languages—II*, pages 511–598. ACM, New York, NY, USA, 1996. ISBN 0-201-89502-1. doi:<http://doi.acm.org/10.1145/234286.1057828>.
- [Kay03] Kay, Alan C. An email to Stefan Ram on the meaning of the term “object-oriented programming”, July 2003. The email is published on the web at http://www.purl.org/stefan_ram/pub/doc_kay_oop_en (accesssed June 6, 2008).
- [Lan66] Landin, Peter J. “The Next 700 Programming Languages.” *Communications of the ACM*, 9(3):157–166, 1966.
- [Mey91] Meyers, Scott. *Effective C++.* Addison-Wesley, 1991.
- [Mey00] Meyer, Bertrand. *Object-Oriented Software Construction.* Prentice Hall, 2000.
- [Mor68] Morrison, Donald R. “PATRICIA—Practical Algorithm To Retrieve Information Coded in Alphanumeric.” *J. ACM*, 15(4):514–534, 1968. ISSN 0004-5411. doi:<http://doi.acm.org/10.1145/321479.321481>.
- [Ode03] Odersky, Martin, Vincent Cremet, Christine Röckl, and Matthias Zenger. “A Nominal Theory of Objects with Dependent Types.” In *Proc. ECOOP’03*, Springer LNCS, pages 201–225. July 2003.

- [Ode05] Odersky, Martin and Matthias Zenger. “Scalable Component Abstractions.” In *Proceedings of OOPSLA*, pages 41–58. October 2005.
- [Ode11] Odersky, Martin. *The Scala Language Specification, Version 2.9*. EPFL, May 2011. Available on the web at <http://www.scala-lang.org/docu/manuals.html> (accessed April 20, 2014).
- [Ray99] Raymond, Eric. *The Cathedral & the Bazaar: Musings on Linux and Open Source by an Accidental Revolutionary*. O’Reilly, 1999.
- [Rum04] Rumbaugh, James, Ivar Jacobson, and Grady Booch. *The Unified Modeling Language Reference Manual (2nd Edition)*. Addison-Wesley, 2004.
- [SPJ02] Simon Peyton Jones, et.al. “Haskell 98 Language and Libraries, Revised Report.” Technical report, <http://www.haskell.org/onlinereport>, 2002.
- [Ste99] Steele, Jr., Guy L. “Growing a Language.” *Higher-Order and Symbolic Computation*, 12:221–223, 1999. Transcript of a talk given at OOPSLA 1998.
- [Vaz07] Vaziri, Mandana, Frank Tip, Stephen Fink, and Julian Dolby. “Declarative Object Identity Using Relation Types.” In *Proc. ECOOP 2007*, pages 54–78. 2007.

About the Authors

Martin Odersky is the creator of the Scala language. He is a professor at EPFL in Lausanne, Switzerland, and a founder of Typesafe, Inc. He works on programming languages and systems, more specifically on the topic of how to combine object-oriented and functional programming. Since 2001 he has concentrated on designing, implementing, and refining Scala. Previously, he has influenced the development of Java as a co-designer of Java generics and as the original author of the current javac reference compiler. He is a fellow of the ACM.

Lex Spoon is a software engineer at Semmle, Ltd. He worked on Scala for two years as a post-doc at EPFL. He has a Ph.D. from Georgia Tech, where he worked on static analysis of dynamic languages. In addition to Scala, he has helped develop a wide variety of programming languages, including the dynamic language Smalltalk, the scientific language X10, and the logic language that powers Semmle. He and his wife live in Atlanta with two cats and a chihuahua.

Bill Venners is president of Artima, Inc., publisher of the Artima Developer website (www.artima.com), and cofounder of Escalate Software, LLC. He is author of the book, *Inside the Java Virtual Machine*, a programmer-oriented survey of the Java platform's architecture and internals. His popular columns in JavaWorld magazine covered Java internals, object-oriented design, and Jini. Active in the Jini Community since its inception, Bill led the Jini Community's ServiceUI project, whose ServiceUI API became the de facto standard way to associate user interfaces to Jini services. Bill is also the lead developer and designer of ScalaTest, an open source testing tool for Scala and Java developers.

Index

Page numbers followed by an n refer to footnotes.

Symbols

- ! (invert)
 - on class Boolean, 125
- ! (message send)
 - on trait Actor, 49
- != (not equals)
 - method on Any, 128, 246
- " (string delimiter), 117
- "" (raw string delimiter), 117
- ' (character delimiter), 116
- () (empty parentheses)
 - on method definitions, 221
 - shorthand for apply method invocation, 79
- () (unit value), 158
- * (repeat)
 - on class String, 97
- * (repeated parameter), 195
- * (times)
 - on numeric types, 124
- + (add element)
 - on Map traits, 382, 553
 - on Set traits, 88, 380, 548
- + (covariant in)
 - List's type parameter, 500
 - variance annotation, 426
- + (plus)
 - on numeric types, 124
- ++ (add elements)
 - on Map traits, 382, 553
 - on Set traits, 380, 548
 - on trait Iterator, 587
 - on Traversable traits, 535
- ++= (add elements to)
 - on trait mutable.Map, 383, 554
 - on trait mutable.Set, 380, 549
- ++= (append)
 - on trait Buffer, 547
- ++=: (prepend)
 - on trait Buffer, 547
- +: (prepend)
 - on Seq traits, 544
- += (add element to)
 - on trait mutable.Map, 383, 554
 - on trait mutable.Set, 380, 549
- += (add to)
 - on trait mutable.Set, 88
 - reassignment with immutable sets and vars, 89
- += (append)
 - on class ArrayBuffer, 376
 - on class ListBuffer, 375, 506
 - on trait Buffer, 547
- +=: (prepend)
 - on class ListBuffer, 375
 - on trait Buffer, 547
- (contravariant in)
 - variance annotation, 426
- (minus)
 - on numeric types, 124
- (remove element)

- on Map traits, 382, 553
- on Set traits, 380, 549
- (remove elements)
 - on Map traits, 382, 553
 - on Set traits, 380, 549
- = (remove elements from)
 - on trait `mutable.Map`, 383, 554
 - on trait `mutable.Set`, 380, 550
- = (remove element from)
 - on trait `mutable.Map`, 383, 554
 - on trait `mutable.Set`, 380, 549
 - on trait `Buffer`, 547
- > (map to), 91
 - in implicit conversion, 484
- / (divided by)
 - on numeric types, 124
- /: (fold left)
 - on class `List`, 361
 - on trait `Iterator`, 590
 - on Traversable traits, 537
- : (colon)
 - in type annotations, 66
- :+ (append)
 - on Seq traits, 544
- :: (cons) class
 - as pattern constructor, 344
 - subclass of `List`, 499–502
- :: (cons) method
 - on class `List`, 82, 341
 - right associativity of, 83, 342
- ::: (concatenation)
 - on class `List`, 82, 345, 501
- :\< (fold right)
 - on class `List`, 362
 - on trait `Iterator`, 590
 - on Traversable traits, 537
- ; (semicolon)
 - inference, 104
- < (less than)
 - on numeric types, 125
- <- (in)
 - in for expressions, 75
- <: (upper bound), 441
- << (shift left)
 - on integral types, 128
- <= (less than or equal to)
 - on numeric types, 125
- = (variable assignment), 66
- == (equals)
 - in set membership, 379
- == (equals)
 - in Scala versus Java, 130
 - in-depth treatment, 674–697
 - method on Any, 128, 246, 674
 - quick introduction, 128–130
- => (right arrow, or “rocket”)
 - in function literals, 74
 - in import statements, 283–284
 - in self types, 669
 - in match alternatives, 170
 - in this aliasing, 753
- > (greater than)
 - on numeric types, 125
- >: (lower bound), 433
- >= (greater than or equal to)
 - on numeric types, 125
- >> (shift right)
 - on integral types, 128
- >>> (unsigned shift right)
 - on integral types, 128
- ??? (unimplemented)
 - on object `Predef`, 347
- @ (at sign)
 - in annotations, 638
 - in patterns, 320
 - to extract XML attributes, 652
- # (pound sign)
 - in inner class type names, 459
- % (remainder)
 - on numeric types, 124
- & (bitwise-and)
 - on integral types, 127
- & (intersect)
 - on Set traits, 380, 549

&& (logical-and)
 on class Boolean, 126

&~ (diff)
 on Set traits, 549

_ (underscore)
 in curried functions, 211
 in function literals, 187, 206
 in identifiers, 148
 in import statements, 284
 in wildcard types, 692
 in match expressions, 169
 used to initialize a field to its
 default value, 400

_* (underscore asterisk)
 in XML pattern matching, 656
 repeated parameter, 196
 sequence wildcard pattern, 628

_1, _2, etc. (tuple accessors), 86

_= (underscore equals)
 in setter method names, 398

\wedge (exclusive-or)
 on integral types, 127

$\wedge\wedge$ (result conversion, or
 “eyebrows”)
 parser combinator, 745

\sim (bitwise complement)
 on integral types, 127

\sim (sequential composition, or
 “squiggle”)
 parser combinator, 745, 754

$\sim!$ (committed sequential
 composition)
 parser combinator, 762

\rightsquigarrow (sequential composition right)
 parser combinator, 746, 755

$\leftarrow\sim$ (sequential composition left)
 parser combinator, 746, 755

\ (extract)
 on class Elem, 652

\\\ (deep extract)
 on class Elem, 652

| (alternative composition)

parser combinator, 746, 755

| (bitwise-or)
 on integral types, 127

| (union)
 on Set traits, 549

|| (logical-or)
 on class Boolean, 126

{ } (curly braces)
 and variable scope, 174
 in class definitions, 136
 in imports, 283
 in XML literals, 648–649
 in XML patterns, 655
 instead of parentheses in
 method invocations, 213
 instead of parentheses in for
 expressions, 163

' (back tick)
 in constants, 314
 in identifiers, 149

A

Abelson, Harold, 401, 518

abs method
 on class Double (via
 RichDouble), 134

 on class Int (via RichInt),
 145, 249

abstract members, 443

abstract modifier
 not needed on abstract methods,
 fields, or types, 220, 443

 on classes, 219

 with override modifier on
 members of traits, 268

abstract types, 455

access modifiers, 286–290

accessor methods, 398

Actor trait
 methods
 ! (message send), 49

actors, 48, 49, 52, 328, 771

add method

on trait `mutable.Set`, 549
addString method
 on class `List`, 353
 on trait `Iterator`, 591
 on `Traversable` traits, 538
Aho, Alfred, 518, 762n
Akka, 48, 50, 52, 328, 771
aliases
 `AnyRef` for `Object`, 250
 type, 444
aliasing
 `this`, 753
 object, *see* defensive copies
alphabetic versus symbolic names,
 750
alternatives
 catch-all, 311
 definition of, 803
 in match expressions, 169, 309
 in catch clauses, 167
 in partial function literals, 328
andThen method
 on trait `Future`, 731
annotations
 and reflection, 704
 applied to expressions, 639
 arguments to, 639
 `@BeanProperty`, 643
 `@deprecated`, 638, 641
 in meta-programming, 638
 Java-specific, 701
 `@native`, 644
 nested, 640
 `@serializable`, 642, 702
 `@SerialVersionUID`, 642
 standard, 640
 syntax of, 639
 `@tailrec`, 643
 `@Test`
 in JUnit 4, 704
 `@throws`, 702
 `@transient`, 643
type, 46, 60, 66
 for debugging, 371
unchecked, 325, 409, 639, 644
used with named arguments,
 640
variance, 426
@volatile, 642
anonymous classes, 448
anonymous functions, *see* function
 literals
ANTLR, 736
Any class, 247
 in Scala class hierarchy
 diagram, 248
AnyRef class, 247
 as alias of `Object`, 250
 in Scala class hierarchy
 diagram, 248
AnyVal class, 247
 in Scala class hierarchy
 diagram, 248
App trait, 110, 766
application
 function to arguments, 188
 partial function, 188, 356
applications, Scala, 108
apply method
 called with parentheses, 79
 in extractors, 623
 on `Array`
 class, 79
 object, 81
 on `List`
 class, 351
 object, 82, 365, 630
 on `Map`
 objects, 91
 traits, 381, 382, 553
 on object `Future`, 716
 on `Seq` objects, 594
 on `Seq` traits, 544

- on Set objects, 87
- on trait PartialFunction, 330
- on FunctionN traits, 184
- args variable
 - in scripts, 71
- arguments
 - command line, in scripts, 71
 - named, 196
 - variable length, 195
 - versus parameters, 810
- arithmetic operations (+, -, *, /, %)
 - on numeric types, 124–125
- Array class, 374
- ArrayBuffer class, 376
- arrays, 236, 374
 - accessed with () not [], 79
 - converting to lists, 390
 - creating and initializing, 81
 - generic, 572
 - passing elements as arguments
 - with _*, 196
 - quick introduction, 78–81
- asInstanceOf method
 - on class Any, 317
- assert method
 - on object Predef, 94, 294
- AssertionError class, 294
- assertions, 294–296
- assignment
 - result is unit value, 159
- associativity, 132–133
 - right versus left, 83, 132
- attributes
 - XML, 647, 652
- automatic
 - boxing, 250
 - conversion, *see* implicit conversion
 - imports, 285–286
- auxiliary constructors, 142–143
- B**
- backtracking, 761
- base classes, *see* superclasses
- BDD, *see* behavior-driven development
- BeanProperty annotation, 643, 662n
- behavior-driven development, 299
- BigInt class, 47
- BigInteger class, 48
- binary compatibility, xxxii, xxxiii, 709
- Bison, 736
- bitwise operations, on integral types
 - logical (&, |, ^, ~), 127
 - shift (<<, >>, >>>), 128
- blank finals (Java)
 - not in Scala, 400
- Bloch, Joshua, 675n, 688n, 695n
- blocks, definition of, 804
- Boolean class, 113, 125
- boolean literals, 119
- bottom types, 252
- bound variables, 163, 191
- boxing, of value types, 250
- Bracha, Gilad, 518
- break keyword (Java)
 - living without, 171
 - not in match expressions, 170
- break method
 - on class Breaks, 173
- breakable method
 - on class Breaks, 173
- Breaks class, 173
- buffer
 - members, 547
- Buffer trait
 - methods
 - ++=: (prepend), 547
 - ++= (append), 547
 - +=: (prepend), 547
 - += (append), 547
 - = (remove element from), 547

clear, 547
clone, 547
insert, 547
insertAll, 547
remove, 547
trimEnd, 547
trimStart, 547
buffered method
 on trait Iterator, 587
ButtonClicked class, 770
by-name parameters, 215, 407
by-value parameters, 756
Byte class, 112

C

C language, 53
 parser generators, 736
C++ language, 53, 92
C# language, 92
 enumerations, 461
 properties, 400
 static extension methods, 474
camel casing, 147
CanBuildFrom trait, 602
capitalization, of identifiers, 147
capitalize method
 on class Int (via RichInt), 134
case classes, 307–308
 versus extractors, 631–632
cases, *see also* alternatives
casting, *see also* toInt, toChar, *etc.*
 with asInstanceOf, 317
 with typed patterns (the preferred style), 317
catch clauses, 166
Cathedral and the Bazaar, The (Raymond), 47
chained package clauses, 280
Char class, 112
character encoding
 in XML, 654
character literals, 116
 escape sequences, 117
checked exceptions, 167, 702
Church, Alonzo, 52
Class class, *see* classOf method
class hierarchy diagram
 for lists, 500
 for maps, 90
 for Scala, 248
 for sets, 88
 for Try, 718
class parameters, 136
 initialization order compared to abstract fields, 449
 not legal on singleton objects, 107
 used to implement abstract fields, 502
classes, 99–101
 abstract, 219
 annotating, 639
 anonymous, 448
 case, 307–308
 companion, 105
 generic, 418
 implicit, 484
 inner, *see* inner classes
 nesting of, 240
 private, 423
 sealed, 323–325
 virtual, 466
classOf method
 on object Predef, 703
clear method
 on trait mutable.Map, 555
 on trait mutable.Set, 380, 550
 on trait Buffer, 547
clone method
 on trait mutable.Map, 555
 on trait mutable.Set, 550
 on trait Buffer, 547
closures, 191–195, 206
 versus Java’s inner classes, 193n

code duplication
 reducing, 58, 203–209

collect method
 on trait Future, 723

collect method
 on trait Iterator, 588

collections, 373–394
 api, 528
 architecture, 597–620
 conversion between Java and Scala, 594–596
 parallel, 46, 529
 views of, 579–584

combinators, 219

companion classes, 105

companion objects, 81, 105
 and factory methods, 422
 and implicit conversion, 478
 visibility, 290

compare method
 of trait Ordered, 265, 439

compatibility, Scala with Java, 45, 55–56

compiler errors
 ';' expected but ',' found, 213
 ... is already defined as ..., 320
 ... is not a legal prefix for a constructor, 460

overloaded method value
 ... with alternatives
 ... cannot be applied to ..., 152

class ... is abstract; cannot be instantiated, 220

class ... needs to be abstract,
 since method ... in class ... of type ... is not defined, 455

class type required, 465

constructor ... cannot be accessed in ..., 422

could not find implicit value for parameter asTraversable, 351

covariant type ... occurs in contravariant position in type ... of parameter of setter ..., 439

covariant type ... occurs in contravariant position in type ... of value ..., 427, 430

error overriding method ... in class ... of type ... method ... cannot override final member, 233

error overriding method ... in class ... of type ... method ... needs 'override' modifier, 230

illegal inheritance from final class, 234

inferred type arguments ... do not conform to method ... type parameter bounds ..., 441

method ... overrides nothing, 229, 455

missing arguments for method ... follow this method with '_' if you want to treat it as a partially applied function, 191

no implicit argument matching parameter type ... was found, 389, 487

not found: value ..., 118, 191

overloaded method value ... with alternatives ... cannot be applied to ..., 483

pattern is unchecked since it is eliminated by erasure, 690

- reassignment to val, 67, 386
- trait ... takes type parameters, 425
- type mismatch, 196, 389, 429, 457, 458, 471, 480, 496, 671, 672
- unreachable code, 322
- value ... is not a member of ..., 140, 451
- compiler warnings
 - match is not exhaustive, 329, 409
 - non variable type-argument
 - ... in type pattern is unchecked since it is eliminated by erasure, 318, 690
- Compilers: Principles, Techniques, and Tools* (Aho, et al.), 764n
- compiling, 109
 - Scala and Java together, 709
- complete function, 330
- complete method
 - on trait Promise, 722
- completeWith method
 - on trait Promise, 722
- complexity, managing, 57
- Component class, 767
- composition, 225, 235
 - mixin, *see* mixin composition
- concat method
 - on object List, 367
 - on Seq objects, 594
- conciseness
 - Scala versus Java, 56–57
- concurrency
 - actors model, 49
 - and testing, 715
 - futures, 714–735
 - shared data and locks, 716
- concurrentmap
 - members, 569
- ConcurrentMap trait
 - methods
 - remove, 569
 - replace, 569
- ConcurrentMap trait
 - methods
 - putIfAbsent, 569
- configuring
 - to wire modules together, 660
 - with Scala code, 671
- cons (:) method
 - on class List, 82, 341, 420, 501
 - right associativity of, 83
 - short for *construct*, 501
- Console object, 95
- constant patterns, 309, 312
- constants, 148
- constructor patterns, 310, 315
- constructors, 77
 - auxiliary, 142–143
 - in Java versus Scala, 137
 - invoking superclass, 228
 - primary, 136–138
 - private, 422
- Container trait, 767
- contains method
 - on Map traits, 382, 553
 - on Seq traits, 545
 - on Set traits, 380, 548
- containsSlice method
 - on Seq traits, 545
- contents property
 - on trait Container, 767
- context bounds, 442, 493
- context-free grammars, 737
- continue keyword (Java)
 - living without, 171
- contravariance, 426, 434–437
- control abstraction, 53, 203–217
- conventions, identifier capitalization, 147

conversion
 between Java and Scala
 collections, 594–596
 between mutable and
 immutable collections, 391
 implicit, 55, 474
 to specific collection types, 390,
 533, 535, 588
copyToArray method
 on class List, 354
 on trait Iterator, 587
 on Traversable traits, 536
copyToBuffer method
 on trait Iterator, 587
 on Traversable traits, 536
corresponds method
 on Seq traits, 545
count method
 on class List, 84
 on trait Iterator, 589
 on Traversable traits, 537
covariance, 426
 of arrays in Java, 428
 of function result type, 435
 of lists, 341, 504
creating and initializing
 arrays, 81
 lists, 82
 maps, 91
 objects with factories, 81, 238
 objects with new, 99
 sets, 87
 singleton objects, 107
 tuples, 86
curly braces
 and variable scope, 174
 in class definitions, 136
 in imports, 283
 in XML literals, 648–649
 in XML patterns, 655
 instead of parentheses in
 method invocations, 213
 instead of parentheses in for
 expressions, 163
currying, 209–211, 356

D

data structures
 fully persistent, 419
 semi-structured, 645
deadlock, 49, 715
deafTo method
 on Reactor, 770
declarations, versus definitions, 806
decrementing
 with -= 1, not --, *see*
 incrementing
def keyword, 68, 99
 annotating, 639
default methods
 in Java 8, xxxiii, 713
default values
 of fields, 400
defensive copies, 137
definitions, versus declarations, 806
dependency injection, 660
deprecated annotation, 638, 701
dequeue method
 on class Queue, 560
DeRemer, Frank, 659n
derived classes, *see* subclasses
deserialization
 XML, 653
Design Patterns (Gamma, *et al.*),
 310n
diff method
 on Seq traits, 546
 on Set traits, 549
Dijkstra, Edsger, 60
distinct method
 on Seq traits, 546
divide and conquer principle, 346
do-while loops, 157
domain objects, 661

- Domain-Driven Design* (Evans), 661n
domain-specific languages, 801
 a little language for digital circuits, 401
 and implicit conversions, 482
 defining an external DSL with parser combinators, 736–746
 in Smalltalk and Lisp, 62
 parser combinators as an internal DSL, 736
 rich wrappers and internal versus external DSLs, 484
 ScalaTest’s matchers DSL, 300
Double class, 112
downloading
 Scala, 64
 source code for book examples, xliii
drop method
 on class List, 84, 350
 on trait Iterator, 589
 on Traversable traits, 536
dropRight method
 on class List, 84
 on Iterable traits, 540
dropWhile method
 on class List, 360
 on trait Iterator, 589
 on Traversable traits, 536
DSLs, *see* domain-specific languages
duplicate method
 on trait Iterator, 587
dynamic
 binding, 231, 260
 typing, 59, 61, 118
- E**
- Eckel, Bruce, 235n
Eclipse IDE, 64, 765
EditDone class, 775
Effective C++ (Meyers), 235n
- Effective Java, Second Edition* (Bloch), 675n, 688n, 695n
efficiency
 and hash consing, 252
 of abstract classes versus traits, 307n
 of arrays, 81, 374
 of case classes versus extractors, 631
 of class ListBuffer, 375, 506
 of fold left and right, 362
 of functional on the outside, imperative on the inside approach, 509
 of immutable objects, 137
 of lists, 373
 of LL(1) versus backtracking parsers, 763
 of looping versus recursion, 198
 of maps, 383
 of merge versus insertion sort, 355
 of sets, 383
 of tail versus non-tail recursion, 507
 of value types, 65, 81, 247, 699
Eiffel language, 62
Elem class, 647, 652
Elem type
 in trait Parsers, 751
elements, XML, 646–647
else clauses, 156
embedded DSLs, *see* domain-specific languages
empty method
 on Map objects, 381, 383
 on Seq objects, 594
 on Set objects, 379, 380
 on Set traits, 549
empty-paren methods, 221
enclosing instances, *see* inner classes
endsWith method

on Seq traits, 545
enqueue method
 on class Queue, 560
ensuring method
 on object Predef, 294
entities, 662
enum keyword (Java), *see*
 Enumeration class
Enumeration class, 461
eq method
 on class AnyRef, 130, 252, 674
equality, *see also* equals method
 != (not equals) method
 on class Any, 128, 246
 == (equals) method
 on class Any, 128, 246, 674
eq method
 on class AnyRef, 130, 252,
 674
in Scala versus Java, 130
in-depth treatment, 674–697
ne method
 on class AnyRef, 130, 252
quick introduction, 128–130
value versus reference, 130
equals method, *see also* equality
 generated for case classes, 308
 on class Any, 129, 674–697
 contract of, 681
 recipe for writing, 693–695
equals method
 on class Any, 247
erasure, 319
 and pattern matching, 690
Erlang language, 49–50, 53, 92
errata, viewing and reporting, xliii
errors, *see also* compiler errors
 handling with exceptions,
 165–169
 in parsing, 759–761
 preventing, 93
escape sequences, for character
 literals, 117
Evans, Eric, 661n
event handling, 770–773, 796
event listeners, 770
event sources, 770
eventually method
 on trait Eventually, 53
example code, for book
 downloading, xliii
 license of, xliii
exception handling, 165–169
 and checked exceptions,
 702–703
ExecutionContext, 716
exists method
 on class List, 84, 208, 361
 on class StringOps, 377
 on trait Iterator, 589
 on Traversable traits, 537
extends keyword, 223
external DSLs, *see* domain-specific
 languages
extractors, 621–625
 and injections, 625
 extractor pattern, 344, 625

F

f string interpolator, 120
F# language, 53, 63
factory methods, 81, 466
factory objects, 238
collect method
 on trait Future, 724
failed method
 on object Future, 721
Failure class, 752
failure method
 on trait Promise, 722
fallbackTo method
 on trait Future, 724
false value, 119
fields, 99–101

abstract, 449
defining, 145
initializing to default values
 with an underscore, 400
overriding, 225–226
parametric, 140, 226
pre-initialized, 449
private, 101, 144
`FileReader` class, 742
files
 ensuring closed with `finally`,
 168
 opening, 95
 reading lines from, 95
`fill` method
 on object `List`, 366
 on `Seq` objects, 594
`filter` method
 on trait `Future`, 722
`filter` method
 on class `List`, 84, 359
 on trait `Iterator`, 589
 on `Traversable` traits, 537
`filterKeys` method
 on `Map` traits, 554
`filterNot` method
 on trait `Iterator`, 589
 on `Traversable` traits, 537
filters
 in for expressions, 162, 515
`final` modifier, 233
 on variables (Java), *see vals*
`finally` clauses, 167
`find` method
 on class `List`, 360
 on trait `Iterator`, 588
 on `Traversable` traits, 536
`findAllIn` method
 on class `Regex`, 634
`findFirstIn` method
 on class `Regex`, 634
`findPrefixOf` method
 on class `Regex`, 634
first-order methods
 on class `List`, 345–357
`flatMap` method
 on class `List`, 358
 on trait `Iterator`, 587
 on `Traversable` traits, 535
 translating for expressions to
 invocations of, 513
`flatMap` method
 on trait `Future`, 719
`flatten` method
 on trait `Future`, 732
`flatten` method
 on class `List`, 351, 362
`Flex`, 736
`Float` class, 112
floating-point literals, 115
`floatingPointNumber` method
 in trait `JavaTokenParsers`,
 738, 744
`fold`
 left, 361
 right, 362
`fold` method
 on object `Future`, 728
`foldLeft` method
 on class `List`, 363
 on trait `Iterator`, 590
 on `Traversable` traits, 537
`foldRight` method
 on class `List`, 363
 on trait `Iterator`, 590
 on `Traversable` traits, 537
`for` expressions, 75, 160, 513
 and extractors, 636
 and `Futures`, 719
 and XML patterns, 656–658
 notation, 518
 translated before type checking,
 526
 types valid after `->`, 525

using patterns in, 330, 514
for loops, *see also* for expressions, 523
forall method
 on class List, 84, 361
 on trait Iterator, 589
 on Traversable traits, 537
force method
 on views, 580
foreach method
 on trait Future, 730
foreach method
 on class Array, 74
 on class List, 84, 359
 on Traversable traits, 535
 overriding, 614
 translating for expressions to
 invocations of, 513
formatted method
 on Any (via StringAdd), 468
formatting strings, 468
Fortran language, 48
Fowler, Martin, 660n
free variables, 191
fromTry method
 on object Future, 721
fsc (fast Scala compiler), 109
fully qualified names, 89
function literals
 and closures, 193
 and single abstract method
 types, 710
 for partial functions, 327
 placeholder syntax, 187, 206
 syntax of, 75
underscores in, 187, 206
 versus function values, 184
function values, 184, 205
 and closures, 193
functional programming, 45, 52–54,
 135
lazy initialization, 454
main ideas of, 53
functional style, 87
 combining with imperative
 style, 509
 in parsing, 751
 methods without side effects, 81
 recognizing, 92
 refactoring functional style to,
 177
functions, *see also* methods
 basic form of, 69
 first-class, 53, 184
 higher-order, 203
 local, 182
 partial, 327–330
 partially applied, 188, 356
 predicates, 58
 procedures, 103
 pure, 222
 recursive, 198
 tail recursive, 199
future method
 on trait Promise, 721
Future object
 methods
 apply, 716
 failed, 721
 fold, 728
 fromTry, 721
 reduce, 729
 sequence, 729
 successful, 721
 traverse, 730
Future trait
 methods
 andThen, 731
 collect, 723
 failed, 724
 fallbackTo, 724
 filter, 722
 flatMap, 719
 flatten, 732

foreach, 730
isCompleted, 717
map, 719
onComplete, 731
recoverWith, 726
recover, 725
transformWith, 733
transform, 726
value, 717
withFilter, 723
zipWith, 732
zip, 728
futures, 714–735

G

Gamma, Erich, 310n
generator, in for expressions, 514
generic arrays, 572
generic types, 418, 425
get method
 on Map traits, 553
getLines method
 on object Source, 95
getOrElse method
 on Map traits, 553
getOrElseUpdate method
 on trait mutable.Map, 554
getter methods, 398, 431, 446, 643, 767
Gosling, James, 428, 518
graphical user interfaces, *see* user interfaces
groupBy method
 on Traversable traits, 537
grouped method
 on Iterable traits, 540
 on trait Iterator, 587
“Growing a language” (Steele), 47n
GUI programming, *see* user interfaces
Guice, 660

H

handlers, exception, *see* catch clauses
hasDefiniteSize method
 on trait Iterator, 588
 on Traversable traits, 536
hash consing, 252
hashCode method
 caching, 697
 generated for case classes, 308
 if overriding equals, 678–679
 on class Any, 246
 contract of, 679
 recipe for writing, 695–697
HashMap class
 in class hierarchy diagram, 90
HashSet class, 87
 creating and initializing
 immutable, 89
 in class hierarchy diagram, 88
Haskell language, 48, 53, 92
 as a lazy functional language, 454
hasNext method
 on trait Iterator, 587
head method
 on class List, 85, 342, 500
 on Traversable traits, 536
headOption method
 on Traversable traits, 536
Hejlsberg, Anders, 441
Hibernate, 662
hiding
 names in import clauses, 284
 names in nested packages, 281
 variables in nested blocks, 176
higher-kinded types, *see* http://booksites.artima.com/programming_in_scala_3ed
higher-order functions, 203
higher-order methods
 on class List, 357–365

I

identifiers, 147–149
 alphanumeric, 147
 capitalization conventions for, 147
 literal (with back ticks), 149
 mixed, 149
 operator, 148

identity
 of objects, testing with eq method, 674

idioms, *see* patterns and idioms

if expressions, 69, 73, 156–157

immutability, 54
 as functional style, 81
 selecting mutable versus immutable collections, 385
 trade-offs, 137

imperative style, 87
 combining with functional style, 509
 recognizing, 92
 refactoring to functional style, 177

implementation traits, 599

implements keyword (Java), *see* mixin composition

implicit keyword, 152

implicit classes, 484

implicit conversion, 55, 295
 a word of caution, 153
 implicit classes, 484
 in-depth treatment, 474–484
 quick introduction, 152
 to rich wrappers, 133

implicit conversions
 when multiple apply, 494

implicit parameters, 485–491

implicit resolution, 603

imports, 89, 281–286
 hiding clauses, 284
 implicit, 108, 285–286

on-demand (*i.e.*, wildcard), 282

renaming clauses, 283

selector clauses, 283

incrementing
 with += 1, not ++, 72

IndexedSeqLike implementation trait, 599

indexOf method
 on Seq traits, 544
 on trait Iterator, 588

indexOfSlice method
 on Seq traits, 544

indexWhere method
 on Seq traits, 544
 on trait Iterator, 589

indices method
 on class List, 351
 on Seq traits, 544

inference
 semicolon, 104–105
 turning off, 748
 type, 61, 91n
 Hindley–Milner style, 371
 the algorithm, 368

infix operator notation, 121

information hiding, 65, 422
 with factory methods, 238

inheritance, 270
 and self types, 790
 extending classes, 223
 mixing in traits, 258
 versus composition, 235

inheritance hierarchy diagram, *see* class hierarchy diagram

init method
 on class List, 85, 348
 on Traversable traits, 536

initialization
 lazy, 451
 of abstract vals, 447
 of arrays, 81
 of classes, *see* constructors

of fields to default values, 400
of instance variables with
 constructor parameters, *see*
 class parameters
of lists, 82
of maps, 91
of sets, 87, 89
of traits, 447
initializers, 145
injections, 625
inner classes
 accessing outer class members
 with a this alias, 753
 and path-dependent types, 459
 and private members, 286
 example of, 782
 granting access to private
 members of inner classes,
 289
 private, to hide implementation,
 425
insert method
 on trait Buffer, 547
insertAll method
 on trait Buffer, 547
insertion sort, 342, 344
instance variables, 101
instanceOf (Java), *see* type tests
Int class, 112
integer literals, 114
IntelliJ IDE, 64
interfaces (Java), *see* traits
internal DSLs, *see* domain-specific
 languages
interoperability, Scala with Java, 45
interpolated string literals, 119
interpreter, 64–66
intersect method
 on Seq traits, 546
 on Set traits, 549
invoking a superclass constructor,
 228
is-a relationships, 235
isCompleted method
 on trait Future, 717
isDefinedAt method
 on Map traits, 553
 on Seq traits, 544
 on trait PartialFunction, 329
isEmpty method
 on class List, 85, 342, 500
 on Map traits, 383
 on trait Iterator, 588
 on Traversable traits, 536
isInstanceOf method
 on class Any, 317
iterable
 members, 540
Iterable traits
 methods
 dropRight, 540
 grouped, 540
 iterator, 540
 sameElements, 540
 sliding, 540
 takeRight, 540
 zip, 540
 zipAll, 540
 zipWithIndex, 540
iterate method
 on Seq objects, 594
iterator
 members, 587
iterator method
 on class List, 354
 on Iterable traits, 540
 on mutable map, 618
Iterator trait
 methods
 /: (fold left), 590
 :\ (fold right), 590
 ++ (add elements), 587
 addString, 591
 buffered, 587

collect, 588
copyToArray, 587
copyToBuffer, 587
count, 589
drop, 589
dropWhile, 589
duplicate, 587
exists, 589
filter, 589
filterNot, 589
find, 588
flatMap, 587
foldLeft, 590
foldRight, 590
forall, 589
grouped, 587
hasDefiniteSize, 588
hasNext, 587
indexOf, 588
indexWhere, 589
isEmpty, 588
length, 588
map, 587
max, 590
min, 590
mkString, 591
next, 587
nonEmpty, 588
padTo, 587
partition, 589
patch, 590
product, 590
reduceLeft, 590
reduceRight, 590
sameElements, 591
size, 588
slice, 589
sliding, 587
sum, 590
take, 589
takeWhile, 589
toArray, 588
toIndexedSeq, 588
toIterable, 588
toList, 588
toMap, 588
toSeq, 588
toSet, 588
toStream, 588
withFilter, 589
zip, 590
zipAll, 590
zipWithIndex, 590

J

Java 8, [xxxiii](#), 709
default methods, [xxxiii](#), 713
lambda expressions, [xxxiii](#), 710
Stream interface, 712
Java language, 54, 92
javac, 704
ANTLR, 736
bytecodes, 698
collections, 594–596
compiling with Scala, 709
concurrency utilities, 715
covariance of arrays, 428
dependency injection in, 660
enumerations, 461
exception handling, 702
inner classes, 459
interfaces and Scala traits, 701
interoperability with Scala, 45, 55–56, 698–713
raw types, 418, 706
static methods, 699
Swing framework, 765–776
threading model, 715
throws keyword, 702
value types, 699
wildcard types, 706
wildcards, 434
Java Native Interface, 644
Java Persistence Architecture, 662
JavaBeans, 86

- JavaConversions object, 594
JavaScript Object Notation, *see* JSON
JavaTokenParsers trait, 738
JFlex, 736
JNI, 644
Joy, Bill, 518
JSON, 741–746
JUnit, 703–704
- K**
- Kay, Alan, 51, 441
keys method
 on Map traits, 382, 553
keySet method
 on Map traits, 383, 553
keysIterator method
 on Map traits, 553
keywords, using as identifiers, 149
- L**
- Label class, 782
LALR(1) parsers, 764
lambda calculus, 53
lambda expressions
 in Java 8, xxxiii, 710
Landin, Peter, 62
last method
 on class List, 85, 348
 on Traversable traits, 536
lastIndexOf method
 on Seq traits, 544
lastIndexOfSlice method
 on Seq traits, 544
lastOption method
 on Traversable traits, 536
laws, 219
layouts, in GUIs, 769
lazy modifier, 452
lazy functional languages, 454
length method
 on class List, 85, 347
 on trait Iterator, 588
- lengthCompare method
 on Seq traits, 544
Lex, 736
lexical analysis, 751, 759
linearization, of traits, 270–274
linked lists, 340
linking
 of modules at runtime, 670
Liskov Substitution Principle, 434
 and equals method, 688
Lisp language, 48, 53
List class, *see also* lists, 82, 373
 first-order methods on, 345–357
 higher-order methods on, 357–365
 immutability, 82
 implementation of, 499–510
 methods
 /: (fold left), 361
 ::: (concatenation), 82, 345, 501
 :\\ (fold right), 362
 :: (cons), 82, 342
 addString, 353
 apply, 351
 copyToArray, 354
 count, 84, 347, 350
 drop, 84, 350
 dropRight, 84
 dropWhile, 360
 exists, 84, 361
 filter, 84, 359
 find, 360
 flatMap, 358
 flatten, 351, 362
 foldLeft, 363
 foldRight, 363
 forall, 84, 361
 foreach, 84, 359
 head, 85, 342
 indices, 351
 init, 85, 348

isEmpty, 85, 342
iterator, 354
last, 85, 348
length, 85
map, 85, 357
mkString, 85, 353
partition, 359
reduceLeft, 97
remove, 85
reverse, 85, 349
sort, 85
sortWith, 365
span, 360
splitAt, 350
tail, 85, 342
take, 350
takeWhile, 360
toArray, 354
toString, 353
unzip, 352
zip, 352
zipWithIndex, 352

List object
methods
 apply, 82, 365, 630
 concat, 367
 fill, 366
 range, 358, 366
 tabulate, 367

ListBuffer class, 83, 375–376, 506

listenTo method
 on Reactor, 770, 798

lists, *see also* List class, 81–83, 340
 appending to, 83
 class hierarchy diagram, 500
 concatenation (::::), 345
 converting to arrays, 390
 converting to strings, 353
 creating and initializing, 82
 diagram showing linked-list
 structure, 504
 in-depth treatment, 340–372

passing elements as arguments
 with `_*`, 196

table of methods, 84

ListView class, 779

literal method
 on trait RegexParsers, 758

literals, 113–119
 array, 81
 boolean, 119
 character, 116
 class, *see* classOf method
 floating point, 115
 identifier, 149
 integer, 114
 interpolated string, 119
 list, 82
 string, 117, 119
 symbol, 118
 XML, 647–649

little languages, *see* domain-specific languages

LL(1) grammars, 762

loadFile method
 on XML, 654

loan pattern, 168, 212

local functions, 182

local variables, 174

locks, and shared data, 716

logical operations (`&&`, `||`, `!`)
 on class Boolean, 126

Long class, 112

lower bounds, 432

LowPriorityImplicits class, 496

LSP, *see* Liskov Substitution Principle

M

magic numbers, 148

main method
 of GUI applications, 766
 of Scala applications, 108

MainFrame class, 767
 attributes

contents, 767
title, 767

map
members, 553

map method
on class List, 85, 357
on trait Iterator, 587
on trait Future, 719
on Traversable traits, 535
translating for expressions to invocations of, 513

Map objects, 91, 381

Map traits, *see* maps
methods
++ (add elements), 553
- (remove element), 553
-- (remove elements), 553
++= (add elements to), 554
+= (add element to), 554
--- (remove elements from), 554
-= (remove element from), 554
apply, 553
clear, 555
clone, 555
contains, 553
filterKeys, 554
get, 553
getOrElse, 553
getOrElseUpdate, 554
isDefinedAt, 553
keys, 553
keySet, 553
keysIterator, 553
mapValues, 554
put, 554
remove, 554
retain, 555
update, 554
updated, 553
values, 553

valuesIterator, 553

Map traits
methods
+ (add element), 553

maps, 89–91, 377–381
class hierarchy diagram, 90
creating and initializing
immutable, 91
creating and initializing
mutable, 90
in library, not language, 46
mutability modeled in hierarchy, 87
table of methods, 382

mapValues method
on Map traits, 554

match expressions
in-depth coverage, 308–325
quick introduction, 169–170

MatchError class, 310
and “not exhaustive” warning, 324
and extractors, 624
not thrown in for expressions, 514, 522

Matsumoto, Yukihiro, 441

max method
on class Int (via RichInt), 97, 134, 249
on trait Iterator, 590
on Traversable traits, 538

member functions, *see* methods

member variables, *see* fields

members
abstract, 443
field, 99
initialization order of, 449
method, 99
no static, 105
type, 444

merge sort, 355

message passing, 49

- meta-programming, 638
- methods, *see also* functions, 99, 180
 - abstract, 220
 - as operators, 121
 - as procedures, 103
 - empty-paren, 221
 - first-order, 345
 - native, 644
 - overloading, 150
 - overriding, 225–226
 - parameterless, 220–223
 - overriding with `vals`, 445, 502
 - parameters of, 102
 - private, 144
 - return from, 102
 - when to invoke with empty parentheses, 123, 221
- Meyer, Bertrand, 221n
- Meyers, Scott, 235n
- `min` method
 - on class `Int` (via `RichInt`), 134, 249
 - on trait `Iterator`, 590
 - on `Traversable` traits, 538
- mixed identifiers, 149
- mixin composition, *see also* traits
 - and self types, 669, 800
 - example of, 793
 - syntax for, 258
- `mkString` method
 - on class `List`, 85, 353
 - on trait `Iterator`, 591
 - on `Traversable` traits, 93, 538
- mock objects, 662
- modules, 659–673
 - runtime linking, 670
- monads, 527
- monitors, 714
- Multi-Java language, 63
- multi-threaded programming, *see* concurrency
- multicore, 49
- multiple return values, 86, 392
- multiple variable definitions, 393
- multiple-line statements, 104
- mutability
 - and `equals`, 680–681
 - of collections, 386
 - of object state, 395

N

- named arguments, 196
- namespaces
 - in C#, 277
 - Scala's two instead of Java's four, 226
- naming conventions, 147
- NaN (not a number), 791, 797
- native annotation, 644
- `ne` method
 - on class `AnyRef`, 130, 252
- nested annotations, 640
- nesting
 - of classes and objects, 240
 - of functions, 182
 - of packages, 277
- .NET, 55, 250, 285
- NetBeans IDE, 64
- `new` keyword, 99
 - not needed when calling factory methods, 81
 - not needed with case classes, 307
- next method
 - on trait `Iterator`, 587
- Nice language, 63
- Nil object, 83, 341, 499–501
- Nilsson, Rickard, 302
- Node class, 647
- NodeSeq class, 648
- nominal subtyping, 460
- None object, 325
 - in extractors, 624
- nonEmpty method

- on trait Iterator, 588
 - on Traversable traits, 536
 - nonvariance, 426
 - Nothing type, 252
 - as result type of throw expressions, 166
 - as type parameter of List, 341
 - in Scala class hierarchy diagram, 248
 - Null class, 252
 - in Scala class hierarchy diagram, 248
 - null value, 252
 - in equals methods, 681
 - using Option instead for optional values, 326
 - NullPointerException, preventing, 326
- O**
- Object class, *see also* AnyRef class
 - in Scala class hierarchy diagram, 248
 - object keyword, 105–107
 - object-oriented programming, 45, 51–52, 135
 - Object-Oriented Software Construction* (Meyer), 221n
 - object-private access with `private[this]`, 289
 - objects
 - annotating, 639
 - companion, *see* companion objects
 - domain, 661
 - entity, 662
 - equality of, *see* equality
 - functional (immutable), 135
 - immutable, 81
 - mock, in testing, 662
 - mutable, 395
 - serializing, 642
- singleton, *see* singleton objects
 - standalone, 107
 - OCaml language, 53, 63, 92
 - on-demand import, 282
 - onComplete method
 - on trait Future, 731
 - operator
 - associativity, 132–133
 - example: class Rational with operator methods, 151
 - identifiers, 148
 - when to use, 750
 - notation, 79–80, 121–123, 147
 - infix, 121
 - postfix, 123
 - prefix, 122
 - “overloading”, 79
 - precedence, 130–132, 147
 - table of, 131
 - opt method
 - on trait Parsers, 757
 - optimization
 - of tail recursion, 201
 - turning off with `notailcalls`, 201
 - of value types, 250
 - Option class, 325–326
 - Ordered trait, 264–266, 385, 439
 - outer classes, *see* inner classes
 - overloading
 - constructors, 142–143
 - methods, 150
 - “operator”, 79
 - override modifier, 138, 229
 - on parametric fields, 227
 - overriding
 - `equals` method, 677
 - defs with vals, 445, 502
 - methods and fields, 225–226
- P**
- package objects, 291
 - package clauses, 277

- package-private access (Java), 289
- packages, 276–281
 - as modules, 659
 - hiding, 281
 - implicitly imported, 285–286
 - unnamed package, 276
- packaging, 277
- padTo method
 - on Seq traits, 544
 - on trait Iterator, 587
- pair, name for Tuple2, 237
- Panel class, 769
- parallel collections, 46, 529
- parallel programming, 714–735
- parameterization
 - with types, 77
 - with values, 77
- parameterized types, 77
 - and object equality, 688–692
- parameterless methods, 220–223
 - overriding with vals, 445, 502
- parameters
 - by-name, 215, 407
 - by-value, 756
 - class, *see* class parameters
 - default values, 197
 - implicit, 442, 479, 485–491
 - named, 196
 - repeated, 81, 195–196
 - vararg matching, 628
 - type, 77
 - versus arguments, 810
- parametric fields, 140, 227
- parentheses
 - using curly braces instead of, 213
 - when to use on method calls, 123, 221
- Parser class, 738
- parser combinators, 736–764, 785–788, 801
- parser generators, 736
- ParseResult class, 751
- parsers, 736–764
- Parsers trait, 750, 757
- partial functions, 327–330
- PartialFunction trait, 329, 771
- partially applied functions, 188, 356
- partition method
 - on class List, 359
 - on trait Iterator, 589
 - on Traversable traits, 537
- passing arguments
 - to superclass a constructor, 228
- patch method
 - on Seq traits, 545
 - on trait Iterator, 590
- path-dependent types, 457–460
 - and inner classes, 459
- Patricia tries, 614
- pattern guards, 321
- pattern matching
 - and extractors, 621
 - constant patterns, 309, 312
 - constructor patterns, 310, 315
 - examples of, 408, 790
 - in event handling, 771
 - in exception handling, 166
 - in for expressions, 330, 514
 - in lists, 343, 501
 - in variable definitions, 327
 - in equals method, 678, 682
 - in-depth coverage, 308–331
 - on XML, 655–658
 - quick introduction, 169–170
 - sequence patterns, 315
 - tuple patterns, 316
 - typed patterns, 317
 - variable patterns, 309, 313
 - variable-binding patterns, 320
 - wildcard patterns, 310, 311
- patterns and idioms
 - conditional initialization, 156

divide and conquer principle,
346
ensuring a resource is closed,
168
functional on the outside,
imperative on the inside,
509
loan pattern, 168, 212
reading lines, characters, *etc.*,
with do-while, 158
rich wrappers pattern, 133–134,
484
using Option not null to
indicate optional values,
326
performance, *see also* efficiency
and multi-core processors, 49
of collection types, 575–579
of Scala compared to Java, 55
Perl language, 46, 632
Pizza language, 63
placeholder syntax
in wildcards, 706
in function literals, 187, 206
PLT-Scheme language, 63
pointers, *see* references
polymorphism, 231
and type inference, 370
pop method
on class Stack, 559
postconditions, *see* ensuring
method
postfix operator notation, 123
pre-initialized fields, 449
precedence, operator, 130–132, 147
table of, 131
preconditions, 139
Predef object
methods
???, 347
assert, 94, 294
classOf, 703
ensuring, 294
println, 108
predicates, 58
prefix operator notation, 122
prefixLength method
on Seq traits, 544
primary constructors, 136–138
private, 422
primitive types, 81
private modifier
and inner classes, 286
augmented with qualifiers, *i.e.*,
private[meeting], 288
granting access to private
members of inner classes,
289
in modules, 663
object-private access with
private[this], 289
on constructors, 422
on fields, 101, 144
on methods, 144
on parametric fields, 227
procedures, 103
processed string literals, 119
product method
on trait Iterator, 590
on Traversable traits, 538
programming in the large, 659
programming in the small, 659
programming style
functional, 87
imperative, 87
modular, 659–673
Promise trait, 721
methods
completeWith, 722
complete, 722
failure, 722
future, 721
success, 722
pronunciation of Scala, 45

properties, 149, 398–401, 767
 verifiable with static typing, 59

protected modifier, 287
 on parametric fields, 227

public access, 101

Publisher trait, 796

push method
 on class Stack, 559

put method
 on trait mutable.Map, 554

putIfAbsent method
 on trait ConcurrentMap, 569

Python language, 46, 48

Q

Queue class, 560

R

r method
 on class String (via
 StringOps), 634

range method
 on object List, 358, 366
 on Seq objects, 594

ranges, of basic types, 113

raw string interpolator, 120

raw strings, 117
 in regular expressions, 633

raw types (Java), 418, 706

Raymond, Eric, 47

reactions property
 on Reactor, 771, 789

Reactor trait, 770

Reader class, 751

reading
 from standard input with
 do-while, 158
 lines from a file, 95

receive method
 on trait Actor, 49

recommended style, *see* style
 recommendations

recover method
 on trait Future, 725

recoverWith method
 on trait Future, 726

recursion, *see* recursion
 in combinator parsers, 756
 tail, 198–202
 optimization, 201

using ListBuffer to prevent
 stack overflow, 375

reduce method
 on object Future, 729

reduceLeft method
 on class List, 97
 on trait Iterator, 590
 on Traversable traits, 538

reduceRight method
 on trait Iterator, 590
 on Traversable traits, 538

refactoring
 and static typing, 60
 and vals, 157
 imperative to functional style,
 177
 reducing code duplication with
 closures, 206

reference
 classes, 250
 definition of, 812
 equality, 130, 251, 674

referential transparency, 54

refinement types, 460

reflection, 704

Regex class, 633

regex method
 on trait RegexParsers, 758

RegexParsers trait, 741, 758, 785

regular expressions, 632
 as parsers, 740, 785–788

relational operations ($>$, $<$, \geq , \leq)
 on numeric types, 125
 on trait Ordered, 264–266

remove method

on class List, 85
on trait ConcurrentMap, 569
on trait mutable.Map, 554
on trait mutable.Set, 550
on trait Buffer, 547
rendererComponent method
 on class Table, 780
rep method
 on trait Parsers, 757
repeated parameters, 81, 195–196
 vararg matching, 628
replace method
 on trait ConcurrentMap, 569
representation independence, 631
repsep method
 on trait Parsers, 757
require method
 on object Predef, 139
resources, ensuring release of, 168,
 212
result type, 68
 covariance of, 435
retain method
 on trait mutable.Map, 555
 on trait mutable.Set, 550
return keyword, 102
return type, 68
returning multiple values, 86, 392
reverse method
 on class List, 85, 349
 on Seq traits, 545
reverseIterator method
 on Seq traits, 545
reverseMap method
 on Seq traits, 545
rich wrappers pattern, 133–134, 484
RichInt class, *see* Int class
rowHeaderView property
 on class ScrollPane, 779
Ruby language, 46, 54, 474
Rumbaugh, James, 272
running a Scala program, *see* scala
runtime type, definition of, 813

S

s string interpolator, 119
SAM types, *see* single abstract
 method types
sameElements method
 on Iterable traits, 540
 on trait Iterator, 591
save method
 on XML, 654
scala (Scala launcher)
 to launch applications, 110
 to launch scripts, 71
 to launch the interpreter, 65
Scala language
 2.12 release, xxxii, xxxvii, 476,
 709–713, 727–733
 class hierarchy diagram, 248
 compatibility with Java, 45,
 55–56, 698–713
 compiling, 109
 with Java, 709
 conciseness versus Java, 56–57
 downloading, 64
 IDEs, 64
 influences on, 61–63
 interpreter shell, 64–66
 naming of source files, 109
 pronunciation of “Scala”, 45
 scalability of, 51–54, 661, 800
 scripts, *see* scripts, Scala
 specification, xxxviii
Scala.js, 55, 716
scalability
 of configuration, 671
 of Scala language, 51–54, 661,
 800
 of teams, 660
scalac (Scala compiler), 109
ScalaCheck, 296, 302–304
Scaladoc, 637
ScalaTest, 53, 296–304

scanner generators, 736
Scheme language, 53
scope
 of implicit conversions, 477
 of variables, 173–177
scripts, Scala, 70–71, 109
 running on Unix, 802
 running on Windows, 802
ScrollPane class, 777, 779
sealed classes, 323–325
sealed modifier, 323, 631
segmentLength method
 on Seq traits, 544
selectors
 in match expressions, 309
selectors, in imports, 283
self references, 141–142
self types, 669, 790, 794
semi-structured data, 645
semicolon inference, 104
 turning off, 748
seq
 factory, 594
 members, 544
Seq objects
 methods
 apply, 594
 concat, 594
 empty, 594
 fill, 594
 iterate, 594
 range, 594
 tabulate, 594
Seq traits, 236
 methods
 +:(prepend), 544
 :+(append), 544
 apply, 544
 contains, 545
 containsSlice, 545
 corresponds, 545
 diff, 546
distinct, 546
endsWith, 545
indexOf, 544
indexOfSlice, 544
indexWhere, 544
indices, 544
intersect, 546
isDefinedAt, 544
lastIndexOf, 544
lastIndexOfSlice, 544
lengthCompare, 544
padTo, 544
patch, 545
prefixLength, 544
reverse, 545
reverseIterator, 545
reverseMap, 545
segmentLength, 544
sortBy, 545
sorted, 545
sortWith, 545
startsWith, 545
union, 546
update, 545
updated, 545
sequence method
 on object Future, 729
sequence patterns, 315
serializable annotation, 642, 702
serialization
 binary, 642
 to and from XML, 649–651
SerialVersionUID annotation, 642
set
 members, 548
Set objects, 87, 379
Set traits, *see* sets
 methods
 ++= (add elements to), 549
 ++ (add elements), 548
 += (add element to), 549

--= (remove elements from),
 550
-- (remove elements), 549
-= (remove element from),
 549
- (remove element), 549
&~ (diff), 549
& (intersect), 549
| (union), 549
+ (add element), 548
add, 549
clear, 550
clone, 550
contains, 548
diff, 549
empty, 549
intersect, 549
remove, 550
retain, 550
subsetOf, 548
union, 549
update, 550
sets, 87–89, 377
 and generic types, 418
 class hierarchy diagram, 88
 creating and initializing
 immutable, 87
 creating and initializing
 mutable, 89
 mutability modeled in
 hierarchy, 87
 table of methods, 380
setter methods, 398, 446, 643, 767
shadowing variables, 176
shared data and locks, 716
shell, Scala interpreter, 64–66
shift operations (<<, >>, >>>)
 on integral types, 128
short circuiting, of logical
 operations, 126
Short class, 112
side effects, 54, 81, 93
minimizing, 94
SimpleSwingApplication class,
 766, 779
Simula language, 51
single abstract method types, 710
singleton objects, 105–107
 as modules, 659
 as seen from Java, 700–701
 in testing, 662
 initialization semantics, 107
 nesting of, 240
 shown with rounded corners in
 hierarchy diagrams, 500
singleton types, 564n, 673
size method
 on Set traits, 380
 on trait Iterator, 588
 on Traversable traits, 536
slice method
 on trait Iterator, 589
 on Traversable traits, 536
sliding method
 on Iterable traits, 540
 on trait Iterator, 587
Smalltalk language, 51, 474
SML language, 53
snoc, 364
Some class, 325
 in extractors, 624
sort
 insertion, 342, 344
 merge, 355
sort method
 on class List, 85
sortBy method
 on Seq traits, 545
sorted method
 on Seq traits, 545
SortedMap trait, 385
SortedSet trait, 385
sortWith method
 on class List, 365

on Seq traits, 545
source code, downloading, *see*
 example code
source files, naming of, 109
Source object, 95
span method
 on class List, 360
 on Traversable traits, 537
specifiers, access, *see* access
 modifiers
specs2, 296, 301
split method
 on class String, 379
splitAt method
 on class List, 350
 on Traversable traits, 537
spreadsheets, 777–801
Spring Framework, 660, 671
Stack class, 559
stack, the
 and tail-recursive functions,
 199, 506
 and thrown exceptions, 166
 and variables captured by
 closures, 195
stackable modifications, 266–270
standalone objects, 107
standard error stream, 95
startsWith method
 on Seq traits, 545
statements
 multiple-line, 104
static members, 105
static typing, 58–61
Steele, Guy, 47, 518
Stream class
 in Scala, 546, 557
Stream interface
 in Java 8, 712
String class, 113
 methods
 r (via StringOps), 634
 stripMargin (via
 StringOps), 118
StringBuilder class, 353
stringLiteral method
 in trait JavaTokenParsers,
 744
stringly typed code, 255
StringOps class, *see also* String
 class, 377, 496
stringPrefix method
 on Traversable traits, 538
strings
 formatting, 468
 interpolated (processed), 119
 iterating through the characters
 of, 58
 literals, 117, 119
 long, 117
 raw, 117, 633
 treating as a sequence (via
 WrappedString), 496
 treating *like* a sequence (via
 StringOps), 496
 treating like a sequence (via
 StringOps), 377
structural subtyping, 460
*Structure and Interpretation of
Computer Programs*
(Abelson, *et al.*), 401
style recommendations
 prefer alphabetic names unless
 symbolic names have
 established meaning, 750
 prefer classes to tuples when
 data combination has
 meaning, 393
 prefer vals, immutable objects,
 and methods without side
 effects, 94
 use implicit conversions with
 restraint, 153
subclasses

and equals method, 685
defining, 223

subsetOf method
on Set traits, 548

subtyping
and type parameters, 425
nominal vs. structural, 460
versus subclassing, 814

subtyping polymorphism, 231

Success class, 751

success method
on trait Promise, 722

successful method
on object Future, 721

sum method
on trait Iterator, 590
on Traversable traits, 538

super references
special treatment in traits, 260

superclasses, 223
invoking constructor on, 228

supertype, 436

Sussman, Gerald J., 401, 518

Swing, 765–776

Swing class, 769
methods
EmptyBorder, 769

switch statement (Java), 169

symbol literals, 118

symbolic versus alphabetic names, 750

syntactical analysis, 759

T

Table class, 777, 780

TableUpdated class, 788

tabulate method
on object List, 367
on Seq objects, 594

tags, XML, 646

tail method
on class List, 85, 342, 500
on Traversable traits, 536

tail recursion, 198–202, 505
optimization, 200
turning off with
notailcalls, 201

verifying with @tailrec, 643

tailrec annotation, 643

take method
on class List, 350
on trait Iterator, 589
on Traversable traits, 536

takeRight method
on Iterable traits, 540

takeWhile method
on class List, 360
on trait Iterator, 589
on Traversable traits, 536

target typing, 186

template, definition of, 815

term, in function literals, 193

Test annotation
in JUnit 4, 704

test suites, 304

testing, 94, 296–305
integration, 660
unit, 177
with mock objects, 662
with singletons, 662

Text class, 647

text method
on class Node, 651

text processing in XML, 646, 651

TextField class, 781

Thinking in Java (Eckel), 235n

this, 141–142
aliasing, 753
and self types, 669

throw expressions, 166

throws annotation, 702

tiny types, 255

to method

on class Int (via RichInt), 79,
134, 249

toArray method
 on class List, 354
 on trait Iterator, 588
 on Traversable traits, 535

toChar method
 on class Int, 784

toIndexedSeq method
 on trait Iterator, 588
 on Traversable traits, 535

toInt method
 on class String (via
 StringOps), 55

toIterable method
 on trait Iterator, 588
 on Traversable traits, 535

toList method
 on class Array, 354, 390
 on class ListBuffer, 375, 506
 on trait Iterator, 588
 on Traversable traits, 535

toMap method
 on trait Iterator, 588
 on Traversable traits, 535

top method
 on class Stack, 559

top method
 on class
 SimpleSwingApplication,
 766

Torreborre, Eric, 301

toSeq method
 on trait Iterator, 588
 on Traversable traits, 535

toSet method
 on trait Iterator, 588
 on Traversable traits, 535

toStream method
 on trait Iterator, 588
 on Traversable traits, 535

toString method, 138, 246

generated for case classes, 308

on class Any, 246

overriding, 138

total function, *see* complete function traits, *see also* mixin composition, 257, 667–670

and abstract parameters, 447

and Java interfaces, 701

annotating, 639

generic, 418, 425

implementation, 599

initializing, 447

linearization of, 270–274

mixing in, 87

transform method
 on trait Future, 726

transformers, 579

transformWith method
 on trait Future, 733

transient annotation, 643

Traversable traits
 methods
 /: (fold left), 537
 :\ (fold right), 537
 ++ (add elements), 535
 addString, 538
 collect, 535
 copyToArray, 536
 copyToBuffer, 536
 count, 537
 drop, 536
 dropWhile, 536
 exists, 537
 filter, 537
 filterNot, 537
 find, 536
 flatMap, 535
 foldLeft, 537
 foldRight, 537
 forall, 537
 foreach, 535
 groupBy, 537

hasDefiniteSize, 536
head, 536
headOption, 536
init, 536
isEmpty, 536
last, 536
lastOption, 536
map, 535
max, 538
min, 538
mkString, 538
nonEmpty, 536
partition, 537
product, 538
reduceLeft, 538
reduceRight, 538
size, 536
slice, 536
span, 537
splitAt, 537
stringPrefix, 538
sum, 538
tail, 536
take, 536
takeWhile, 536
toArray, 535
toIndexedSeq, 535
toIterable, 535
toList, 535
toMap, 535
toSeq, 535
toSet, 535
toStream, 535
view, 538, 580
withFilter, 537

TraversableLike implementation
trait, 599

traverse method
on object Future, 730

TreeMap class, 385

TreeSet class, 385

trimEnd method

on trait Buffer, 547

trimStart method
on trait Buffer, 547

true value, 119

Try class
class hierarchy diagram, 718

Try class, 716–718

try expressions, 165–169

tuple patterns, 316

tuples, 392–394
creating and using, 86
one-based element access, 87
result of -> operation, 91
when to use a class instead, 393
zipped method on, 367

type aliases, 444

type annotations, 46, 60, 66
for debugging, 371

type casts, *see* casting

type constructors, 425

type erasure, 319

type inference, 61, 91n
Hindley-Milner style, 371
the algorithm, 368

type keyword
in singleton types, such as
db.type, 673
in type alias definitions, 378, 444

type members, 444–445

type parameterization, *see* parameterized types

type parameters, 346, 418
in parser results, 751
lower bounds, 432
upper bounds, 439

type tests
with isInstanceOf, 317
with typed patterns (preferred style), 317

type-driven design, 433

typed patterns, 317

- types
 - abstract, 455
 - bottom, 252
 - erasure, 690
 - generic, 418
 - ground, 816
 - in for expressions, 526
 - integral, 112
 - numeric, 112
 - path-dependent, 457–460
 - primitive, 81
 - refinement, 460
 - result, 68
 - return, 68
 - runtime, 816
 - self, 669, 790, 794
 - singleton, 673
 - static, 816
 - wildcard, 692, 706–709
- typing
 - dynamic, 59, 61, 118
 - static, 58–61
 - target, 186
- U**
- Ullman, Jeffrey, 518
- unapply method
 - in extractors, 622
- unapplySeq method
 - in extractors, 628
- unary operations, 122, 149
- unchecked annotation, 325, 409, 639, 644
- Unicode, 116
- Unified Modeling Language Reference Manual, The*
(Rumbaugh, et al.), 272n
- uniform access principle, 221
- union method
 - on Seq traits, 546
 - on Set traits, 549
- Unit class, 93
- unit testing, 94, 177, 296–305
- unit value, 158
- unnamed package, 276
- until method
 - on class Int (via RichInt), 237, 249, 392
- unzip method
 - on class List, 352
- update method
 - on class Array, 80
 - on Seq traits, 545
 - on trait mutable.Map, 554
 - on trait mutable.Set, 550
- updated method
 - on Map traits, 553
 - on Seq traits, 545
- upper bounds, 439
- user interfaces, 765–801
 - reactive programming, 777, 801

V

- vals, *see also* variables
 - abstract, 445
 - annotating, 639
 - as fields, 99
 - conditional initialization of, 156
 - defining, 66–68
 - lazy, 452
 - preferring over vars, 92
 - referencing mutable objects, 78
 - “val” on class parameters, 227
- Value class, 462
- value classes, 247
- value method
 - on trait Future, 717
- value parameterization, 77
- ValueChanged class, 797
- values method
 - on class Enumeration, 462
 - on Map traits, 383, 553
- valuesIterator method
 - on Map traits, 553
- van Rossum, Guido, 441
- vararg matching, 628

variable patterns, 309, 313
variable-binding patterns, 320
variable-length arguments, or
 “varargs”, *see* repeated
 parameters
variables
 bound, 163, 191
 captured by closures, 195
 defining, 66–68
 using patterns, 327, 393
 fields, 99–101
 final (Java), *see* vals
 free, 191
 instance, 101
 local, 174
 multiple definitions of, 393
 reassignable, *see also* vars, 398
 scope, 173–177
 shadowing, 176
variance, 426
 annotations, 425–429
 compiler checking of,
 429–432, 439
 declaration-site, 434
 use-site, 434
vars, *see also* variables
 abstract, 446
 and mutable objects, 397
 annotating, 639
 as fields, 99
 defining, 66–68
 on class parameters, 227
 programming without, 92
Vector class, 607
verifiable properties, 59
view method
 on Traversable traits, 538,
 580
viewportView property
 on class ScrollPane, 779
views, 579–584
virtual classes, 466

volatile annotation, 642, 701
W
Wall, Larry, 441
warnings, *see* compiler warnings
weak hash maps, 568
while loops, 71–73, 157–159
 as imperative style, 92
wildcard patterns, 310, 311
wildcard types, 692, 706–709
wildcard types (Java), 706
Wirth, Niklaus, 518
with keyword, 259
withFilter method
 on trait Future, 723
 on trait Iterator, 589
 on Traversable traits, 537
 translating for expressions to
 invocations of, 513
WrappedString class, 496

X
XML, 645–658
 attributes, 647, 652
 character encoding, 654
 configuration files, 660, 671
 deserialization, 653
 elements, 646–647
 literals, 647–649
 pattern matching, 655–658
 serialization, 649–651
 tags, 646
 text, 646
 using an at sign (@) to extract
 attributes , 652
 using curly braces ({}) in
 pattern matching, 655
XPath, 651
XML object
 methods
 loadFile, 654
 save, 654
XPath, 651

Y

Yacc, [736](#)

yield keyword

 in for expressions, [164](#), [513](#)

Z

zip method

 on class List, [352](#)

 on Iterable traits, [540](#)

 on trait Iterator, [590](#)

zip method

 on trait Future, [728](#)

zipAll method

 on Iterable traits, [540](#)

 on trait Iterator, [590](#)

zipped method

 on tuples, [367](#)

zipWith method

 on trait Future, [732](#)


zipWithIndex method

 on class List, [352](#)

 on Iterable traits, [540](#)

 on trait Iterator, [590](#)

Take the fun path to deeper understanding
with this new book from Artima Press:



Scala Puzzlers is a collection of enigmatic Scala code examples that behave highly contrary to expectations. Working through these code examples and the subsequent explanations will provide important and often fundamental insights into Scala. Get ready for a fun journey that will take you further down the road to Scala mastery.

Scala Puzzlers: The fun path to deeper understanding

by Andrew Phillips and Nermin Šerifović

ISBN: 978-0-9815316-7-0


\$38.95 paper book / \$25.00 PDF eBook

Order your copy now at:

http://www.artima.com/shop/scala_puzzlers

[Cover](#) · [Overview](#) · [Contents](#) · [Discuss](#) · [Suggest](#) · [Glossary](#) · [Index](#)

Other titles from Artima Press



Property-based testing allows you to express your tests in terms of functions called “properties” that describe your code’s behavior, leaving the task of test case generation and evaluation to the testing tool. *ScalaCheck: The Definitive Guide* is the authoritative guide to ScalaCheck, a property-based testing tool for Scala. Written by the creator of ScalaCheck, this book will help you learn how to take advantage of this valuable complement to traditional testing techniques.


ScalaCheck: The Definitive Guide

by Rickard Nilsson

ISBN: 978-0-9815316-9-4

\$24.95 paper book / \$15.00 PDF eBook

Order it now at: <http://www.artima.com/shop/scalacheck>



Akka Concurrency is the authoritative guide to concurrent programming with Akka. Written as a practical guide, it will teach you not just the “what” and “how” of Akka, but also the “why.” Akka isn’t just a toolkit you can use to write your concurrent applications: it embodies a set of paradigms you can use to *reason* about those applications. This book will give you a whole new perspective on how you design, build, and think about concurrent applications on the JVM.

Akka Concurrency

by Derek Wyatt

ISBN: 978-0-9815316-6-3

\$45.95 paper book / \$26.95 PDF eBook

Order it now at: http://www.artima.com/shop/akka_concurrency